pepco
An Exelon Company

TREATABILITY STUDY REPORT
FINAL

Benning Road Facility
3400 Benning Road, NE
Washington, DC 20019



TREATABILITY STUDY REPORT
FINAL

Benning Road Facility
3400 Benning Road, N.E.
Washington, DC 20019

PREPARED FOR:

Pepco and Pepco Energy Services
701 9th Street, NW
Washington, DC 20068

PREPARED BY:

AECOM
430 National Business Parkway, STE 190
Annapolis Junction, MD 20701

August 2021

Contents

1 Introduction 1-1

1.1 Site Setting 1-2

1.2 Remedy Framework 1-2

1.3 Remedial Options to be considered in the Feasibility Study 1-3

1.4 Cap Amendment Selection 1-6

2 Sample Collection and Field Testing 2-1

2.1 Overview 2-1

2.2 Hydrologic/Hydraulic Data Collection, Sedimentation Assessment 2-1

2.2.1 Topographic and Bathymetric Survey 2-2

2.2.2 Tidal and Current Monitoring 2-2

2.2.3 Outfall Monitoring 2-5

2.2.4 Sedimentation Study 2-7

2.3 Seepage Measurements 2-9

2.3.1 Field Measurements 2-9

2.3.2 Collection of Cores for Laboratory Study 2-10

2.4 Cove Ecological Survey 2-10

2.4.1 Vegetation Survey 2-10

2.4.2 Macroinvertebrate Community Survey 2-10

2.5 SEDflume Core Collection 2-11

2.6 Sample Collection for Dewatering Testing 2-12

2.7 Sample Collection for Sequestration Testing 2-13

2.8 Deviation from TSWP 2-14

2.9 Residuals Management 2-14

3 Results and Discussion 3-1

3.1 Overview 3-1

3.2 Hydrologic/Hydraulic, Sedimentation Assessment 3-1

3.2.1 Topographic and Bathymetric Survey 3-1

3.2.2 Surface Water Flow Monitoring 3-1

3.2.3 Acoustic Doppler Current Profiler 3-2

3.2.4 Outfall Evaluation 3-3

3.2.5 Cove Sedimentation 3-7

3.3 Seepage Measurements 3-9
3.3.1 Field Measurements 3-9
3.3.2 Laboratory Study 3-10
3.4 Cove Ecological Survey 3-11
3.4.1 Cove Vegetation Survey 3-11
3.4.2 Macroinvertebrate Community Survey 3-12
3.5 Sediment Stability Assessment 3-13
3.5.1 Core Management Prior to SEDflume Testing 3-13
3.5.2 SEDflume Apparatus and Test Procedure Summary 3-13
3.5.3 SEDflume Test Conditions 3-13
3.5.4 SEDflume Testing Results 3-14
3.6 Sediment Dewatering Tests 3-15
3.6.1 Sediment Solidification/Stabilization Tests 3-15
3.6.2 Geotextile Tube Gravity Dewatering 3-18
3.7 PCB Sequestration Study 3-20
3.7.1 Amendment Selection and Procurement 3-21
3.7.2 Amendment Mixing into Sediments 3-21
3.7.3 PCB Measurement in Sediment Porewater and Worms 3-21

4 Conclusions 4-1

Hydrologic/Hydraulic, Sedimentation Assessment 4-1
Seepage Measurements 4-2
Cove Ecological Survey 4-2
Sediment Stability Assessment 4-3

5 References 5-1

List of Figures

Figure 1-1: Site Location Map ..... See attached

Figure 1-2: Site Plan and Investigation Areas ..... See attached

Figure 2-1: Treatability Study Sampling/Investigation Locations ..... See attached

Figure 2-2: Transducer Stations and ADCP Locations ..... See attached

Figure 2-3: Cove Outfall Locations ..... See attached

Figure 2-4: Sediment Trap and Sediment Mat Locations ..... See attached

Figure 2-5: Constituent Sequestration Assessment and Seepage Evaluation ..... See attached

Figure 2-6: Seepage Meter Schematic ..... See attached

Figure 2-7: Benthic Macroinvertebrate Survey ..... See attached

Figure 2-8: SEDflume Core Locations ..... See attached

Figure 2-9: Sediment Dewatering Study ..... See attached

Figure 3-1: Waterside Investigation Area Bathymetric Survey (June 2020) and Cove Topographic Survey (May 2020) ..... See attached

Figure 3-2: Observed Water Level Data: August 1 to August 7, 2020 ..... See attached

Figure 3-3: CHANN ADCP Current Speed and Direction Distributions (ADCP 2 and ADCP 3) ..... See attached

Figure 3-4: River ADCP Current Speed and Direction Distributions (ADCP 1 and ADCP 4) ..... See attached

Figure 3-5: 16 CHANN ADCP 2 (7/29/ to 9/11/2020) and ADCP 3 (8/27/ to 9/17/2020) Current Speed (cm/s) and Direction (°N) ..... See attached

Figure 3-6: Observed Wet Weather Discharge at Outfalls 3 & 4 ..... See attached

Figure 3-7: Observed Dry Weather Discharge at Outfalls 3 & 4 ..... See attached

Figure 3-8: Sediment Hydraulic Conductivity Test ..... See attached

Figure 3-9: Vegetation Survey ..... See attached

Figure 3-10: Critical Shear Stress in Unamended and Amended Sediment ..... See attached

Figure 3-11: PCB Concentration in Sediment Porewater from Exposure Chambers 3-22

Figure 3-12: PCB Bioaccumulation in Worm Tissue 3-24

Figure 3-13: Worm Dry Weight Recoveries Following Bioaccumulation Study 3-25

List of Tables

Table 1-1: Remedial Options to be Considered in the Feasibility Study 1-4

Table 2-1: TS Field Testing Locations ..... See attached

Table 2-2: Permits Obtained for TS Field Activities ..... See attached

Table 2-3: Surface Water Station Summary 2-3

Table 2-4: ADCP Location Coordinates, Deployment, and Recovery Dates 2-4

Table 2-5: ADCP Station Information and Sampling Details ..... See attached

Table 2-6: Summary of Outfalls Discharging to Cove 2-6

Table 2-7: Sediment Core Collection and Experimental Design for SEDflume Study 2-12

Table 2-8: Deviations from TSWP 2-14

Table 3-1: Observed MHT and MLT at Each Station, as of March 31, 2021 3-2

Table 3-2: Near-bottom Currents Summary 3-2

Table 3-3: Treatability Study Stormwater Results ..... See attached

Table 3-4: Treatability Study Sediment Results ..... See attached

Table 3-5: Annual TSS Loading to Cove by Outfall 3-6

Table 3-6: Annual Aqueous-Phase PCB Loading to Cove by Outfall 3-6

Table 3-7: Annual Sorbed-Phase PCB Loading to Cove by Outfall 3-7

Table 3-8: Sediment Trap and Mat Results – Depth and Mass of Sediment Collected 3-8

Table 3-9: Seepage Velocity Calculations 3-9

Table 3-10: Laboratory Seepage Measurement Before and After Amendment Application 3-11

Table 3-11: Untreated Material Characterization 3-16

Table 3-12: Pre- and Post-Solidification Sample Results ..... See attached

Table 3-13: Round 1 Experimental Mixtures Observations 3-16

Table 3-14: Round 2 Experimental Mixtures Observations 3-17

Table 3-15: Final Round of Reagent Drying Evaluations:
Mixture Designs, VOC Monitoring, Pocket Penetrometer and Paint Filter Testing 3-18

List of Tables (continued)

Table 3-16: Solids Content and Density of Sediment 3-19
Table 3-17: Jar Testing Performance Results 3-19
Table 3-18: Pillow Test Filter Cake Solids 3-20
Table 3-19: Experimental Design for Laboratory Treatability Study 3-21
Table 3-20: Reduction of PCB Homolog Concentration in Sediment Porewater Compared to Untreated Control 3-23
Table 3-21: Reduction of PCB Bioaccumulation in Worm Tissue Compared to Untreated Control 3-24

List of Appendices

Appendix A: Photographic Log
Appendix B: Eurofins TestAmerica Lab Packages
Appendix C: DPW Outfall Monitoring Results
Appendix D: In-situ Remediation Treatability Studies for Cove Sediments
Appendix E: Macroinvertebrate Community Survey Results
Appendix F: Anacostia River Native and Amended Sediment Erodibility Study
Appendix G: KEMRON Dewatering Study Report
Appendix H: IAI Sediment Treatability Testing Report

List of Acronyms

AC	activated carbon
ac	Acres
AECOM	AECOM Technology Services, Inc.
ARSP	Anacostia River Sediment Study
ASOS	Automated Surface Observation System
BAZ	Bioactive Zone
BERA	Baseline Ecological Risk Assessment
BHHRA	Baseline Human Health Risk Assessment
BMP	Best Management Practice
Bss	below sediment surface
cfs	cubic feet per second
cm	centimeters
cm/d	centimeters per day
cm/yr	centimeters per year
CMP	Corrugated Metal Pipe
COPC	Constituents of Potential Concern
CTE	Central Tendency Exposure
DI	Ductile Iron
District	District of Columbia
DOEE	District Department of Energy and Environment
DPW	D.C. Department of Public Works
DRO	Deisel-Range Organics
EMNR	Enhanced Monitored Natural Recovery
FAA	Federal Aviation Administration
ft	feet
FS	Feasibility Study
GAC	granulated activated carbon
GPS	Global Positioning System
HI	Hazard Index
In	inches
in/hr	inches per hour
KDCA	Ronald Reagan Washington National Airport
LOI	Loss on Igintion
M	meters
µg/kg	micrograms per kilogram
MLLW	mean lower-low water
MSL	Mean Sea Level
MTL	mean tide level
MNR	Monitored Natural Recovery
MSGP	Multi-Sector General Permit for Stormwater Discharges from Industrial Activities
NAVD88	North American Vertical Datum of 1988
ng/l	Nanograms per Liter
NOAA	National Oceanic and Atmospheric Administration
NPDES	National Pollutant Discharge Elimination System

List of Acronyms (continued)

NPS	National Park Service
NRCS	Natural Resources Conservation Services
NTU	Nephelometric Turbidity Units
NWP	Nationwide Permits
ORO	Extended-Range Organics
Pa	Pascal (Newtons/Square Meter)
pg/l	picograms per liter
ppb	parts per billion
PAC	powdered activated carbon
PAH	Polycyclic Aromatic Hydrocarbons
PCB	Polychlorinated Biphenyl
PCDD	Polychlorinated Dibenzodioxin
Pepco	Potomac Electric Power Company and Pepco Energy Services, Inc.
RCP	Reinforced Concrete Pipe
RI	Remedial Investigation
RI/FS	Remedial Investigation/Feasbility Study
RME	Reasonable Maximum Exposure
ROD	Record of Decision
SPME	Solid Phase Microextraction
SWMM	Stormwater Management Model
SWPPP	Stormwater Pollution Prevention Plan
TR-55	Technical Release 55
TOC	Total Organic Carbon
TS	Treatability Study
TSS	Total Suspended Solids
TSWP	Treatability Study Work Plan
TPH	Total Petroleum Hydrocarbons
UMBC	University of Maryland Baltimore County
USACE	U.S. Army Corps of Engineers
USDA	United States Department of Agriculture
USEPA	U.S. Environmental Protection Agency
Yr	year

An Exelon Company

1 Introduction

The Potomac Electric Power Company (Pepco) is performing a Remedial Investigation/Feasibility Study (RI/FS) at Pepco's Benning Road facility (the Site), located at 3400 Benning Road NE, Washington, DC, and a segment of the Anacostia River (the River) adjacent to the Site, under the oversight of the District Department of Energy and Environment (DOEE). The location of the Site is depicted in **Figure 1-1**.

The Study Area for the RI/FS consists of a "Landside Investigation Area" focused on the Site itself, and a "Waterside Investigation Area" focused on the shoreline and sediments in the segment of the Anacostia River in close proximity to the Site. The areas encompassed by the investigation are shown on **Figure 1-2**. The purpose of the Benning Road facility RI/FS is to: (a) characterize environmental conditions within the Study Area, (b) investigate whether and to what extent past or current conditions at the Site have caused or contributed to contamination of River sediments, (c) assess current and potential risk to human health and the environment posed by conditions within the Study Area, and (d) develop and evaluate potential remedial actions, as may be warranted. The Final Remedial Investigation Report (Final RI Report) for the Benning Road Site was submitted to DOEE on February 28, 2020 and was approved by DOEE on March 02, 2020. The Final RI Report addresses the first three objectives outlined above, and the forthcoming FS Report will address the development and evaluation of potential remedial actions.

As part of the FS process, Pepco identified the need for a Treatability Study (TS) involving both field data collection and bench-scale studies to support the evaluation of potential remedial alternatives to address sediments in the Waterside Investigation Area. No such need was identified for the Landside Investigation Area to date (however, additional pre-design sampling will be performed to determine PCE plume sourcing and migration in the Landside Investigation Area and a final determination regarding the need for a landside treatability study will be made based on the results of this sampling).

The Waterside Investigation Area treatability studies will focus on the following key FS data needs:

- Analysis of the effectiveness of sequestration agents (the use of amendments to reduce bioavailability of contaminants by sorption) and other active and inert capping materials;
- Hydrologic/hydraulic data collection and outfall assessment to understand how these data may affect design and performance of remedial alternatives, including restoration;
- Geotechnical evaluations to determine the feasibility of capping systems and ex-situ sediment dewatering; and
- Sedimentation studies to evaluate the effect of ongoing upstream sources on the performance of remedial alternatives.

In November 2018, a Draft TS Work Plan (TSWP) for the Waterside Investigation Area was submitted to DOEE. The Draft TSWP was updated to reflect DOEE's review comments and provided to DOEE in December 2019 as a Draft Final document. In January 2020, DOEE provided comments on the Draft Final TSWP. The Final TSWP was updated to reflect this second round of DOEE comments and submitted to DOEE on March 13, 2020. DOEE approved the Final TSWP on March 18, 2020.

The TSWP outlined the scope of work for TS in the Waterside Investigation Area, with focus on the approximately 4.2-acre cove of the River which is located just north of the Site beyond the National

Park Service (NPS) Kenilworth Maintenance Yard property (the Cove). The Cove receives storm water conveyed from the Site via Pepco's outfall 013 and multiple additional non-Pepco outfalls, and is depicted in **Figure 1-1** and **Figure 1-2**.

1.1 Site Setting

The 77-acre Site is entirely fenced and access is controlled at all times. The former Benning Road Power Plant was located in the western portion of the Site until it was permanently shut down in 2012. Demolition and removal of the power plant building and related infrastructure was completed in 2015. Most of the Site is currently occupied by the Benning Service Center, which supports activities related to construction, operation and maintenance of Pepco's electric power transmission and distribution system serving the Washington, DC area. Three substations serving Pepco's transmission and distribution system are also located on this Site. The Site is separated from the Anacostia River by a thin strip of land a portion which is part of Anacostia Park and a portion of which serves as the National Park Service Kenilworth Maintenance Yard (as shown on Figure 1-2). The River is an urban tidal estuarine river corridor with multiple historical and current sources of contamination, both up- and down-stream of the Site.

1.2 Remedy Framework

The remedy framework proposed by Pepco for addressing areas of elevated sediment concentrations of constituents of potential concern (COPC) within the Waterside Investigation Area is intended to fit within the adaptive management strategy for the Anacostia River Sediment Project (ARSP) described in the Interim Record of Decision (ROD) released on September 30, 2020. The Interim ROD calls for eliminating exposure to eleven sediment "hot spots" within the DC portion of the ARSP Study Area through early actions. Sediment within the Waterside Investigation Area is being managed under a separate regulatory agreement and is, therefore, not included among these eleven Early Action Areas. The Interim ROD adopts an adaptive management approach to: (1) help reduce the uncertainties; (2) provide information on the performance of the interim remedial action; and (3) inform DOEE's subsequent remedial decision-making, which may involve additional remedial actions in the ARSP study area, or modifications to the selected interim remedy. Although source control is not part of the selected interim remedy, DOEE, in cooperation with the corresponding agencies from Prince George's County, Montgomery County, and the State of Maryland are engaged in efforts to control contaminant sources external to the ARSP study area in the upstream Anacostia River watershed. DOEE views such efforts as critical to achieving the overall cleanup of the study area water bodies (DOEE, 2020). This treatability study focuses on potential remedial alternatives to address elevated contaminant concentrations in the Cove, although the technologies evaluated may also be applicable to possible remedial actions elsewhere in the Waterside Investigation Area. The remedial actions supported by this TS are considered an early action and that, consistent with the adaptive management strategy for the ARSP, may need to be augmented by future actions by Pepco.

A substantial portion of the RI focused on field sampling and data analysis to define the nature and extent of COPCs in groundwater, soils, and Anacostia River sediment and surface water. Extensive RI data were collected during two phases of investigation, extending from 2013 to 2018, to document the presence and general distribution of COPCs. A number of different organic and inorganic constituents were detected in these environmental media, and potential risks associated with exposure to these constituents were evaluated in a Site-specific Baseline Human Health Risk Assessment (BHHRA) and a Site-specific Baseline Ecological Risk Assessment (BERA). Potential risks to various human and environmental receptors were evaluated using conservative risk analysis tools and an extensive Site-specific data set in accordance with U.S. Environmental Protection Agency (USEPA) and DOEE guidance. The human health risk assessment also evaluated fish consumption pathways, relying on fish tissue data collected by DOEE and others from the broader Anacostia River.

Within the Landside Investigation Area, the BERA and BHHRA determined that exposure to environmental media at the Site posed no unacceptable ecological risk and only limited potential risks to human health from potential future exposure to contaminated soil within the Site, given appropriate institutional controls (e.g., restricted access to subsurface soils and to uncharacterized portions of the site, such as switchyards). Although remedial action is potentially warranted within portions of the Landside Investigation Area, no treatability studies were deemed necessary at this time for the evaluation of remedial alternatives to address these Landside conditions.

Within the Waterside Investigation Area, potential risks to human health posed by exposure to water and surface sediments are all within EPA's acceptable risk ranges, and ecological risks posed by conditions in the Waterside Investigation Area are relatively low and not substantively different from risks at reference areas considered in the RI. The RI found that concentrations of polychlorinated biphenyls (PCBs) and other COPCs were elevated in surficial sediment in the Cove compared to background, and the BERA findings indicate a low to indeterminate potential for risks to benthic receptors exposed to surficial sediments in this area. The BERA determined that the bioactive zone (BAZ) in the Waterside Investigation Area ranges from 0 to 6 inches (typically 4 inches or less) and in the Cove, ranges from 0.16 to 4.76 inches in depth.

None of the potential cumulative receptor carcinogenic risks evaluated in the RI exceed the upper end of USEPA's target risk range of 10^{-6} to 10^{-4} for consumption of Upper Anacostia River fish for the reasonable maximum exposure (RME) scenario (for the purpose of the RI, the Upper Anacostia was operationally defined as the River reach that is upstream of the CSX bridge.). Noncarcinogenic hazards exceed USEPA's target hazard index (HI) of 1 for consumption of Upper Anacostia River fish. Fish consumption hazards estimated using data collected by DOEE throughout the Anacostia and Potomac Rivers likewise exceed the noncancer target HI of 1; these findings suggest multiple sources of PCBs and other urban contaminants, including upstream of the extent of the tidal influence of the Waterside Investigation Area. The RI further concluded that considerable uncertainties remain relative to the relationship between COPCs in sediment within the Waterside Investigation Area and Anacostia River fish tissue residues.

The FS will evaluate remedial alternatives to control exposure to soil at the Site and to address sediment conditions in the Waterside Investigation Area. In particular, eliminating exposures to contaminated sediment within the Cove is expected to reduce the overall surface weighted average of PCBs within the Waterside Investigation Area to a level consistent with existing currently measured local background conditions. Background threshold values (BTVs) of 182 parts per billion (ppb) for PCB Aroclors and 423 ppb for PCB Congeners were established in the Final RI (AECOM, 2020). The pre-remedial Surface Weighted Average Concentration (SWAC) of PCBs in the Waterside Investigation Area is estimated to be 334 ppb (measured as PCB Aroclors). A preliminary analysis indicated that active remediation of the surface sediment in the 4.2-acre Cove through capping or removal would reduce the SWAC in the overall Waterside Investigation Area to 195 ppb (measured as Aroclors), in line with the upstream currently-measured background conditions. Given the source control measures that will be undertaken for the ARSP, upstream background concentrations are expected to decline in future years, which could result in a new baseline for comparison.

1.3 Remedial Options to be considered in the Feasibility Study

In accordance with USEPA guidance and regulations, the FS for the Waterside Investigation Area will include an initial screening of a range of potential remedial options followed by a detailed evaluation of the most promising options. Technologies to be considered in the FS and the data needed to evaluate these technologies in the FS are summarized in **Table 1-1.**

Table 1-1: Remedial Options to be Considered in the Feasibility Study

Remedial Approach	Description	Site Conditions Favoring	Data Need(s)
Monitored Natural Recovery (MNR)	Uses un-enhanced naturally-occurring processes to transform, immobilize, isolate, or otherwise remove COPCs	Where natural recovery processes are expected to continue at rates similar to existing conditions; Where human exposure is limited or can be limited by institutional controls; Where COPC exposures to biota are already approaching remedial cleanup levels; Where the sediment bed is stable and likely to remain stable after remedial actions are completed.	Sediment stability: deposition rate, erosion potential, water depth/bathymetry, in-water and shoreline infrastructure, sediment hardness and slope conditions, and groundwater/surface water interactions Sediment characteristics: Physical properties (grain size, density, consolidation), benthic community, and bioturbation COPC characteristics: Horizontal and vertical distribution, COPC type and concentration in sediment and in surface water/outfalls, exposure pathways, mobility mechanisms, bioavailability and bioaccumulation potential, transformation, and degradation Hydrodynamic assessment: groundwater/surface water interactions; tidal water fluctuation; surface water flowrates and velocities; outfall discharge
Enhanced Monitored Natural Recovery (EMNR)	Relies on one or more technologies (i.e., thin layer capping; reactive amendments) to enhance ongoing natural recovery processes while minimizing the effects on the aquatic environment	Same as MNR except can be applied where ongoing natural processes are slow as the technology will hasten recovery	*Same as MNR with the following additions*: Constituent sequestration assessment: effectiveness of various types of amendment, dose rate of effective amendments (as function of sediment grain size and TOC)
Capping	Placement of granular material over sediments to reduce direct exposure; cap materials can be amended to attenuate contaminant flux	Where hydrodynamic conditions are not likely to compromise the cap Where long-term risk reduction outweighs habitat disruption Where sediment has sufficient strength to support the cap materials	*Same as MNR and EMNR with the following additions*: Bathymetric characteristics: complete delineation of bathymetry for area/volume computations Sediment bearing capacity: measure in situ sediment physical characteristics to assess strength COPC isolation assessment: theoretical and empirical data used in modeling assessment to predict COPC mobility

Table 1-1: Remedial Options to be Considered in the Feasibility Study
(continued)

Remedial Approach	Description	Site Conditions Favoring	Data Need(s)
Dredging/ Excavation	Removal of sediment to either the depth of constituent impact or a shallower depth that meets the remedial goal	Where contaminant mass and risk of erosion make cap placement impractical Where required to accommodate for placement of cap materials Where long-term risk reduction outweighs habitat disruption	*Same as MNR, EMNR and Cap with the following additions*: Sediment dewatering characteristics for mechanical and/or hydraulic dredging: grain size distribution with hydrometer; solids content and moisture content; TOC; various gravity, mechanical and centrifugal dewatering assessments; filtrate water quality assessment; amendment dewatering study
Restoration	Restoration of habitat disrupted by dredging and/or placement of cap	Where remedial activities disrupt habitat Where existing habitat is compromised due to contamination which remedial activities ameliorate Where integrating remediation and restoration activities provides value relative to regulatory framework	*Same as MNR, EMNR and Permeable Cap with the following additions*: Plant community assessment: observation of plant species on and adjacent to restoration site; observation of substrate characterization with depth Invertebrate community assessment will rely on benthic invertebrate data collected during the RI, supplemented by data to be collected as part of this TSWP

Sources of information:
U.S. EPA, 2005.
ITRC, 2014.

1.4 Cap Amendment Selection

Pepco selected three activated carbon (AC) amendment types to be evaluated in the TS laboratory batch experiments. While the success of AC materials, such as granular activated carbon (GAC) and powdered activated carbon (PAC), is well documented for in-situ treatment of hydrophobic organic compounds such as PCBs, the delivery of bulk AC in submerged aquatic environments can be challenging. Therefore, various AC dry broadcast delivery products, such as SediMite™ and permeable AquaGate+® products, were selected for inclusion in this assessment. A description of these products and their applications is provided below. All three products chosen for testing are readily available in bulk quantities needed for full-scale treatment.

Bulk Activated Carbon (GAC/PAC): Bulk AC, including PAC and GAC, can be applied directly to in-situ sediments for sequestration of hydrophobic organic compounds, such as PCBs, or these materials can be mixed with sand to form a permeable thin layer cap system. There are substantial delivery challenges associated with use of PAC as a stand-alone remedy in a system such at the Anacostia River; therefore, this TS focuses on use of bulk GAC, which can be applied directly to sediment as a stand-alone technology or mixed with capping materials to enhance performance of the cap. When used as a stand-alone technology, GAC relies on bioturbation and other natural processes to distribute AC throughout the BAZ. GAC procured from Calgon Corporation (F-300 with 20 to 50 mesh size) was selected for the bench-scale studies. This coal based activated carbon was recently specified for a large-scale GAC application project for the remediation of Spirit Lake Estuary Site in Duluth Minnesota.



Granular AC F-300 mixed with sand prior to SEDflume study (photo provided by Integral).

SediMite™: SediMite is a patented pelletized material containing high doses of AC (50% by dry weight) that is designed to deliver AC to in-situ sediments. SediMite pellets can use varying sizes of AC. In the current study, AC sourced from virgin coal with a size range of 80 to 325 mesh was used. Once deployed, SediMite pellets sink forming a thin, permeable layer on the sediment surface. SediMite pellets break down over a period of time (which can be engineered to range from one week to several months, depending on the site characteristics and project requirements) releasing AC into the aquatic environment. Over time, the AC becomes incorporated into the sediment BAZ via natural process such as bioturbation, further stabilizing the material into the surface of the sediment. SediMite can be deployed either as a stand-alone response action, or can be mixed with sand or other inert materials as part of a capping system. When used as a stand-alone technology, SediMite relies on bioturbation and other natural processes to distribute AC throughout the BAZ.



SediMite Pellets (Source: http:/www.sedimite.com)

AquaBlok® Delivery Products: AquaBlok® delivery products include AquaGate®+PAC (powdered activated carbon with <325 mesh size), a patented AC delivery product that is manufactured by AquaBlok, Ltd. AquaGate+PAC is a composite-aggregate material comprised of a dense aggregate core surrounded by a mixture of clay or clay-sized particles, polymers for binding, and PAC (5%, 10%, or custom concentration by dry weight). AquaGate+PAC sinks, to form a thin layer of AC-rich material on the sediment surface. AquaGate+PAC can be deployed either as a stand-alone response action, or can be mixed with sand or other inert materials as part of a capping system. When used as a stand-alone technology, AquaGate+PAC relies on bioturbation and other natural processes to distribute AC throughout the BAZ. AquaGate+PAC made with 10% PAC by weight sourced from lignite-based activated carbon was selected for use in the bench-scale studies.



AquaGate+PAC
(Source: http:/www.aquablok.com)

2 Sample Collection and Field Testing

2.1 Overview

Field activities to support the TS were initiated on May 18, 2020, and were conducted in accordance with the approved TSWP and US EPA's Guidance for Conducting Treatability Studies under CERCLA (EPA, 1992). The scope of work included the following: hydrologic/hydraulic assessment, sedimentation assessment, seepage measurements, Cove ecological survey, sediment stability assessment, sediment dewatering study, and sequestration study. The specific field tasks and locations including coordinates are presented in **Table 2-1** and field-testing locations are provided on **Figures 2-1 to 2-9**. A photolog documenting field activities is provided in **Appendix A**.

Several permits from regulatory and other government agencies were obtained prior to initiating TS field activities. These took the form of either new permits or modifications to the permits previously obtained for the RI/FS work, and included a Special Use Permit obtained from National Park Service to conduct sediment testing, a Nationwide Permit from USACE to conduct data collection and field sampling, a Water Quality Certification from DOEE for river sediment sampling, and a Scientific Research Permit from DOEE to capture, handle, and collect aquatic specimens for scientific purposes. These permits are summarized in **Table 2-2**. Pepco mobilized to the site on May 18, 2020, following receipt of all permits with the exception of the Scientific Research Permit, which was approved on June 3, 2020. There were several delays in securing permits, mobilizing field sampling teams, and setting up laboratory tests due to restrictions associated with COVID-19, which resulted in the delay of the Treatability Study field work schedule.

2.2 Hydrologic/Hydraulic Data Collection, Sedimentation Assessment

Hydrologic and hydraulic data were collected as part of this TS to support the evaluation of multiple components of various remedial scenarios. For the MNR and EMNR remedial scenarios, hydrologic data are needed to assess the physical stability of in situ sediment. The physical data required for assessment of MNR and EMNR will also be used to confirm capping system material stability. Updated bathymetric data are needed to support MNR, EMNR, capping system, and dredging remedial scenario evaluations, as well as restoration planning.

Hydrologic/hydraulic parameters included in this study include, (a) flood levels and seasonal flow conditions (e.g., velocities and shear stress during major flood events), (b) tidal fluctuation/inundation levels in relation to surface elevations, (c) quality, volume, and velocities of flows into the Cove from existing discharge outfalls under proposed scenarios, and (d) effects on riverine hydrodynamics from surface contour and hydrology changes in the Cove. This information is needed to assess the suitability and sustainability of the remediated Site to support wetland plant species given the tidal fluctuation/inundation and various hydrologic inputs to the system. In addition to collecting accurate bathymetry and flow data, there is a need to better understand groundwater hydrology flux into the overlying sediment within the Cove. This information will help inform the need for amendments as well as the selection of granular backfill materials.

Sedimentation assessment involved installing several sediment traps to measure quality and quantity of sediment deposition to help with the evaluation of MNR/EMNR and potential for recontamination of any capping-type remedies in the Cove.

2.2.1 Topographic and Bathymetric Survey

Bathymetric and side scan sonar data for the Waterside Investigation Area were previously collected in 2013 via hydrographic survey. These data are referenced to the Mean Lower-Low Water (MLLW) datum and the North American Vertical Datum of 1988 (NAVD 88), and provide good coverage in the river channel and into the western part of the Cove. Due to limitations in the technologies used in this hydrographic survey, and the shallow water depths in the Cove, the investigation area did not span the extent of the entire Cove.

Mercado Consultants, Inc. (Mercado) of Ashton, MD, a qualified DC-licensed surveyor, and Gahagan & Bryant Associates, Inc. (GBA) of Virginia Beach, VA were retained to survey the Cove area and collect additional bathymetric data from the Waterside Investigation Area; these areas are identified on **Figure 1-2**.

The Cove survey was conducted by Mercado between May 18, 2020 and May 29, 2020. Given the limited water depth in the Cove, the survey was conducted at low tide using upland topographical survey techniques. The limit of the survey extended approximately 50 feet beyond the Cove boundary towards landside to cover the entire Cove and the landside areas surrounding the Cove. A small landside area to the southwest of the Cove and adjacent to Anacostia River was also surveyed. On June 9, 2020, GBA completed a bathymetric survey of the Waterside Investigation Area. The bathymetric survey was conducted from a boat fitted with ODOM CV100 (200 kHz) echo sounder to measure the water depth under the boat.

2.2.2 Tidal and Current Monitoring

2.2.2.1 Surface Water Stations

Three surface water stations, each equipped with a pressure transducer datalogger, were installed in the Waterside Investigation Area during June and July 2020 to support the hydrodynamic analysis and design of the remediation. The stations are located downstream of the Cove near the Benning Road Bridge (TRANS-01), upstream of the Cove (TRANS-02), and in the Cove (TRANS-03), as depicted in **Figure 2-2**.

The transducer stands were constructed on June 17, 2020. The TRANS-01 stand was installed on one of the protective wood pilings under Benning Road Bridge. The TRANS-02 and TRANS-03 stands were each installed on a T-post which was directly inserted into the sediment. The stands consist of 2-inch PVC pipe with a lower section of slotted screen, a polyethylene box, and a 4-foot staff gauge. The PVC pipe was capped at the bottom and mounted vertically to the wood piling (TRANS-01) or T-post (TRANS-02 and TRANS-03) via metal clamps and screws. A lid and a lock were added to the top of the PVC pipe. A polyethylene box to hold remote monitoring system equipment was mounted at each location, either near the top of the PVC pipe or on the T-post, and was secured by a lock. Additionally, staff gauges were installed at each location. (See **Appendix A**, Photos 9 and 11 to 15.)

On July 9 and 14, 2020, Mercado surveyed the transducer top of casing elevations to the North American Vertical Datum of 1988 (NAVD 88). On July 17, 2020, the staff gauge heights were calibrated by Mercado and set to MLLW.

On July 15, 2020, the remote monitoring system (vanEssen Diver-Link telemetry unit and a vanEssen Diver datalogger) was installed at each surface water station. The Diver-Link unit was placed inside the polyethylene box. The Diver datalogger was connected to the Diver-Link unit via a data transmission cable and lowered into river water inside the PVC pipe. The Diver dataloggers at TRANS-01 and TRANS-02 were adjusted to a depth in the water so that it remained above the sediment and fully submerged in

the water at all times. However TRANS-03, installed in the Cove, was set at a location that goes dry at low tide. All remote monitoring systems were configured per manufacturer instructions and set up to record data on water level (pressure), water temperature, and conductivity every five minutes. The recorded data is remotely transferred daily to Diver-Hub, a cloud-based web portal system for real-time data monitoring. Installation details are provided in **Table 2-3** below.

Table 2-3: Surface Water Station Summary

Location ID	Date Installed (Datalogger)	Top of Casing Elevation (ft)*	Location Relative to the Cove	Northing**	Easting**
TRANS-01	7/15/2020	7.072	Downstream	448217.393	1323232.324
TRANS-02	7/15/2020	5.992	Upstream	450557.709	1323825.263
TRANS-03	7/15/2020	4.864	Cove	449684.952	1324177.091

*Vertical Datum: NAVD 88
**Coordinate System: US State Plane 1983/ NAD 83/Maryland 1900/ US survey Feet

To capture the seasonal water level variation, monitoring will continue over a 12-month period. On August 27, 2020, October 1, 2020 and December 29, 2020, all three stations were visited for routine maintenance. At each station, the Diver datalogger was retrieved from the casing, cleaned of accumulated mud/debris on the surface, and reinstalled. Following cleaning, the datalogger was reinstalled to the same elevation, which is marked on the transducer cable. Time was recorded for when the datalogger was retrieved and reinstalled. It is anticipated that routine maintenance events will be needed approximately once a month to once every other month.

2.2.5.2 Acoustic Doppler Current Profiler (ADCP)

The ADCP data collected as detailed below will be used in future hydrodynamic analyses in support of the remedy design for the Cove area. The future analyses may include sediment scour calculations and estimation of sediment CAP thickness and armor size to minimize scour.

ADCP Setup, Deployment and Recovery Specifics

ADCP field measurements included the setup and deployment of two ADCP units to monitor river flow for a period of one month along the north transect and for approximately 20 days along the south transect (**Figure 2-2**). Two acoustic doppler current profiler (ADCP) units (ADCP-01 and ADCP-02) were deployed in the river near the Cove area on July 29, 2020, as depicted in **Figure 2-2**. The ADCPs were used to measure water current velocities over a depth range using the Doppler effect of sound waves scattered back from particles within the water column. Each ADCP unit was mounted to a customized metal frame (with dimensions of about 1 ft × 1 ft × 4 ft) and transported to deployment location via boat. The metal frame was slowly lowered to the river bottom via a single fixed pulley on the boat crane. The ADCP unit was adjusted to be positioned parallel to the anticipated overall current direction at the deployment location. ADCP-1 was positioned parallel to the River and ADCP-2 was positioned at an angle towards the Cove. The ADCP units were left in place to collect current data for approximately four weeks.

On August 27, 2020, to better understand the river currents in proximity to the Cove, the two ADCP units were retrieved from river bottom and deployed at two new locations (ADCP-03 and ADCP-04), as depicted in **Figure 2-2**. ADCP-3 was positioned at an angle towards the Cove and ADCP-4 was positioned parallel to the River. The two units were left in place until ADCP-03 was retrieved from river bottom on September 17,

2020 and ADCP-04 on October 1, 2020. The ADCP units were removed from the metal frames and sent to data processing facility for data retrieval.

The ADCP location coordinates, and deployment and recovery dates, are presented in **Table 2-4**. ADCP deployment and recovery pictures are provided in **Appendix A** (photos 16-19).

Table 2-4: ADCP Location Coordinates, Deployment, and Recovery Dates

Location ID	Install		Water Depth Install (ft)	Recovery		Northing*	Easting*
	Date	Time		Date	Time		
ADCP-1 (River)	7/29/2020	0934 AM	~7.0 ft	8/27/2020	0850 AM	450025.7	1323676
ADCP-2 (CHANN)	7/29/2020	1019 AM	~4.5 ft	8/27/2020	1030 AM	449982.1	1323728
ADCP-3 (CHANN) (formerly ADCP-2)	8/27/2020	1100 AM	~2.5 ft	9/17/2020	1405 PM	449692.1	1323579
ADCP-4 (River) (formerly ADCP-1)	8/27/2020	0945 AM	~7.0 ft	10/1/2020	0905 AM	449759.4	1323477

*Coordinate System: US State Plane 1983/ NAD 83/Maryland 1900/ US survey Feet

ADCP Channel Measurements

The ADCP near the Cove named "CHANN" station was initially deployed on July 29, 2020 (site 2). The station was recovered and redeployed to a second location on August 27, 2020 (site 3). The CHANN ADCP was relocated because the first deployment location was several feet deeper than the planned location and not as far into the "channel" of the cove as expected, due to site inaccessibility from the vessel. The CHANN ADCP did not experience any debris fouling issues.

The original deployment site was anticipated to be positioned at river depth of 3 to 6 feet, based on preliminary planning. However, due to access difficulties the actual installation depth was deeper. Further complicating the first deployment was the steep slope of the bathymetry at the deployment site (from offshore to inshore near the cove area). This resulted in a moderately tilted instrument frame, slightly reducing the effective range of the ADCP.

Due to the deeper deployment site and the steep bathymetry causing frame tilt, there are periods during mid-to-high portions of the tidal cycle that the ADCP signal did not reach the water surface, and the velocity profile did not capture the complete water column. The second deployment location was in shallower water in line with the expected range of water depths for the deployment. Otherwise, all data were free of debris impact or other acoustic interference issues except for data collected during a very brief period (September 8, 2020 from 10:30 to 12:30) that were removed from the processed dataset due to signal interference within the water column (possible fish, leafy debris, etc.). On September 11, 2020 at 12:50, the ADCP battery began failing and all data from this point and after were removed from the processed dataset. ADCP instruments collect current and directional data in the water column in 0.1 meter slices. Data for each slice is saved to a bin sequentially numbered beginning with Bin 1 at 0.5 m above the mudline. Additional station information, such as average water depth, number of valid bins, ADCP bin size, ADCP record interval and ADCP bin heights above seabed (m) are presented in **Table 2-5**.

ADCP River Measurements

The ADCP at the "RIVER" station was initially deployed on July 29, 2020 (site 1). The ADCP was recovered and redeployed to a second location on August 27, 2020 (site 4). The second location was in similar river depth and approximately 100 m downriver of the first deployment location. The RIVER ADCP experienced extensive debris fouling and entanglement during extended periods of this deployment, as summarized below:

ADCP data in bins 1 and 2 were removed from the post-processed dataset due to acoustic signal interference and fouling in the immediate vicinity of the transducer head for the following periods:

- 8/4/2020 08:50 to 8/27/2020 08:50
- 9/3/2020 18:30 to 9/10/2020 14:00

It is noted that both interferences occurred immediately after the onset of high flow events, indicating that debris was likely brought downriver and entangled with the instrument frame, but not necessarily affecting the entire acoustic profile.

It should be noted that these two time periods were also characterized by very low signal-to-noise ratios in one of the transducer beams, indicating at least some partial signal blockage. Due to the acoustic signal blockage, the remaining bins of data (bins 3 and above) during the above time periods should be used with caution, depending on the data use goals. The data appear of good quality, but the signal strength in one beam was near the noise floor.

On September 10, 2020 at 14:00, the ADCP and frame were completely covered by debris, eliminating transmission of the acoustic signal; all data beyond this time were removed from the processed dataset. The ADCP battery died shortly thereafter on September 12, 2020. Additional station information, such as, average water depth, number of valid bins, ADCP bin size, ADCP record interval and ADCP bin heights above riverbed (m) are presented in **Table 2-5**.

2.2.3 Outfall Monitoring

The objectives of the outfall evaluation conducted for the Cove were to: (a) evaluate hydrology at the end-of-pipe at each outfall, (b) assess the potential for recontamination as a result of discharge from each outfall, and (c) assess the sedimentation contribution from each outfall. To support these objectives, data collection activities as described herein were performed between July and October of 2020 except as noted otherwise.

As described in the March 2020 TSWP, four outfalls were known to discharge into the Cove; one additional outfall was identified during the TS field work in summer 2020. These five outfalls are summarized in **Table 2-6** and are shown in **Figure 2-3** (see also **Appendix A**, Photos 1-4). One of these outfalls is from the Pepco Benning facility (Outfall 013 under the facility's NPDES permit). Three of the outfalls drain stormwater from the waste transfer station located just east of the Cove. These discharges are authorized under the U.S. Environmental Protection Agency's NPDES Multi-Sector General Permit for Stormwater Discharges from Industrial Activities ("MSGP"). The stormwater drainage system at the facility was confirmed by recent evaluations conducted by the D.C. Department of Public Works ("DPW") (including CCTV inspection). These outfalls are referred to by DPW as outfall "POD-002," and "POD-003". POD-002 discharges stormwater collected in drop inlets draining the area to the south of the waste transfer building. POD-003 was recently determined by DPW to be connected to drop inlets in the drive area at the southwest corner of the waste transfer station site (and may drain other areas as well). The sources of the other two outfalls are unknown, but based on their orientation, they may drain areas of the National Park Service Kenilworth Maintenance Yard located adjacent to the south shore of the Cove. Information recently obtained from DPW confirmed that there is a sixth outfall that discharges into the Cove. Referred to by DPW as POD-001, this

outfall is connected by an underground pipe to a bioretention pond located in the northwest corner of the waste transfer station site that collects roof drainage from the waste transfer station building and water collected in the drainage swale along the northern property boundary. The discharge from this outfall also is authorized under the MSGP. This outfall and the associated drainage pipe are depicted on **Figure 2-3**. See also photo 4B in **Appendix A**. Previously believed to be a culvert that conveyed surface flow under the Anacostia Riverwalk Trail, this outfall was not sampled during the Treatability Study field investigation. However, the results of periodic sampling of this outfall (as well as DPW POD-002) by DPW pursuant to the MSGP are provided at **Appendix C**.

Table 2-6: Summary of Outfalls Discharging to Cove

Outfall	Pipe Size	Invert Elevation*	Source
1	21" RCP	2.47'	DPW Transfer Station (POD-002)
2	54" CMP External, 36" DI Internal	-1.42'	Pepco (Facility Outfall 013)
3	12" RCP	2.60'	DPW Transfer Station (POD-003)
4	15" CMP	2.67'	Unknown
5	12" RCP	5.51' **	Unknown
6	12" RCP	not measured	DPW Transfer Station (POD-001)

*Elevations shown use the NAVD88 datum as identified in 2020 site survey.

**Site survey captured top of pipe elevation. Estimated invert shown here based on 12" diameter and assumed 3" pipe wall thickness.

In addition to the six discharge outfalls described above, there are four culverts that convey surface stormwater flow under the Anacostia Riverwalk Trail (two located just east of the Cove and two located just south of the Cove). Discharges from these culverts flow over the ground surface into the Cove. The culverts and associated discharge points are identified on **Figure 2-3** (see also **Appendix A**, Photo 5).

On April 2, 2021, a site visit was conducted to assess a silt pond located on the south portion of the KPS property near the Cove. Although no discharge from the pond was observed during the site visit, a riprap spillway was observed on the southwest side of the pond, which discharges to the north shore of the Cove. According to NPS, silt ponds were constructed on the north, east and south sides of the KPS to collect surface water runoff and allow for sedimentation prior to discharge to the adjacent surface water features during overflow events (NPS, 2008). The location of the south silt pond and riprap spillway are identified on **Figure 2-3** and photos are included in **Appendix A**.

To further assess potential contributions to the Cove from surrounding sites, the following additional sampling is planned: (i) stormwater discharge from DPW POD-001, (ii) soil and sediments on each side of the four culverts under the Riverwalk Trail, and within the spillway of the silt pond at the KPS site, and (iii) water and sediments from the silt pond. If feasible, stormwater samples may be collected from discharges from the culverts and spillway. Samples will be analyzed for PCB congeners as well as dioxins and furans. An addendum to this report will be prepared to document the results of this additional sampling.

2.2.3.1 Flow Data Collection

To support the end-of-pipe hydrologic analysis, flow data were collected at Outfalls 1, 3, and 4, using live flow transducers (vanEssen TD-Divers) installed at the end of the pipe and connected to data logger units (Nexsens X2 Data Loggers). These sensors monitored discharge rate and water level in each outfall every 15 minutes. Data collection commenced from these transducers on July 31, 2020.

At Outfall 5, the installation of a live flow transducer was inhibited by debris and the deteriorating state of the outfall conduit. Consequently, flow data were collected using a "bucket test" which estimated flow by timing

how long it took for the discharge to fill a 5-gallon bucket. These measurements were conducted three separate times during wet weather.

As shown in **Table 2-6**, Outfall 2 is a 36-inch pipe concrete-encased within a 54-inch exterior pipe. The 54-inch exterior pipe extends about two feet beyond the end of the inner 36-inch conveyance pipe, complicating the installation of any monitoring device. In addition, the invert of Outfall 2 made it difficult to customize an insert for a flow meter and a sediment trap. The invert of the discharge pipe is below the water level in the Cove and subject to tidal influences impeding the use of "bucket tests". As a result, no flow measurements were taken for this outfall as part of the TS field work. As discussed below, flow and drainage area data for this outfall were obtained from prior site evaluations

2.2.3.2 Outfall Stormwater Sampling

Stormwater grab samples were collected from five of the six outfalls discharging to the Cove during three storm events: July 22 (Outfalls 1, 2, 3, and 5), August 13 (Outfall 4) and October 29 (all five outfalls). At each outfall location, a decontaminated dipper was used to collect effluent from each pipe before it mixed with water in the Cove. Samples were then transferred to sample bottles and packed on ice for transport to Eurofins TestAmerica. Samples were analyzed for Total Suspended Solids (TSS) (method 2540-D), Total PCBs (method E1668C), Total Metals (method SW6020A), Total Polycyclic Aromatic Hydrocarbons (PAHs) (method SW8270D LL), and Total Petroleum Hydrocarbons – Diesel-Range Organics/Extended-Range Organics (TPH-DRO/ORO) (method SW8015D DRO).

2.2.3.3 Sediment Trap Installation

During the installation of flow transducers at Outfalls 1, 3, and 4, traps were placed at the ends of each outfall to collect sediment entrained in the discharge. The accumulated contents of each trap were collected on October 15 and sent to Eurofins TestAmerica for analysis. Sediment samples were analyzed for Total PCBs (method E1668C), Total Organic Carbon (method LKTOC), Total Metals (method SW6020A), DRO/ORO (method SW8015C DRO), Total PAHs (method SW8270D LL), and Total Polychlorinated Dibenzodioxins (PCDDs) (method SW8290A).

2.2.4 Sedimentation Study

The purpose of the sedimentation study was to collect information to further evaluate sedimentation characteristics of the Cove to support the assessment of depositional rates and verify the stability of amendments placed for purposes of EMNR as well as for capping system design.

As reported in the RI, radio-isotope dating of a sediment core collected in the Cove was completed to assess sediment stability and understand sediment deposition rates. Data from this core indicate a deposition rate of approximately 1 centimeter/year (cm/yr) in the Cove. As part of the Treatability Study sediment traps and mats were used to develop further understanding of the current rate and extent of the observed sediment deposition in the Cove.

Standard sediment traps were initially proposed to be placed inside the Cove to assess sediment accumulation over a set time period. However, upon investigation it was determined that insufficient water depths were present in the Cove to effectively submerge the standard sediment traps. Therefore, the proposed standard sediment traps were relocated to areas in the river to ensure that the minimum water depth requirements were met (water level at least 1 to 2 feet above the sediment traps at low tide). In the Cove, sediment mats were used in lieu of sediment traps. These mats can be used in shallow inter-tidal zones and are a modified approach that utilizes nylon carpet squares to capture sediment deposition.

2.2.4.1 Standard Sediment Traps

Three standard sediment traps (SEDTRAP-01, SEDTRAP-02, and SEDTRAP-03) were installed on June 16, 2020 at locations depicted in **Figure 2-4**. The sediment trap design was similar to that used for the New Bedford Harbor Superfund Site. Each trap consisted of a 1-gallon jug fitted with an entrance funnel and placed inside a 5-gallon bucket weighted by stones. Each sediment trap was placed on the river bottom and marked with a buoy tied to the bucket via rope.

The sediment traps were to be left in place for a period of a few weeks to three months to assess sediment accumulation. However, each of the sediment traps was displaced and required resetting during that period. On July 13, 2020, SEDTRAP-01 was found at a location downstream of where it was installed. On July 14, 2020, SEDTRAP-02 was found at location upstream of where it was installed. These two sediment traps may have been moved by intensive floods/flows or large floating trees/logs in the river. On July 14, 2020, both SEDTRAP-01 and SEDTRAP-02 were cleaned and reset at their original installed locations. On August 27, 2020, SEDTRAP-03 was found tangled with a large floating log and had been moved downstream. SEDTRAP-03 was cleaned and reset at the original installed location on August 27, 2020.

On September 17, 2020, each of the standard sediment traps was retrieved from the river bottom. Depth of accumulated sediment was measured, and sediment samples were collected for laboratory analysis. The samples were labeled with sample location, date and time, and packed on ice in a cooler submitted to Eurofins TestAmerica for analysis of total organic carbon, PCB Congeners, grain size and bulk density.

2.2.4.2 Sediment Mats

Nylon carpet square mats were installed at three locations (SEDMAT-01, SEDMAT-02, and SEDMAT-03) in the Cove, as depicted in **Figure 2-4**. SEDMAT-01 and SEDMAT-02 were installed on June 17, 2020, and SEDMAT-03 was installed on June 22, 2020. At each location, four 2×2-foot mats were placed on top of the sediment during low tide, with all four mats spaced evenly to form a circle of approximate eight feet diameter. Each mat was secured to the sediment via thin iron wire at four corners with no overlap with other mats. These mats have a surface roughness that limits loss of sediment from flooding events and are readily installed on irregular inter-tidal surface. The mats were left in place for approximately four months. Precaution was taken at all times to avoid disturbing the accumulated sediment on the mats during deployment.

On October 15, 2020, sediment thickness was measured and samples were collected at all three locations. Sampling was conducted during low tide while the sediment mats were fully exposed. Sediment thickness was measured on only one of the four mats at each location to avoid disturbing the other three mats. Using a metric ruler, nine separate measurements were collected to provide an average sediment thickness at each location. Following measurement collection, sediment samples were collected from the mat and submitted for laboratory analysis. The samples were labeled with sample location, date and time, and packed on ice in a cooler submitted to Eurofins TestAmerica for analysis of total organic carbon, PCB Congeners, and grain size.

In order to further evaluate sediment accumulation, one undisturbed sediment mat at each location was used to determine total sediment mass. Taking great care to avoid sediment loss, the entire accumulation of sediment on a single mat was deposited into laboratory provided pre-tared gallon sized jugs using a dedicated HPDE scoop. The filled jugs were labeled with sample location, date and time and submitted to Eurofins TestAmerica at ambient temperature to calculate total wet sediment weight and analyze percentage of solids.

In order to account for the sediment remaining in the nap on the surface of the cleared mats, the cleared mats were submitted to the laboratory to measure the remaining sediment. Prior to packing the mats for shipment to the lab, a spray bottled filled with distilled water was used to remove sediment adhered to the underside of the mat only. For each location, the sediment mat and scoop used to collect the sediment were placed in an oversized plastic bag labeled with sample location, date and time, and were submitted to Eurofins TestAmerica for analysis of rinsed sediment dry weight.

2.3 Seepage Measurements

Seepage velocity is a key parameter for cap design. The rate of seepage through the overlying sediment varies over time and with location based on the tidal fluctuations and groundwater discharge dynamics. Therefore, the objectives of seepage study are to:

1. Measure groundwater seepage velocity at three locations in the Cove; and
2. Measure change in groundwater seepage velocity after amendment of sediments with sorbent materials being tested as part of the treatability study (granular activated carbon [GAC], AquaGate®+PAC, and SediMite™)

The first objective of the study was achieved by installing seepage meters in the Cove. A laboratory study was performed to address the second objective.

2.3.1 Field Measurements

In order to measure groundwater seepage velocity into the overlying sediment, three seepage meters constructed by UMBC were deployed at three locations (SEEP-01, SEEP-02, and SEEP-03) in the Cove area, as depicted in **Figure 2-5**. The seepage meters for this study were based on the design described in USGS (2008) which is an adaptation of the original design by Lee and Cherry (1978). As illustrated in **Figure 2-6**, the meters were constructed out of 55-gallon plastic drums that were cut in half. The drums were fitted with a vent tube and a tube with a stopcock that was connected to a 4L seepage collection bag. A total of four seepage meters were fabricated (three for deployment in the field and a fourth one as backup).

The seepage meters were installed in the field by UMBC with assistance from AECOM field crew. Based on the available bathymetry data presented in the TSWP, all three sampling locations were expected to be under less than two feet of water at low tide. Therefore, installation was performed at low tide for easiest access to the sediment surface. The open side of the half drum was inserted into the sediment bed leaving about 6” above the sediment surface. The seepage meters were installed at the three proposed locations in the Cove as indicated in the TSWP. The meters were allowed to equilibrate for more than a week in the field before performing measurements.

To perform the seepage measurement, the 4L plastic bag was first filled with 1L of water and then attached to the collection tube. The stopcock in the collection tube was opened to allow the flow of water between the collection bag and the drum. After 0.5-1 hour of operation, the stopcock was closed and the collection bag removed. The change in volume of water in the bag was used to calculate the seepage volume. A net gain in the volume of water indicates flux into the River and a net loss in volume indicates flux into the subsurface sediments. The change in volume during the period the bag was attached is the volumetric rate of flow through the portion of the sediment bed covered by the drum (volume/time). The volumetric rate can then be divided by the area covered by the drum to express seepage as a flux velocity (distance/time).

Two sets of measurements were performed:

1. Multiple measurements during a rising tide cycle on October 18, 2020
2. Multiple measurements during a falling tide cycle on October 28, 2020

In addition to the seepage measurements, shallow sediment samples were collected at the three seepage meter locations on September 17, 2020 to assess the physical characteristics of the sediment, including grain size and bulk density to support the seepage meter data evaluation. Using a shallow push corer, sediment samples were collected from the top 1-foot of sediment at the seepage meter locations shown on **Figure 2-5**. The samples were packed in a cooler with ice and submitted to Eurofins TestAmerica for grain size analysis.

2.3.2 Collection of Cores for Laboratory Study

A laboratory study was designed to investigate the change in groundwater seepage velocity of sediments after amendment with sorbent materials being tested as part of the treatability study (GAC, Aquagate+PAC, and SediMite). This study was conducted using the sediment cores collected in the Cove. A total of eight undisturbed sediment cores were collected from the Cove to perform laboratory measurement of the change in seepage with sediment amendments. The eight cores were manually collected in the vicinity of the Seepage Meter 2 at low tide using pre-marked 2-inch PVC tubes, advanced to a depth of 1-foot. Laboratory seepage study is further described in **Section 3.3.2**.

2.4 Cove Ecological Survey

To evaluate possible restoration actions as part of the remedial alternatives to be considered in the FS, an assessment of current ecological conditions within the Cove was completed. This assessment included the collection of benthic community data in the Cove, review of existing benthic community data collected as part of the RI, and an ecological survey to obtain a detailed inventory of the plant community in areas where submergent/floating-leaved plant communities exist within the Cove.

2.4.1 Vegetation Survey

A vegetation survey was conducted by an AECOM wetland scientist on May 18, 2020 to characterize the baseline conditions of the vegetation community present in the Cove. There is currently a discrete area in the north-central portion of the Cove that appears to be slightly shallower and supports a submerged/floating-leaved plant community. A detailed inventory of the plant community within this portion of the Cove, in relation to survey information and surface water flow conditions, can assist in evaluating potential tidal marsh restoration alternatives that consider plant species, surface elevations, and substrate conditions.

In addition to the wetland vegetation identified in the Cove, a cursory review of multiple surrounding freshwater tidal marshes was also completed. The evaluation of surrounding tidal emergent marsh communities also provides biological analogs that inform design efforts for tidal marsh restoration.

2.4.2 Macroinvertebrate Community Survey

A focused infaunal macroinvertebrate survey was conducted to supplement the existing benthic infauna data, which were collected as part of the Benning RI. R.J. Diaz and Daughters (Diaz) of Ware Neck, VA and Normandeau Associates, Inc. (Normandeau) of Stowe, PA were retained to support the supplemental macroinvertebrate community survey within the Waterside Investigation Area. The survey was conducted using artificial substrates (Hester-Dendy samplers) to characterize the composition and diversity of the

community currently present in the Cove. The sampling methods are similar to those used in the ARSP RI. Locations that are permanently inundated were identified for deploying the Hester-Dendy samplers to ensure that the samplers remain submerged during low tide. On June 16, 2020, three Hester-Dendy samplers (HD-01, HD-03, and HD-04) were deployed in the vicinity of the Cove area and one sampler (HD-02) was deployed downstream of the Cove in the Waterside Investigation Area, as depicted in **Figure 2-7**. The Hester-Dendy samplers were secured to a cinder block with a rope. The cinder block was then lowered to the river bottom and tied to a T-post inserted into sediment about 2 feet away from the cinder block. The Hester-Dendy samplers were left in place to attract aquatic macroinvertebrate populations. During the deployment period, the Hester-Dendy samplers were checked regularly to ensure that they were submerged under water at all times.

On July 14, 2020, HD-02 and HD-03 were observed to be exposed during low tide. On July 16, 2020, these two samplers were retrieved, cleaned of deposited materials on the sampler plates, and re-deployed (using the same methods described previously) at new locations with deeper water columns approximately 10 ft away from the previous locations.

After a six-week deployment period, HD-01 and HD-04 were retrieved on July 29, 2020, and HD-02 and HD-03 were retrieved on August 27, 2020. Upon removal, each Hester-Dendy sampler was placed in a bag and preserved with 70% alcohol solution. The samplers were packed in a cooler on ice and shipped to Normandeau's taxonomic laboratory to perform taxonomic identification of invertebrates that colonized the Hester-Dendy samplers during the 6-week deployment period.

2.5 SEDflume Core Collection

Physical stability is critical to the overall effectiveness and long-term performance of remedies involving MNR, EMNR, and capping systems, as well as for habitat restoration. Physical stability of sediments is governed by a complex set of factors including, but not limited to, the underlying properties of the sediment, site hydrological conditions, amendment/cap material selection and design, depth of water, bathymetry, biological activity, and the presence of engineered site features such as armor stone and surface water channels. SEDflume is a laboratory testing apparatus that evaluates erosion as a function of applied shear stresses by measuring the response of the sediment bed (or amended bed) to erosive force. A SEDflume study was conducted to evaluate physical sediment stability both in the Cove and in the main channel of the Anacostia River in the vicinity of the site. Cove sediment stability was evaluated with and without carbon amendments.

A total of twenty cores (see **Table 2-7** below) were collected from 7 locations (SED5CSF, SED6C/R6-04SF, SED7BSF, SED8CSF, SED7DSF, SED7ESF, and SED9.5BSF) within the Waterside Investigation Area, as depicted in **Figure 2-8**. Five cores each were collected from two locations (SED7DSF and SED7ESF) within the Cove. These Cove cores were used to: (a) evaluate un-amended conditions; (b) evaluate amended conditions as a thin layer application (SediMite and AquaGate+PAC), (c) evaluate a sand/cap condition. Sediment properties of each core including grain size, bulk density, water content, and loss of ignition were also measured as part of the evaluation. Two cores each were collected from the remaining five locations (SED5CSF, SED6C/R6-04SF, SED7BSF, SED8CSF, and SED9.5BSF) within the Waterside Investigation Area. These cores were tested without amendments to assess erodibility under existing conditions. The locations of the cores were determined on the basis of sediment type and flow regime to ensure the results of the study are representative of the range of conditions in the Cove and the river, including the federal navigation channel immediately adjacent to the Cove.

Table 2-7: Sediment Core Collection and Experimental Design for SEDflume Study

Sampling Location	Total Number of Cores per Sampling Location	Amendment Types	Concentration or Thickness	Number of Cores
SED7DTS	5	None (site sediment only)	NA	1
		SediMite™	3%	1
		AquaGate®+PAC	5%	1
		Sand/ Cap Media	6 inches	1
		Reserve	TBD	1
SED7ETS	5	None (site sediment only)	NA	1
		SediMite™	3%	1
		AquaGate®+PAC	5%	1
		Sand/Cap Media	6 inches	1
		Reserve	TBD	1
Riverine Locations (SED5CSF, SED6C/R6-04SF, SED7BSF, SED8CSF, and SED9.5BSF)	2	None (site sediment only)	NA	5
		Reserve	TBD	5
			Total Number of Cores	**20**

The cores were collected by Integral Consulting Inc. (Integral) between June 1, 2020 and June 4, 2020 via push coring technique using specialized box cores (measuring 10 cm X 15 cm) that can be fully integrated into the SEDflume system in the laboratory. Coring locations were targeted in the field using global positioning system (GPS). All cores were collected manually from a boat, properly sealed and secured, and shipped in specialized containers which minimize disruption during shipping and handling.

During coring activities, turbidity monitoring was performed from a support boat to ensure no significant sediment was disturbed due to coring operations. The turbidity monitoring boat moved between an upstream location and a downstream location with each approximately 50 feet away from the coring location. GPS coordinates were collected for the upstream and downstream locations. Turbidity readings were recorded at both upstream and downstream locations before coring started, every 15 minutes during coring, and after coring ended. Three turbidity readings were recorded at each location at one foot below water surface, one foot above river bottom, and the midpoint in the water column, respectively. If the water column was less than 3 feet deep, only one reading was recorded at the midpoint. Turbidity was monitored using a U.S. Environmental PRO DSS YSI Multiparameter Meter, which was calibrated daily for turbidity prior to use and checked for calibration at the end of each day. Following completion of coring activities, the cores were shipped by Integral to its fixed sediment laboratory in Santa Cruz, California.

2.6 Sample Collection for Dewatering Testing

Should the remedial action call for removal of sediment in the Cove, mechanical dredging/excavation using temporary sheet piling or other system to isolate the River from the Cove may be used; however, it may be appropriate also to consider hydraulic removal as an alternative. Both methods will entrain water as the sediment is removed, hydraulic removal considerably more than mechanical removal. The excess water will

need to be removed in order to transport the sediment to a disposal facility. For mechanically dredged sediment, water removal will likely be accomplished by gravity draining followed by amendment. During this dewatering study, sediment samples were managed using a range of drying amendments following gravity draining. To evaluate dewatering of hydraulically dredged sediment, dewatering was conducted using gravity geotextile tubes following dilution of sediment to represent a hydraulic dredge slurry. These two sediment dewatering approaches are referred to as “mechanically dredged sediment solidification” and “geotextile tube gravity dewatering test”. This study targeted sediment collected from the upper 2 feet of the sediment column in the Cove.

Sediment samples were collected from two locations in the Cove (SED7C and SED7.5E) on June 5, 2020 to support the dewatering testing activities. These locations, shown on **Figure 2-9**, were selected based prior grain size analysis of Cove sediments and site inspection with the objective of capturing the full range of sediment properties (i.e., particle size distribution, percent solids) that are anticipated on the site. Samples were collected during low tide while the sediment surface was exposed. Using a clean shovel, samples were collected from the top 0 to 18 inches of sediment and placed in 5-gallon HDPE buckets. Two buckets of sediment collected from each location (four total) were shipped to KEMRON Environmental Services (KEMRON) for initial characterization testing and reagent drying evaluations. Two buckets of sediment collected from each location (four total) were also shipped to Infrastructure Alternatives, Inc. (IAI) to perform jar testing and geotextile tube gravity dewatering. Additionally, six 5-gallon carboys of surface water were also collected from the Cove and shipped to IAI on June 5, 2020 to support the geotextile dewatering study.

2.7 Sample Collection for Sequestration Testing

The results of the RI indicate that concentrations of several COPCs in sediment in the Waterside Investigation Area, particularly in the Cove, pose a potential risk to benthic receptors, and that concentrations of COPCs such as PCBs are higher in the Cove than elsewhere in the Waterside Investigation Area. Therefore, EMNR technologies that reduce the bioavailability of PCBs and other COPCs through sequestration will be considered in the FS.

Contaminant sequestration assessment data using site-specific sediment and a range of activated carbon (AC) products will be used in the evaluation and design of EMNR and active caps. The TSWP included bench-scale laboratory testing to: (a) determine the effectiveness of a variety of demonstrated AC amendments to sequester and to reduce the bioavailability of PCBs in sediment obtained from the Waterside Investigation Area, and (b) identify effective dose(s) of a subset of amendments. Various AC dry broadcast delivery products, such as SediMite and permeable AquaGate+PAC products were included in the assessment.

To support the evaluation of EMNR, UMBC was contracted to conduct a contaminant sequestration assessment using site-specific sediment and a range of AC products. On June 5, 2020, a composite surface sediment sample was collected from the BAZ (0 to 10 cm) at two locations in the Cove to determine the effectiveness of selected sequestration agents in bench scale studies. The two locations, SED7E and SED7.5E (**Figure 2-5**), represent the highest PCB surficial bulk sediment concentration (1,900 micrograms per kilogram [µg/kg] at SED7.5E) and dissolved phase PCB pore water concentration (10,000 picograms per liter [pg/L] at SED7E) within the Waterside Investigation Area. The sediment sample was packed in a cooler with ice and transferred to Dr. Upal Ghosh of UMBC following sample collection.

In addition, eight intact sediment cores were collected by UMBC on October 28, 2020 from the top foot within the Cove for laboratory studies to evaluate sediment hydraulic conductivity before and after application of AC amendment products. The cores were collected near Seepage Meter 2 (Seep-02), shown on **Figure 2-5**. The 2” diameter cores each measured one foot in length.

2.8 Deviation from TSWP

This section describes the deviations from the approved TS Work Plan during the implementation of field activities. Deviations are noted in **Table 2-8** below. The deviations were primarily the result of additional scope of work performed beyond the approved work plan.

Table 2-8: Deviations from TSWP

TSWP Scope	Deviations from Scope	Rationale
Four standard sediment traps were proposed to be installed within the Cove, as depicted in Figure 2-2 in the TSWP.	Three standard sediment traps were installed in the River outside the Cove and three sediment mats were installed within the Cove.	Due to the limited water depths in the Cove, the four locations proposed in the TSWP could not satisfy the condition for submerging the sediment traps at low tide. Therefore, sediment mats consisting of nylon carpet squares were installed as an alternative to the standard sediment traps. Three sediment mats were installed in the Cove. In addition, three standard traps were installed outside the Cove.
Three surface water stations were proposed to be installed to support the hydrodynamic analysis and design of the remediation.	In addition to the three surface water stations, installed as proposed in the TSWP, Acoustic Doppler Current Profilers (ADCPs) were deployed in four locations the Waterside Investigation Area to the west of the Cove.	ADCPs were deployed in the Anacostia River in order to measure water current velocities over a depth range in the river near the Cove. The deployment of ADCPs will provide additional current data to support hydrodynamic analysis.
The TSWP proposed to collect stormwater samples during a storm event from the three non-Pepco outfalls and from Outfall 013.	Two rounds of stormwater samples were collected from four non-Pepco outfalls (including two of the newly discovered outfalls) and Outfall 013 during storm events.	Additional outfalls were discovered in the Cove.
SEDflume location at R6-03SF could not be sampled.	Cores could not be collected at R6-03SF. Instead, core samples were collected at SED9.5BSF.	Refusals were encountered when coring at R6-03SF. After five attempts, this location was deemed as not feasible for taking a core sample. The two proposed core samples were collected from a new location at SED9.5BSF instead.
The TSWP proposed field measurement of groundwater seepage velocity at three locations in the Cove.	The treatability study also investigated the change in groundwater seepage velocity after amendment of sediments with sorbent materials (GAC, AquaGate®+PAC, and SediMite™)	For amendments containing bentonite clays (AquaGate and SediMite), there is potential for the bentonite component to significantly reduce the hydraulic conductivity of the surface sediments.

2.9 Residuals Management

Residuals and wastes derived from the field activities included the following:

- Disposable material during sampling activities, such as personal protective equipment, used sediment mats, plastic sheeting, plastic scoops, etc.
- Excess sediment leftover from sampling activities

- Decontamination water

All residuals and wastes were containerized in 5-gallon buckets and sent to Pepco's Benning Road Facility for proper disposal. Through October 31, 2020, three 5-gallon buckets were sent to the Benning Road Facility for disposal.

3 Results and Discussion

3.1 Overview

All planned treatability studies have been completed. This section presents the results of the treatability studies. The long-term tidal data collection is planned for one full year and was intended to continue beyond the treatability study phase to provide information necessary for remedy design. To date approximately six months of tidal data has been collected and will be discussed in this report. In addition, data collected under several of the studies described in this document will be further interpreted and analyzed as necessary to inform remedy evaluation during the Feasibility Study and Remedial Design phases of the project.

3.2 Hydrologic/Hydraulic, Sedimentation Assessment

3.2.1 Topographic and Bathymetric Survey

The topographic and bathymetric survey data were collected in May and June 2020 to verify the current grades in the Cove relative to tidal stages. The survey results are presented in **Figure 3-1**. Bathymetry appears to be similar to the 2013 bathymetry with the shallowest areas occurring immediately south of the Benning Road bridge and much of the navigational channel within the Waterside Investigation Area at the authorized depth of 8 ft. (or greater), except for a small portion of the channel in front of the Cove, where the depth is 6 ft. The perimeter of the Cove is at or above MLLW with the side slopes going up steeply to an elevation of 10 to 12 ft. The results of the topographic and bathymetric surveys will be used in evaluating target elevations for various remedy components.

3.2.2 Surface Water Flow Monitoring

Three surface water monitoring stations were installed in July 2020 to record water level (stage), temperature, and conductivity at locations distributed within the Study Area. These monitoring stations will remain in place until the summer of 2021 (for a total duration of approximately 12 months) to capture longer-term trends in tides and water levels over multiple seasons. This data will be incorporated into future analyses to improve understanding of the Cove's flow patterns under a variety of normal and extreme flow conditions. Velocity patterns will be paired with critical shear data from the SEDflume analysis (**Section 3.3**) to identify stability criteria for various remedy components.

The three surface water monitoring stations were equipped with a staff gauge and a recording pressure transducer (Van Essen CTD-diver) to monitor and record water surface elevation at each location. Each station was equipped with a Van Essen Diver-Link telemetry unit to record atmospheric pressure, and allow for daily data uploads and remote access from each station. As shown in **Figure 2-4,** two stations were installed in the Anacostia River: one approximately 1700 feet downstream of the Cove (Trans-01) and the other approximately 800 feet upstream of the Cove (Trans-02). A third was installed within the Cove (Trans-03).

To date, approximately 34 weeks of data has been collected from the three surface water monitoring stations (July 15, 2020 to March 31, 2021), with a 3-week gap in data collection. Transducers ran out of available memory on December 29, 2020 and were not serviced until January 21, 2021, at which point data collection resumed. **Figure 3-2** displays a sample week of observed data from the three transducers, including several days of normal tidal activity (August 1 to August 4, 2020) as well as a low tide storm surge

event (August 4 and August 5, 2020) caused by the impacts of Hurricane Isaias. It should be noted that Station Trans-03, located within the Cove, typically runs dry during low tide.

As can be seen in **Figure 3-2**, water levels at the three sites have slightly different baseline levels, likely based on the placement of each station and differences in hydraulic head at each site. To quantify these differences in hydraulic head, observed mean high tide (MHT) and mean low tide (MLT) were quantified for each site based on the 34 weeks of data collected. These levels are shown below in **Table 3-1**. MLT was not calculated at Station Trans-03 as the station typically runs dry during low tide.

Table 3-1: Observed MHT and MLT at Each Station, as of March 31, 2021

Station	Location	Observed MHT, ft*	Observed MLT, ft*
Trans-01	1700 ft Downstream of Cove	2.24	-1.03
Trans-02	800 ft Upstream of Cove	2.14	-0.88
Trans-03	Within Cove	2.71	Not Determined

*Elevations are shown in the North American Vertical Datum of 1988 (NAVD88)

3.2.3 Acoustic Doppler Current Profiler

The ADCP data collected as detailed below will be used in the future hydrodynamic model for the Cove area as needed. This data will also be useful for sediment scour calculations and to estimate sediment CAP thickness and armor size to minimize scour.

Current speed and direction distributions for the locations oriented toward the Cove (CHANN ADCP 2 and ADCP 3) are presented in **Figure 3-3**. Current speed and direction distributions for the locations oriented along the main channel (River ADCP 1 and ADCP 4) are presented in **Figure 3-4**. The measured near-bottom currents that have most influence in the transport of bottom sediments are presented below:

Table 3-2: Near-bottom Currents Summary

Location	Tide	Average (cm/s)	Maximum (cm/s)	Approximate Cardinal Direction	Direction of Average (°N)	Direction of Maximum (°N)
ADCP-1	Flood	15.2	38.8	Northeast	65	58
	Ebb	13.9	110.3	Southwest	246	246
ADCP 2	Flood	14.1	35.1	Northeast	63	59
	Ebb	17.0	109.5	Southwest	228	229
ADCP 3	Flood	13.2	33.2	Northeast	55	50
	Ebb	16.0	113.3	Southwest	227	229
ADCP-4	Flood	16.3	45.5	Northeast	56	47
	Ebb	17.2	85.4	Southwest	235	236

The larger currents flowing towards SW during two occasions were further investigated correlating with wind and tidal fluctuations. CHANN ADCPs shows two dominant current speed peaks, first peak on 8/4/2020 (8:30 to 23:50 hrs EDT) and the second peak on 9/10/2020 (14:30 to 23:50 hrs EDT) (**Figure 3-5**). These two peaks with larger currents flowing towards SW show correlation with strong wind towards south and southwest and a rain event in the area on these days.

3.2.4 Outfall Evaluation

3.2.4.1 Chemical Analysis of Discharge

Two full sets of wet-weather stormwater discharge samples were collected from five of the six outfalls in the Cove. Water samples were collected during three storm events: July 22, 2020 (Outfalls 1, 2, 3, and 5), August 13, 2020 (Outfall 4) and October 29, 2020 (five outfalls). The stormwater samples collected from each outfall were sent to Eurofins TestAmerica for analysis of metals (EPA 6020A and 7470A), TSS (EPA 2540D), PCB Congeners (EPA 1668C), PAHs (EPA 8270D), and DRO/ORO (EPA 8015D). Lab packages and results from these analyses are provided in **Appendix B** and presented in **Table 3-3**.

During the installation of flow transducers at Outfalls 1, 3, and 4, sediment traps were placed at the ends of each outfall to collect sediment entrained in the discharge. The accumulated contents of each trap were collected on October 15, 2020 and sent to Eurofins TestAmerica for analysis of the same parameters as those tested in the stormwater samples. The analytical results are presented in **Table 3-4** and lab packages are provided in **Appendix B**.

3.2.4.2 End-Of-Pipe Hydrology

The hydrology of each discharge point was evaluated to estimate the drainage area served by each outfall. The findings of this analysis may be used to estimate flow rates and velocities discharging from each conduit under various design storms to inform the design of the remedial action proposed for the Cove.

Outfall 1

Outfall 1 (DPW POD-002) drains into the Cove through a relatively large (21") reinforced concrete pipe (RCP). As noted above, this outfall drains the south side of the waste transfer station building, an area that is almost entirely covered with impervious surfaces. The DPW facility's Stormwater Pollution Prevention Plan (SWPPP) dated April 2021 provided information on the size of the drainage areas served by each of the Facility's outfalls. Based on the Site Map provided in the SWPPP, Outfall 1 (DPW POD-002) drains a catchment of approximately 4.05 acres. Over the course of observation for Outfall 1, spanning from July 30, 2020 to September 7, 2020, no dry weather flow was observed. The peak flow rate observed at Outfall 1 over the period of data collection was 55 cubic feet per second (cfs), observed during the August 4, 2020 storm event.

Outfall 2

Outfall 2 serves the Pepco Benning Facility under NPDES Permit DC000094 (listed as Outfall 013 under the permit). The conduit draining into the Cove is a large 36-inch ductile iron (DI) pipe, concrete-encased in a 54-inch corrugated metal pipe (CMP) sheath.

As noted above in **Section 2.2.3.2**, no flow measurements could be taken from Outfall 2 as part of the Treatability Study field work. However, the Benning Road stormwater system was subject to an extensive hydraulic and hydrologic modeling effort between February 2017 and January 2019, which included detailed modeling of the site using the USEPA Stormwater Management Model (SWMM) and installation of several stormwater best management practices (BMPs). Based on these analyses, Outfall 2 was found to serve a drainage area of 57.98 acres with a composite curve number of 92.4. The detailed SWMM model of Outfall 2 built between 2017-2019 can be leveraged during the remedial design of the Cove to design energy dissipation and flow management structures for the outfall (AECOM, 2019).

Outfalls 3 & 4

Outfall 3 (DPW POD-003) drains the roadway in the southwest corner of the DPW waste transfer site (and possibly other areas) into the Cove through a 12-inch RCP. As noted above, this outfall was recently

determined to be connected to drop inlets in the drive area at the southwest corner of the waste transfer station site (and may drain other areas as well). Based on the Site Map provided in the DPW facility's SWPPP, Outfall 3 drains a catchment of approximately 0.4 acres.

Outfall 4 drains stormwater from unknown areas into the Cove through a 15-inch CMP.

As shown in **Figure 3-6**, Outfalls 3 and 4 discharge stormwater under wet weather conditions; these outfalls flows during rain events at rates and times proportionate to those observed at Outfall 1. However, as observed during the storm events on August 4, 17, and 18, 2020, Outfall 3 appears to operate as a low-flow drainage conduit, and Outfall 4 appears to discharge significant flow only as an apparent "relief" to Outfall 3. When Outfall 4 is discharging, flow through Outfall 3 stops suddenly, indicating the possible presence of a pump system driving one or both outfalls. The peak observed flow rate at Outfalls 3 and 4 during the period of observation were 11.15 and 13.87 cfs, respectively.

In addition, Outfalls 3 and 4 appear to serve as dry weather flow discharge conduits, possibly discharging groundwater or other effluent to the Cove. During two extended periods of dry weather, from September 12 to 24, 2020 and October 18 to 21, 2020, discharge from Outfall 3 was observed to occur on a regular basis. Small bursts of flow were observed to occur consistently every 12-13 hours, possibly indicating the timed operation of a pump system or lift station. These discharges had an average peak flow rate of 5.2 cfs, with a maximum peak of 11.1 cfs. Further demonstrating a link between Outfalls 3 and 4, minor discharge from Outfall 4 was observed whenever dry weather flow through Outfall 3 exceeded 10 cfs. The September period of observed dry weather behavior is shown in **Figure 3-7**.

Further investigation is planned to better understand the sources of drainage to Outfalls 3 and 4 (under both wet and dry conditions) and their configuration and operation. Any additional information obtained will be documented in an addendum to this report.

Outfall 5

Outfall 5 drains into the Cove via a 12-inch RCP conduit embedded into an eroded portion of the Cove bank. As discussed in **Section 2.2.3,** a flow gage was not installed at the outfall due to poor conditions. Instead, three bucket tests were conducted during storm events on July 22, August 13, and October 29, producing flow rate observations of 0.006 cfs, 0.02 cfs, and 0.18 cfs, respectively. The drainage area of this outfall cannot be estimated using the Rational Method without discharge data taken across the full storm as there is no way of determining peak discharge rate. It can be surmised, however, that the drainage area served by Outfall 5 is likely to be small in comparison to other outfalls draining into the Cove.

Outfall 6

Recently discovered to be part of the DPW Transfer Station stormwater system, Outfall 6 (DPW POD-1) discharges to the cove via a 12" RCP conduit. As noted above, this outfall was recently determined to drain a bioretention pond located in the northwest corner of the waste transfer station site that collects roof drainage from the waste transfer station building. Based on the Site Map provided in the DPW Facility's SWPPP, Outfall 6 drains a catchment of approximately 2.73 acres.

3.2.4.3 Outfall Sediment Contribution

To calculate the magnitude of sediment contributed to the Cove by each outfall, annualized TSS loading was estimated based on the end-of-pipe hydrology analysis and the wet weather samples collected during the July 22, 2020, August 13, 2020, and October 29, 2020 storm events. Outfall 5 was not analyzed due to lack of data on its contributing watershed. However, due to the relatively small flows (when compared to the

other outfalls draining to the cove) and the low TSS levels detected in its discharge, the magnitude of sediment contribution from Outfall 5 is qualitatively assessed to be relatively low. Outfall 6 was not analyzed as no stormwater samples were collected from this discharge as part of this study.

To estimate sediment loading, an annualized approach based on drainage basin size and annual rainfall was taken. Between 2010 and 2019, the average annual rainfall total observed in Washington, DC was 42.51 inches. The total amount of rainfall converted to runoff in a given year was estimated using the Curve Number (CN) method as described in the United States Department of Agriculture's (USDA) Natural Resources Conservation Service (NRCS) Technical Release 55 publication (TR-55). The CN for the drainage basin served by the Pepco Benning Facility Outfall 2 was estimated to be 92.4. Following the TR-55 curve number runoff procedure, a one-inch storm produces 0.42 inches of runoff for a CN of 92.4. Similarly, a CN of 98 was estimated for DPW facility POD-001 and POD-003 based on aerial imagery provided in the facility's SWPPP. For a CN of 98, a one-inch storm produces 0.79 inches of runoff. . The results of this analysis are shown below in **Table 3-5**.

Table 3-5: Annual TSS Loading to Cove by Outfall

Outfall	Source	Average Annual Rainfall (in)	Drainage Area (acres)	Runoff Rate, %	Runoff (in)	Q (gal)	Sampled TSS (mg/L) by Sample Date		Average Sampled TSS, mg/L	TSS Loading (tons/yr)
							7/22, 8/13	10/29		
1	DPW POD-002	42.51	4.05	79.09	33.62	3,697,079	32	83	57.5	0.89
2	Pepco 013	42.51	57.98	42.10	17.90	28,174,80	29	54	41.5	4.88
3	DPW POD-003	42.51	0.40	79.09	33.62	365,144	98	640	369	0.56
4	Unknown	42.51	0.40	79.09	33.62	365,144	17	12	14.5	0.02
5	Unknown						17	180	98.5	

As it is difficult to combine Outfalls 3 and 4 to reflect the findings of the previous section, they are analyzed here as two outfalls serving the same size drainage basin. However, it is important to note that only stormwater flows from Outfalls 3 and 4 were sampled. Frequent dry weather flows were identified from these outfalls that likely come from a different source. These dry weather discharges therefore likely contribute additional TSS loading to the Cove. Additional study is planned to further evaluate the magnitude of sediment contribution from Outfalls 3 and 4, and the results will be documented in an addendum to this report.

3.2.4.4 Potential for Recontamination from Outfall Discharge

To assess the potential for PCB recontamination of the Cove, annualized PCB loading contributed to the Cove by each outfall was calculated using the same approach described in **Section 3.2.4.3** to estimate annualized TSS loading. The results of this analysis, as applied to the stormwater discharge sampling, are shown below in **Table 3-6**. It should be noted that the stormwater samples were not filtered prior to analysis for PCBs, so the data presented in **Table 3-6** represent a combination of dissolved PCBs and PCBs sorbed to TSS in the stormwater discharge.

Table 3-6: Annual Aqueous-Phase PCB Loading to Cove by Outfall

Outfall	Source	Average Annual Rainfall (in)	Drainage Area (acres)	Runoff Rate, %	Runoff (in)	Q (gal)	Sampled Total PCBs (ng/L) by Sample Date		Average Sampled PCBs (ng/L)	PCB Loading (g/yr)
							7/22, 8/13	10/29		
1	DPW POD-002	42.51	4.05	79.09	33.62	3,697,079	60	47	50	0.69
2	Pepco 013	42.51	57.98	42.10	17.90	28,174,808	19	48	33.5	3.54
3	DPW POD-003	42.51	0.40	79.09	33.62	365,144	16	97	56.5	0.08
4	Unknown	42.51	0.40	79.09	33.62	365,144	5.1	4.7	4.9	0.01
5	Unknown						3.1	35	19.05	

As discussed in **Section 2.2.3**, sediment traps were installed at Outfalls 1, 3, and 4 to capture sediment discharged by the outfalls. Sediment from these traps was tested for the same constituents as the

stormwater samples. Analytical results are included in **Appendix B** of this report and presented in **Table 3-4**. The results of this analysis are summarized below in **Table 3-7.**

Table 3-7: Annual Sorbed-Phase PCB Loading to Cove by Outfall

Outfall	Source	TSS Loading (tons/yr)	Sediment Total PCBs (sorbed) (ng/g)	Sorbed PCB Loading (g/yr)
1	DPW POD-002	0.89	57	0.05
3	DPW POD-003	0.56	22	0.01
4	unknown	0.02	150	0.003

It should be noted that the calculations presented in **Tables 3-6 and 3-7** are preliminary and are based on limited sample sets (two and one, respectively), and limited information regarding drainage areas. Measured concentrations for these events may or may not be representative of average annual effluent quality. Additional sampling data are needed to estimate long-term loading. Furthermore, NPDES sampling results provided by DPW indicate elevated TSS concentrations collected from Outfall 1 (DPW POD-002) on October 18, 2017 (1,200 mg/L) and September 7, 2018 (5,000 mg/L), and from Outfall 3 (DPW POD-003) on December 4, 2020 (2,600 mg/L), significantly exceeding the Benchmark Monitoring Concentration (BMC) of 100 mg/L associated with the MSGP. In addition, chemical oxygen demand, Ammonia as N, and several metals including aluminum, copper, iron, lead, and zinc also exceeded their respective BMCs by several orders of magnitude. Copies of available DPW stormwater monitoring reports are included as **Appendix C** along with tables summarizing analytical data for DPW POD-001 and DPW POD-002. As noted above, additional sampling is planned for discharges to the Cove. The results of this supplemental sampling and data evaluation will be documented in an addendum to this report.

3.2.5 Cove Sedimentation

3.2.5.1 In-Laboratory Testing

On September 17, 2020, the three standard sediment traps installed at the river bottom were retrieved for sediment sampling. Accumulated sediment was collected and submitted to Eurofins TestAmerica for analysis of TOC (Lloyd_Kahn_Mod – Total Organic Carbon), PCB Congeners (EPA 1668C), grain size (ASTM D422) and bulk density (ASTM D5057). The analytical results are presented in **Table 3-4** and lab packages are provided in **Appendix B**.

On October 15, 2020, sediment samples were collected at all three sediment mat locations for laboratory analysis and to quantify sediment accumulation. The sediment samples collected for chemical analysis were submitted to Eurofins TestAmerica for analysis of total organic carbon (Lloyd_Kahn_Mod – Total Organic Carbon), PCB Congeners (EPA 1668C), and grain size (ASTM D422). Samples collected for quantification of sediment accumulation, as described in **Section 2.2.4**, were submitted to Eurofins TestAmerica to calculate total wet sediment weight and percentage of solids (SM 2540G). Additionally, to quantify sediment remaining in the nap of mats, the sediment mats were submitted to Eurofins TestAmerica to calculate the rinsed sediment dry weight (SM 2540G). The sediment mass results are summarized in **Table 3-8** below. Lab packages and results are provided in **Appendix B**.

Table 3-8: Sediment Trap and Mat Results
Depth and Mass of Sediment Collected

Location ID	Original Date Installed	Date Reinstalled	Removal Date	Total Days Deployed	Sediment Thickness (mm)	Estimated Rate of Sedimentation (cm/yr)	Sediment Mass (kg, wet weight)	Sediment Mass (kg, dry weight)
SEDTrap-01	6/16/20	7/14/20	9/17/20	65	101.6*	57	NA	NA
SEDTrap-02	6/16/20	7/14/20	9/17/20	65	152.4*	86	NA	NA
SEDTrap-03	6/16/20	8/27/20	9/17/20	21	50.8*	88	NA	NA
SEDMAT-01	6/17/20	--	10/15/20	120	2.56**	0.78	2.38	1.05
SEDMAT-02	6/17/20	--	10/15/20	120	42.44**	13	13.9	3.76
SEDMAT-03	6/22/20	--	10/15/20	115	22.67**	7.2	9.49	3.17

* Approximate thickness in one sediment jar ** Average thickness of nine measurements per mat

The results from the in-river sediment traps suggest a depositional environment. While **Table 3-8** lists estimated rates of sedimentation of 57 to 88 cm/yr for these sediment traps, this should not be considered a measure of the actual sedimentation rates because they do not account for resuspension, bed transport, and equilibrium dynamics.

Within the Cove, the sedimentation dynamics and trapping capacity are difficult to quantify. However, the observed sedimentation patterns for the sediment traps located within the Cove indicate that the Cove continues to act as a sediment sink in places, particularly for particles suspended in flows entering the Cove via the outfalls. SEDMAT-1 is located near Outfalls 1 and 2 and as such will likely be directly subjected to any runoff related dynamics, which likely promote the suspension of sediments. SEDMAT-2 is located in the vicinity of the surface runoff discharge from Kenilworth Park South Landfill and in a more vegetated and quiescent area of the Cove and would therefore tend to see the highest measured sedimentation rates. SEDMAT-3 is fairly close, or within, part of the Cove's tidal conveyance network utilized during the transition between tides. This area would be subject to resuspension from the tide. Looking at the sedimentation rates in **Table 3-8**, the general relative differences between the three (3) sedimentation mats aligns with the dynamic characteristics of the different areas within the Cove where the mats were placed. However, because the processes affecting actual long term sedimentation occur over an extended period during different conditions (ex. spring rains, summer vegetation growth, etc.) the values presented in **Table 3-8** should be viewed as providing insight into whether that area of the Cove is depositional and how it would likely compare, in a relative sense, to the other areas. For example, storm runoff likely carries sediment over SEDMAT-1 where it then enters depositional areas located around SEDMAT-2 and SEDMAT-3 – depending on the tidal conditions at the time of the runoff.

Accurate sedimentation rate calculations require multi-year investigations where seasonal influences can be captured. This means that while both the sedimentation traps and mats help provide understanding into the depositional characteristics of the area, the radio-isotope core taken at SED7E is likely a more reliable basis for estimating actual long-term sedimentation rates. SED7E has a calculated sedimentation rate of 1.2 cm/yr based on the Cs-137 maximum in the high resolution core.

The analytical results presented in **Table 3-4** indicate total PCB concentrations ranging from 120 to 290 ppb in samples collected from the standard sediment traps installed in the River and from 730 to 1,500 ppb in samples collected from the sediment mats in the Cove. The grain size analysis indicates that the composition of sediments in the sediment traps and on the mats is fairly consistent and consists mostly of silt and clay particles (~63 to 80%). The variance in sediment volumes accumulated on the mats and the

PCB concentrations observed suggest localized reworking of existing sediments within the Cove potentially due to extreme flows experienced during major storms.

3.3 Seepage Measurements

3.3.1 Field Measurements

Groundwater seepage velocity is a critical parameter that determines the ultimate flux of pollutants from deeper sediments into the overlying water where negative water quality impacts may result. The exchange between groundwater and surface water can vary greatly among sites and can be both positive (from groundwater to surface) or negative (from surface water to groundwater). In addition, the seepage can also be a function of tidal stage for sites influenced by tidal cycling leading to a phenomenon often called tidal pumping where the flux is positive at low tide and switches to a negative value at high tide.

To perform the seepage measurement, a 4L plastic bag was first filled with 1L of water and then attached to the collection tube. The stopcock in the collection tube was opened to allow the flow of water between the collection bag and the drum. After 0.5-1 hr of operation, the stopcock was closed and the collection bag removed. The volume of water remaining in the bag was used to calculate the seepage volume. Two sets of measurements were performed:

- Multiple measurements during a rising tide cycle on October 18, 2020
- Multiple measurements during a falling tide cycle on October 28, 2020

The discharge velocity was calculated by dividing the discharge flow rate by the cross-sectional area of the seepage meter drum. Calculated discharge velocities are provided in **Table 3-9**. Field procedures and results are presented in **Appendix D**.

Table 3-9: Seepage Velocity Calculations

18-Oct	**Rising Tide**				
Seepage Meter 1		min	Vol	rate (ml/min)	notes
9:13 AM	10:02 AM	49	0	0.00	
10:02 AM	10:55 AM	53	-100	-1.89	
12:29 PM	1:02 PM	33	160	4.85	
1:04 PM	2:05 PM	61	-160	-2.62	
2:07 PM	2:55 PM	48	0	0.00	
		244	-100	-0.41	
Seepage Meter 2					
10:49 AM	11:58 AM	69	0	0.00	
12:02 PM	12:38 PM	36			vented air
12:42 PM	2:00 PM	78	20	0.26	
2:02 PM	2:50 PM	48	-20	-0.42	
		231	0	0.00	
Seepage Meter 3					
10:55 AM	12:13 PM	78	-275	-3.53	
12:15 PM	1:12 PM	57	0	0.00	
1:14 PM	2:13 PM	59	-40	-0.68	
2:15 PM	3:04 PM	49	60	1.22	
		243	-255	-1.05	
Average of 3 (ml/min)				**-0.49**	
Area of drum =	2721.481	sqcm			
Darcy velocity	**cm/min)**			**-0.00017873**	
	cm/d			**-0.26**	

28-Oct	**Falling Tide**			
Seepage Meter 1		min	Vol	rate
8:04 AM	8:34 AM	30	300	10.00
8:42 AM	9:46 AM	64	100	1.56
9:48 AM	10:35 AM	47	200	4.26
10:38 AM	11:30 AM	52	128	2.46
		193	728	3.77
Seepage Meter 2				
8:07 AM	8:40 AM	33	0	0.00
8:44 AM	9:50 AM	54	220	4.07
9:53 AM	10:45 AM	52	80	1.54
10:48 AM	11:07 AM	19	280	14.74
		158	580	3.67
Seepage Meter 3				
8:12 AM	8:47 AM	35	400	11.43
8:50 AM	9:57 AM	67	140	2.09
9:58 AM	10:50 AM	52		0.00
10:51	11:39 AM	48	0	0.00
		202	540	2.67
Average of 3 (ml/min)				**3.37**
Area of drum =	2721.5	sqcm		
Darcy velocity	**cm/min**			**0.001239**
	cm/d			**1.78**

As shown in **Table 3-9**, the average seepage velocity was -0.26 centimeters/day (cm/d) during a rising tide and 1.78 cm/d during a falling tide. These seepage velocity measurements will be used in conjunction with previously collected pore water data to calculate PCB flux.

3.3.2 Laboratory Study

The RI determined that groundwater discharge is not a significant pathway for the discharge of contaminants to the River. However, groundwater flow into the river could drive contaminant flux from deeper contaminated sediments into overlying shallower sediments and surface water. To better understand changes in groundwater discharge to the Cove from different remedial options, UMBC was contracted to conduct an in-laboratory study to evaluate hydraulic conductivity of shallow Cove sediments before and after application of the amendments discussed above (granular AC, SediMite and AquaGate+PAC). Thin layer placement of granular material like sand may not have a major impact on hydraulic conductivity and discharge unless additional compaction takes place due to the weight of the placed material; however, amendments containing bentonite clays (AquaGate+PAC and SediMite) have the potential for the bentonite component to significantly reduce the hydraulic conductivity of surface sediments mixed with amendments. Bentonite is a swelling clay and is often used in applications where a reduction in hydraulic conductivity is desired. This can be beneficial from a remedy perspective if the groundwater is redirected away from the treated sediment layer, reducing the overall flux of groundwater through the contaminated zone in sediments.

Eight intact sediment cores were collected on October 28, 2020 from the top foot of sediment in the Cove to perform laboratory measurements of the change in seepage with sediment amendments applied. The simulated discharge flow setup was constructed in the laboratory using the 1-foot length, 2” diameter cores collected from the Cove. An adjustable height constant head tank was used to create a discharge velocity through each of the intact cores matching the discharge velocity measured in the field. The laboratory setup is illustrated in **Figure 3-8** and procedures are described in **Appendix D**. Three trials were conducted on the untreated cores to determine seepage rates prior to the addition of amendments. Following the initial trials, the amendments (granular AC [GAC], SediMite [SM] and AquaGate+PAC [AG]) were each added to two cores and allowed 14 hours to stabilize prior to testing seepage rates. A second set of measurements was collected from the amended cores two days following amendment application. The discharge was measured by collecting water flow from the top of each core over a fixed period of time. The results are provided in **Table 3-10** below.

The laboratory seepage measurements indicate that the amendments will likely reduce hydraulic conductivity through the native sediments in the Cove. The study showed seepage rate reductions ranging from 25 – 78% compared to untreated sediments. Reductions were observed for all three amendment products; however, it is possible that after a longer period of hydration and swelling of the bentonite clay, further reductions in seepage may be observed for the bentonite clay-containing amendments.

Table 3-10: Laboratory Seepage Measurement Before and After Amendment Application

REPLICATE 1	Before Amendment			14 hr After Amendment			
	flow (ml/min)	StdErr			flow (ml/min)	StdErr	% reduction
1A	80.0	0.0		1A (GAC)	36.2	0.4	55%
3A	168.3	3.1		3A (AG)	97.7	1.0	42%
4A	310.0	8.2		4A (SM)	158.3	1.0	49%
				2 days After Amendment			
					flow (ml/min)	StdErr	% reduction
				1A (GAC)	54	0	33%
				3A (AG)	88	0	48%
				4A (SM)	142	0.71	54%
REPLICATE 2	Before Amendment			14 hr After Amendment			
	flow (ml/min)	StdErr			flow (ml/min)	StdErr	% reduction
2B	5.5	0.015		2B (GAC)	1.5	0.015	73%
3B	10.5	0.015		3B (AG)	4.8	0.041	54%
4B	22.3	0.041		4B (SM)	16.7	0.093	25%
				2 days After Amendment			
					flow (ml/min)	StdErr	% reduction
				2B (GAC)	1.2	0	78%
				3B (AG)	3.2	0.014	69%
				4B (SM)	13.0	0.040	42%

3.4 Cove Ecological Survey

A summary of the Cove vegetation survey and the macroinvertebrate community survey is presented in the following sections.

3.4.1 Cove Vegetation Survey

A detailed vegetation survey within the Cove was completed on May 18, 2020, to characterize the baseline conditions of the vegetation community present in the Cove. Distinct areas were delineated based on the dominant plant species within each area. Four areas dominated by different plant species (i.e., vegetation areas) were delineated within the Cove and their boundaries are identified on **Figure 3-9**.

Aerial cover was estimated for each plant species identified within each vegetation area. For the purposes of this survey, dominant plant species are defined as plant species that account for at least 20 percent of the total aerial cover within a vegetation area. The scientific name, common name, and approximate percent aerial cover of each species within the four vegetation areas surveyed is identified on the *Cove Vegetation Summary Table* inset on **Figure 3-9**. The four vegetation areas surveyed within the Cove, from the lowest to highest elevations, are described below.

Vegetation Area 1 (VA 1) is freshwater tidal marsh consisting of a nearly monotypic stand of *Nuphar advena* (yellow pond-lily). VA 1 occupies the lowest elevation within the Cove that is vegetated (-1.5 to 2 ft). Areas within the Cove that are at lower elevations than this *Nuphar advena* stand generally consist of unvegetated tidal mudflats.

Vegetation Area 2 (VA 2) is a freshwater tidal marsh that is dominated by *Iris pseudacorus* (pale-yellow iris) and *Peltandra virginica* (green arrow-arum). Other associated species present within VA 2 include *Persicaria maculosa* (spotted lady's-thumb), *Pontederia cordata* (pickerelweed), and *Hibiscus moscheutos* (crimson-eyed rose-mallow). VA 2 is mostly located at a slightly higher elevation than VA 1 (0 to 2 ft).

Vegetation Area 3 (VA 3) is a freshwater tidal marsh that is dominated by *Persicaria maculosa*, with other associated species including *Commelina virginica* (Virginia dayflower), and *Iris pseudacorus*. VA 3 is mostly located at a slightly higher elevation than VA 2 (0 to 2.5 ft).

Vegetation Area 4 (VA 4) is a freshwater tidal marsh that is dominated by *Persicaria maculosa* and *Iris pseudacorus*. Other associated species present within VA 4 include *Persicaria maculosa*, *Pontederia cordata*, and *Hibiscus moscheutos*. VA 4 is located at a similar elevation to VA 3 (0 to 3 ft).

In addition to the wetland vegetation identified in the Cove, a cursory review of multiple surrounding freshwater tidal marshes was also completed on May 18, 2020. These included the Kenilworth Marsh located approximately 1 mile upstream of the Cove, which is fed by the Anacostia River, and two freshwater tidal marshes located within 0.5 mile downstream of the Cove, along the east bank of the Anacostia River. The dominant and associated species identified in Vegetation Areas 1-4 were also observed in these nearby freshwater tidal marshes both upstream and downstream, including nearly monotypic stands of *Nuphar advena*. Dominant species identified in the nearby upstream and downstream freshwater tidal marshes that were not observed in the Cove include *Typha angustifolia* (narrow-leaf cattail) and *Phragmites australis* (common reed).

3.4.2 Macroinvertebrate Community Survey

A macroinvertebrate community survey was conducted at four locations in the Waterside Investigation Area in June through August 2020. This survey was conducted using Hester-Dendy samplers and the results are based on the numbers and identification of macroinvertebrates that colonized the samplers during their six-week deployment in the river. The macroinvertebrate community survey results are presented in **Appendix E**.

A total of 1,030 individuals representing 36 taxa were collected at the four Hester-Dendy sampling locations in July-August 2020. The highest numbers of taxa were identified at location HD04 (20 taxa), which is located in the Cove, and the lowest numbers of taxa were identified at locations, HD01 and HD02 (7 taxa were identified at each location), which are outside of the Cove. The results of this study found the macroinvertebrate taxa to be typical of tidal freshwater systems within Chesapeake Bay, which are well adapted to high levels of turbidity and soft unstable substrates, and dominated by oligochaetes and chironomid insect larvae.

The results of this survey are comparable to the results of macroinvertebrate community surveys conducted in 2016 and 2017 to support the ARSP Baseline Ecological Risk Assessment (BERA) and the Benning Road site BERA, respectively. This survey was conducted using the same methodology used for the macroinvertebrate community survey conducted for the ARSP as described in the ARSP RI Report (Tetra Tech, 2019). The ARSP BERA sampling locations in 2016 do not overlap with the four 2020 sampling locations in the Waterside Investigation Area but are located upstream and downstream of the area. However, the major taxa and community composition collected in 2016 for the ARSP BERA are similar to the taxa collected during this study in 2020. In addition, the macroinvertebrate community survey conducted in 2017 for the Benning Road BERA based on sediment grab samples collected within and outside of the Cove found similar numbers of taxa and community composition to this 2020 study.

3.5 Sediment Stability Assessment

Integral was subcontracted by AECOM to conduct a SEDflume study to evaluate the physical sediment stability within the Waterside Investigation Area. As described in **Section 2.5**, sediment cores were collected from both the Cove (SED7DSF and SED7ESF) and in the main channel of the Anacostia River in the vicinity of the site (SED5CSF, SED6C/R6-04SF, SED7BSF, SED8CSF and SED9.5BSF); sample locations are presented in **Figure 2-8**. Two cores were collected from each of the five main channel locations for evaluation of unamended sediment and five cores were collected from each of the 2 Cove locations for evaluation of unamended sediment, sediment with carbon amendments (SediMite and AquaGate+PAC) and sediment with sand/cap media applied.

3.5.1 Core Management Prior to SEDflume Testing

Upon receipt of the box cores at the laboratory, two cores from each of the seven locations were inspected and designated as A and B. Core A was archived and core B was tested in an unamended condition. The remaining three cores collected from each of the two Cove locations were designated as cores C, D and E and were amended with SediMite, AquaGate+PAC and sand cap plus GAC, respectively, as described in detail in **Appendix F**. The amount of each respective amendment used was calculated to achieve the target carbon content percentages cited in **Table 2-7**. AECOM calculated the amount of each material to be added based on the carbon content of each amendment and advised the lab of the thickness of material that corresponded to the carbon target. Integral administered that material first by performing a trial placement of material into an empty core barrel to ensure the proper amount of material was used. This was done because some of the amendments change physical condition when hydrated and it was clear that measuring the delivered thickness after hydration would be difficult. The material applied to each empty core barrel was then administered to the assigned cores through standing water. Sufficient time was given to allow the standing water to become visually clear. At that point, for cores C and D, a fine probe was used to "mix" the amendment into the underlying sediment material to simulate the contact the amendment may achieve with the sediment through bioturbation. The cores were then allowed to "settle" for 28 days. Core E – the one treated with carbon amended sand – was allowed to rest for 28 days but no mixing with the probe was conducted.

3.5.2 SEDflume Apparatus and Test Procedure Summary

A photograph of the SEDflume apparatus is shown as Figure 2 in **Appendix F**. It is a straight flume with an open area through which a rectangular cross-sectional core containing sediment can be inserted. The core measures 10X15 cm in cross section and is placed on the hydraulic jack shown in the figure. The jack is raised vertically until the core section is inserted into the flume and flush with the flume duct bottom. The flume is then filled with site water; a ball valve regulates the water that enters the flume (thereby controlling the flowrate over the sediment). The rate of flow through the duct is incrementally increased over time. Each rate results in a shear stress over the sediment core with the potential to cause erosion; each shear stress is applied for a minimum of 20 seconds and a maximum of 10 minutes; no more than 2 cm of sediment was allowed to erode during each cycle. The sediment core is continually raised using the hydraulic jack so that the top of the core was maintained flush with the flume floor. A total of five shear stresses are applied to generate a plot of erosion as a function of shear stress. The selected shear stresses applied consider the range of potential flows in the vicinity of the River and Cove from which the sediment cores were extracted.

3.5.3 SEDflume Test Conditions

As noted above, the flow sent into the flume corresponds to a shear stress which has the potential to erode sediment from the core. How much sediment is eroded is a function of the bulk density of the sediment and

the applied shear stress. For each core, the erosion (in cm/s) is measured as a function of applied shear stress and recorded against the corresponding core depth interval. Shear stresses applied started at 0.1 Pascal (Pa) and then doubled successively until five intervals were tested. The stresses included 0.1, 0.2, 0.4, 0.8, 1.6, 3.2 and 6.4 Pa. The information is recorded in a set of curves which, when compared to the core profile, can show visual evidence that correlates to marked changes in erodibility. The comparison of erodibility with depth within each core reveals how erodible the core is. Additionally, prior to beginning each rate cycle, a small sample of sediment is removed from the surface to obtain grain size data so it is possible to correlate the erosion rate to grain size and then assess how the erodibility of the core changes with depth.

3.5.4 SEDflume Testing Results

Appendix F presents a comprehensive summary of all test results including:

- Plots of erosion rate as a function of applied shear test for five (5) intervals;
- Photos of core cross sections compared to erosion rates measured as a function of shear;
- Bar graphs of the erosion rate ratio within each core by interval depth; and
- Measured grain size as a function of depth.

Additionally, photographs were taken within each core where there was evidence of benthic activity, unique sediment observations and other phenomena.

Cores from the River are compared to one another as well as unamended cores from the Cove; amended cores in the Cove are compared to unamended cores from the Cove. During remedial design, the information obtained from SEDflume analysis will be used together with data obtained from the monitoring station transducers and subsequent modeling to determine if each core location is net erosional, net depositional or transitional, and further, if the application of carbon-amended cover is stable in each environment as well as the comparable stability of each cover. These analyses will be done at a future date as part of the remedy design. Observations that can be made at this time from summary of test results are as follows:

- While Riverine cores vary to some degree from location to location, the erodibility relative to applied shear stress are similar both at the surface and with depth suggesting that along the Anacostia River in the vicinity of the Cove, there is no substantial difference in sediment stability.
- All Riverine cores show evidence of increased shear resistance with depth likely due to consolidation of underlying sediment; however, no cores show evidence of a transition from depositional sediment to pre-anthropogenic material; one core contained non-biodegradable human waste (plastic bandaid) at depth confirming the area from which the core was collected is recent anthropogenic deposition.
- While there were differences in the erodibility of the various amended cores, there was no substantive difference between the two Cove core locations.
- Amendments added to the Cove sediment generally decreased the erodibility of the material; this was particularly evident in the carbon-amended sand cores where the addition of 6” of sand consolidated the core material and increased density and erosion resistance.
- In both the AquaGate+PAC and SediMite amended applications, both Cove core locations showed evidence of biological activity (bioturbation) and transport of carbon into underlying sediment.

- AquaGate+PAC, which has a range of particle sizes that extend from sand- to gravel-size, created a more erosion resistant cover relative to SediMite. The bentonite component of this material created a cementitious gel which bound the particles and when the erosional forces were increased, the layer was observed to lift from the surface. The flowrate that created this force is expected to be significantly higher than those encountered in the River or Cove hydraulic system.
- The amended sand layer appeared to create a more erosion resistant condition at the intersection of the carbon sand and the sediment. Close observation noted that at the interface of the amended sand and sediment there was evidence of a secreted material that may be related to benthic mortality. Benthic activity appeared to cease after placement of the amended sand potentially due to the creation of an anoxic environment and/or the consolidation and densification of the underlying sediment. The net impact is a very erosion-resistant condition at the interface due to the combination of these factors. The interface depth was orders of magnitude less erodible than native sediment.

Integral Consulting provided a series of graphs that compared the unamended Cove cores to amended cores identifying critical shear stress to depth. This figure is reproduced in **Figure 3-10**. Other physical characteristics were also compared; plots are included in **Appendix F**. These plots illustrate some of the observations made above.

3.6 Sediment Dewatering Tests

3.6.1 Sediment Solidification/Stabilization Tests

Bench scale laboratory investigation was conducted under subcontract to KEMRON Environmental Services, Inc. located in Atlanta, Georgia. The two representative and independent sediment samples collected within the upper 1 to 2 feet from the Cove were sent to the laboratory for testing. After receiving the buckets of sediment from the field, each bucket/sample was logged, recording the consistency, color, and odor of each sample. Each sample was photographed in an as-received condition then homogenized in the shipping bucket until visually uniform. A subsample was collected for preliminary physical analyses consisting of the following: solids content/water content; total organic content, density and grain size distribution (including hydrometer). Additionally, aliquots of the samples were submitted to Eurofins TestAmerica for analysis of PCB Aroclors (EPA 8082) and PCB Congeners (EPA 1668C). Photographs and as-received material characterization parameters are provided in **Appendix G** (Table 1). In summary, both Cove samples were similar in grain size and according to ASTM D2487 classified as a silty sand (ML). The unit weight, however, varied as did the moisture content. These differences gave rise to differing dewatering behavior as the higher moisture content, lower unit weight (sample SED7.5E) failed the free moisture test (EPA Method 9095) while the slightly lower moisture, higher unit weight sample (SED7C) passed the free moisture test. A summary of this initial material characterization is provided in **Table 3-11** below. The PCB analytical results are presented in **Table 3-12** and the lab reports are included in **Appendix B**.

An Exelon Company

Table 3-11: Untreated Material Characterization

Testing Parameter	Test Method	Unit	Untreated Material	
			SED7C-DEW	SED7.5E-DEW (0-18')
Particle Size Distribution	ASTM D422			
Gravel		%	0.1	0.7
Sand		%	18.5	16.0
Silt		%	66.3	68.4
Clay		%	15.1	14.9
Sample Description (1)	ASTM D2487		Brown silt with sand	Grayish Brown silt with sand
Sample Classification (2)	ASTM D2487		ML	ML
Moisture Content	ASTM D2216			
Average ASTM Moisture Content		%	78.79	114.58
Average Percent Solids		%	55.93	46.62
Unit Weight	ASTM D7263			
Average Bulk Unit Weight		pcf	93.3	84.5
Paint Filter	EPA Method 9095		PASS	FAIL

Notes:
(1)Sample color determined by the Munsell Soil Color Charts.
(2) Sample classification based on the Unified Classification System.
%= Percent
pcf = Pounds per cubic foot

To reduce moisture content, a 2-step reagent study was performed. The first step included evaluating a range of amendments to observe the impact each had on the sediment matrix. This first round assessment was applied to SED 7.5E because it failed the paint filter test. During the first round, several amendments were applied including Type I Portland Cement (PC), lime kiln dust (LKD), Calciment™ and ZapZorb ™. For each amendment, a range of reagent addition rates were applied which varied based on the amendment. **Table 3-13** provides a summary of the experimental mixes originally derived.

Table 3-13: Round 1 Experimental Mixtures Observations

KEMRON Sample No.	Untreated Material	Reagent Type	Reagent Addition % by Wet Soil Wt.	Pocket Penetrometer (TSF)	Pocket Penetrometer (TSF)	VOC Monitoring (ppm)
				24 hour	4 Day	24 hour
EXP-001	SED7.5E-DEW (0-18')	Type I Portland Cement	2	0	0	3.1
EXP-002	SED7.5E-DEW (0-18')	Type I Portland Cement	4	0	0	7.2
EXP-003	SED7.5E-DEW (0-18')	Type I Portland Cement	8	0	0	5.4
EXP-004	SED7.5E-DEW (0-18')	Lime Kiln Dust	5	0	0	5.8
EXP-005	SED7.5E-DEW (0-18')	Lime Kiln Dust	7.5	0	0	3.8
EXP-006	SED7.5E-DEW (0-18')	Lime Kiln Dust	15	0	0	4.4
EXP-007	SED7.5E-DEW (0-18')	ZapZorb	0.5	0	0	3.2
EXP-008	SED7.5E-DEW (0-18')	ZapZorb	1.5	0	0	3.0
EXP-009	SED7.5E-DEW (0-18')	ZapZorb	3	0	0	2.8
EXP-010	SED7.5E-DEW (0-18')	Calciment	2	0	0	1.7
EXP-011	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	0.25	0	0	1.5

Each mix was observed and photographed immediately after mixing and the headspace for each mix was monitored for VOCs. A photographic log of all of these mixtures is included in **Appendix G**. Headspace monitoring was conducted by inserting the amended sediment immediately after it was blended into a sealed plastic bag and then measuring off gassing. Both strength (using a pocket penetrometer) and VOCs

were monitored after 24 hours; and strength alone was measured after 4 days. Those results showed that low concentrations of VOCs were emitted for each amendment and that none of the experimental mixtures developed any measurable strength over the 4-day cure period.

Despite the unmeasurable strength gain observed during the initial round of amendment testing, amendment testing displayed substantively different visible moisture/solids conditions as the result of amendment addition. In particular, the ZapSorb™ was observed to produce a dry soil-like appearance compared to other admixtures even at very low doses (doses in the initial mix development ranged from 0.5-3% wet weight of sediment). Based on these results, several additional test blends were made combining ZapZorb™ at low dosages with low dosages of Portland Cement for strength as a blended reagent mixture. The results are shown on **Table 3-14**. These data showed that blending of ZapZorb™ and PC did not produce increased strength. This second round also looked at higher addition rates of Calciment™ to determine if the initial round trial was too low. Testing confirmed that Calciment™ at higher dosages did not increase strength.

Table 3-14: Round 2 Experimental Mixtures Observations

KEMRON Sample No.	Untreated Material	Reagent Type	Reagent Addition % by Wet Soil Wt.	Pocket Penetrometer (TSF)	Pocket Penetrometer (TSF)
				24 hour	4 Day
EXP-001	SED7.5E-DEW (0-18')	Type I Portland Cement	2	0	0
EXP-002	SED7.5E-DEW (0-18')	Type I Portland Cement	4	0	0
EXP-003	SED7.5E-DEW (0-18')	Type I Portland Cement	8	0	0
EXP-004	SED7.5E-DEW (0-18')	Lime Kiln Dust	5	0	0
EXP-005	SED7.5E-DEW (0-18')	Lime Kiln Dust	7.5	0	0
EXP-006	SED7.5E-DEW (0-18')	Lime Kiln Dust	15	0	0
EXP-007	SED7.5E-DEW (0-18')	ZapZorb	0.5	0	0
EXP-008	SED7.5E-DEW (0-18')	ZapZorb	1.5	0	0
EXP-009	SED7.5E-DEW (0-18')	ZapZorb	3	0	0
EXP-010	SED7.5E-DEW (0-18')	Calciment	2	0	0
EXP-011	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	0.25	0	0
EXP-012	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	5 / 2	0	0
EXP-013	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	10 / 4	0	0
EXP-014	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 3	0	0
EXP-015	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	1 / 3	0	0
EXP-016	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 5	0	0
EXP-017	SED7.5E-DEW (0-18')	Calciment	5	0	0
EXP-018	SED7.5E-DEW (0-18')	Calciment	7.5	0	0
EXP-019	SED7.5E-DEW (0-18')	Calciment	10	0	0

This information was used to conduct a third round of evaluation which evaluated the effectiveness of a 2-step amendment addition of ZapZorb™ and PC added (in that order) to assess if phased reaction might be advantageous to strength gain. This round also assessed PC addition at rates higher than 8% by weight (demonstrated in the initial round to show poor strength gain) raising the PC addition to 15%. Results demonstrated strength gain with PC at 15% but the 2-step amendment addition process showed no substantial benefit.

On the basis of this information, a final set of amendment admixtures was generated. **Table 3-15** below summarizes the final set of amendments used along with the strength gain results observed. All blends passed EPA Method 9095 but only those that contained PC gained strength. An addition rate of 10% PC by weight proved to yield early strength gain believed to be sufficient should sediment disposal require it. Sediment from both locations – SED7.5E and SED7C – were evaluated at these amendment ratios. After curing 7 days, samples were submitted to Eurofins TestAmerica for leachability testing, waste characteristics and analysis of PCB Aroclors. Compared to the pre-solidification sample results, PCB

concentrations decreased by 20 to 30%. The analytical results are presented in **Table 3-12** and the lab reports are included in **Appendix B**.

Table 3-15: Final Round of Reagent Drying Evaluations
Mixture Designs, VOC Monitoring, Pocket Penetrometer and Paint Filter Testing

KEMRON Sample Number	Untreated Material Type	Reagent Type	Reagent Addition % by Wet Soil wt.	VOC Monitoring (ppm)		Pocket Penetrometer (tsf)				Cure Day	Paint Filter Testing
				At Mixing	1 hour	1 Day	3 Day	5 Day	7 Day		Pass/Fail
0746-001	SED7C-DEW	Zapzorb	0.5	0.0	0.2	0.00	0.00	0.00	0.00	7	Pass
0746-002	SED7C-DEW	Zapzorb/Type I Portland Cement	0.5/10.0	0.7	0.7	1.00	2.50	3.50	4.00	7	Pass
0746-003	SED7C-DEW	Type I Portland Cement	10.0	0.2	2.0	0.50	2.00	3.00	3.50	7	Pass
0746-004	SED7C-DEW	Type I Portland Cement	15.0	1.4	1.6	2.00	>4.5	>4.5	>4.5	7	Pass
0746-005	SED7.5E-DEW	Zapzorb	0.5	0.4	0.2	0.00	0.00	0.00	0.00	7	Pass
0746-006	SED7.5E-DEW	Zapzorb/Type I Portland Cement	0.5/10.0	0.0	0.5	1.50	1.50	1.75	2.75	7	Pass
0746-007	SED7.5E-DEW	Type I Portland Cement	10.0	0.0	0.6	1.00	2.00	2.50	2.75	7	Pass
0746-008	SED7.5E-DEW	Type I Portland Cement	15.0	0.0	0.7	2.50	>4.5	>4.5	>4.5	7	Pass

Notes:
% = Percent
Wt= Weight
TSF = Tons per square foot
s.u. = standard units
lb/ft^3 = pounds per cubic foot
lb/in^2 = pounds per square inch
cm/sec = centimeter per second

3.6.2 Geotextile Tube Gravity Dewatering

Bench scale laboratory evaluations were conducted by Infrastructure Alternatives, Inc. located in Rockford, Michigan. AECOM shipped 5 gallons of sediment from each field location as well as 10 gallons of surface water from the site which was used to prepare a dredge slurry to the proportion that hydraulic dredging operations commonly generate during operations. Upon sample receipt, sediment and surface water were photographed. Standing water over the sediment in each bucket was removed from the surface prior to homogenizing and characterizing the material for solids content and density. Documentation of the condition of the as-received material is included in **Appendix H**. **Table 3-16** below summarizes the as-received sediment characterization.

Table 3-16: Solids Content and Density of Sediment

Sample Location	Solids Content (%)	Density (lbs/gal)
SED 7C-GTX	40.0	11.2
SED 7.5E-GTX	37.9	10.8

Using this information, dredge slurries were prepared by mixing sediment with the site surface water. The target dredge mix was 10% solids by volume. Each of these slurries was jar tested to evaluate a range of chemical conditioning programs. Conditioners varying in ionic charge, structure and molecular weight were prepared to a concentration of 0.5% product by volume and added to 100 mL slurry and observations were recorded such as floc appearance, water release and water clarity. From this preliminary assessment, the best performing conditioning agents were identified and scaled up to a 500 mL volume and poured through geotextile tube fabric; the solids captured on the fabric was evaluated at 1 and 15 minutes following pour and then again at 24 hours. AquaHawk 7840 was identified as the best performing conditioner and the dosage rate of 2.70 lbs (polymer)/dry ton sediment was found to be sufficient. **Table 3-19** below summarizes the performance of this conditioning agent. All conditioning agents and observations are included in **Appendix H** (Attachment B).

Table 3-17: Jar Testing Performance Results

Sample Location	Slurry Solids (%)	1 Minute Solids (%)	15 Minute Solids (%)	24 Hour Solids (%)
SED 7C-GTX	9.61	34.0	35.9	41.6
SED 7.5E-GTX	9.45	27.4	27.3	34.7

This information was used to establish bench scale geotextile tube pillow testing parameters. It was assessed that a slightly higher solids slurry could be generated during field scale operations, so a target 15% slurry was selected for the pillow testing apparatus. Pillow tests use a fabricated geotextile pillow that simulates a geotextile tube in the field. The samples used in the laboratory are fabricated by geotextile material manufacturers and are fitted with a filling spout. Using site sediment from each location and site water approximately 50 L sample volume at approximately 15% solids content was prepared to conduct each test. A solution of the conditioning agent was applied to the sample volume at the dosage rate of 2.70 lbs (polymer)/dry ton sediment as determined during the jar test. The volume was “mixed” by 3 exchanges from one vessel to another to simulate the field scale operation which usually involves injecting polymer solution to the dredge slurry surge line and allowing the turbulence of the flow to disburse the agent. The conditioned sample slurry was then poured into the geotextile pillow and the filtrate was allowed to bleed from the fabric. The filtrate was captured at time intervals 0-1 minute, 1-10 minutes, 10-60 minutes and 1-24 hours. In full-scale operations, the filtrate will be collected in aggregate and cycled through a treatment system; however, the characteristics of the filtrate vary substantially from the release of the filtrate during the first several minutes (referred to as “first blush”) to longer term sustained flows. The treatment system must consider these fluctuations to adequately treat the filtrate coming off a geotextile tube field.

One pillow test simulating field scale geotextile tube gravity dewatering was conducted for each sediment location. The filter cake solids performance for each sample was run for 7 days; results are shown in **Table 3-18**.

Table 3-18: Pillow Test Filter Cake Solids

Sample Location	24 Hour Solids (%)	48 Hour Solids (%)	96 Hour Solids (%)	7 Day Solids (%)	7-Day Method 9095
SED 7C-GTX	47.0	47.2	48.8	50.1	Pass
SED 7.5-GTX	39.5	48.3	38.5	41.7	Pass

The filtrate collected during successive time intervals was measured for volume and turbidity. Detailed data collected during the tests are provided in **Appendix H** (Attachment C). In summary, the 50 L sample produced approximately 33-34 L of filtrate with 35-45% of that volume being released in the first minute. The peak turbidity of that "first blush" was 78 Nephelometric Turbidity Units (NTU) for SED 7C-GTX and 40 NTU for SED 7.5E-GTX; sustained turbidity (i.e., between 1 and 24 hours) was 27 and 24 NTU, respectively.

These results demonstrate that geotextile tube gravity dewatering will deliver a suitable dewatered material for transport for disposal. The filtrate generated will require management to reduce turbidity and/or offsite disposal to a licensed facility.

3.7 PCB Sequestration Study

The overall objective of the sequestration study is to evaluate the effectiveness of three carbon/treatment amendments in reducing the bioavailability of PCBs in sediment collected from an impacted area within the Cove. PCB bioavailability in sediments is being tested using two metrics: 1) freely dissolved concentration of PCBs in sediment porewater measured using passive sampling, and 2) bioaccumulation of PCBs in the freshwater oligochaete (*Lumbriculus variegatus*) based on laboratory bioaccumulation studies. The specific study objectives are to:

- Evaluate the effect of dose of sorbent amendments on the reduction of porewater PCB concentration in Cove sediments;
- Compare across three AC amendment techniques described in **Table 3-19**;
- Compare reduction in freely dissolved PCB concentration against reduction of bioaccumulation in benthic organisms; and
- Evaluate any negative impacts of treatment dose on organism growth and survival in the bioaccumulation studies.

Table 3-19: Experimental Design for Laboratory Treatability Study

Amendment	AC in Treated Sediment	AC in Amendment Product	Dose of Amendment	# of Replicates
Clean control sediment	0	NA	0	3
Untreated Cove sediment	0	NA	0	3
Treatment 1: Granular Activated Carbon	1, 3, and 5%	100%	1, 3, and 5%	3 per dose
Treatment 2: SediMite with AC	1, 3, and 5%	50%	2, 6, and 10%	3 per dose
Treatment 3: AquaBlok with AC	1, 3, and 5%	10%	10, 30, and 50%	3 per dose
Total samples				**33**

3.7.1 Amendment Selection and Procurement

The following three amendments listed in the TSWP were procured by AECOM and provided to UMBC. All three products chosen for testing are available in bulk quantities needed for full-scale treatment.

- Granular Activated Carbon procured from Calgon Corporation (F-300). This coal based activated carbon was recently specified for a large-scale GAC application project for the remediation of Spirit Lake Estuary Site in Duluth Minnesota.
- SediMite™ made with 50% by weight of a fine activated carbon (virgin coal) was procured from the manufacturer for use in the experiments.
- AquaGate® made with 10% by weight of a powdered activated carbon (lignite-based) was procured from the manufacturer for use in the experiments.

3.7.2 Amendment Mixing into Sediments

Each sediment sample was first homogenized prior to collection of triplicate subsamples for the analysis of PCBs and TOC. Three liter subsamples of the homogenized sediment were placed in clean containers for mixing with the carbon amendments. Each container with 3L of sediments was treated with an amendment at a dose specified in **Table 3-19**. Amendments were mixed well with the sediment, and then allowed to equilibrate for a period of one month prior to porewater and bioaccumulation testing. The mixing conditions tested provide an indication of long-term performance of the amendment after natural mixing through bioturbation and other natural processes in the field.

3.7.3 PCB Measurement in Sediment Porewater and Worms

The bioaccumulation and porewater measurements were performed simultaneously in identical exposure chambers, which are described below. Laboratory bioaccumulation assays were conducted using the freshwater oligochaete *Lumbriculus variegatus* commonly used to perform bioaccumulation assays for freshwater sediments. The laboratory bioaccumulation studies followed methods described in Beckingham and Ghosh (2010) which is based on standard test guidelines (USEPA 2000). The bioaccumulation test is designed to evaluate the effectiveness of the selected carbon amendment in reducing biological uptake of PCBs at the base of the benthic food web. Bioaccumulation assessment was conducted in triplicate for each

of the control and treated sediments described in **Table 3-19** resulting in a total of 33 exposure chambers. Clean, laboratory cultured freshwater oligochaetes (*Lumbriculus variegatus*) were obtained from Aquatic Research Organisms, Hampton, New Hampshire. Organisms were exposed to the sediments in 1L glass beakers (1000 g wet sediment and 1.1 g wet weight of organisms per beaker (0.15 g dry); 3 replicates per treatment) for 28 days and maintained at 23 ± 1 °C in a water bath with a 16 hour light:8 hour dark photoperiod. The bioaccumulation setup in the laboratory is shown in the photolog (**Appendix A**). A 0.5 g polyethylene passive sampler was also inserted into each of the exposure chambers to measure the concentration of freely dissolved PCBs in the porewater. At the termination of the experiment, organisms were successfully removed from the sediments and allowed to depurate ingested sediment for 6 hours in a clean beaker containing water. The porewater passive samplers were also recovered from each beaker and stored for analysis. Analytical methods and results are provided in In-situ Remediation Treatability Studies Report, which is included as **Appendix D**

3.7.3.1 Sediment Porewater Concentrations

Total PCBs and the PCB homolog groups were analyzed in the sediment porewater collected from each of the exposure chambers. The measured freely dissolved PCB concentration in porewater of the untreated sediment was 3.3 nanograms per liter (ng/L). As shown in **Figure 3-11**, the results of the porewater concentrations from amended sediments show that granular size AC is minimally effective in reducing porewater concentration of PCBs even at a dose of 5% by weight of sediment. However, both SediMite and AquaGate+PAC are effective in reducing porewater PCB concentrations at all dosing levels with the powdered AC used in AquaGate+PAC (minimum 90% of AC is <325 mesh) being the most effective for a given dose. This observation is consistent with previous published results that demonstrated that effectiveness of AC is a strong function of particle size. Although reductions were observed for lower chlorinated homologs, particle size effect was the most the greatest PCB apparent for the more hydrophobic compounds (i.e. hexa and higher homolog groups) as shown in **Table 3-20**.

Both 3% and 5% amendment of AC in the 80-325 mesh (SediMite) and all three doses of powdered form (AquaGate+PAC) are able to reduce the PCB porewater concentration below the USEPA ambient water quality criteria value of 0.64 ng/L for 10^{-5} incremental cancer risk for human health via fish consumption.

Figure 3-11: PCB Concentration in Sediment Porewater from Exposure Chambers




Table 3-20: Reduction of PCB Homolog Concentration in Sediment Porewater Compared to Untreated Control

% Reductions	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG 1%	AG3%	AG5%
Mono									
Di	59	88	100	100	100	100	100	100	100
Tri	-11	18	15	92	100	100	95	100	100
Tetra	-21	0	-18	39	77	93	70	99	99
Penta	7	12	1	28	49	75	42	91	97
Hexa	-13	6	-4	3	14	37	22	77	85
Hepta	-1	16	7	10	19	28	19	68	84
Octa	3	8	1	1	20	8	-8	56	54
TOTAL	**-8**	**16**	**8**	**68**	**87**	**94**	**81**	**98**	**99**

3.7.3.2 PCB Bioaccumulation in Worms

Total PCBs and the PCB homolog groups were analyzed in the worm tissue collected from the worms that were exposed to untreated and treated sediments for 28 days in the culture chambers. PCB concentration in worms exposed to control sediments was minimal compared to the uptake in the worms exposed to untreated sediment from the Cove. Treatment of the sediment with granular size AC showed little change in the biouptake of total PCBs in worms, regardless of dosing level. However, both SediMite and AquaGate+PAC effectively reduced tissue PCB concentrations at 3% and 5% dosing levels with the powdered AC used in AquaGate+PAC being the most effective as shown in **Figure 3-12**. The results of PCB bioaccumulation in treated sediments are consistent with the observation of greater reduction for the lower chlorinated homologs, especially for the finer AC particle size. While, the reduction of PCB uptake for the di, tri, and tetra chlorobiphenyls was 100% for both SediMite and AquaGate+PAC amendments of the fine and powdered AC amendments respectively, the powdered AC was more effective for the higher more hydrophobic homologs in the short-term study. This is a reflection of the slow mass transfer of the strongly hydrophobic compounds that require longer time or finer grained AC for the movement of the molecules from the sediment to the AC particles. The reduction results are presented in **Table 3-21** below.

Overall, the bioaccumulation study demonstrates that application of a powdered AC to the study sediments was effective in reducing both porewater PCB concentration and PCB biouptake in worms by more than 90% at a dose of 3% or higher. In the present study, the different sized AC were added via different methods of application: as GAC directly, as finer sized AC in the form of SediMite or powered AC in the form of AquaGate+PAC pellets. It is expected that the powdered AC applied via any of these methods of delivery is likely to provide strong reductions in PCB bioavailability in sediments.

Figure 3-12: PCB Bioaccumulation in Worm Tissue




Table 3-21: Reduction of PCB Bioaccumulation in Worm Tissue Compared to Untreated Control


% Reductions	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG1%	AG3%	AG5%
Mono									
Di	100	100	100	84	100	100	100	100	100
Tri	76	56	75	95	100	100	100	100	100
Tetra	44	19	40	75	100	100	96	100	100
Penta	30	-3	11	23	75	87	66	98	100
Hexa	22	-1	7	5	56	55	40	87	98
Hepta	20	7	6	16	60	47	26	82	98
Octa	25	17	20	24	52	42	23	85	99
Nona	16	8	18	52	100	100	67	100	100
TOTAL	**31**	**9**	**18**	**30**	**71**	**70**	**55**	**92**	**99**

3.7.3.3 Worm Survival and Recovery from Bioaccumulation Study

Worm survival and recovery was monitored to evaluate the effect of treatment dose and any negative impacts on organism during the bioaccumulation studies. Following the bioaccumulation study, worm tissue recovery was assessed to evaluate dry tissue mass in the untreated sediment compared to the amended sediments. As discussed in **Appendix D** and shown in **Figure 3-13** below, worm recovery was good in all three granular AC treatments and comparable to or higher than the untreated control sediments. Worm recoveries were 86-95% for the three SediMite treatments and 75-114% for the three AquaGate treatments. There appears to be a small impact on worm recovery with decreasing particle size of AC amendment.

Among the treatments, AquaGate 3% and 5% gave the lowest recoveries, while the 1% granular AC treatment gave the highest recovery.

Figure 3-13: Worm Dry Weight Recoveries Following Bioaccumulation Study



*0.15 grams of worm dry mass added to each beaker (red line)

4 Conclusions

Pepco has completed the TS described herein as part of the FS process to support the evaluation of potential remedial alternatives to address sediments in the Waterside Investigation Area. Activities were conducted in accordance with the Final Treatability Study Workplan approved by DOEE on March 18, 2020, which focuses on the approximately 4.2-acre Cove located just north of the Site beyond the National Park Service Kenilworth Maintenance Yard property. The TS activities included: (1) Hydrologic/Hydraulic, Sedimentation Assessment; (2) Seepage Measurements; (3) Cove Ecological Survey; (4) Sediment Stability Assessment; (5) Sediment Dewatering Tests; and PCB Sequestration Study. Key conclusions from these activities are presented below:

Hydrologic/Hydraulic, Sedimentation Assessment

- Bathymetry collected during 2020 is similar to the 2013 bathymetry with the shallowest areas of the navigational channel occurring immediately south of the Benning Road bridge and much of the navigational channel in the Waterside Investigation Area is at the authorized depth of 8 ft. (or greater), except for a small portion of the channel in front of the Cove, where the depth is 6 ft.
- The perimeter of the Cove is at or above MLLW. Much of the Cove runs dry during low tide.
- Based on approximately eight months of tidal data collected at upstream and downstream stations along the River, the observed MHT and MLT are 2.14 to 2.71 ft, and -0.88 to -1.03 referenced to NAVD88.
- ADCP measurements indicate average near-bottom current ranges for flood tide and ebb tide to be 13.2 to 16.3 cm/s and 13.9 to 17.2 cm/s, respectively. Flood and ebb currents noted are approximately in northeast and southwest directions.
- ADCP measurements indicate maximum near-bottom current ranges for flood and ebb tide to be 33.2 to 45.5 cm/s, and 85.4 to 113.3 cm/s, respectively. Flood and ebb currents noted are approximately in northeast and southwest directions.
- Ebb currents appear to be generally stronger. Peak ebb current appears to correlate with strong wind towards south and southwest and a rain event.
- A total of six outfalls were identified as discharging into the Cove. One of these outfalls is Pepco's Outfall 013. Three other outfalls drain the D.C. transfer station property. The remaining two outfalls are of unknown origin. One of the three outfalls associated with the waste transfer station property (DPW POD-001) was not identified until after the field sampling was completed. Additional sampling is planned to assess potential impacts to the Cove from this outfall. In addition, further investigation is planned to confirm the sources of both wet and dry weather flow to Outfall 3 (DPW POD-003) and Outfall 4 (unknown origin) as well as the apparent interconnection of the drain pipes leading to these two outfalls.
- Field survey also identified four other culverts associated with the Anacostia Trail and one surface water discharge point from the Kenilworth Park South Landfill to the north shore of the Cove. Additional sampling is planned to further assess potential impacts to the Cove of flows from these discharge points.

- Flow data could not be collected on Outfall 5 due to accessibility and poor condition of the outfall. Based on limited manual measurements collected, it appears that the drainage area served by Outfall 5 is likely to be small in comparison to other outfalls draining into the Cove.
- Approximate sediment loads to the Cove based on total suspended solids for Outfalls 1 through 4 are 0.89, 4.88, 0.56, and 0.02 tons/year, respectively.
- Approximate PCB loads to Cove based on aqueous PCB concentrations for Outfalls 1 through 4 are 0.69, 3.54, 0.08 and 0.01 g/year, respectively. It should be noted that these calculations are preliminary and are based on only two sets of samples. Measured concentrations for these events may or may not be representative of average annual effluent quality. These loading estimates will be updated based on the results of additional sampling that is planned for the various discharge points in the Cove.
- The sediment trap results show that the Cove and the Waterside Investigation Area locations investigated are in general depositional. Accurate sedimentation rate calculations require multi-year investigations where seasonal influences can be captured. This means that while both the sediment traps and mats help provide understanding into the depositional characteristics of the area, the radio-isotope core taken at SED7E is likely a more reliable basis for estimating actual long-term sedimentation rates.
- PCB concentrations ranging from 120 to 290 ppb were detected in samples collected from the standard sediment traps installed in the River and from 730 to 1,500 ppb in samples collected from the sediment mats in the Cove. The grain size analysis indicates that the composition of sediments in the sediment traps and on the mats is fairly consistent and consists mostly of silt and clay particles (~63 to 80%).

Seepage Measurements

- In-situ seepage measurements were collected at three locations in the Cove. The average seepage velocity was -0.26 cm/d during a rising tide and 1.78 cm/d during a falling tide. These seepage velocity measurements will be used in conjunction with previously collected pore water data to calculate PCB flux.
- A laboratory seepage study was also conducted to investigate the hydraulic conductivity of shallow Cove sediments before and after application of the activated carbon amendment materials. The laboratory seepage measurements indicate that the amendments will likely reduce hydraulic conductivity through the native sediments in the Cove. The study showed seepage rate reductions ranging from 25 – 78% compared to untreated sediments. Similar reductions were observed for all three amendment products; however, it is possible that after a longer period of hydration and swelling of the bentonite clay, further reductions in seepage may be observed for the bentonite-clay containing amendments.

Cove Ecological Survey

- A vegetation survey of the Cove and multiple surrounding freshwater marshes in the area was conducted. Types of vegetation observed in the Cove were also observed in nearby freshwater tidal marshes both upstream and downstream, including nearly monotypic stands of *Nuphar advena*. Dominant species identified in the nearby upstream and downstream freshwater tidal marshes that were not observed in the Cove include *Typha angustifolia* (narrow-leaf cattail) and *Phragmites australis* (common reed).
- A macroinvertebrate survey was conducted in the Cove and adjacent wetland using Hester-Dendy samplers. The results of this study found the macroinvertebrate taxa to be typical of tidal freshwater

systems within Chesapeake Bay, which are well adapted to high levels of turbidity and soft unstable substrates and are dominated by oligochaetes and chironomid insect larvae.

- The results of the macroinvertebrate survey are comparable to the results of macroinvertebrate community surveys conducted in 2016 and 2017 to support the ARSP Baseline Ecological Risk Assessment (BERA) and the Benning Road site BERA, respectively.

Sediment Stability Assessment

- While Riverine cores vary to some degree from location to location, the erodibility relative to applied shear stress are similar both at the surface and with depth suggesting that along the Anacostia River in the vicinity of the Cove, there is no substantial difference in sediment stability.
- All Riverine cores show evidence of increased shear resistance with depth likely due to consolidation of underlying sediment; however, no cores show evidence of a transition from depositional sediment to pre-anthropogenic material; one core contained non-biodegradable human waste (plastic bandaid) at depth confirming the area from which the core was collected is recent deposition.
- While there were differences in the erodibility of the various amended cores, there was no substantive difference between the two Cove core locations.
- Amendments added to the Cove sediment generally decreased the erodibility of the material; this was particularly evident in the carbon-amended sand cores where the addition of 6” of sand consolidated the core material and increased density and erosion resistance.
- In both the AquaGate+PAC and SediMite amended applications, both Cove core locations showed evidence of biological activity (bioturbation) and transport of carbon into underlying sediment.
- AquaGate+PAC, which has a range of particle sizes that extend from sand- to gravel-size, created a more erosion resistant cover relative to SediMite. The bentonite component of this material created a cementitious gel which bound the particles and when the erosional forces were increased, the layer was observed to lift from the surface. The flow that created this force is expected to be significantly higher than those encountered in the River or Cove hydraulic system.
- The amended sand layer appeared to create a very erosion resistant condition at the intersection of the carbon sand and the sediment. Close observation noted that at the interface of the amended sand and sediment there was evidence of a secreted material that may be related to benthic mortality. Benthic activity appeared to cease after placement of the amended sand potentially due to the creation of an anoxic environment and/or the consolidation and densification of the underlying sediment. The net impact is a very erosion-resistant condition at the interface due to the combination of these factors. The interface depth was orders of magnitude less erodible than native sediment.

Sediment Dewatering Tests

- Two types of dewatering tests were conducted on Cove sediments. Sediment solidification/ stabilization tests were conducted on higher solids content material (representative of mechanically dredged sediment) collected from within the upper 1 to 2 feet from the Cove. Geotextile tube tests were conducted on slurry prepared in the lab with a 10% to 15% solids content (representative of hydraulically dredged sediment).
- Solidification/stabilization tests were conducted in two steps. Several amendments including Type I Portland Cement (PC), lime kiln dust (LKD), Calciment™ and ZapZorb™ were first added in different mix ratios to the sediment samples. No measurable strength gain was observed during the

initial round of amendment testing in four days for any amendment. ZapSorb™ was observed to produce a dry soil-like appearance compared to other admixtures even at very low doses (0.5-3%).

- In the second step, sequential amendment addition of ZapZorb™ and PC (in that order) was tried to assess if phased reaction might be advantageous to strength gain. PC at 10% along with ZapZorb™ resulted in early strength gain believed to be sufficient should sediment disposal require it.
- For the geotextile tube test, a jar test was first conducted as a screening step using conditioners varying in ionic charge, structure and molecular weight. AquaHawk 7840 was identified as the best performing conditioner at a dosage rate of 2.70 lbs (polymer)/dry ton.
- The best performing conditioner was then added to a geotextile pillow simulating field scale geotextile tube gravity dewatering. The pillow test produced 42 to 50% filter cake solids in seven days passing paint filter test.
- A 50 L slurry sample produced approximately 33-34 L of filtrate with 35-45% of that volume being released in the first minute. The peak turbidity of that "first blush" was 40 to 78 NTU. Sustained turbidity (i.e., between 1 and 24 hours) was 24 to 27 NTU.
- The tests demonstrated that the geotextile tube gravity dewatering will deliver dewatered material suitable for transport and disposal. The filtrate generated will require management to reduce turbidity and chemical concentrations to meet disposal/discharge requirements.

PCB Sequestration Study

- Sediments amended with three different activated carbon products (Calgon Carbon F-300 GAC with 20-50 mesh size, SediMite™ made with 50% by weight of a fine activated carbon with 80-325 mesh size, and AquaGate® made with 10% by weight of a powdered activated carbon with <325mesh size) were studied at three different dosages (1, 3 and 5%) to observe reductions in pore water PCB concentration and tissue concentrations.
- Porewater concentrations from amended sediments show that granular size AC is minimally effective in reducing porewater concentration of PCBs even at a dose of 5% by weight of sediment. Both SediMite and AquaGate are effective in reducing porewater PCB concentrations at all dosing levels with the powdered AC used in AquaGate being the most effective for a given dose.
- Both 3% and 5% amendment of AC in the 80-325 mesh (SediMite) and all three doses of powdered form (AquaGate) are able to reduce the PCB porewater concentration below the USEPA ambient water quality criteria value of 0.64 ng/L for 10^{-5} incremental cancer risk for human health via fish consumption.
- The results also demonstrated that effectiveness of AC is a strong function of its particle size. This observation is consistent with published results from other studies.
- The greatest PCB reductions were observed for lower chlorinated homologs, particle size effect was the most apparent for the more hydrophobic compounds (i.e. hexa and higher homolog groups).
- Treatment of the sediment with granular size AC showed little change in the biouptake of total PCBs in worms, regardless of dosing level. However, both SediMite and AquaGate+PAC effectively reduced tissue PCB concentrations at 3% and 5% dosing levels with the powdered AC used in AquaGate+PAC being the most effective.
- The results of PCB bioaccumulation in treated sediments are consistent with the observation of greater reduction for the lower chlorinated homologs, especially for the finer AC particle size.

- Overall, the bioaccumulation study demonstrates that application of a powdered AC to the study sediments was effective in reducing both porewater PCB concentration and PCB biouptake in worms by more than 90% at a dose of 3% or higher.
- Worm recovery was good in all three GAC treatments and comparable to or higher than the untreated control sediments. Worm recoveries were 86-95% for the three SediMite treatments and 75-114% for the three AquaGate treatments. There appears to be a small impact on worm recovery with decreasing particle size of AC amended. Among the treatments, AquaGate 3% and 5% gave the lowest recoveries, while the 1% GAC treatment gave the highest recovery.

5 References

AECOM, 2019. Hydraulic Modeling of the Benning Road Facility Storm Water Treatment and Drainage System. Prepared for Potomac Electric Power Company, 701 9th Street, NW, Washington, DC 20068. Prepared by AECOM.

AECOM, 2020. Final Remedial Investigation Report. Prepared for Potomac Electric Power Company, 701 9th Street, NW, Washington, DC 20068. February 2020.

Beckingham, B. and Ghosh, U. Comparison of field vs. laboratory exposures of L. variegatus to PCB impacted river sediments. *Environ. Toxicol. Chem*., 29, 2851-2858, 2010.

Infrastructure Alternatives, Inc., 2020. Benning Road Facility Treatability Report.

Integral Consulting, Inc., 2020. Anacostia River Native and Amended Sediment Erodibility Study,

ITRC, 2014. *Contamination Sediments Remediation: Remedy Selection for Contaminated Sediments, Remedy Selection for Contaminated Sediments*. August 2014.

Lee, D.R., and Cherry, J.A., 1978, A field exercise on groundwater flow using seepage meters and mini-piezometers: Journal of Geological Education, v. 27, p. 6–20.

National Park Service, 2008. Final Remedial Investigation at the Kenilworth Park South Landfill N.E. Washington, DC. Prepared by Ecology and Environment, Inc. June 2008.

Navy, Department of, 2014. FFA Final Report, Operable Unit 2 Remedial Investigation Report, Washington Navy Yard, Washington, DC. Prepared by CH2MHill. February 2014.

Solder, J.E.; Gilmore, T.E.; Genereux, D.P.; Solomon, D.K. A Tube Seepage Meter for In Situ Measurement of Seepage Rate and Groundwater Sampling. Groundwater. 54, 588–595. 2016.

TetraTech. 2018. Draft Remedial Investigation Report. Anacostia River Sediment Project. Washington D.C. Prepared for District of Columbia, Department of Energy and Environment. Prepared by TetraTech, Sterling, VA. March 30.

U.S. Army Corps of Engineers, 2010. Sediment Trap Study Summary Report, New Bedford Harbor Superfund Site Operable Unit #1, New Bedford, MA, Contract No. W912WJ-09-D-0001-0010.

USDA NRCS, 1986. *Technical Release 55, Urban Hydrology for Small Watersheds*. June.

USGS, 2008. Field Techniques for Estimating Water Fluxes Between Surface Water and Ground Water. Techniques and Methods 4–D2. U.S. Department of the Interior, U.S. Geological Survey, Reston, Virginia: 2008.


USEPA, 2014. Quantifying Seepage Flux using Sediment Temperatures EPA/600/R-15/454. December 2014.

U.S. EPA, 2005. *Contaminated Sediment Remediation Guidance for Hazardous Waste Sites*, EPA-540-R-05-012 OSWER 9355.0-85, December 2005.

U.S. EPA, 2000. *Methods for Measuring the Toxicity and Bioaccumulation of Sediment-Associated Contaminants with Freshwater Invertebrates.* 2000.

U.S. EPA, 1992. *Guidance for Conducting Treatability Studies under CERCLA*, EPA-540-R-92-071a

Figures



AECOM

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

SITE LOCATION MAP

FIGURE 1-1



LEGEND

- Outfall Locations
- National Park Service Kenilworth Maintenance Yard
- D.C. Department of Public Works Solid Waste Transfer Station
- Waterside Investigation Area
- Benning Road Facility Property Boundary
- Cove

AECOM

0 400 Feet

N E S W

BENNING ROAD FACILITY RI/FS PROJECT 3400 BENNING RD., NE WASHINGTON, DC 20019			SITE PLAN AND INVESTIGATION AREAS	
Date: 11/6/2020	Drawn By: JB	Checked By: SAP		FIGURE 1-2

SEDTRAP-03
SED9.5BSF
TRANS-02
SEDTRAP-02
SED8CSF
ADCP-01
ADCP-02
HD-03
SED7BSF
SED7C
SEDMAT-02
SEEP-01
SED7DSF
SED7.5E
ADCP-04
SEDMAT-03
SED7ESF/SED7E
ADCP-03
SEEP-02
SEEP-03
HD-04
TRANS-03
HD-01
SEDMAT-01
SED6C/R6-04SF
SEDTRAP-01
SED5CSF
HD-02
TRANS-01

LEGEND

- Sedflume
- Transducer & Staff Gauge
- Standard Sediment Trap
- Sediment Mat
- Hester-Dandy Sampler
- Acoustic Doppler Current Profiler
- Seepage Meter
- Constituent Sequestration/ Isolation Assessment
- Sediment Dewatering
- Waterside Investigation Area
- Benning Road Facility Property Boundary

AECOM

0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

TREATABILITY STUDY
SAMPLING/INVESTIGATION LOCATIONS

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-1

TRANS-02

ADCP-01

ADCP-02

ADCP-04

ADCP-03

TRANS-03

TRANS-01

LEGEND

- Transducer & Staff Gauge
- Acoustic Doppler Current Profiler
- Waterside Investigation Area
- Benning Road Facility Property Boundary

AECOM


0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

TRANSDUCER STATIONS
AND ADCP LOCATIONS

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-2



Outfall ID	Latitude	Longitude
Outfall 01 (DPW POD-002)	38.901191	-76.958167
Outfall 02 (Pepco Outfall 013)	38.901182	-76.958185
Outfall 03 (DPW POD-003)	38.901176	-76.958245
Outfall 04	38.901231	-76.959051
Outfall 05	38.901143	-76.959805
Outfall 06 (DPW POD-001)	38.901404	-76.958078

LEGEND

- Surveyed Outfalls
- Outfall Locations
- Culvert Pipe
- Outfall Pipe
- Unknown Outfall Pipe
- Benning Road Facility Property Boundary
- Waterside Investigation Area

Type

- KPS Silt pond
- Riprap Spillway

- Navigational Channel (Approx)
- 2.0' Contour (Bathymetry – June 2020)
- 1.0' Contour (Cove Survey – May 2020)

0 100 200 Feet

N


AECOM

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

COVE OUTFALL LOCATIONS

Date: 5/14/2021	Drawn By: DCB	Checked By: RD		FIGURE 2-3

Document Path: S:\Projects\IMS\DUE_DLGNCE\ANACOSTIA\Bathymetry_2020\OutfallLocations.mxd



AECOM


0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

SEDIMENT TRAP AND
SEDIMENT MAT LOCATIONS

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-4



AECOM


0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019


CONSTITUENT SEQUESTRATION
ASSESSMENT AND SEEPAGE EVALUATION

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-5



Schematic of seepage meter tabricated at UMBC using a 55 gallon drum following method described in USGS (2008).

Seepage Meter Schematic	Benning Road Facility RI/FS Project 3400 Benning Road, NE Washington, DC 20019	AECOM
FIGURE 2-6		



AECOM


0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

BENTHIC MACROINVERTEBRATE SURVEY

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-7



AECOM


0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

SEDFLUME CORE LOCATIONS

Date: 11/24/2020	Drawn By: JB	Checked By: SED		FIGURE 2.8



AECOM

0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

SEDIMENT DEWATERING STUDY

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 2-9

Bathymetry (FT, Mean Lower Low Water)

< -2.0	-2.0 - -4.0	-4.0 - -6.0	-6.0- -8.0	-8.0 - -10.0	-10.0 - -12.0	-12.0 - -14.0	-14.0 - -16.0	-16.0 - -18.0	> -18.0

Cove Survey (FT, Mean Lower Low Water)

<-4.0	-4.0 - -2.0	-2.0 - 0.0	0.0 - 2.0	2.0 - 4.0	4.0 - 6.0	6.0 - 8.0	8.0 - 10.0	10.0 - 12.0	12.0 - 14.0	14.0 - 16.0

LEGEND


- Navigational Channel (Approx)
- 2.0' Contour
- Benning Road Facility Property Boundary
- Waterside Investigation Area

0 200 400 Feet

N

AECOM

BENNING ROAD FACILITY RI/FS PROJECT 3400 BENNING RD., NE WASHINGTON, DC 20019			WATERSIDE INVESTIGATION AREA BATHYMETRIC SURVEY (JUNE 2020) AND COVE TOPOGRAPHIC SURVEY (MAY 2020)	
Date: 10/28/2020	Drawn By: DCB	Checked By: RD		FIGURE 3-1




Observed Water Level Data: August 1 to August 7, 2020

FIGURE 3-2


Benning Road Facility RI/FS Project
3400 Benning Road, NE
Washington, DC 20019

AECOM

CHANN ADCP 2 Bin 1 (7/29/2020 to 8/27/2020)




CHANN ADCP 3 Bin 1 (8/27/2020 to 9/11/2020)




AECOM	Benning Road Facility RI/FS Project 3400 Benning Rd., NE Washington, DC 20019	**CHANN ADCP Current Speed and Direction Distributions** **Figure 3-3**


River ADCP 1 Bin 3 (7/29/2020 to 8/27/2020)




River ADCP 4 Bin 3 (8/27/2020 to 9/10/2020)




AECOM	Benning Road Facility RI/FS Project 3400 Benning Rd., NE Washington, DC 20019	**River ADCP Current Speed and Direction Distributions** **Figure 3-4**



CHANN ADCP 2 and ADCP 3 Current Speed and Direction	Benning Road Facility RI/FS Project 3400 Benning Road, NE Washington, DC 20019	AECOM
FIGURE 3-5		






Observed Wet Weather Discharge at Outfalls 3 & 4

FIGURE 3-6

Benning Road Facility RI/FS Project
3400 Benning Road, NE
Washington, DC 20019

AECOM




Observed Dry Weather Discharge at Outfalls 3 & 4

FIGURE 3-7


Benning Road Facility RI/FS Project
3400 Benning Road, NE
Washington, DC 20019

AECOM



Laboratory experimental setup to measure change in discharge velocity after placement of amendments.

Sediment Hydraulic Conductivity Test	Benning Road Facility RI/FS Project 3400 Benning Road, NE Washington, DC 20019	AECOM
FIGURE 3-8		



THE COVE VEGETATION SUMMARY TABLE

VEGETATION AREA ID	VEGETATION PRESENT		APPROXIMATE PERCENT AERIAL COVER
	SCIENTIFIC NAME	COMMON NAME	
1	*Nuphar advena*	yellow pond-lily	100
2	*Iris pseudacorus*	pale-yellow iris	30
	Peltandra virginica	green arrow-arum	20
	Persicaria maculosa	spotted lady's-thumb	10
	Pontederia cordata	pickerelweed	5
	Hibiscus moscheutos	crimson-eyed rose-mallow	3
3	*Persicaria maculosa*	spotted lady's-thumb	60
	Commelina virginica	Virginia dayflower	5
	Iris pseudacorus	pale-yellow iris	3
4	*Persicaria maculosa*	spotted lady's-thumb	35
	Iris pseudacorus	pale-yellow iris	25
	Pontederia cordata	pickerelweed	5
	Peltandra virginica	green arrow-arum	5

LEGEND

- Outfall Locations
- Navigational Channel (Approx)
- 2.0’ Contour (Bathymetry – June 2020)
- 1.0’ Contour (Cove Survey – May 2020)
- Benning Road Facility Property Boundary
- Waterside Investigation Area
- 1 Vegetation Areas

0 200 400 Feet


N

AECOM

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

VEGETATION SURVEY

Date: 11/4/2020 | Drawn By: DCB | Checked By: RD | FIGURE 3-9



Critical Shear Stress in Unamended and Amended Sediment

FIGURE 3-10

Benning Road Facility RI/FS Project
3400 Benning Road, NE
Washington, DC 20019

AECOM

Tables

Table 2-1
TS Field Testing Locations
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

TS Activity	Location ID	Coordinates	
		Northing	Easting
Macroinvertebrate Community Survey	HD-01	449652.467	1323597.122
	HD-02	448752.357	1323121.862
	HD-03	449995.067	1323773.862
	HD-04	449689.557	1324177.982
Sedimentation Study	SEDTrap-01	449564.549	1323513.652
	SEDTrap-02	450078.689	1323792.293
	SEDTrap-03	450676.22	1323891.093
	SEDMAT-01	449635.48	1324180.062
	SEDMAT-02	449830.851	1324027.501
	SEDMAT-03	449725.82	1323945.33
Tidal Monitoring	TRANS-01	448217.393	1323232.324
	TRANS-02	450557.709	1323825.263
	TRANS-03	449684.952	1324177.091
Current Monitoring	ADCP-01	449689.557	1324177.982
	ADCP-02	449995.067	1323773.862
	ADCP-03	449692.103	1323578.663
	ADCP-04	449759.378	1323476.882
Seepage Meter Study	SEEP-01	449800.86	1323697.84
	SEEP-02	449702.99	1323903.87
	SEEP-03	449679.32	1324137.06
Outfall Evaluation	Outfall 01	449600.043	1324238.397
	Outfall 02 (Pepco Outfall 013)	449596.581	1324233.273
	Outfall 03	449594.384	1324216.175
	Outfall 04	449614.499	1323986.758
	Outfall 05	449582.346	1323772.208
Dewatering Testing	SED7C	449832.311	1323713.523
	SED7.5E	449781.777	1324040.935
Sequestration Testing	SED7E	449731.91	1323946.35
	SED7.5E	449781.777	1324040.935
Sedflume Core Collection	SED5CSF	449342.73	1323349.47
	SED6C/R6-04SF	449573.51	1323506.4
	SED7BSF	449849.21	1323649.18
	SED7DSF	449795.33	1323805.11
	SED7ESF	449731.91	1323946.35
	SED9.5BSF	450613.01	1323968.01
	SED8CSF	450066.21	1323799.86

Table 2-2
Permits Obtained for TS Field Activities
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

Permit Name	Issuing Agency	Permit Number	Purpose	Date Applied	Date Received
Special Use Permit	NPS	NCA 9500-20-001	River sediment sampling	3/9/2020	5/7/2020
Department of Army Nationwide Permit	USACE	NAB-2012-02589-20200324	Conduct data collection and field sampling	3/9/2020	3/24/2020
DOEE waiver	DOEE	--	Waive the turbidity curtain and adjust the trubidity monitoring distances	4/9/2020	4/13/2020
Water Quality Certification	DOEE	DC-020-001	River sediment sampling	3/9/2020	3/25/2020
Concurrence on time-of-year requirement	USACE	--	Conduct field activities between March 1 and June 30	4/21/2020	4/22/2020
Scientific Research Permit	DOEE	--	Capture, handle, and collect fish and aquatic specimens for sientific purposes	4/3/2020	6/3/2020
Local Notice to Mariners	DHS	--	Conduct investigation activities in Anacostia River	5/15/2020	5/18/2020

Notes:
USACE - US Army Corps of Engineers
DDOE - District Department of the Environment
NPS - National Parks Service

Table 2-5
ADCP Station Information and Sampling Details
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

Station:	Anacostia River: CHANN 2 and 3

Position #1:	38 54.1349 N, 076 57.5977 W
For time series spanning:	29-Jul-2020 10:50:00 to 27-Aug-2020 10:20:00
Position #2:	38 54.0873 N, 076 57.6293 W
For time series spanning:	27-Aug-2020 10:30:00 to 11-Sep-2020 12:40:00
Avg Water Depth @ Location #1:	2.92 m
Avg Water Depth @ Location #2:	1.27 m

Number of Valid Bins:	21
ADCP Bin Size:	0.1 m
ADCP Record Interval:	10 minutes

ADCP Bin Heights Above Seabed (m):

Bin01_HAB	Bin02_HAB	Bin03_HAB	Bin04_HAB	Bin05_HAB	Bin06_HAB	Bin07_HAB	Bin08_HAB	Bin09_HAB	Bin10_HAB	Bin11_HAB	Bin12_HAB
0.5	0.6	0.7	0.8	0.9	1	1.1	1.2	1.3	1.4	1.5	1.6
Bin13_HAB	Bin14_HAB	Bin15_HAB	Bin16_HAB	Bin17_HAB	Bin18_HAB	Bin19_HAB	Bin20_HAB	Bin21_HAB			
1.7	1.8	1.9	2	2.1	2.2	2.3	2.4	2.5			

Time Series Variables:

Timestamp:	Date/Time of observation (EDT)
Water_Depth:	Distance from Surface to Seabed (m)
BinDep_XX:	Distance from Surface to Center of Bin XX (m)
Spd_XX:	Current Speed in Bin XX (cm/s)
Dir_XX:	Current Direction in Bin XX (degrees True)
East_XX:	East Component of Current Velocity in Bin XX (cm/s)
North_XX:	North Component of Current Velocity in Bin XX (cm/s)
Vert_XX:	Vertical Component of Current Velocity in Bin XX (cm/s)

Table 2-5
ADCP Station Information and Sampling Details
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

Station:	Anacostia River: RIVER 1 and 4
Position #1:	38 54.1421 N, 076 57.6087 W
For time series spanning:	29-Jul-2020 09:40:00 to 27-Aug-2020 08:50:00
Position #2:	38 54.0983 N, 076 57.6507 W
For time series spanning:	27-Aug-2020 09:00:00 to 10-Sep-2020 14:00:00
Avg Water Depth @ Location #1:	3.01 m
Avg Water Depth @ Location #2:	2.60 m
Number of Valid Bins:	29
ADCP Bin Size:	0.1 m
ADCP Record Interval:	10 minutes

ADCP Bin Heights Above Seabed (m):

Bin01_HAB	Bin02_HAB	Bin03_HAB	Bin04_HAB	Bin05_HAB	Bin06_HAB	Bin07_HAB	Bin08_HAB	Bin09_HAB	Bin10_HAB	Bin11_HAB	Bin12_HAB
0.5	0.6	0.7	0.8	0.9	1	1.1	1.2	1.3	1.4	1.5	1.6
Bin13_HAB	Bin14_HAB	Bin15_HAB	Bin16_HAB	Bin17_HAB	Bin18_HAB	Bin19_HAB	Bin20_HAB	Bin21_HAB	Bin22_HAB	Bin23_HAB	Bin24_HAB
1.7	1.8	1.9	2	2.1	2.2	2.3	2.4	2.5	2.6	2.7	2.8
Bin25_HAB	Bin26_HAB										
2.9	3										

Time Series Variables:

Timestamp:	Date/Time of observation (EDT)
Water_Depth:	Distance from Surface to Seabed (m)
BinDep_XX:	Distance from Surface to Center of Bin XX (m)
Spd_XX:	Current Speed in Bin XX (cm/s)
Dir_XX:	Current Direction in Bin XX (degrees True)
East_XX:	East Component of Current Velocity in Bin XX (cm/s)
North_XX:	North Component of Current Velocity in Bin XX (cm/s)
Vert_XX:	Vertical Component of Current Velocity in Bin XX (cm/s)

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
2540-D	Total Suspended Solids	mg/l	33	31	83	29	54	98	640	17	12	17	180
E1668C	Decachlorobiphenyl (PCB-209)	ng/l	0.023 JN	0.024 JN	0.053 J	0.17	0.13	0.074 J	0.15 J	0.014 J	0.010 JN	0.010 J+	0.024 JN
E1668C	Dichlorobiphenyl	ng/l	0.46	0.52	1.6	0.58	1.2	2.1	14	0.16	0.1	0.27	1.9
E1668C	Heptachlorobiphenyl	ng/l	11	15	8.3	3.8	9.2	2.3	8	1	1.1	0.45	4.1
E1668C	Hexachlorobiphenyl	ng/l	20	25	14	6	15	4.3	20	1.8	1.7	0.99	12
E1668C	Monochlorobiphenyl	ng/l	0.16	0.17	0.75	0.028 J	0.057	0.029 J	0.33 J	0.015 J	0.0091 J	0.0084 J	0.045
E1668C	Nonachlorobiphenyl	ng/l	0.57	0.71	0.27 J	1.2	0.9	0.17 J	0.43	0.032 J	0.029 J	0.024 J	0.14
E1668C	Octachlorobiphenyl	ng/l	5	6.3	2.9	1.9	2.6	0.71	2.2	0.25	0.23	0.11 J	0.96
E1668C	PCB, Total Congeners	ng/l	53	67	47	19	48	16	97	5.1	4.7	3.1	35
E1668C	PCB-1	ng/l	0.088 JN	0.1	0.62	0.014 JN	0.035 J	0.016 J	0.19 J	0.0063 J+	0.0037 JN	0.0033 J+	0.023 J
E1668C	PCB-10	ng/l	< 0.0028 U	< 0.0026 U	< 0.028 U	< 0.0020 U	0.012 JN	< 0.0099 UJ	< 0.029 U	< 0.0033 U	< 0.0022 U	< 0.0027 U	< 0.0023 U
E1668C	PCB-100	ng/l	0.0090 J	0.0063 JN	0.0087 J	0.0048 JN	0.047 J	< 0.0018 U	0.026 J	0.0034 JN	0.0022 J	0.0016 JN	0.0086 J
E1668C	PCB-101	ng/l	1.6	1.7	1.8	0.47	1.5	0.47 J	2.6	0.15	0.16	0.12 J	0.96
E1668C	PCB-102	ng/l	0.022 J	0.026 JN	0.020 J	0.010 J	0.043 J	< 0.0017 U	0.061 J	0.0056 JN	0.0029 J	< 0.00090 U	0.028 J
E1668C	PCB-103	ng/l	0.0043 J	< 0.00069 U	< 0.0032 U	< 0.00075 U	0.020 J	< 0.0018 U	0.015 J	< 0.00094 U	< 0.00062 U	< 0.00093 U	0.0044 JN
E1668C	PCB-104	ng/l	< 0.00036 U	< 0.00053 U	< 0.0025 U	< 0.00057 U	0.0017 J	< 0.0014 U	< 0.0032 U	< 0.00072 U	< 0.00047 U	< 0.00071 U	< 0.00031 U
E1668C	PCB-105	ng/l	1.2	1.5	1.2	0.27	0.46	0.29	1.7	0.064	0.059	0.054 J	0.48
E1668C	PCB-106	ng/l	< 0.0083 U	< 0.010 U	< 0.019 U	< 0.0030 U	< 0.0023 U	< 0.033 U	< 0.035 U	< 0.0020 U	< 0.0013 U	< 0.0029 U	< 0.0058 U
E1668C	PCB-107	ng/l	0.19 JN	0.27	0.17 J	0.043 J	0.11	< 0.035 U	0.23 JN	0.011 J	0.010 JN	0.0069 JN	0.079 JN
E1668C	PCB-108	ng/l	0.10 JN	0.14 J	0.075 JN	0.026 J	0.052 J	< 0.034 U	0.11 JN	0.0067 JN	0.0063 JN	0.0062 JN	0.050 J
E1668C	PCB-109	ng/l	1.1	1.2	1.1 J	0.38 J	0.94	0.32 J	1.6 J	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-11	ng/l	0.34	0.38	1.1	0.45	0.57	2.0 J	11	0.098	0.050 JN	0.25	1.4
E1668C	PCB-110	ng/l	2	1.9	2.5	0.64	1.8	0.5	3	0.31	0.27	0.19	1.3
E1668C	PCB-111	ng/l	0.0039 J	< 0.00049 U	< 0.0023 U	< 0.00053 U	< 0.00024 U	< 0.0013 U	< 0.0029 U	< 0.00066 U	< 0.00043 U	< 0.00065 U	< 0.00029 U
E1668C	PCB-112	ng/l	0.0020 JN	0.0068 JN	0.017 J	< 0.00055 U	0.0055 JN	0.11 JN	0.011 J	0.0012 J	0.00097 JN	< 0.00069 U	0.0017 JN
E1668C	PCB-113	ng/l	1.6	1.7	1.8	0.47	1.5	0.47 J	2.6	0.15	0.16	0.12 J	0.96
E1668C	PCB-114	ng/l	0.039 JN	0.071 J	0.051 JN	0.011 JN	0.017 JN	< 0.028 U	0.052 JN	< 0.0019 U	0.0017 JN	< 0.0027 U	0.018 J
E1668C	PCB-115	ng/l	2	1.9	2.5	0.64	1.8	0.5	3	0.31	0.27	0.19	1.3
E1668C	PCB-116	ng/l	0.27	0.26	0.25 J	0.088 J	0.25	0.051 JN	0.35 J	0.037 J	0.026 J	0.023 J	0.15
E1668C	PCB-117	ng/l	0.27	0.26	0.25 J	0.088 J	0.25	0.051 JN	0.35 J	0.037 J	0.026 J	0.023 J	0.15
E1668C	PCB-118	ng/l	2.5	3.2	2.5	0.58	1.2	0.63	3.4	0.14	0.14	0.13	1.1
E1668C	PCB-119	ng/l	1.1	1.2	1.1 J	0.38 J	0.94	0.32 J	1.6 J	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-12	ng/l	0.0088 JN	0.015 J	< 0.025 U	0.011 J	0.031 J	< 0.0090 UJ	0.19 JN	0.0071 JN	< 0.0020 U	< 0.0025 U	0.031 JN
E1668C	PCB-120	ng/l	0.0047 JN	< 0.00050 U	0.012 JN	< 0.00053 U	0.0054 JN	< 0.0013 U	0.018 JN	< 0.00068 U	< 0.00044 U	< 0.00067 U	0.0021 JN
E1668C	PCB-121	ng/l	< 0.00035 U	< 0.00051 U	< 0.0024 U	< 0.00055 U	0.0012 JN	< 0.0013 U	< 0.0031 U	< 0.00070 U	< 0.00045 U	< 0.00068 U	< 0.00030 U
E1668C	PCB-122	ng/l	0.038 JN	0.050 JN	0.029 JN	0.0095 JN	0.014 JN	< 0.038 U	< 0.041 U	< 0.0023 U	0.0027 J	< 0.0034 U	0.017 J
E1668C	PCB-123	ng/l	0.035 J	0.027 JN	0.022 JN	0.012 J	0.016 JN	< 0.029 U	0.042 JN	0.0032 JN	0.0017 JN	< 0.0028 U	0.010 JN
E1668C	PCB-124	ng/l	0.10 JN	0.14 J	0.075 J	0.026 J	0.052 J	< 0.034 U	0.11 J	0.0067 JN	0.0063 J	0.0062 J+	0.050 J
E1668C	PCB-125	ng/l	1.1	1.2	1.1 J	0.38 J	0.94	0.32 J	1.6 J	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-126	ng/l	0.078	0.076 J	0.048 JN	0.0091 JN	0.0091 J	< 0.042 UJ	< 0.038 U	0.0027 JN	< 0.0015 U	< 0.0033 U	0.022 JN
E1668C	PCB-127	ng/l	< 0.0083 U	< 0.010 U	< 0.019 U	< 0.0030 U	< 0.0023 U	< 0.033 U	< 0.035 U	< 0.0020 U	< 0.0013 U	< 0.0029 U	< 0.0058 U
E1668C	PCB-128	ng/l	0.76	1	0.61 J	0.19	0.36	0.14 J	0.60 J	0.065 JN	0.049 J	0.033 J	0.37
E1668C	PCB-129	ng/l	4.6	6.2	3.7	1.4	3.1	1.2	5.2	0.41	0.41	0.26 J	2.8
E1668C	PCB-13	ng/l	0.0088 JN	0.015 J	< 0.025 U	0.011 J	0.031 J	< 0.0090 UJ	0.19 J	0.0071 JN	< 0.0020 U	< 0.0025 U	0.031 J
E1668C	PCB-130	ng/l	0.28	0.38	0.17 JN	0.071 JN	0.17	< 0.072 U	0.25 JN	0.024 JN	0.023 J	0.014 JN	0.16
E1668C	PCB-131	ng/l	0.049 JN	0.071 J	< 0.051 U	< 0.0095 U	0.027 J	< 0.075 U	< 0.091 U	< 0.0042 U	0.0046 JN	< 0.0086 U	0.028 J
E1668C	PCB-132	ng/l	1.4	1.8	0.91	0.43	0.99	0.33	1.6	0.14	0.11	0.081	0.94
E1668C	PCB-133	ng/l	0.053 J	0.056 J	< 0.046 U	< 0.0086 U	0.034 JN	< 0.068 U	< 0.083 U	< 0.0038 U	0.0037 J	< 0.0078 U	0.028 J

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
E1668C	PCB-134	ng/l	0.25	0.29	0.12 J	0.056 J	0.16	< 0.071 U	0.19 J	0.020 JN	0.014 J	< 0.0082 U	0.14
E1668C	PCB-135	ng/l	0.71	0.76	0.62 J	0.33	1.1	0.21 JN	0.96	0.15	0.13	0.046 JN	0.58
E1668C	PCB-136	ng/l	0.23	0.28	0.19 J	0.1	0.36	0.085 J	0.41	0.043	0.04	0.016 J	0.24
E1668C	PCB-137	ng/l	0.23 JN	0.3	0.14 JN	0.043 J	0.09	< 0.061 U	0.19 J	0.015 JN	0.0096 JN	0.013 J	0.11 JN
E1668C	PCB-138	ng/l	4.6	6.2	3.7	1.4	3.1	1.2	5.2	0.41	0.41	0.26 J	2.8
E1668C	PCB-139	ng/l	0.066 JN	0.069 JN	0.047 J	0.015 JN	0.032 J	< 0.060 U	< 0.074 U	0.0099 J	0.0040 JN	< 0.0070 U	0.037 J
E1668C	PCB-14	ng/l	< 0.0022 U	< 0.0020 U	< 0.021 U	< 0.0015 U	< 0.0021 U	< 0.0076 UJ	< 0.022 U	< 0.0025 U	< 0.0017 U	< 0.0021 U	< 0.0018 U
E1668C	PCB-140	ng/l	0.066 JN	0.069 JN	0.047 J	0.015 JN	0.032 J	< 0.060 U	< 0.074 U	0.0099 J	0.0040 J	< 0.0070 U	0.037 J
E1668C	PCB-141	ng/l	0.97	1.3	0.59	0.32	0.7	0.19 JN	0.82	0.084	0.087	0.053 J	0.48
E1668C	PCB-142	ng/l	< 0.036 U	< 0.053 U	< 0.046 U	< 0.0085 U	< 0.0057 U	< 0.068 U	< 0.082 U	< 0.0038 U	< 0.0029 U	< 0.0078 U	< 0.014 U
E1668C	PCB-143	ng/l	0.25	0.29	0.12 J	0.056 J	0.16	< 0.071 U	0.19 J	0.020 JN	0.014 J	< 0.0082 U	0.14
E1668C	PCB-144	ng/l	0.09	0.087	0.061 JN	0.042 J	0.13	0.038 J	0.11 J	0.019 JN	0.013 J	0.0071 J	0.063
E1668C	PCB-145	ng/l	< 0.00046 U	< 0.0012 U	< 0.0023 U	< 0.0010 U	0.0019 J	< 0.00094 U	< 0.0032 U	< 0.00080 U	< 0.00057 U	< 0.00054 U	0.0027 J
E1668C	PCB-146	ng/l	0.55	0.69	0.35 JN	0.19	0.49	< 0.060 U	0.59	0.056	0.048 JN	0.033 J	0.36
E1668C	PCB-147	ng/l	3.9	4.8	2.2	1.2	3.2	0.84	4	0.33	0.35	0.18	2.5
E1668C	PCB-148	ng/l	0.0022 JN	< 0.0017 U	< 0.0033 U	< 0.0014 U	0.0035 J	< 0.0013 U	< 0.0046 U	< 0.0011 U	< 0.00080 U	< 0.00076 U	< 0.00075 U
E1668C	PCB-149	ng/l	3.9	4.8	2.2	1.2	3.2	0.84	4	0.33	0.35	0.18	2.5
E1668C	PCB-15	ng/l	0.040 J	0.047 J	0.13 J	0.058 J	0.18	0.031 JN	0.65	0.022 J	0.015 J+	0.013 JN	0.13
E1668C	PCB-150	ng/l	< 0.00044 U	0.0023 JN	< 0.0022 U	< 0.00098 U	0.0059 J	< 0.00090 U	< 0.0031 U	< 0.00076 U	< 0.00054 U	< 0.00051 U	< 0.00051 U
E1668C	PCB-151	ng/l	0.71	0.76	0.62 J	0.33	1.1	0.21 JN	0.96	0.15	0.13	0.046 JN	0.58
E1668C	PCB-152	ng/l	< 0.00047 U	0.0035 J	< 0.0024 U	< 0.0011 U	0.0024 J	< 0.00097 U	< 0.0033 U	< 0.00082 U	< 0.00059 U	< 0.00055 U	0.0012 JN
E1668C	PCB-153	ng/l	3.8	4.9	2.6	1.2	2.7	0.98	3.6	0.26	0.3	0.18	2
E1668C	PCB-154	ng/l	0.015 J	0.010 JN	0.024 J	0.0077 JN	0.028 J	0.0064 JN	0.021 J	0.0027 JN	0.0017 JN	< 0.00061 U	0.0078 JN
E1668C	PCB-155	ng/l	< 0.00044 U	< 0.0012 U	< 0.0022 U	< 0.00098 U	< 0.00035 U	< 0.00090 U	< 0.0031 U	< 0.00076 U	< 0.00055 U	< 0.00052 U	< 0.00051 U
E1668C	PCB-156	ng/l	0.57	0.73	0.45 J	0.13 J	0.22	0.098 JN	0.50 J	0.043 J	0.035 J	0.021 J+	0.23
E1668C	PCB-157	ng/l	0.57	0.73	0.45 J	0.13 J	0.22	0.098 JN	0.50 J	0.043 J	0.035 J	0.021 J+	0.23
E1668C	PCB-158	ng/l	0.51	0.64	0.37 J	0.14	0.28	0.12 J	0.45	0.048	0.035 JN	0.023 J	0.27
E1668C	PCB-159	ng/l	0.054 J	0.065 JN	< 0.031 U	0.013 J	0.029 J	< 0.045 U	< 0.055 U	0.0043 J	0.0036 JN	< 0.0052 U	< 0.0091 U
E1668C	PCB-16	ng/l	0.040 J	0.042 J	0.12 J	0.018 JN	0.15	0.014 JN	0.69	0.0087 J	0.0060 JN	0.0057 J	0.18
E1668C	PCB-160	ng/l	4.6	6.2	3.7	1.4	3.1	1.2	5.2	0.41	0.41	0.26 J	2.8
E1668C	PCB-161	ng/l	< 0.024 U	< 0.035 U	< 0.030 U	< 0.0057 U	< 0.0038 U	0.094 JN	< 0.055 U	< 0.0025 U	< 0.0019 U	< 0.0052 U	< 0.0090 U
E1668C	PCB-162	ng/l	0.041 JN	0.065 J	< 0.030 U	< 0.0056 U	0.0084 J	< 0.044 U	< 0.054 U	< 0.0025 U	< 0.0019 U	< 0.0051 U	0.0096 JN
E1668C	PCB-163	ng/l	4.6	6.2	3.7	1.4	3.1	1.2	5.2	0.41	0.41	0.26 J	2.8
E1668C	PCB-164	ng/l	0.28	0.41	0.21 J	0.095	0.22	< 0.048 U	0.28 J	0.027 JN	0.027 J	0.017 J	0.17
E1668C	PCB-165	ng/l	< 0.027 U	< 0.040 U	< 0.035 U	< 0.0065 U	< 0.0043 U	< 0.051 U	< 0.062 U	< 0.0029 U	< 0.0022 U	< 0.0059 U	< 0.010 U
E1668C	PCB-166	ng/l	0.76	1	0.61 J	0.19	0.36	0.14 J	0.60 J	0.065 JN	0.049 J	0.033 J	0.37
E1668C	PCB-167	ng/l	0.17	0.23	0.14 JN	0.052 J	0.1	< 0.036 U	0.15 JN	0.017 J	0.012 J	0.0082 JN	0.074
E1668C	PCB-168	ng/l	3.8	4.9	2.6	1.2	2.7	0.98	3.6	0.26	0.3	0.18	2
E1668C	PCB-169	ng/l	0.051 JN	0.10 JN	< 0.022 U	< 0.0050 U	0.0075 JN	< 0.039 U	< 0.042 U	< 0.0021 U	< 0.0015 U	< 0.0046 U	< 0.0080 U
E1668C	PCB-17	ng/l	0.028 JN	0.034 J	0.12 JN	0.021 JN	0.18	0.019 JN	0.67	0.0082 JN	0.0075 JN	0.0064 J	0.17
E1668C	PCB-170	ng/l	1.3	1.7	0.92	0.48	1.1	0.22 JN	1.1	0.13	0.14	0.059 J	0.58
E1668C	PCB-171	ng/l	0.27	0.37	0.24 J	0.11 J	0.31	0.084 J	0.25 J	0.043 J	0.036 J	0.015 JN	0.14
E1668C	PCB-172	ng/l	0.19	0.26	0.16 J	0.077 J	0.19	0.052 J	0.14 J	0.026 J	0.020 J	0.010 JN	0.081
E1668C	PCB-173	ng/l	0.27	0.37	0.24 J	0.11 J	0.31	0.084 J	0.25 J	0.043 J	0.036 J	0.015 J+	0.14
E1668C	PCB-174	ng/l	1.6	2.1	1	0.49	1.2	0.27	0.96 JN	0.13	0.14	0.059 J	0.53
E1668C	PCB-175	ng/l	0.036 JN	0.073 J	0.027 JN	0.021 J	0.042	< 0.0055 U	0.032 JN	0.0071 J	0.0047 J	0.0034 JN	0.017 JN
E1668C	PCB-176	ng/l	0.17	0.22	0.076 J	0.059 J	0.14	0.024 JN	0.099 J	0.015 J	0.014 J	0.0055 JN	0.058
E1668C	PCB-177	ng/l	0.68	0.9	0.47	0.25	0.63	0.12 JN	0.49	0.08	0.072	0.032 J	0.27

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
E1668C	PCB-178	ng/l	0.32	0.41	0.21 J	0.11	0.23	0.068 JN	0.20 J	0.028 J	0.023 J	0.011 J	0.088
E1668C	PCB-179	ng/l	0.76	1	0.33 JN	0.21	0.54	0.18 J	0.41	0.054	0.053	0.030 J	0.24
E1668C	PCB-18	ng/l	0.073 J	0.081 J	0.31 J	0.036 JN	0.38	0.034 JN	1.5	0.016 JN	0.017 J	0.014 J	0.4
E1668C	PCB-180	ng/l	3	4.1	2.6	0.93	2.4	0.60 JN	2.3	0.25	0.3	0.12 J	1.1
E1668C	PCB-181	ng/l	< 0.00091 U	< 0.0061 U	< 0.0079 U	< 0.0027 U	0.0069 J	< 0.0054 U	< 0.0097 U	< 0.00095 U	< 0.0014 U	< 0.0029 U	< 0.0011 U
E1668C	PCB-182	ng/l	< 0.00087 U	< 0.0059 U	< 0.0076 U	0.0066 JN	0.0076 JN	< 0.0052 U	< 0.0094 U	< 0.00092 U	< 0.0013 U	< 0.0028 U	< 0.0011 U
E1668C	PCB-183	ng/l	1	1.3	0.63 J	0.33	0.75	0.24 J	0.67 J	0.086	0.09	0.040 J	0.35
E1668C	PCB-184	ng/l	< 0.00074 U	< 0.0050 U	< 0.0065 U	< 0.0022 U	< 0.00081 U	< 0.0045 U	< 0.0080 U	< 0.00078 U	< 0.0011 U	< 0.0024 U	< 0.00093 U
E1668C	PCB-185	ng/l	1	1.3	0.63 J	0.33	0.75	0.24 J	0.67 J	0.086	0.09	0.040 J	0.35
E1668C	PCB-186	ng/l	< 0.00072 U	< 0.0049 U	< 0.0063 U	< 0.0022 U	< 0.00078 U	< 0.0043 U	< 0.0078 U	< 0.00076 U	< 0.0011 U	< 0.0023 U	< 0.00090 U
E1668C	PCB-187	ng/l	1.9	2.6	1.4	0.59	1.4	0.4	1.1	0.15	0.16	0.060 JN	0.56
E1668C	PCB-188	ng/l	< 0.00055 U	< 0.0039 U	< 0.0056 U	< 0.0017 U	0.0039 J	< 0.0035 U	< 0.0065 U	< 0.00066 U	< 0.00097 U	< 0.0018 U	< 0.00074 U
E1668C	PCB-189	ng/l	0.032 JN	0.08	0.025 J	0.016 J+	0.033 J	< 0.052 U	0.044 J	0.0054 J	< 0.0018 U	< 0.0049 U	0.016 J
E1668C	PCB-19	ng/l	0.0070 J	0.0068 JN	0.037 J	0.0078 J	0.053	< 0.0014 U	0.12 J	< 0.0015 U	0.0018 JN	< 0.0011 U	0.036 J
E1668C	PCB-190	ng/l	0.2	0.25	0.16 J	0.067 J	0.18	0.049 JN	0.19 J	0.027 J	0.020 JN	0.0086 JN	0.079
E1668C	PCB-191	ng/l	0.039 JN	0.049 JN	0.043 J	0.013 JN	0.038	< 0.0041 U	0.028 J	0.0051 JN	0.0060 J	< 0.0022 U	0.017 J
E1668C	PCB-192	ng/l	< 0.00076 U	< 0.0051 U	< 0.0067 U	< 0.0023 U	< 0.00083 U	< 0.0046 U	< 0.0082 U	< 0.00080 U	< 0.0012 U	< 0.0024 U	< 0.00095 U
E1668C	PCB-193	ng/l	3	4.1	2.6	0.93	2.4	0.60 JN	2.3	0.25	0.3	0.12 J	1.1
E1668C	PCB-194	ng/l	1.2	1.4	0.6	0.38	0.62	0.14 JN	0.56	0.064	0.053	0.025 JN	0.26
E1668C	PCB-195	ng/l	0.41	0.17	0.23 J	0.16	0.23	< 0.065 UJ	0.15 JN	0.037 J	0.026 J	< 0.011 U	0.082 JN
E1668C	PCB-196	ng/l	0.58	0.79	0.36 J	0.18	0.29	0.077 JN	0.25 JN	0.030 J	0.029 J	0.023 J	0.12
E1668C	PCB-197	ng/l	0.036 JN	0.076 J	0.030 J	0.016 JN	0.018 J	< 0.0080 UJ	< 0.0079 U	< 0.00080 U	< 0.0012 U	< 0.0045 U	0.0062 JN
E1668C	PCB-198	ng/l	1.4	1.9	0.9	0.55	0.71	0.25 JN	0.63 J	0.067 J	0.061 J	0.039 JN	0.26
E1668C	PCB-199	ng/l	1.4	1.9	0.9	0.55	0.71	0.25 JN	0.63 J	0.067 J	0.061 J	0.039 JN	0.26
E1668C	PCB-2	ng/l	0.015 J	0.014 J	0.035 JN	0.0051 J+	0.0064 J+	< 0.0015 U	0.028 JN	0.0035 JN	< 0.0021 U	0.0024 JN	0.0068 JN
E1668C	PCB-20	ng/l	0.17	0.18	0.60 J	0.18	0.72	0.14 J	2.4	0.051 J	0.041 J	0.033 J	0.63
E1668C	PCB-200	ng/l	0.14	0.2	0.076 J	0.040 J	0.068	0.029 JN	0.068 J	0.0069 J	0.0057 JN	< 0.0040 U	0.018 JN
E1668C	PCB-201	ng/l	0.16	0.24	0.086 JN	0.064 J	0.079	< 0.0073 UJ	0.064 J	0.0060 JN	0.0075 J	< 0.0041 U	0.020 JN
E1668C	PCB-202	ng/l	0.28	0.37	0.11 JN	0.12	0.14	0.040 JN	0.12 J	0.0084 JN	0.0078 JN	< 0.0046 U	0.047
E1668C	PCB-203	ng/l	0.79	1.1	0.46	0.33	0.46	0.17 J	0.34 JN	0.035 J	0.036 J	0.019 JN	0.14
E1668C	PCB-204	ng/l	< 0.0014 U	< 0.0071 U	< 0.0094 U	< 0.0040 U	< 0.00097 U	< 0.0080 UJ	< 0.0079 U	< 0.00080 U	< 0.0012 U	< 0.0045 U	< 0.0019 U
E1668C	PCB-205	ng/l	0.052 J	0.061 J	< 0.023 U	0.025 J+	0.026 J	< 0.050 UJ	< 0.029 U	< 0.0020 U	< 0.0037 U	< 0.0088 U	0.011 J
E1668C	PCB-206	ng/l	0.44	0.54	0.21 JN	0.85	0.67	0.17 JN	0.37 J	0.032 J	0.020 J	0.024 JN	0.11
E1668C	PCB-207	ng/l	0.050 J	0.059 J	< 0.025 U	0.073 J	0.052	< 0.042 U	< 0.024 U	< 0.0041 U	0.0047 J	< 0.0058 U	0.011 J
E1668C	PCB-208	ng/l	0.083	0.11	0.056 J	0.24	0.18	< 0.062 U	0.060 JN	< 0.0041 U	0.0043 JN	< 0.0062 U	0.023 JN
E1668C	PCB-21	ng/l	0.091 J	0.11 J	0.33 J	0.049 J	0.28	0.071 J	1.5	0.022 J	0.014 J+	0.015 JN	0.36
E1668C	PCB-22	ng/l	0.069 J	0.076 J	0.21 J	0.059 J	0.22	0.053 J	0.83	0.022 J	0.012 J	0.012 J	0.23
E1668C	PCB-23	ng/l	< 0.0018 U	< 0.0020 U	< 0.0071 U	< 0.0013 U	< 0.0011 U	< 0.0051 U	< 0.0097 U	< 0.0013 U	< 0.00073 U	< 0.0013 U	< 0.0014 U
E1668C	PCB-24	ng/l	0.0019 J	0.0015 JN	0.0083 JN	0.0011 J	0.0065 JN	< 0.00095 U	0.023 JN	< 0.0011 U	0.00088 J	< 0.00075 U	0.0060 JN
E1668C	PCB-25	ng/l	0.011 J	0.011 J	0.035 J	0.010 J	0.073	0.0091 JN	0.13 J	0.0038 JN	0.0017 JN	0.0021 JN	0.041
E1668C	PCB-26	ng/l	0.024 J	0.027 J	0.077 J	0.018 J	0.14	0.021 J	0.38 J	0.0077 J	0.0045 JN	0.0042 JN	0.1
E1668C	PCB-27	ng/l	0.0058 J	0.0055 JN	0.021 JN	0.0033 JN	0.036 J	< 0.00082 U	0.098 J	< 0.00092 U	0.0012 JN	< 0.00065 U	0.026 J
E1668C	PCB-28	ng/l	0.17	0.18	0.60 J	0.18	0.72	0.14 J	2.4	0.051 J	0.041 J	0.033 J	0.63
E1668C	PCB-29	ng/l	0.024 J	0.027 J	0.077 J	0.018 J	0.14	0.021 J	0.38 J	0.0077 J	0.0045 J+	0.0042 JN	0.1
E1668C	PCB-3	ng/l	0.052 J	0.053 J	0.096 JN	0.0087 JN	0.016 J	0.013 J	0.11 J	0.0048 JN	0.0033 J+	0.0027 J+	0.015 J
E1668C	PCB-30	ng/l	0.073 J	0.081 J	0.31 J	0.036 JN	0.38	0.034 JN	1.5	0.016 JN	0.017 J	0.014 J	0.4
E1668C	PCB-31	ng/l	0.13	0.15	0.5	0.1	0.51	0.11 JN	2.1	0.037 J	0.026 JN	0.028 J	0.56
E1668C	PCB-32	ng/l	0.028 J	0.028 J	0.10 J	0.025 J	0.18	0.012 JN	0.47	0.011 J	0.0077 J+	0.0046 JN	0.12

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
E1668C	PCB-33	ng/l	0.091 J	0.11 J	0.33 J	0.049 J	0.28	0.071 J	1.5	0.022 J	0.014 J+	0.015 JN	0.36
E1668C	PCB-34	ng/l	< 0.0019 U	< 0.0021 U	< 0.0073 U	< 0.0013 U	0.0017 JN	< 0.0053 U	< 0.010 U	< 0.0013 U	< 0.00076 U	< 0.0014 U	< 0.0015 U
E1668C	PCB-35	ng/l	0.012 J	0.011 JN	0.022 J	0.028 J	0.030 J	0.015 JN	0.098 J	< 0.0013 U	< 0.00074 U	0.0020 JN	0.023 J
E1668C	PCB-36	ng/l	< 0.0017 U	< 0.0019 U	< 0.0069 U	< 0.0013 U	0.0036 J	< 0.0049 U	< 0.0095 U	< 0.0012 U	< 0.00071 U	< 0.0013 U	0.0030 J
E1668C	PCB-37	ng/l	0.084	0.092	0.20 JN	0.089	0.27	0.046 JN	0.72	0.031 J	0.018 J	0.016 J	0.19
E1668C	PCB-38	ng/l	< 0.0019 U	< 0.0021 U	< 0.0074 U	< 0.0014 U	< 0.0011 U	< 0.0053 U	< 0.010 U	< 0.0013 U	< 0.00076 U	< 0.0014 U	< 0.0015 U
E1668C	PCB-39	ng/l	< 0.0017 U	< 0.0019 U	< 0.0066 U	< 0.0012 U	0.0021 J	< 0.0048 U	< 0.0091 U	< 0.0012 U	< 0.00068 U	< 0.0012 U	0.0015 JN
E1668C	PCB-4	ng/l	0.020 JN	0.018 J	0.12 J	0.024 JN	0.17	< 0.012 U	0.44 JN	0.011 J	0.013 JN	< 0.0035 U	0.091
E1668C	PCB-40	ng/l	0.13 J	0.20 J	0.29 JN	0.077 J	0.4	0.18 J	1.7	0.028 JN	0.014 J	0.019 JN	0.46
E1668C	PCB-41	ng/l	0.13 J	0.20 J	0.29 J	0.077 J	0.4	0.18 J	1.7	0.028 JN	0.014 J	0.019 JN	0.46
E1668C	PCB-42	ng/l	0.055 J	0.076 J	0.11 JN	0.031 J	0.18	< 0.040 U	0.72	0.015 J	0.0073 J	0.0063 JN	0.2
E1668C	PCB-43	ng/l	< 0.0079 U	< 0.011 U	< 0.017 U	< 0.0035 U	0.026 J	< 0.037 U	0.077 J	< 0.0026 U	< 0.0011 U	< 0.0047 U	0.027 J
E1668C	PCB-44	ng/l	0.27 J+	0.4	0.59 J	0.13 J+	0.82	0.27 JN	2.8	0.044 J+	0.031 J	< 0.041 U	0.84
E1668C	PCB-45	ng/l	0.032 J+	0.043 J	0.071 JN	0.024 J+	0.18	< 0.042 U	0.53 J	< 0.0029 U	0.0049 J	< 0.0064 U	0.16
E1668C	PCB-46	ng/l	0.012 J	0.018 J	< 0.023 U	0.0083 J	0.049	< 0.051 U	0.18 J	< 0.0035 U	< 0.0016 U	< 0.0063 U	0.051
E1668C	PCB-47	ng/l	0.27 J+	0.4	0.59 J	0.13 J+	0.82	0.27 J+	2.8	0.044 J+	0.031 J	< 0.041 U	0.84
E1668C	PCB-48	ng/l	0.038 JN	0.057 J	0.11 J	0.016 J	0.096	0.068 J	0.69	0.0073 JN	0.0041 J	0.0070 J	0.17
E1668C	PCB-49	ng/l	0.13 J	0.19	0.31 J	0.069 J	0.52	0.16 J	1.5	0.023 J	0.018 J	0.014 JN	0.46
E1668C	PCB-5	ng/l	< 0.0029 U	0.0028 JN	< 0.028 U	< 0.0020 U	0.0036 JN	< 0.010 UJ	< 0.030 U	< 0.0033 U	< 0.0022 U	< 0.0028 U	0.0057 JN
E1668C	PCB-50	ng/l	0.018 JN	0.030 J	0.055 J	0.014 J	0.16	< 0.039 U	0.33 J	0.0064 J	0.0040 J	< 0.0048 U	0.1
E1668C	PCB-51	ng/l	0.032 J+	0.043 J	0.071 J	0.024 J+	0.18	< 0.042 U	0.53 J	< 0.0029 U	0.0049 J	< 0.0064 U	0.16
E1668C	PCB-52	ng/l	0.41	0.62	0.75	0.16	1	0.54	3.9	0.059	0.053	0.048 J	1.3
E1668C	PCB-53	ng/l	0.018 JN	0.030 J	0.055 J	0.014 J	0.16	< 0.039 U	0.33 J	0.0064 J	0.0040 J	< 0.0048 U	0.1
E1668C	PCB-54	ng/l	< 0.00020 U	< 0.00026 U	< 0.0016 U	0.0018 J	0.0059 J	< 0.00083 U	< 0.0014 U	< 0.00086 U	< 0.00019 U	< 0.00040 U	0.0010 JN
E1668C	PCB-55	ng/l	0.011 J	0.013 JN	0.018 JN	0.0047 JN	0.014 J	< 0.029 U	0.042 JN	0.0039 JN	< 0.00089 U	< 0.0036 U	0.013 J
E1668C	PCB-56	ng/l	0.17	0.23	0.25 J	0.078 J	0.27	0.13 J	1	0.032 J	0.017 J	0.018 J	0.24
E1668C	PCB-57	ng/l	< 0.0062 U	< 0.0083 U	< 0.013 U	< 0.0028 U	0.0057 JN	< 0.029 U	< 0.026 U	< 0.0021 U	< 0.00090 U	< 0.0037 U	< 0.0039 U
E1668C	PCB-58	ng/l	< 0.0063 U	< 0.0084 U	< 0.014 U	< 0.0028 U	< 0.0021 U	< 0.030 U	< 0.026 U	< 0.0021 U	< 0.00092 U	< 0.0037 U	< 0.0039 U
E1668C	PCB-59	ng/l	0.017 J	0.026 J	0.052 J	0.011 J	0.064 J	< 0.028 U	0.23 J	0.0045 JN	0.0031 J	< 0.0035 U	0.074 J
E1668C	PCB-6	ng/l	0.0098 JN	0.010 JN	< 0.025 U	0.0063 JN	0.049	< 0.0089 UJ	0.22 J	0.0033 JN	0.0040 JN	< 0.0024 U	0.044 JN
E1668C	PCB-60	ng/l	0.088	0.13	0.14 J	0.040 J	0.13	0.061 JN	0.41	0.020 J	0.0091 J	0.011 J	0.12
E1668C	PCB-61	ng/l	0.88	1.4	1.1 J	0.28 J	0.97	0.68 J	4.1	0.093 J	0.074 J	0.072 J	1.1
E1668C	PCB-62	ng/l	0.017 J	0.026 J	0.052 J	0.011 J	0.064 J	< 0.028 U	0.23 J	0.0045 JN	0.0031 J	< 0.0035 U	0.074 J
E1668C	PCB-63	ng/l	0.0074 JN	0.013 JN	0.020 J	0.0036 JN	0.021 J	< 0.027 U	0.066 JN	< 0.0019 U	< 0.00083 U	< 0.0034 U	0.013 JN
E1668C	PCB-64	ng/l	0.11	0.17	0.24 J	0.061 J	0.26	0.14 J	1.3	0.034 J	0.021 J	0.013 JN	0.37
E1668C	PCB-65	ng/l	0.27 J+	0.4	0.59 J	0.13 J+	0.82	0.27 J+	2.8	0.044 J+	0.031 J	< 0.041 U	0.84
E1668C	PCB-66	ng/l	0.32	0.47	0.45	0.16	0.58	0.25	2	0.058	0.035 J	0.032 J	0.48
E1668C	PCB-67	ng/l	0.0088 JN	0.012 J	0.012 JN	0.0046 JN	0.014 JN	< 0.026 U	0.052 JN	< 0.0018 U	< 0.00078 U	< 0.0032 U	0.013 JN
E1668C	PCB-68	ng/l	< 0.0055 U	< 0.0073 U	< 0.012 U	< 0.0025 U	0.0080 J	< 0.026 U	< 0.023 U	< 0.0018 U	< 0.00080 U	< 0.0032 U	0.0041 JN
E1668C	PCB-69	ng/l	0.13 J	0.19	0.31 J	0.069 J	0.52	0.16 J	1.5	0.023 J	0.018 J	0.014 JN	0.46
E1668C	PCB-7	ng/l	< 0.0026 U	< 0.0024 U	< 0.025 U	< 0.0018 U	0.0077 JN	< 0.0091 UJ	0.035 JN	< 0.0030 U	< 0.0020 U	< 0.0025 U	0.0062 JN
E1668C	PCB-70	ng/l	0.88	1.4	1.1 J	0.28 J	0.97	0.68 J	4.1	0.093 J	0.074 J	0.072 J	1.1
E1668C	PCB-71	ng/l	0.13 J	0.20 J	0.29 J	0.077 J	0.4	0.18 J	1.7	0.028 JN	0.014 J	0.019 JN	0.46
E1668C	PCB-72	ng/l	< 0.0061 U	< 0.0081 U	< 0.013 U	< 0.0027 U	0.010 J	< 0.029 U	< 0.026 U	< 0.0020 U	< 0.00089 U	< 0.0036 U	0.0041 J
E1668C	PCB-73	ng/l	< 0.0079 U	< 0.011 U	< 0.017 U	< 0.0035 U	0.026 J	< 0.037 U	0.077 J	< 0.0026 U	< 0.0011 U	< 0.0047 U	0.027 J
E1668C	PCB-74	ng/l	0.88	1.4	1.1 J	0.28 J	0.97	0.68 J	4.1	0.093 J	0.074 J	0.072 J	1.1
E1668C	PCB-75	ng/l	0.017 J	0.026 J	0.052 J	0.011 J	0.064 J	< 0.028 U	0.23 J	0.0045 JN	0.0031 J	< 0.0035 U	0.074 J
E1668C	PCB-76	ng/l	0.88	1.4	1.1 J	0.28 J	0.97	0.68 J	4.1	0.093 J	0.074 J	0.072 J	1.1

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
E1668C	PCB-77	ng/l	0.13	0.17	0.13 JN	0.048 J	0.087	0.061 J	0.24 J	0.014 J	0.0081 J+	0.011 JN	0.094
E1668C	PCB-78	ng/l	< 0.0063 U	< 0.0084 U	< 0.014 U	< 0.0028 U	< 0.0021 U	< 0.030 U	< 0.026 U	< 0.0021 U	< 0.00092 U	< 0.0037 U	< 0.0039 U
E1668C	PCB-79	ng/l	0.017 JN	0.020 J	0.017 JN	0.0035 JN	0.0086 J	< 0.026 U	< 0.023 U	< 0.0018 U	< 0.00079 U	< 0.0032 U	0.0092 J
E1668C	PCB-8	ng/l	0.044 J	0.048 J	0.22 J	0.033 J	0.19	0.021 JN	1.2	0.020 JN	0.021 JN	0.0092 JN	0.21
E1668C	PCB-80	ng/l	< 0.0053 U	< 0.0071 U	< 0.012 U	< 0.0024 U	< 0.0018 U	< 0.025 U	< 0.022 U	< 0.0018 U	< 0.00078 U	< 0.0032 U	< 0.0033 U
E1668C	PCB-81	ng/l	< 0.0056 U	< 0.0074 U	< 0.012 U	< 0.0025 U	0.0033 JN	< 0.025 U	< 0.021 U	< 0.0019 U	< 0.00084 U	< 0.0033 U	< 0.0033 U
E1668C	PCB-82	ng/l	0.23	0.22	0.23 J	0.068 J	0.16	0.046 JN	0.32 J	0.027 JN	0.018 J	0.018 JN	0.11
E1668C	PCB-83	ng/l	0.77	0.77	0.82	0.24	0.78	0.021 JN	1.2	0.086	0.066 JN	0.052 JN	0.47
E1668C	PCB-84	ng/l	0.33	0.38	0.31 J	0.095 JN	0.37	0.11 J	0.73	0.051	0.035 J	0.025 JN	0.27
E1668C	PCB-85	ng/l	0.27	0.26	0.25 J	0.088 J	0.25	0.051 JN	0.35 J	0.037 J	0.026 J	0.023 J	0.15
E1668C	PCB-86	ng/l	1.1	1.2	1.1 JN	0.38 J	0.94	0.32 J	1.6 JN	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-87	ng/l	1.1	1.2	1.1 J	0.38 J	0.94	0.32 J	1.6 J	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-88	ng/l	0.11 JN	0.15 J	0.17 J	0.052 J	0.26	0.064 J	0.31 J	0.023 J	0.017 J	0.011 JN	0.14
E1668C	PCB-89	ng/l	0.0092 JN	0.013 J	< 0.0037 U	0.0047 JN	0.010 JN	< 0.0020 U	0.022 JN	< 0.0011 U	< 0.00070 U	< 0.0011 U	0.0067 JN
E1668C	PCB-9	ng/l	< 0.0026 U	0.0035 JN	< 0.026 U	< 0.0018 U	0.011 JN	< 0.0093 UJ	0.081 JN	< 0.0031 U	< 0.0021 U	< 0.0025 U	0.014 JN
E1668C	PCB-90	ng/l	1.6	1.7	1.8	0.47	1.5	0.47 J	2.6	0.15	0.16	0.12 J	0.96
E1668C	PCB-91	ng/l	0.11 JN	0.15 J	0.17 J	0.052 J	0.26	0.064 J	0.31 J	0.023 J	0.017 J	0.011 JN	0.14
E1668C	PCB-92	ng/l	0.23	0.27	0.22 J	0.075 J	0.31	0.077 J	0.38 JN	0.031 J	0.025 J	0.018 J	0.17
E1668C	PCB-93	ng/l	0.0090 J	0.0063 JN	0.0087 JN	0.0048 JN	0.047 J	< 0.0018 U	0.026 JN	0.0034 JN	0.0022 JN	0.0016 JN	0.0086 J
E1668C	PCB-94	ng/l	0.0025 JN	< 0.00078 U	< 0.0037 U	0.0018 JN	0.017 J	< 0.0020 U	0.0093 JN	< 0.0011 U	< 0.00070 U	< 0.0011 U	0.0033 JN
E1668C	PCB-95	ng/l	0.89	1.1	0.87 JN	0.32	1.3	0.36 JN	2.5	0.14	0.15	0.081	1
E1668C	PCB-96	ng/l	0.0034 J	0.0037 JN	< 0.0028 U	0.0029 J	0.014 J	< 0.0015 U	0.019 JN	< 0.00081 U	< 0.00053 U	< 0.00080 U	0.0060 JN
E1668C	PCB-97	ng/l	1.1	1.2	1.1 J	0.38 J	0.94	0.32 J	1.6 J	0.11 J	0.098 J	0.081 JN	0.61
E1668C	PCB-98	ng/l	0.022 J	0.026 JN	0.020 JN	0.010 J	0.043 JN	< 0.0017 U	0.061 JN	0.0056 JN	0.0029 JN	< 0.00090 U	0.028 J
E1668C	PCB-99	ng/l	0.77	0.77	0.82	0.24	0.78	0.021 JN	1.2	0.086	0.066 J	0.052 JN	0.47
E1668C	Pentachlorobiphenyl	ng/l	12	13	12	3.4	9.7	3	19	1.2	1.1	0.82	7
E1668C	Tetrachlorobiphenyl	ng/l	2.9	4.3	4.7	1.2	5.9	2.5	22	0.44	0.3	0.30 J	6.3
E1668C	Trichlorobiphenyl	ng/l	0.77	0.86	2.7	0.65	3.2	0.54	12	0.22	0.16	0.14 J	3.1
SW6020A	Aluminum	ug/l	570	710	1100	530	920	650	6200	380	380	260	2200
SW6020A	Antimony	ug/l	1.2 J	1.1 J	0.88 J	1.9 J	1.3 J	2.2	5.4	0.51 J	0.48 J	1.3 J	2
SW6020A	Arsenic	ug/l	0.99 J	1.1	0.56 J	1.1	1.4	2.1	2.6	2.1	2.9	1.4	2.4
SW6020A	Barium	ug/l	19	20	22	15	14	28	150	12	10	21	56
SW6020A	Beryllium	ug/l	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	0.27 J	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
SW6020A	Cadmium	ug/l	0.27 J	0.23 J	< 1.0 U	0.30 J	< 1.0 U	0.25 J	1	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
SW6020A	Calcium	ug/l	11000	11000	7000	8700	5500	28000	28000	14000	9300	18000	18000
SW6020A	Chromium	ug/l	3.6	3.5	3.2	3	3.9	5.1	17	2.1	1.8 J	9.7	5.8
SW6020A	Cobalt	ug/l	0.89	0.98	0.7	0.89	0.97	2.5	4.4	0.52	0.58	0.68	1.4
SW6020A	Copper	ug/l	17	17	12	24	14	47	86	8.2	4.5	20	19
SW6020A	Iron	ug/l	1500	1700	2300	1200	2300	2200	13000	720	870	650	4200
SW6020A	Lead	ug/l	9.7	11	18	20	21	48	100	3.4	3.6	5.5	14
SW6020A	Magnesium	ug/l	1100	1200	1300	1600	2100	2600	4900	3300	2300	1800	3600
SW6020A	Manganese	ug/l	36	37	37	52	58	100	190	21	16	30	68
SW6020A	Nickel	ug/l	3	3.1	2.4	4.5	8.7	8.8	13	6.8	5.4	4.1	7.2
SW6020A	Potassium	ug/l	3200	3300	1200	2600	1100	14000	3100	2000	3100	5500	1700
SW6020A	Selenium	ug/l	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U
SW6020A	Silver	ug/l	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	0.20 J	1	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
SW6020A	Sodium	ug/l	5000	4900	1500	5400	2000	18000	3500	7900	4700	12000	2400
SW6020A	Thallium	ug/l	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U

Table 3-3
Treatability Study Stormwater Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	Outfall 01			Outfall 02		Outfall 03		Outfall 04		Outfall 05	
		Sample ID	OFW0100N	OFW0100R	OFW0100N-102920	OFW0200N	OFW0200N-102920	OFW0300N	OFW0300N-102920	OFW0400N	OFW0400N-102920	OFW0500N	OFW0500N-102920
		Sample Date	7/22/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	7/22/2020	10/29/2020	8/13/2020	10/29/2020	7/22/2020	10/29/2020
		Sample Type	N	FD	N	N	N	N	N	N	N	N	N
Method	Chemical Name	Units											
SW6020A	Vanadium	ug/l	4	4.3	3.8	8	18	9.1	16	29	26	10	12
SW6020A	Zinc	ug/l	110	130	110	150	100	300	650	36	39	74	100
SW7470A	Mercury	ug/l	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U	< 0.20 U
SW8015D DRO	Diesel Range Organics (C10-C28)	ug/l	1900 J+	1800 J+	2800 J+	840 J+	360 J+	8200 J+	12000 J+	330 J+	< 460 U	2000 J+	1200 J+
SW8015D DRO	ORO (C24-C40)	ug/l	2800 J+	2700 J+	3900 J+	1000 J+	450 J+	7200 J+	11000 J+	560 J+	250 J	2800 J+	2000 J+
SW8270D LL	Acenaphthene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Acenaphthylene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	0.096 J	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Anthracene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Benzo(a)anthracene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	0.12 J	< 0.15 U	< 0.18 U	0.085 J	< 0.18 U
SW8270D LL	Benzo(a)pyrene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	0.069 J	< 0.18 U
SW8270D LL	Benzo(b)fluoranthene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	0.12 J	< 0.16 U	0.16 J	< 0.15 U	< 0.18 U	0.13 J	< 0.18 U
SW8270D LL	Benzo(g,h,i)perylene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	0.075 J	0.12 J	< 0.15 U	< 0.18 U	0.17	< 0.18 U
SW8270D LL	Benzo(k)fluoranthene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	0.15	< 0.18 U
SW8270D LL	Chrysene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	0.094 J	< 0.16 U	0.17 J	< 0.15 U	< 0.18 U	0.14 J	< 0.18 U
SW8270D LL	Dibenzo(a,h)anthracene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	0.17	< 0.18 U
SW8270D LL	Fluoranthene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	0.088 J	0.17 J	0.077 J	0.31	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Fluorene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Indeno(1,2,3-cd)pyrene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.19 U	< 0.15 U	< 0.18 U	0.16	< 0.18 U
SW8270D LL	Naphthalene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	< 0.18 U	< 0.16 U	0.059 J	< 0.15 U	< 0.18 U	< 0.15 U	< 0.18 U
SW8270D LL	Phenanthrene	ug/l	0.061 J	0.058 J	0.066 J	0.071 J	0.11 J	0.088 J	0.19	0.058 J+	< 0.18 U	0.074 J	< 0.18 U
SW8270D LL	Pyrene	ug/l	< 0.15 U	< 0.16 U	< 0.18 U	< 0.16 U	0.14 J	0.15 J	0.31	< 0.15 U	< 0.18 U	< 0.15 U	0.053 J

Notes:
ng/L = nanogram per liter
ug/l = micrograms per liter
J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte.
J+ = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte and may be biased high.
JN = The analyte was tentatively identified (Estimated Maximum Possible Concentration); the associated numerical value is the approximate concentration of the analyte in the sample.
U = The analyte was not detected above the indicated reporting detection limit.
Sample Type Codes:
N = Normal sample
FD = Filed Duplicate sample

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
D422	Hydrometer Reading 1 - Percent Finer	% passed				71.7	78.3	33.2	21.1	41.4	39.4			
D422	Hydrometer Reading 2 - Percent Finer	% passed				61.3	71.8	30.1	17.9	33.2	29.9			
D422	Hydrometer Reading 3 - Percent Finer	% passed				52.1	61.4	24.3	14.7	25	25.1			
D422	Hydrometer Reading 4 - Percent Finer	% passed				45.2	52.3	21.1	13.1	20	20.4			
D422	Hydrometer Reading 5 - Percent Finer	% passed				38.3	41.9	18	9.9	15.1	15.6			
D422	Hydrometer Reading 6 - Percent Finer	% passed				29	31.5	13.5	6.7	10.1	10.9			
D422	Hydrometer Reading 7 - Percent Finer	% passed				21	19.7	9.7	3.5	8.5	7.3			
D422	Sieve Size #10 - Percent Finer	% passed				100	98.5	74.9	82.6	97.6	97.8			
D422	Sieve Size #100 - Percent Finer	% passed				94.1	86.7	42.1	66.6	84.3	79.5			
D422	Sieve Size #20 - Percent Finer	% passed				99.5	96.7	69.4	78.9	95	95.6			
D422	Sieve Size #200 - Percent Finer	% passed				91	82.4	36.4	62.2	79.5	66.9			
D422	Sieve Size #4 - Percent Finer	% passed				100	100	80.5	87.6	100	100			
D422	Sieve Size #40 - Percent Finer	% passed				97.7	93.9	58.2	74.7	91.8	91.5			
D422	Sieve Size #60 - Percent Finer	% passed				96	90.8	48.5	70.7	88.5	87.1			
D422	Sieve Size #80 - Percent Finer	% passed				95.2	88.4	44.6	68.5	86.5	83.4			
D422	Sieve Size 0.375 inch - Percent Finer	% passed				100	100	100	95.4	100	100			
D422	Sieve Size 0.75 inch - Percent Finer	% passed				100	100	100	100	100	100			
D422	Sieve Size 1 inch - Percent Finer	% passed				100	100	100	100	100	100			
D422	Sieve Size 1.5 inch - Percent Finer	% passed				100	100	100	100	100	100			
D422	Sieve Size 2 inch - Percent Finer	% passed				100	100	100	100	100	100			
D422	Sieve Size 3 inch - Percent Finer	% passed				100	100	100	100	100	100			
D4464	Gravel (greater than 2 mm)	percent							< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U
D4464	Very Coarse Sand (1 to 2 mm)	percent							< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U
D4464	Coarse Sand (0.5mm to 1 mm)	percent							< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U	< 0.01 U
D4464	Medium Sand (0.25 to 0.5 mm)	percent							3.03	3.05	0.02	< 0.01 U	2.22	1.86
D4464	Fine Sand (0.125 to 0.25mm)	percent							15.96	10.65	9.34	7.3	12.41	17.67
D4464	Very Fine Sand (0.0625 to 0.125 mm)	percent							17.54	13.59	13.35	12.5	15.98	17.39
D4464	Silt (0.00391 to 0.0625 mm)	percent							57.76	67.45	70.76	70.72	61.97	56.12
D4464	Total Silt and Clay (0 to 0.0626 mm)	percent							63.48	72.72	77.29	80.2	69.39	63.08
D4464	Clay (less than 0.00391 mm)	percent							5.72	5.27	6.53	9.48	7.42	6.96
D5057	BULK DENSITY OF SOILS	g/cc				1.7	1.5	2.1				1.4	1.4	1.4
E1668C	Decachlorobiphenyl (PCB -209)	ng/g	0.034 J	0.082	0.25				1.1	0.76	0.94	0.56	0.57	0.37
E1668C	Dichloro iphenyl	ng/g	1.1	0.93	1.4				13	21	30	5.1	4.1	3.9
E1668C	Heptachlorobiphenyl	ng/g	11	4	40				150	160	280	42	21	12
E1668C	Hexachlorobiphenyl	ng/g	16	7.9	57				210	220	400	75	51	24
E1668C	Monochlorobiphenyl	ng/g	0.19	0.0098 J	0.09				0.63	0.89	1.5	0.24	0.17	0.26
E1668C	Nonachlorobiphenyl	ng/g	0.35	0.21	0.87				5.9	5.1	7.2	1.9	1.5	0.92
E1668C	Octachlorobiphenyl	ng/g	3.4	0.86	9.2				36	40	67	11	5.6	3.5
E1668C	PCB , Total Congeners (Provided by Lab)	ng/g	57	22	150				730	930	1500	290	190	120
E1668C	PCB -1	ng/g	0.12	0.0055 J	0.047 J				0.34	0.43	0.77	0.13	0.091	0.17
E1668C	PCB -10	ng/g	< 0.0077 U	< 0.011 U	< 0.010 U				0.071 J	0.099 J	0.16	0.055	0.041	0.042
E1668C	PCB -100	ng/g	0.012 J	< 0.0018 U	0.029 J				0.5	0.39	1.2	0.22	0.12	0.13
E1668C	PCB -101	ng/g	2.1	0.84	3.8				26	29	50	10	8.1	4
E1668C	PCB -102	ng/g	0.035 J	0.015 J	0.10 J				0.58	0.8	1.5	0.37	0.27	0.18
E1668C	PCB -103	ng/g	< 0.0019 U	< 0.0018 U	0.015 J				0.19	0.24	0.84	0.12	0.06	0.042
E1668C	PCB -104	ng/g	< 0.0014 U	< 0.0014 U	< 0.00096 U				< 0.0026 U	< 0.0031 U	0.026 J	< 0.00062 U	< 0.00061 U	0.0030 J
E1668C	PCB -105	ng/g	1.2	0.3	1.3				8	9.7	13	3.5	3.9	1.5
E1668C	PCB -106	ng/g	< 0.0071 U	< 0.0076 U	< 0.0079 U				< 0.025 U	< 0.028 U	< 0.023 U	< 0.0086 U	< 0.0068 U	< 0.0046 U
E1668C	PCB -107	ng/g	0.17	0.055 J	0.23				1.6	2.1	3.2	0.72	0.63	0.24
E1668C	PCB -108	ng/g	0.10 J	0.025 J	0.15				0.81	0.98	1.4	0.37	0.36	0.13

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
E1668C	PCB -109	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -11	ng/g	0.78	0.82	0.24				2.2	0.58	2.4	0.34	0.39	0.19
E1668C	PCB -110	ng/g	3.2	1.3	7.8				31	33	52	11	10	4.8
E1668C	PCB -111	ng/g	< 0.0013 U	< 0.0013 U	< 0.00089 U				< 0.0024 U	< 0.0029 U	< 0.0019 U	< 0.00058 U	< 0.00056 U	< 0.00030 U
E1668C	PCB -112	ng/g	0.0091 J	< 0.0013 U	0.0094 J				0.12 J	0.083 J	0.24	0.04	0.027	0.016 J
E1668C	PCB -113	ng/g	2.1	0.84	3.8				26	29	50	10	8.1	4
E1668C	PCB -114	ng/g	0.053 J	0.0086 J	0.058 J				0.32	0.53	0.67	0.2	0.2	0.08
E1668C	PCB -115	ng/g	3.2	1.3	7.8				31	33	52	11	10	4.8
E1668C	PCB -116	ng/g	0.45	0.15 J	0.67				4.4	4.8	7	1.8	1.7	0.84
E1668C	PCB -117	ng/g	0.45	0.15 J	0.67				4.4	4.8	7	1.8	1.7	0.84
E1668C	PCB -118	ng/g	2.4	0.79	3				19	23	36	8.4	8.4	3.3
E1668C	PCB -119	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -12	ng/g	< 0.0070 U	< 0.0097 U	0.056 J				0.47	0.86	1.1	0.19	0.13	0.11
E1668C	PCB -120	ng/g	< 0.0014 U	0.0069 J	0.010 J				0.085 J	0.12 J	< 0.0019 U	0.032	0.022 J	0.0086 J
E1668C	PCB -121	ng/g	< 0.0014 U	< 0.0013 U	< 0.00093 U				< 0.0025 U	< 0.0030 U	< 0.0020 U	< 0.00060 U	< 0.00059 U	< 0.00032 U
E1668C	PCB -122	ng/g	0.035 J	0.010 J	0.038 J				0.37	0.41	0.57	0.16	0.15	0.072
E1668C	PCB -123	ng/g	0.052 J	0.013 J	0.042 J				0.35	0.39	0.65	0.16	0.2	0.088
E1668C	PCB -124	ng/g	0.10 J	0.025 J	0.15				0.81	0.98	1.4	0.37	0.36	0.13
E1668C	PCB -125	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -126	ng/g	0.022 J	< 0.0085 U	0.021 J				0.11 J	0.21	0.36	0.034	0.024	0.011 J
E1668C	PCB -127	ng/g	< 0.0071 U	< 0.0076 U	< 0.0079 U				< 0.025 U	< 0.028 U	< 0.023 U	< 0.0086 U	0.0086 J	< 0.0046 U
E1668C	PCB -128	ng/g	0.61	0.3	1.6				5.4	5.4	8.8	2.1	1.8	0.77
E1668C	PCB -129	ng/g	3.9	1.9	12				46	48	81	16	12	5.6
E1668C	PCB -13	ng/g	< 0.0070 U	< 0.0097 U	0.056 J				0.47	0.86	1.1	0.19	0.13	0.11
E1668C	PCB -130	ng/g	0.23	0.11	0.71				2.6	2.6	4.5	0.92	0.71	0.3
E1668C	PCB -131	ng/g	0.041 J	< 0.016 U	0.12				0.33	0.41	0.75	0.18	0.16	0.061
E1668C	PCB -132	ng/g	1.2	0.51	4.2				13	14	27	5.2	3.9	1.7
E1668C	PCB -133	ng/g	0.026 J	0.023 J	0.13				0.56	0.65	1.3	0.26	0.14	0.069
E1668C	PCB -134	ng/g	0.17	0.063 J	0.67				2.2	2.1	4	0.87	0.65	0.28
E1668C	PCB -135	ng/g	1	0.56	5.8				18	19	34	5.3	3.1	1.7
E1668C	PCB -136	ng/g	0.29	0.16	1.8				5.4	5.6	11	1.8	1.1	0.58
E1668C	PCB -137	ng/g	0.19	0.055 J	0.4				1.4	1.3	2.1	0.56	0.57	0.21
E1668C	PCB -138	ng/g	3.9	1.9	12				46	48	81	16	12	5.6
E1668C	PCB -139	ng/g	0.057 J	0.022 J	0.14				0.45	0.4	0.92	0.23	0.2	0.076
E1668C	PCB -14	ng/g	< 0.0059 U	< 0.0082 U	< 0.0077 U				< 0.017 U	< 0.019 U	< 0.0067 U	< 0.0022 U	< 0.0022 U	< 0.0021 U
E1668C	PCB -140	ng/g	0.057 J	0.022 J	0.14				0.45	0.4	0.92	0.23	0.2	0.076
E1668C	PCB -141	ng/g	0.75	0.25	2.4				10	11	20	3.5	2.2	1.1
E1668C	PCB -142	ng/g	< 0.016 U	< 0.015 U	< 0.016 U				< 0.057 U	< 0.057 U	< 0.062 U	< 0.018 U	< 0.012 U	< 0.0066 U
E1668C	PCB -143	ng/g	0.17	0.063 J	0.67				2.2	2.1	4	0.87	0.65	0.28
E1668C	PCB -144	ng/g	0.12	0.056 J	0.67				1.9	2.1	3.8	0.63	0.37	0.2
E1668C	PCB -145	ng/g	< 0.0013 U	< 0.0017 U	0.0079 J				< 0.0031 U	< 0.0034 U	< 0.0027 U	0.0053 J	0.0053 J	0.0026 J
E1668C	PCB -146	ng/g	0.45	0.3	1.7				7	7.6	14	2.6	1.5	0.72
E1668C	PCB -147	ng/g	2.8	1.5	13				42	45	86	16	9.6	4.7
E1668C	PCB -148	ng/g	< 0.0019 U	< 0.0024 U	< 0.0019 U				0.043 J	0.042 J	0.12	0.029	0.0096 J	0.0067 J
E1668C	PCB -149	ng/g	2.8	1.5	13				42	45	86	16	9.6	4.7
E1668C	PCB -15	ng/g	0.14	0.067 J	0.58				4.7	7.2	9.3	1.4	1	0.84
E1668C	PCB -150	ng/g	< 0.0013 U	< 0.0016 U	0.0086 J				0.042 J	0.059 J	0.15	0.026	0.012 J	0.0071 J
E1668C	PCB -151	ng/g	1	0.56	5.8				18	19	34	5.3	3.1	1.7
E1668C	PCB -152	ng/g	< 0.0014 U	< 0.0018 U	< 0.0014 U				< 0.0032 U	< 0.0035 U	0.067 J	0.012 J	0.0069 J	0.0054 J
E1668C	PCB -153	ng/g	2.8	1.6	8.4				39	43	77	14	8.9	4.4

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
E1668C	PCB -154	ng/g	0.021 J	0.021 J	0.056 J				0.37	0.41	0.94	0.19	0.095	0.05
E1668C	PCB -155	ng/g	< 0.0013 U	< 0.0017 U	< 0.0013 U				< 0.0030 U	< 0.0033 U	0.0098 J	< 0.00055 U	< 0.00062 U	< 0.00028 U
E1668C	PCB - 156	ng/g	0.46	0.14	0.84				3.8	4.1	6.3	1.5	1.3	0.52
E1668C	PCB - 157	ng/g	0.46	0.14	0.84				3.8	4.1	6.3	1.5	1.3	0.52
E1668C	PCB - 158	ng/g	0.42	0.17	1.1				4	4.3	7.2	1.6	1.2	0.53
E1668C	PCB - 159	ng/g	0.025 J	< 0.0098 U	0.14				0.49	0.59	1	0.16	0.076	0.045
E1668C	PCB - 16	ng/g	0.12	0.021 J	0.076				2.1	4.4	6.2	1.2	0.82	1
E1668C	PCB - 160	ng/g	3.9	1.9	12				46	48	81	16	12	5.6
E1668C	PCB - 161	ng/g	< 0.011 U	< 0.0097 U	< 0.011 U				< 0.038 U	< 0.038 U	< 0.041 U	0.016 J	< 0.0079 U	0.0051 J
E1668C	PCB -162	ng/g	0.012 J	< 0.0096 U	0.029 J				0.14 J	0.12 J	0.25	0.044	0.025	0.010 J
E1668C	PCB -163	ng/g	3.9	1.9	12				46	48	81	16	12	5.6
E1668C	PCB -164	ng/g	0.26	0.12	0.99				3.1	3.4	6	1.1	0.81	0.38
E1668C	PCB -165	ng/g	< 0.012 U	< 0.011 U	< 0.012 U				< 0.043 U	< 0.043 U	< 0.047 U	< 0.013 U	< 0.0090 U	< 0.0050 U
E1668C	PCB -166	ng/g	0.61	0.3	1.6				5.4	5.4	8.8	2.1	1.8	0.77
E1668C	PCB -167	ng/g	0.14	0.063 J	0.37				1.6	1.7	2.7	0.52	0.4	0.18
E1668C	PCB -168	ng/g	2.8	1.6	8.4				39	43	77	14	8.9	4.4
E1668C	PCB -169	ng/g	< 0.0083 U	< 0.0074 U	< 0.0081 U				< 0.029 U	< 0.029 U	< 0.032 U	0.061	0.026	0.017 J
E1668C	PCB -17	ng/g	0.12	0.021 J	0.073				2.4	5.8	8.8	1.8	1.3	1.5
E1668C	PCB -170	ng/g	1.3	0.5	4.5				18	19	32	5.1	2.6	1.5
E1668C	PCB -171	ng/g	0.32	0.12 J	1.3				5.4	5.5	9.5	1.4	0.74	0.38
E1668C	PCB -172	ng/g	0.18	0.075	0.82				3.3	3.6	6	0.85	0.42	0.25
E1668C	PCB -173	ng/g	0.32	0.12 J	1.3				5.4	5.5	9.5	1.4	0.74	0.38
E1668C	PCB -174	ng/g	1.4	0.44	5.3				20	21	36	5.3	2.6	1.6
E1668C	PCB -175	ng/g	0.040 J	0.016 J	0.18				0.72	0.69	1.4	0.2	0.095	0.055
E1668C	PCB -176	ng/g	0.13	0.044 J	0.57				2.2	2.3	4.3	0.64	0.3	0.17
E1668C	PCB -177	ng/g	0.65	0.25	2.8				11	11	19	2.9	1.4	0.88
E1668C	PCB -178	ng/g	0.29	0.11	1				4	4.1	7.4	1.1	0.54	0.32
E1668C	PCB -179	ng/g	0.56	0.19	2.2				8.4	8.8	16	2.5	1.1	0.67
E1668C	PCB -18	ng/g	0.28	0.058 J	0.17				5.3	11	15	3.1	2.2	2.5
E1668C	PCB -180	ng/g	2.9	1.1	11				41	44	72	11	5.2	3.3
E1668C	PCB -181	ng/g	0.011 J	< 0.0054 U	< 0.0030 U				0.072 J	0.077 J	< 0.0069 U	0.032	0.028	< 0.00059 U
E1668C	PCB -182	ng/g	< 0.0036 U	0.0052 J	< 0.0029 U				0.091 J	0.10 J	0.19	0.043	0.010 J	0.011 J
E1668C	PCB -183	ng/g	0.9	0.32	3.4				13	13	24	3.6	1.7	1
E1668C	PCB -184	ng/g	< 0.0031 U	< 0.0044 U	< 0.0025 U				< 0.0056 U	< 0.0083 U	< 0.0057 U	< 0.0011 U	< 0.0012 U	< 0.00048 U
E1668C	PCB -185	ng/g	0.9	0.32	3.4				13	13	24	3.6	1.7	1
E1668C	PCB -186	ng/g	< 0.0030 U	< 0.0043 U	< 0.0024 U				< 0.0054 U	< 0.0081 U	< 0.0055 U	< 0.0011 U	< 0.0012 U	< 0.00047 U
E1668C	PCB -187	ng/g	1.6	0.69	6.1				23	24	42	6.5	3.2	1.9
E1668C	PCB -188	ng/g	< 0.0025 U	< 0.0038 U	< 0.0022 U				< 0.0048 U	< 0.0070 U	0.045 J	< 0.00087 U	< 0.0010 U	< 0.00041 U
E1668C	PCB -189	ng/g	0.019 J	< 0.0069 U	0.13				0.56	0.64	1	0.17	0.09	0.053
E1668C	PCB -19	ng/g	0.031 J	< 0.0025 U	0.017 J				0.77	0.99	1.9	0.64	0.48	0.52
E1668C	PCB -190	ng/g	0.21	0.084	0.81				3.2	3.5	5.6	0.89	0.51	0.29
E1668C	PCB -191	ng/g	0.032 J	0.018 J	0.17				0.65	0.74	1.3	0.21	0.11	0.063
E1668C	PCB -192	ng/g	< 0.0032 U	< 0.0045 U	< 0.0026 U				< 0.0057 U	< 0.0086 U	< 0.0058 U	< 0.0011 U	< 0.0013 U	< 0.00050 U
E1668C	PCB -193	ng/g	2.9	1.1	11				41	44	72	11	5.2	3.3
E1668C	PCB -194	ng/g	0.81	0.19	2.2				8.8	9.6	16	2.9	1.4	0.83
E1668C	PCB -195	ng/g	0.31	0.08	0.91				3.5	3.8	6.8	1.1	0.54	0.33
E1668C	PCB -196	ng/g	0.4	0.099	1.1				4.3	4.6	8	1.2	0.57	0.35
E1668C	PCB -197	ng/g	0.0088 J	0.0088 J	0.046 J				0.25	0.26	0.49	0.096	0.042	0.024
E1668C	PCB -198	ng/g	0.93	0.26	2.5				9.9	11	18	2.9	1.5	0.95
E1668C	PCB -199	ng/g	0.93	0.26	2.5				9.9	11	18	2.9	1.5	0.95

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
E1668C	PCB -2	ng/g	0.014 J	< 0.00092 U	< 0.0011 U				0.045 J	0.14 J	0.19	0.033	0.023	0.024
E1668C	PCB -20	ng/g	0.54	0.17	1.1				15	32	37	7.5	4.2	3.8
E1668C	PCB -200	ng/g	0.09	0.019 J	0.27				1	1.1	1.9	0.32	0.14	0.094
E1668C	PCB -201	ng/g	0.094	0.025 J	0.23				0.97	1.1	1.9	0.32	0.15	0.092
E1668C	PCB -202	ng/g	0.17	0.051 J	0.4				1.6	1.8	3	0.57	0.3	0.19
E1668C	PCB -203	ng/g	0.54	0.13	1.4				5.5	6.1	9.8	1.8	0.93	0.58
E1668C	PCB -204	ng/g	< 0.0034 U	< 0.0038 U	< 0.0042 U				< 0.0069 U	< 0.0089 U	< 0.0067 U	< 0.0016 U	< 0.0011 U	< 0.00041 U
E1668C	PCB -205	ng/g	0.025 J	< 0.0097 U	0.11				0.4	0.48	0.82	0.15	0.071	0.044
E1668C	PCB -206	ng/g	0.27	0.16	0.67				4.4	3.8	5.3	1.4	1.1	0.66
E1668C	PCB -207	ng/g	0.025 J	< 0.010 U	0.063 J				0.4	0.37	0.59	0.14	0.1	0.06
E1668C	PCB -208	ng/g	0.050 J	0.045 J	0.14				1.1	0.9	1.3	0.37	0.32	0.2
E1668C	PCB -21	ng/g	0.27	0.081 J	0.43				5.3	14	15	2.5	1.7	1.6
E1668C	PCB -22	ng/g	0.21	0.056 J	0.34				4.5	10	12	2.3	1.3	1.2
E1668C	PCB -23	ng/g	< 0.0033 U	< 0.0033 U	< 0.0038 U				< 0.016 U	< 0.020 U	0.031 J	0.0052 J	0.0044 J	0.0033 J
E1668C	PCB -24	ng/g	0.0050 J	< 0.0017 U	0.0044 J				0.095 J	0.18	0.32	0.077	0.052	0.059
E1668C	PCB -25	ng/g	0.034 J	0.0099 J	0.063 J				1.1	2.4	4.9	0.75	0.43	0.39
E1668C	PCB -26	ng/g	0.078 J	0.022 J	0.12 J				2	4.5	9.4	1.3	0.75	0.68
E1668C	PCB -27	ng/g	0.017 J	< 0.0015 U	0.015 J				0.63	1.1	1.6	0.47	0.35	0.36
E1668C	PCB -28	ng/g	0.54	0.17	1.1				15	32	37	7.5	4.2	3.8
E1668C	PCB -29	ng/g	0.078 J	0.022 J	0.12 J				2	4.5	9.4	1.3	0.75	0.68
E1668C	PCB -3	ng/g	0.051 J	0.0043 J	0.043 J				0.24	0.32	0.5	0.08	0.054	0.069
E1668C	PCB -30	ng/g	0.28	0.058 J	0.17				5.3	11	15	3.1	2.2	2.5
E1668C	PCB -31	ng/g	0.42	0.12 J	0.75				9.7	23	27	5.2	3.2	3
E1668C	PCB -32	ng/g	0.12	0.020 J	0.093				2.7	4.6	6.6	1.8	1.1	1.1
E1668C	PCB -33	ng/g	0.27	0.081 J	0.43				5.3	14	15	2.5	1.7	1.6
E1668C	PCB -34	ng/g	< 0.0034 U	< 0.0034 U	< 0.0040 U				< 0.017 U	0.10 J	0.16	0.037	0.019 J	0.017 J
E1668C	PCB -35	ng/g	0.017 J	0.0064 J	0.022 J				0.3	0.46	0.7	0.11	0.064	0.053
E1668C	PCB -36	ng/g	< 0.0032 U	< 0.0032 U	< 0.0037 U				< 0.016 U	< 0.020 U	< 0.017 U	< 0.0051 U	< 0.0040 U	0.0038 J
E1668C	PCB -37	ng/g	0.33	0.069 J	0.65				6.3	13	14	2.2	1.1	0.86
E1668C	PCB -38	ng/g	< 0.0034 U	< 0.0035 U	< 0.0040 U				< 0.017 U	< 0.021 U	< 0.018 U	< 0.0055 U	< 0.0043 U	< 0.0028 U
E1668C	PCB -39	ng/g	0.0044 J	< 0.0031 U	< 0.0036 U				< 0.015 U	0.060 J	< 0.016 U	0.033	0.019 J	0.016 J
E1668C	PCB -4	ng/g	0.073 J	< 0.013 U	0.067 J				1.2	2.2	3.6	1	0.87	0.96
E1668C	PCB -40	ng/g	0.52	0.11 J	0.32				6.2	12	17	3.9	2.3	2.1
E1668C	PCB -41	ng/g	0.52	0.11 J	0.32				6.2	12	17	3.9	2.3	2.1
E1668C	PCB -42	ng/g	0.22	0.044 J	0.13				2.9	5.4	9.1	1.9	1.1	0.94
E1668C	PCB -43	ng/g	0.028 J	< 0.0068 U	< 0.014 U				0.32	0.64	0.89	0.26	0.18	0.14
E1668C	PCB -44	ng/g	0.77	0.25	0.66				11	19	35	7.4	4.5	3.8
E1668C	PCB -45	ng/g	0.14	0.025 J	0.10 J				2.4	3.4	6.3	1.6	0.89	0.93
E1668C	PCB -46	ng/g	0.044 J	< 0.0093 U	0.024 J				0.69	1	1.9	0.46	0.27	0.27
E1668C	PCB -47	ng/g	0.77	0.25	0.66				11	19	35	7.4	4.5	3.8
E1668C	PCB -48	ng/g	0.15	0.019 J	0.062 J				1.7	4.2	4.9	1.3	0.77	0.67
E1668C	PCB -49	ng/g	0.42	0.12 J	0.36				7.1	12	27	4.7	2.9	2.3
E1668C	PCB -5	ng/g	< 0.0078 U	< 0.011 U	< 0.010 U				0.065 J	0.13 J	0.18	0.024 J	0.023	0.027
E1668C	PCB -50	ng/g	0.10 J	0.019 J	0.076 J				1.8	2.4	5	1.3	0.8	0.73
E1668C	PCB -51	ng/g	0.14	0.025 J	0.10 J				2.4	3.4	6.3	1.6	0.89	0.93
E1668C	PCB -52	ng/g	0.91	0.33	1.2				14	21	48	9	6	4.3
E1668C	PCB -53	ng/g	0.10 J	0.019 J	0.076 J				1.8	2.4	5	1.3	0.8	0.73
E1668C	PCB -54	ng/g	< 0.0011 U	< 0.00085 U	< 0.00058 U				0.058 J	0.058 J	0.2	0.055	0.027	0.034
E1668C	PCB -55	ng/g	0.027 J	< 0.0053 U	0.029 J				0.31	0.7	0.76	0.14	0.099	0.048
E1668C	PCB -56	ng/g	0.48	0.069 J	0.47				5.1	10	12	2.7	1.5	1.1

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
E1668C	PCB -57	ng/g	< 0.0064 U	< 0.0054 U	< 0.011 U				< 0.025 U	0.12 J	0.36	0.055	0.025	0.019 J
E1668C	PCB -58	ng/g	< 0.0065 U	< 0.0055 U	< 0.011 U				0.033 J	0.061 J	0.22	0.028	0.016 J	0.010 J
E1668C	PCB -59	ng/g	0.078 J	0.017 J	0.076 J				1.1	2	2.9	0.68	0.4	0.34
E1668C	PCB -6	ng/g	0.026 J	< 0.0096 U	0.063 J				0.8	1.6	2.7	0.39	0.27	0.29
E1668C	PCB -60	ng/g	0.28	0.043 J	0.25				2.5	5	5.5	1.4	0.78	0.57
E1668C	PCB -61	ng/g	1.6	0.35	1.8				17	35	47	10	6.3	4.2
E1668C	PCB -62	ng/g	0.078 J	0.017 J	0.076 J				1.1	2	2.9	0.68	0.4	0.34
E1668C	PCB -63	ng/g	0.025 J	< 0.0049 U	0.017 J				0.37	0.78	1.1	0.26	0.16	0.11
E1668C	PCB -64	ng/g	0.36	0.1	0.41				4.7	8.6	12	3	1.8	1.5
E1668C	PCB -65	ng/g	0.77	0.25	0.66				11	19	35	7.4	4.5	3.8
E1668C	PCB -66	ng/g	0.84	0.17	1				11	22	28	6.4	3.7	2.6
E1668C	PCB -67	ng/g	0.025 J	< 0.0047 U	0.020 J				0.34	0.81	1.1	0.2	0.1	0.077
E1668C	PCB -68	ng/g	< 0.0057 U	< 0.0048 U	< 0.0095 U				0.082 J	0.072 J	0.35	0.056	0.024	0.020 J
E1668C	PCB -69	ng/g	0.42	0.12 J	0.36				7.1	12	27	4.7	2.9	2.3
E1668C	PCB -7	ng/g	< 0.0071 U	< 0.0098 U	0.015 J				0.14 J	0.26	0.4	0.072	0.051	0.065
E1668C	PCB -70	ng/g	1.6	0.35	1.8				17	35	47	10	6.3	4.2
E1668C	PCB -71	ng/g	0.52	0.11 J	0.32				6.2	12	17	3.9	2.3	2.1
E1668C	PCB -72	ng/g	< 0.0063 U	< 0.0053 U	< 0.011 U				0.12 J	0.17 J	0.92	0.084	0.044	0.033
E1668C	PCB -73	ng/g	0.028 J	< 0.0068 U	< 0.014 U				0.32	0.64	0.89	0.26	0.18	0.14
E1668C	PCB -74	ng/g	1.6	0.35	1.8				17	35	47	10	6.3	4.2
E1668C	PCB -75	ng/g	0.078 J	0.017 J	0.076 J				1.1	2	2.9	0.68	0.4	0.34
E1668C	PCB -76	ng/g	1.6	0.35	1.8				17	35	47	10	6.3	4.2
E1668C	PCB -77	ng/g	0.2	0.058 J	0.23				2	3	3.7	0.69	0.39	0.28
E1668C	PCB -78	ng/g	< 0.0065 U	< 0.0055 U	< 0.011 U				< 0.026 U	< 0.029 U	< 0.030 U	< 0.0081 U	< 0.0049 U	< 0.0036 U
E1668C	PCB -79	ng/g	0.017 J	< 0.0047 U	0.014 J				0.13 J	0.16 J	0.27	0.065	0.047	0.022
E1668C	PCB -8	ng/g	0.13	0.038 J	0.37				3.5	7.4	9.9	1.5	1.2	1.3
E1668C	PCB -80	ng/g	< 0.0055 U	< 0.0046 U	< 0.0093 U				< 0.022 U	< 0.025 U	< 0.025 U	< 0.0069 U	< 0.0042 U	< 0.0030 U
E1668C	PCB -81	ng/g	0.0071 J	< 0.0049 U	< 0.010 U				0.048 J	0.073 J	0.13	0.026	0.015 J	0.0090 J
E1668C	PCB -82	ng/g	0.32	0.09	0.46				2.9	3.7	4.6	1.2	1.1	0.55
E1668C	PCB -83	ng/g	1.1	0.53	1.7				13	15	24	5.6	4.8	2.3
E1668C	PCB -84	ng/g	0.57	0.17	1.1				5.3	6.2	14	2.4	2	1
E1668C	PCB -85	ng/g	0.45	0.15 J	0.67				4.4	4.8	7	1.8	1.7	0.84
E1668C	PCB -86	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -87	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -88	ng/g	0.22	0.091 J	0.77				3.6	3.8	8.2	1.5	1.2	0.71
E1668C	PCB -89	ng/g	0.017 J	< 0.0020 U	0.024 J				0.18	0.31	0.46	0.12	0.094	0.051
E1668C	PCB -9	ng/g	< 0.0072 U	< 0.010 U	< 0.0094 U				0.18	0.41	0.57	0.097	0.076	0.076
E1668C	PCB -90	ng/g	2.1	0.84	3.8				26	29	50	10	8.1	4
E1668C	PCB -91	ng/g	0.22	0.091 J	0.77				3.6	3.8	8.2	1.5	1.2	0.71
E1668C	PCB -92	ng/g	0.34	0.11	0.76				4.7	5	10	1.9	1.4	0.69
E1668C	PCB -93	ng/g	0.012 J	< 0.0018 U	0.029 J				0.5	0.39	1.2	0.22	0.12	0.13
E1668C	PCB -94	ng/g	< 0.0021 U	< 0.0020 U	0.016 J				0.18	0.15 J	0.46	0.093	0.05	0.046
E1668C	PCB -95	ng/g	1.5	0.72	5.3				21	22	53	8.6	6.4	3.5
E1668C	PCB -96	ng/g	0.010 J	< 0.0015 U	0.027 J				0.17	0.2	0.51	0.1	0.062	0.055
E1668C	PCB -97	ng/g	1.7	0.53	2.3				15	17	26	6.3	5.6	2.6
E1668C	PCB -98	ng/g	0.035 J	0.015 J	0.10 J				0.58	0.8	1.5	0.37	0.27	0.18
E1668C	PCB -99	ng/g	1.1	0.53	1.7				13	15	24	5.6	4.8	2.3
E1668C	Pentachlorobiphenyl	ng/g	16	5.8	30				160	180	310	65	57	27
E1668C	Tetrachlorobiphenyl	ng/g	7.2	1.7	7.2				93	170	270	58	35	27
E1668C	Trichlorobiphenyl	ng/g	2.6	0.65	3.9				58	130	160	31	19	19

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
LKTOC	Total Organic Carbon	mg/kg							85000	82000	75000	37000	38000	31000
SW6020A	Aluminum	mg/kg	1400	1300	3900									
SW6020A	Antimony	mg/kg	0.21	0.63	0.44									
SW6020A	Arsenic	mg/kg	0.55	1.2	7.6									
SW6020A	Barium	mg/kg	17	13	41									
SW6020A	Beryllium	mg/kg	0.050 J	0.069 J	0.46									
SW6020A	Cadmium	mg/kg	0.31	0.13	0.6									
SW6020A	Calcium	mg/kg	10000	18000	4600									
SW6020A	Chromium	mg/kg	4.9	5	21									
SW6020A	Cobalt	mg/kg	1.8	1.9	7.8									
SW6020A	Copper	mg/kg	14	35	55									
SW6020A	Iron	mg/kg	6300	8400	30000									
SW6020A	Lead	mg/kg	15	28	35									
SW6020A	Magnesium	mg/kg	3700	8700	3100									
SW6020A	Manganese	mg/kg	72	110	300									
SW6020A	Nickel	mg/kg	4.2	12	29									
SW6020A	Potassium	mg/kg	140	160	520									
SW6020A	Selenium	mg/kg	< 0.32 U	0.088 J	0.33 J									
SW6020A	Silver	mg/kg	0.085	0.046 J	0.24									
SW6020A	Sodium	mg/kg	170	190	77									
SW6020A	Thallium	mg/kg	< 0.065 U	0.063 J	0.13									
SW6020A	Vanadium	mg/kg	11	24	75									
SW6020A	Zinc	mg/kg	98	47	1200									
SW7471	Mercury	mg/kg	0.016	0.036	0.084									
SW8015C DRO	Diesel Range Organics (C10-C20)	mg/kg	160 J	810	35 J									
SW8015C DRO	Oil Range Organics (C20-C36)	mg/kg	1600	4400	540									
SW8270D LL	Acenaphthene	ug/kg	< 180 U	< 120 U	< 190 U									
SW8270D LL	Acenaphthylene	ug/kg	< 180 U	< 120 U	44 J									
SW8270D LL	Anthracene	ug/kg	< 180 U	< 120 U	< 190 U									
SW8270D LL	Benzo(a)anthracene	ug/kg	93 J	63 J	99 J									
SW8270D LL	Benzo(a)pyrene	ug/kg	< 180 U	< 120 U	84 J									
SW8270D LL	Benzo( )fluoranthene	ug/kg	130 J	77 J	120 J									
SW8270D LL	Benzo(g,h,i)perylene	ug/kg	< 180 U	< 120 U	150 J									
SW8270D LL	Benzo(k)fluoranthene	ug/kg	55 J	70 J	< 190 U									
SW8270D LL	Chrysene	ug/kg	150 J	95 J	110 J									
SW8270D LL	Dibenzo(a,h)anthracene	ug/kg	< 180 U	< 120 U	< 190 U									
SW8270D LL	Fluoranthene	ug/kg	200	98 J	120 J									
SW8270D LL	Fluorene	ug/kg	< 180 U	< 120 U	< 190 U									
SW8270D LL	Indeno(1,2,3-cd)pyrene	ug/kg	< 180 U	< 120 U	98 J									
SW8270D LL	Naphthalene	ug/kg	< 180 U	< 120 U	< 190 U									
SW8270D LL	Phenanthrene	ug/kg	57 J	44 J	50 J									
SW8270D LL	Pyrene	ug/kg	240	100 J	100 J									
SW8290A	1,2,3,4,6,7,8-Heptachlorodibenzofuran	pg/g	9.2	9.7	29									
SW8290A	1,2,3,4,6,7,8-Heptachlorodibenzo-p-dioxin	pg/g	53	22	190									
SW8290A	1,2,3,4,7,8,9-Heptachlorodibenzofuran	pg/g	1.2 J	0.84 J	3.6									
SW8290A	1,2,3,4,7,8-Hexachlorodibenzofuran	pg/g	2.7 J	1.9 J	11									
SW8290A	1,2,3,4,7,8-Hexachlorodibenzo-p-dioxin	pg/g	1.5 J	1.4 J	8.6									
SW8290A	1,2,3,6,7,8-Hexachlorodibenzofuran	pg/g	1.6 J	1.1 J	6.9									
SW8290A	1,2,3,6,7,8-Hexachlorodibenzo-p-dioxin	pg/g	3.1 J	1.9 J	14									
SW8290A	1,2,3,7,8,9-Hexachlorodibenzofuran	pg/g	0.23 J	< 0.14 U	0.59 J									

Table 3-4
Treatability Study Sediment Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	OUTFALL 01	OUTFALL 03	OUTFALL 04	SEEP-01	SEEP-02	SEEP-03	SEDMAT-01	SEDMAT-02	SEDMAT-03	SEDTRAP-01	SEDTRAP-02	SEDTRAP-03
		Sample ID	0FS0100N	0FS0300N	0FS0400N	SEE0101N	SEE0201N	SEE0301N	SMS0100N	SMS0200N	SMS0300N	STS0100N	STS0200N	STS0300N
		Sample Interval				0-12"	0-12"	0-12"						
		Sample Date	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020	10/15/2020	10/15/2020	10/15/2020	9/17/2020	9/17/2020	9/17/2020
Method	Chemical Name	Units												
SW8290A	1,2,3,7,8,9-Hexachlorodibenzo-p-dioxin	pg/g	3.6	2.6 J	22									
SW8290A	1,2,3,7,8-PeCDF	pg/g	0.87 J	0.52 J	3.4									
SW8290A	1,2,3,7,8-Pentachlorodibenzo-p-dioxin	pg/g	1.3 J	1.1 J	6.9									
SW8290A	2,3,4,6,7,8-Hexachlorodibenzofuran	pg/g	1.7 J	0.99 J	6.8									
SW8290A	2,3,4,7,8-Pentachlorodibenzofuran	pg/g	1.4 J	0.88 J	5.6									
SW8290A	2,3,7,8-Tetrachlorodibenzofuran	pg/g	0.8	0.44 J	2.4									
SW8290A	2,3,7,8-Tetrachlorodibenzo-p-dioxin	pg/g	0.25 J	0.14 J	1.3									
SW8290A	Octachlorochlorodibenzofuran	pg/g	18	7.1	46									
SW8290A	Octachlorochlorodibenzo-p-dioxin	pg/g	460	180	3700									
SW8290A	Total HpCDD	pg/g	270	48	430									
SW8290A	Total HpCDF	pg/g	23	15	65									
SW8290A	Total HxCDD	pg/g	34	20	170									
SW8290A	Total HxCDF	pg/g	18	11	89									
SW8290A	Total PeCDD	pg/g	68	10	190									
SW8290A	Total PeCDF	pg/g	17	12	110									
SW8290A	Total TCDD	pg/g	7.8	4.2	35									
SW8290A	Total TCDF	pg/g	17	13	110									

Notes:
ng/g = nanogram per gram
pg/g = picogram per gram
ug/kg = micrograms per kilogram
J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte.
U = The analyte was not detected above the indicated reporting detection limit.

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

Changed from 3-14 to 3-12

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	Decachlorobiphenyl (PCB-209)	ng/g	0.74		1.4	
E1668C	Dichlorobiphenyl	ng/g	13		74	
E1668C	Heptachlorobiphenyl	ng/g	210		1100	
E1668C	Hexachlorobiphenyl	ng/g	270		1400	
E1668C	Monochlorobiphenyl	ng/g	0.71		4	
E1668C	Nonachlorobiphenyl	ng/g	5.3		20	
E1668C	Octachlorobiphenyl	ng/g	50		250	
E1668C	PCB-1	ng/g	0.33		2.2	
E1668C	PCB-10	ng/g	0.12		0.42	
E1668C	PCB-100	ng/g	0.51		1.5	
E1668C	PCB-101	ng/g	32		160	
E1668C	PCB-102	ng/g	0.91		3.1	
E1668C	PCB-103	ng/g	0.55		1.3	
E1668C	PCB-104	ng/g	0.015		< 0.012	
E1668C	PCB-105	ng/g	6.8		40	
E1668C	PCB-106	ng/g	< 0.016		0.13	
E1668C	PCB-107	ng/g	2		9.3	
E1668C	PCB-108	ng/g	0.86		4.5	
E1668C	PCB-109	ng/g	16		79	
E1668C	PCB-11	ng/g	0.38		0.56	
E1668C	PCB-110	ng/g	29		140	
E1668C	PCB-111	ng/g	< 0.0011		< 0.011	
E1668C	PCB-112	ng/g	0.09		0.34	
E1668C	PCB-113	ng/g	32		160	
E1668C	PCB-114	ng/g	0.47		2.6	
E1668C	PCB-115	ng/g	29		140	
E1668C	PCB-116	ng/g	4.3		19	
E1668C	PCB-117	ng/g	4.3		19	
E1668C	PCB-118	ng/g	22		110	
E1668C	PCB-119	ng/g	16		79	
E1668C	PCB-12	ng/g	0.5		2.5	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-120	ng/g	0.18		0.65	
E1668C	PCB-121	ng/g	< 0.0012		< 0.012	
E1668C	PCB-122	ng/g	0.34		1.9	
E1668C	PCB-123	ng/g	0.38		2	
E1668C	PCB-124	ng/g	0.86		4.5	
E1668C	PCB-125	ng/g	16		79	
E1668C	PCB-126	ng/g	0.15		0.73	
E1668C	PCB-127	ng/g	0.04		0.22	
E1668C	PCB-128	ng/g	5.5		29	
E1668C	PCB-129	ng/g	53		280	
E1668C	PCB-13	ng/g	0.5		2.5	
E1668C	PCB-130	ng/g	3		14	
E1668C	PCB-131	ng/g	0.45		2.5	
E1668C	PCB-132	ng/g	17		91	
E1668C	PCB-133	ng/g	0.86		4	
E1668C	PCB-134	ng/g	2.7		14	
E1668C	PCB-135	ng/g	24		130	
E1668C	PCB-136	ng/g	7.5		41	
E1668C	PCB-137	ng/g	1.1		5.3	
E1668C	PCB-138	ng/g	53		280	
E1668C	PCB-139	ng/g	0.58		2.4	
E1668C	PCB-14	ng/g	< 0.0061		< 0.040	
E1668C	PCB-140	ng/g	0.58		2.4	
E1668C	PCB-141	ng/g	13		75	
E1668C	PCB-142	ng/g	< 0.060		< 0.31	
E1668C	PCB-143	ng/g	2.7		14	
E1668C	PCB-144	ng/g	2.6		16	
E1668C	PCB-145	ng/g	0.02		< 0.017	
E1668C	PCB-146	ng/g	10		50	
E1668C	PCB-147	ng/g	59		310	
E1668C	PCB-148	ng/g	0.12		0.26	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-149	ng/g	59		310	
E1668C	PCB-15	ng/g	3.7		25	
E1668C	PCB-150	ng/g	0.1		0.44	
E1668C	PCB-151	ng/g	24		130	
E1668C	PCB-152	ng/g	0.019		< 0.018	
E1668C	PCB-153	ng/g	54		290	
E1668C	PCB-154	ng/g	0.73		3.4	
E1668C	PCB-155	ng/g	< 0.00098		< 0.017	
E1668C	PCB-156	ng/g	3.9		22	
E1668C	PCB-157	ng/g	3.9		22	
E1668C	PCB-158	ng/g	4.4		25	
E1668C	PCB-159	ng/g	0.91		5.2	
E1668C	PCB-16	ng/g	6.8		24	
E1668C	PCB-160	ng/g	53		280	
E1668C	PCB-161	ng/g	< 0.040		< 0.20	
E1668C	PCB-162	ng/g	0.11		0.87	
E1668C	PCB-163	ng/g	53		280	
E1668C	PCB-164	ng/g	4		21	
E1668C	PCB-165	ng/g	< 0.045		< 0.23	
E1668C	PCB-166	ng/g	5.5		29	
E1668C	PCB-167	ng/g	1.6		9.4	
E1668C	PCB-168	ng/g	54		290	
E1668C	PCB-169	ng/g	< 0.032		< 0.16	
E1668C	PCB-17	ng/g	8.9		27	
E1668C	PCB-170	ng/g	23		130	
E1668C	PCB-171	ng/g	6.9		38	
E1668C	PCB-172	ng/g	4		24	
E1668C	PCB-173	ng/g	6.9		38	
E1668C	PCB-174	ng/g	27		150	
E1668C	PCB-175	ng/g	1		5.9	
E1668C	PCB-176	ng/g	3.3		17	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-177	ng/g	14		78	
E1668C	PCB-178	ng/g	5.5		28	
E1668C	PCB-179	ng/g	12		64	
E1668C	PCB-18	ng/g	18		57	
E1668C	PCB-180	ng/g	53		290	
E1668C	PCB-181	ng/g	< 0.0017		< 0.033	
E1668C	PCB-182	ng/g	0.16		0.81	
E1668C	PCB-183	ng/g	18		96	
E1668C	PCB-184	ng/g	< 0.0014		< 0.027	
E1668C	PCB-185	ng/g	18		96	
E1668C	PCB-186	ng/g	< 0.0014		< 0.026	
E1668C	PCB-187	ng/g	32		170	
E1668C	PCB-188	ng/g	< 0.0012		< 0.023	
E1668C	PCB-189	ng/g	0.71		4	
E1668C	PCB-19	ng/g	1.6		4.7	
E1668C	PCB-190	ng/g	3.9		22	
E1668C	PCB-191	ng/g	0.9		5.4	
E1668C	PCB-192	ng/g	< 0.0015		< 0.028	
E1668C	PCB-193	ng/g	53		290	
E1668C	PCB-194	ng/g	13		65	
E1668C	PCB-195	ng/g	5.2		27	
E1668C	PCB-196	ng/g	5.8		29	
E1668C	PCB-197	ng/g	0.43		2	
E1668C	PCB-198	ng/g	13		64	
E1668C	PCB-199	ng/g	13		64	
E1668C	PCB-2	ng/g	0.096		0.33	
E1668C	PCB-20	ng/g	21		110	
E1668C	PCB-200	ng/g	1.3		7.1	
E1668C	PCB-201	ng/g	1.5		6.9	
E1668C	PCB-202	ng/g	2.2		10	
E1668C	PCB-203	ng/g	7.1		36	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-204	ng/g	< 0.0013		< 0.025	
E1668C	PCB-205	ng/g	0.61		3.2	
E1668C	PCB-206	ng/g	3.9		15	
E1668C	PCB-207	ng/g	0.46		1.8	
E1668C	PCB-208	ng/g	0.93		3.2	
E1668C	PCB-21	ng/g	7.9		58	
E1668C	PCB-22	ng/g	5.8		40	
E1668C	PCB-23	ng/g	< 0.018		< 0.096	
E1668C	PCB-24	ng/g	0.26		1.1	
E1668C	PCB-25	ng/g	1.9		8.1	
E1668C	PCB-26	ng/g	4		17	
E1668C	PCB-27	ng/g	1.6		4.5	
E1668C	PCB-28	ng/g	21		110	
E1668C	PCB-29	ng/g	4		17	
E1668C	PCB-3	ng/g	0.28		1.5	
E1668C	PCB-30	ng/g	18		57	
E1668C	PCB-31	ng/g	16		90	
E1668C	PCB-32	ng/g	6.8		21	
E1668C	PCB-33	ng/g	7.9		58	
E1668C	PCB-34	ng/g	0.14		0.4	
E1668C	PCB-35	ng/g	0.27		2	
E1668C	PCB-36	ng/g	< 0.018		< 0.093	
E1668C	PCB-37	ng/g	6.4		44	
E1668C	PCB-38	ng/g	< 0.019		< 0.10	
E1668C	PCB-39	ng/g	0.12		0.47	
E1668C	PCB-4	ng/g	1.9		7.7	
E1668C	PCB-40	ng/g	12		47	
E1668C	PCB-41	ng/g	12		47	
E1668C	PCB-42	ng/g	5.6		20	
E1668C	PCB-43	ng/g	0.83		2.6	
E1668C	PCB-44	ng/g	21		76	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-45	ng/g	4.4		14	
E1668C	PCB-46	ng/g	1.4		4.7	
E1668C	PCB-47	ng/g	21		76	
E1668C	PCB-48	ng/g	4.4		17	
E1668C	PCB-49	ng/g	14		45	
E1668C	PCB-5	ng/g	0.088		0.53	
E1668C	PCB-50	ng/g	3.5		9.2	
E1668C	PCB-51	ng/g	4.4		14	
E1668C	PCB-52	ng/g	26		95	
E1668C	PCB-53	ng/g	3.5		9.2	
E1668C	PCB-54	ng/g	0.13		0.14	
E1668C	PCB-55	ng/g	0.31		2.2	
E1668C	PCB-56	ng/g	9.3		42	
E1668C	PCB-57	ng/g	0.13		0.39	
E1668C	PCB-58	ng/g	0.072		0.19	
E1668C	PCB-59	ng/g	1.9		7.3	
E1668C	PCB-6	ng/g	1.5		6	
E1668C	PCB-60	ng/g	2.7		20	
E1668C	PCB-61	ng/g	33		150	
E1668C	PCB-62	ng/g	1.9		7.3	
E1668C	PCB-63	ng/g	0.77		2.9	
E1668C	PCB-64	ng/g	8.8		33	
E1668C	PCB-65	ng/g	21		76	
E1668C	PCB-66	ng/g	20		82	
E1668C	PCB-67	ng/g	0.57		3	
E1668C	PCB-68	ng/g	0.15		0.31	
E1668C	PCB-69	ng/g	14		45	
E1668C	PCB-7	ng/g	0.2		0.95	
E1668C	PCB-70	ng/g	33		150	
E1668C	PCB-71	ng/g	12		47	
E1668C	PCB-72	ng/g	0.29		0.82	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	PCB-73	ng/g	0.83		2.6	
E1668C	PCB-74	ng/g	33		150	
E1668C	PCB-75	ng/g	1.9		7.3	
E1668C	PCB-76	ng/g	33		150	
E1668C	PCB-77	ng/g	2		11	
E1668C	PCB-78	ng/g	< 0.033		< 0.19	
E1668C	PCB-79	ng/g	0.23		1.1	
E1668C	PCB-8	ng/g	4.6		29	
E1668C	PCB-80	ng/g	< 0.028		< 0.16	
E1668C	PCB-81	ng/g	0.047		0.46	
E1668C	PCB-82	ng/g	3.1		14	
E1668C	PCB-83	ng/g	16		65	
E1668C	PCB-84	ng/g	6.4		28	
E1668C	PCB-85	ng/g	4.3		19	
E1668C	PCB-86	ng/g	16		79	
E1668C	PCB-87	ng/g	16		79	
E1668C	PCB-88	ng/g	3.9		15	
E1668C	PCB-89	ng/g	0.38		1.4	
E1668C	PCB-9	ng/g	0.29		1.6	
E1668C	PCB-90	ng/g	32		160	
E1668C	PCB-91	ng/g	3.9		15	
E1668C	PCB-92	ng/g	6.1		25	
E1668C	PCB-93	ng/g	0.51		1.5	
E1668C	PCB-94	ng/g	0.2		0.39	
E1668C	PCB-95	ng/g	25		120	
E1668C	PCB-96	ng/g	0.25		0.71	
E1668C	PCB-97	ng/g	16		79	
E1668C	PCB-98	ng/g	0.91		3.1	
E1668C	PCB-99	ng/g	16		65	
E1668C	Pentachlorobiphenyl	ng/g	180		850	
E1668C	Tetrachlorobiphenyl	ng/g	170		690	

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
E1668C	Trichlorobiphenyl	ng/g	110		510	
E1668C	PCB, Total Congeners	ng/g	1000		5000	
SW8082A L	Aroclor-1016	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1221	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1232	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1242	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1248	ug/kg	210	160	630	440
SW8082A L	Aroclor-1254	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1260	ug/kg	360	280	1500	1200
SW8082A L	Aroclor-1262	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
SW8082A L	Aroclor-1268	ug/kg	< 7.4	< 6.9	< 9.8	< 8.1
PCB-Aroclo	PCB, Total Aroclors	ug/kg	570	440	2100	1600
SW1020	Ignitability	deg F		< 0		< 0
SW9014	Cyanide	mg/kg		0.62		0.47
SW9034	Sulfide	mg/kg		59		41
SW6010	Arsenic	mg/l		< 0.50		0.057
SW6010	Barium	mg/l		0.3		0.37
SW6010	Cadmium	mg/l		< 0.50		< 0.50
SW6010	Chromium	mg/l		0.019		< 0.50
SW6010	Lead	mg/l		< 0.50		< 0.50
SW6010	Selenium	mg/l		0.036		< 0.50
SW6010	Silver	mg/l		< 0.50		< 0.50
SW7470A	Mercury	mg/l		< 0.00020		< 0.00020
SW8081B	Chlordane (Technical)	mg/l		< 0.0050		< 0.0050
SW8081B	Endrin	mg/l		< 0.00050		< 0.00050
SW8081B	gamma-BHC (Lindane)	mg/l		< 0.00050		< 0.00050
SW8081B	Heptachlor	mg/l		< 0.00050		< 0.00050
SW8081B	Heptachlor Epoxide	mg/l		< 0.00050		< 0.00050
SW8081B	Methoxychlor	mg/l		< 0.00050		< 0.00050
SW8081B	Toxaphene	mg/l		< 0.040		< 0.040
SW8151A	2,4,5-TP (Silvex)	mg/l		< 0.010		< 0.010

Table 3-1
Pre- and Post-Solidification Sample Results
Benning Road Facility TS Project
3400 Benning Road, NE
Washington, DC 20019

		Location ID	SED7C		SED7.5E	
		Sample ID	SED7C-DEW (0-18")	0746-009	SED7.5E-DEW (0-18")	0746-010
		Description	Pre-Solidification	Post-Solidification	Pre-Solidification	Post-Solidification
		Sample Date	6/26/2020	10/13/2020	6/26/2020	10/13/2020
		Sample Type	N	N	N	N
Method	Chemical Name	Units				
SW8151A	2,4-D	mg/l		< 0.040		< 0.040
SW8260C	1,1-Dichloroethene	mg/l		< 0.20		< 0.20
SW8260C	1,2-Dichloroethane	mg/l		< 0.20		< 0.20
SW8260C	2-Butanone	mg/l		< 0.20		< 0.20
SW8260C	Benzene	mg/l		< 0.20		< 0.20
SW8260C	Carbon Tetrachloride	mg/l		< 0.20		< 0.20
SW8260C	Chlorobenzene	mg/l		< 0.20		< 0.20
SW8260C	Chloroform	mg/l		< 0.20		< 0.20
SW8260C	Tetrachloroethylene	mg/l		< 0.20		< 0.20
SW8260C	Trichloroethene	mg/l		< 0.20		< 0.20
SW8260C	Vinyl Chloride	mg/l		< 0.20		< 0.20
SW8270D	1,4-Dichlorobenzene	mg/l		< 0.050		< 0.050
SW8270D	2,4,5-Trichlorophenol	mg/l		< 0.050		< 0.050
SW8270D	2,4,6-Trichlorophenol	mg/l		< 0.050		< 0.050
SW8270D	2,4-Dinitrotoluene	mg/l		< 0.050		< 0.050
SW8270D	2-Methylphenol	mg/l		< 0.050		< 0.050
SW8270D	4-Methylphenol	mg/l		< 0.050		< 0.050
SW8270D	Hexachlorobenzene	mg/l		< 0.050		< 0.050
SW8270D	Hexachlorobutadiene	mg/l		< 0.050		< 0.050
SW8270D	Hexachloroethane	mg/l		< 0.050		< 0.050
SW8270D	Nitrobenzene	mg/l		< 0.050		< 0.050
SW8270D	Pentachlorophenol	mg/l		< 0.25		< 0.25
SW8270D	Pyridine	mg/l		< 0.10		< 0.10

Notes:
ng/g = nanogram per gram
mg/kg = milograms per kilogram
ug/kg = micrograms per kilogram
deg F = Degrees Fahrenheit
mg/L = milligrams per liter
J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte.
U = The analyte was not detected above the indicated reporting detection limit.

Appendices

Appendix A

Photographic Log

AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. **1**	**Date:** 05/21/2020

Description:

Five outfalls by the south/southeast bank of the Cove.

Outfalls #1 and #3 are associated with the DC Transfer Station. Outfall #2 is a Pepco outfall. The others are unknown of origin.

Outfall #4 and #5 were found during land survey. (picture taken facing southwest)




Photo No. **2**	**Date:** 05/20/2020

Description:

Outfall #1: DC Transfer Station outfall (DPW Outfall 002), 21" concrete pipe.

Outfall #2: Pepco outfall (Pepco Outfall 013); 54" corrugated metal pipe (external) and 36" iron pipe (internal).

Outfall #3: DC Transfer Station outfall (DPW Outfall 003), 12" concrete pipe.

(picture taken facing south)



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 3	**Date:** 05/19/2020

Description:

Outfall #4: unknown 15" corrugated metal pipe. This pipe was found during land survey on 05/19/2020.

(picture taken facing southwest)



Photo No. 4A and 4B	**Date:** 4A: 5/21/20 4B: 5/6/21

Description:

<u>Photo 4A (left)</u>
Outfall #5: unknown 21" concrete pipe.
This pipe was found during land survey on 05/21/2020.

(picture taken facing south)

<u>Photo 4B (right)</u>
D.C. Transfer Station outfall (Outfall 001), 12" concrete pipe.

(picture taken facing northeast)





AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 5	**Date:** 04/08/2020

Description:

Two concrete culverts for conveying stormwater runoff under Anacostia Riverwalk Trail.

(picture taken facing northeast)



Photo No. 6	**Date:** 04/02/2021

Description:

Kenilworth Park South Silt Pond located adjacent to the Cove.

(picture taken facing southeast)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 7	**Date:** 04/02/2021

Description:

Riprap spillway for discharge from Kenilworth Park South Silt Pond.

(picture taken facing northwest)



Photo No. 8	**Date:** 04/02/2021

Description:

Riprap spillway for discharge from Kenilworth Park South Silt Pond, extending towards the Cove.

(picture taken facing west)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. **9**	**Date:** 07/09/2020

Description:

Adjusting staff gauge to set “0” reading at MLLW (Location: SG-03) while surveying the top of casing for a transducer.




Photo No. **10**	**Date:** 06/05/2020

Description:

Conducting hydrographic survey to collect bathymetric data for the Waterside Investigation Area. Given the limited water depth in the area, the Cove was surveyed at low tide using upland topographical survey techniques, while the rest of the investigation area was surveyed via hydrographic survey in a boat.



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 11	Date: 06/17/2020

Description:

A PVC conduit for transducer and a staff gauge secured to a metal post which was inserted to the river bottom. The lower part of the conduit has multiple screens/seams to maintain the same water level inside and outside the conduit. (ID/Location: TRANS-03 and SG-03 near Pepco outfall in the Cove)



Photo No. 12	Date: 07/14/2020

Description:

A poly box/case was installed at each of the casing for transducers to house the equipment (Location/ID: TRANS-02).



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 13	**Date:** 07/14/2020

Description:

The poly box/case, as well as the casing for transducer, was locked for security reasons (Location/ID: TRANS-01).



Photo No. 14	**Date:** 07/14/2020

Description:

The transducer and associated components were programed and set up in the casing and the poly box/case (Location/ID: TRANS-01).



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 15	**Date:** 07/15/2020

Description:

The transducer and associated components were programed and set up in the casing and the poly box/case (Location/ID: TRANS-02).



Photo No. 16	**Date:** 07/30/2020

Description:

Preparing an acoustic doppler current profiler (ADCP) for deployment in the river. The ADCP was secured by an anchor and marked with a buoy in the river. (ID: ADCP-01)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 17	Date: 07/29/2020

Description:


Lowering an ADCP to the river bottom via ropes. The sensor direction was adjusted to be paralleled to the river current. Two ADCP in total were deployed in the river to measure water current velocities over a depth range.



Photo No. 18	Date: 09/17/2020

Description:

An Acoustic Doppler Current Profiler (ADCP) was retrieved from the river bottom via crane in a boat after deployment period.
(ID/Location: ADCP-03)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 19	Date: 10/01/2020

Description:

An Acoustic Doppler Current Profiler (ADCP) was retrieved from the river bottom via crane in a boat after deployment period.
(ID/Location: ADCP-04)



Photo No. 20	Date: 07/15/2020

Description:

A temporary HDPE pipe elbow was installed at the mouth of Outfall #1 concrete pipe. The HDPE elbow serves as an extension of the concrete pipe to allow installation of a sediment trap at the outlet.
(Location/ID: Outfall #1)



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 21	**Date:** 07/30/2020

Description:

A sediment trap and a flow meter installed within the HDPE pipe extension. (Location/ID: Outfall #1)



Photo No. 22	**Date:** 07/30/2020

Description:

A sediment trap and a flow meter installed in the HDPE pipe extension. (Location/ID: Outfall #3)



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 23	**Date:** 07/28/2020

Description:

A data logger and a solar power panel were installed on two T-posts inserted to the ground (~ 40 feet north of Outfall #1).



Photo No. 24	**Date:** 07/30/2020

Description:

Powered by the solar power panel, the data logger receives flow data transmitted from the flow meters installed at Outfall #1 and Outfall #3.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. **25**	**Date:** 07/14/2020

Description:

A temporary HDPE pipe was installed at Outfall #4 to facilitate data collection as the bottom of the existing corrugated metal pipe was corroded. The HDPE elbow serves as an extension of the concrete pipe to allow installation of a sediment trap at the outlet. A sediment trap and a flow meter were installed within the HDPE pipe extension. (Location/ID: Outfall #4)



Photo No. **26**	**Date:** 07/30/2020

Description:

A data logger and a solar power panel were installed on two T-posts inserted to the ground (~ 5 feet away from Outfall #4). Powered by the solar power panel, the data logger receives flow data transmitted from the flow meters installed at Outfall #4.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 27	**Date:** 06/04/2020

Description:

Preparing an empty sediment box core for sedflume sampling in a boat (sample ID/location: SED7ESF).




Photo No. 28	**Date:** 06/04/2020

Description:

Inserting an empty sedflume box core into sediment in a boat (sample ID/location: SED7ESF).



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. **29**	**Date:** 06/04/2020

Description:

Inserting a sediment box core into sediment at river bottom (sample ID/location: SED7ESF).



Photo No. **30**	**Date:** 06/04/2020

Description:

Retrieving a sediment box core sample from river bottom in a boat (sample ID/location: SED7ESF).



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 31	**Date:** 06/04/2020

Description:

Sealing a sediment box core sample in a boat at the Cove following retrieval of the core (sample ID/location: SED7ESF).

Sediment core sample was collected and contained in the box for Sedflume testing.



Photo No. 32	**Date:** 06/04/2020

Description:

Preparing sediment box core samples for shipment.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 33	**Date:** 06/04/2020

Description:

Turbidity monitoring was conducted in a dedicated boat moving between 50 feet of upstream and downstream from the sampling location during seflume operation.

Equipment (YSI ProDSS Multi-Parameter Water Quality Meter, 4-port digital Sampling System) was used for turbidity monitoring.



Photo No. 34	**Date:** 06/16/2020

Description:

Standard sediment traps. Clean gravel was placed at the bottom of the bucket as weight.



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 35	Date: 06/16/2020

Description:

A standard sediment trap was attached to a buoy via rope and lower to the river bottom.



Photo No. 36	Date: 06/16/2020

Description:

Holes in the standard sediment trap bucket to allow water to flow out when the trap is retrieved from the river bottom. A rebar was installed at the bottom to keep the bucket from tipping over while at the river bottom.



AECOM

PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 37	Date: 06/16/2020

Description:


A standard sediment trap placed at river bottom. (sediment trap ID: SEDTRAP-02 near north end of the Cove)



Photo No. 38	Date: 06/17/2020

Description:

Installing turf mats in the Cove near Pepco outfall during low tide. Four mats were installed as duplicates at one location. Mats were secured to the sediment by metal wires and flagged for the locations. (ID/Location: SEDMAT-01 near Pepco outfall)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. **39**	**Date:** 06/17/2020

Description:

Turf mats installed near the northern bank of the Cove. (ID/Location: SEDMAT-02)



Photo No. **40**	**Date:** 10/15/2020

Description:

A sediment mat was identified for measurement of accumulated sediment after deployment period. (ID/Location: SEDMAT-01)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 41	Date: 10/15/2020

Description:

Depths of accumulated sediment on top of the mat surface were measured with a ruler. A number of nine measurements were performed and averaged for a mat.
(ID/Location: SEEP-01)



Photo No. 42	Date: 10/15/2020

Description:

Sediment sampling from a sediment mat was performed by carefully transferring all accumulated sediment from the mat surface to sampling containers via a scoop. The mat and the scoop were also collected for analysis after transferring all sediment.
(ID/Location: SEDMAT-03)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 43	Date: 10/09/2020

Description:

After accumulated sediment on top of the sediment mat was transferred to sampling containers, the underside of the mat was scraped of sediment before the mat was collected for analysis. (ID/Location: SEEP-03)



Photo No. 44	Date: 09/15/2020

Description:

Accessing proposed location for installation of a seepage meter via boat during low tide.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 45	Date: 09/15/2020

Description:

The seepage meter is comprised of a bottomless drum and a re-sealable bag. The bag is connected to the drum via vinyl tubing. The connection to the drum is submerged under water inside the drum to allow water to move between the bag and the drum. There is an extended PVC vent on top of the drum to maintain atmosphere pressure inside the drum and to prevent river water from entering the drum through the vent. (ID/Location: SEEP-01)




Photo No. 46	Date: 09/15/2020

Description:

The bottomless drum is directly pushed into the sediment to a depth so that tubing connection to the drum is submerged under water and above sediment inside the drum. After the installation, the seepage meter is left for equilibrium before measurement can be conducted. The seepage meter is secured with a big rock and flagged. (ID/Location: SEEP-01)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 47	Date: 09/15/2020

Description:

After the installation, the bag is filled with some river water for testing to ensure water can move between the bag and the drum.
(ID/Location: SEEP-01)



Photo No. 48	Date: 09/17/2020

Description:

A seepage meter installed in the middle of the Cove near northern bank. A total number of three seepage meters were installed.
(ID/Location: SEEP-02)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 49	Date: 09/17/2020

Description:

A seepage meter installed inside the Cove near Pepco outfall and a transducer station (TRANS-03). A total number of three seepage meters were installed.
(ID/Location: SEEP-03)



Photo No. 50	Date: 09/17/2020

Description:

A sediment sample was collected from a seepage meter installation location via shallow push core. a 1-foot sediment from the surface was taken and mixed in a zip-lock bag to create a composite sample.
(ID/Location: SEEP-01)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 51	Date: 10/09/2020

Description:


Accessing a seepage meter after equilibrium to conduct measurements during low tide. (ID/Location: SEEP-02)



Photo No. 52	Date: 10/09/2020

Description:

Measurements were conducted at a seepage meter after equilibrium to determine the groundwater hydrology flux into the overlying sediment. The measurement was performed by adding distill water in the bag and measuring the amount of water leaving or entering the bag after a period of time. (ID/Location: SEEP-01)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 53	Date: 10/09/2020

Description:

Measurements were conducted at a seepage meter after equilibrium to determine the groundwater hydrology flux into the overlying sediment. The measurement was performed by adding distill water in the bag and measuring the amount of water leaving or entering the bag after a period of time. (ID/Location: SEEP-01)



Photo No. 54	Date: 10/09/2020

Description:

Eight intact cores collected for laboratory seepage study. (ID/Location: SEEP-03)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 55	Date: 10/09/2020

Description:

Sediment laboratory study for the placement of amendments. A sediment sample was homogenized prior to collection of triplicate subsamples for the analysis of PCBs and Total Organic Carbon. Three liter subsamples of the homogenized sediment were placed in clean containers for mixing with the carbon amendments.



Photo No. 56	Date: 06/16/2020

Description:

Laboratory bioaccumulation study with freshwater oligochaetes. Bioaccumulation setup with air tubes supplying sparging air to oxygenate the overlying water.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 57	**Date:** 06/16/2020

Description:

Left and middle: Clean, laboratory cultured freshwater oligochaetes (Lumbriculus variegatus) were added to the sediments in 1L glass beakers (1000 g wet sediment and 1 g organisms per beaker; 3 replicates per treatment).
Right: closeup of worms in culture chamber.



Photo No. 58	**Date:** 06/16/2020

Description:

A Hester-Dandy sampler was secured to a weight block via rope.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 59	Date: 06/16/2020

Description:

The weight block with a Hester-Dandy sampler secured was tied to a metal post which was inserted to the river bottom.



Photo No. 60	Date: 06/16/2020

Description:

A Hester-Dandy sampler was installed at the river bottom. (ID/Location: HD-4 in the Cove near Pepco outfall)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 61	Date: 07/14/2020

Description:

A Hester-Dandy sampler was found exposed during low tide (Location/ID: HD-03).



Photo No. 62	Date: 07/16/2020

Description:

The exposed Hester-Dandy sampler (Location/ID: HD-03) was retrieved, cleaned, and re-set at a deeper location approximately 12 feet away from where it was previously installed.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 63	Date: 07/14/2020

Description:

A Hester-Dandy sampler was found exposed during low tide (Location/ID: HD-02).



Photo No. 64	Date: 07/16/2020

Description:

The exposed Hester-Dandy sampler (Location/ID: HD-02) was retrieved, cleaned, and re-set at a deeper location approximately 12 feet away from where it was previously installed.



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 65	Date: 07/29/2020

Description:


A Hester-Dandy sampler was retrieved during low tide from the river after a 6-week deployment. Before the sampler was retrieved, there was approximately 5 inch of water above the sampler in the river. (ID: HD-1)



Photo No. 66	Date: 07/29/2020

Description:

After being retrieved from the river during low tide, a Hester-Dandy sampler was stored in 70% alcohol and sent to lab for benthic macro invertebrate organism analysis. (ID: HD-4)



PHOTOGRAPHIC LOC
PEPCO TREATABILITY STUDY

Photo No. 67	Date: 06/05/2020

Description:

Collecting sediment samples for sequestration study during low tide. (sample ID: SED7E)



Photo No. 68	Date: 06/04/2020

Description:

Surface water samples in 5-gallon carboys collected for geotextile dewatering. The samples were collected from the boat using a whale pump.



Appendix B

Eurofins TestAmerica Lab Packages

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-108704-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
8/7/2020 4:25:46 PM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 5
Certification Summary 7
Sample Summary 10
Method Summary 11
Lab Chronicle 12
Client Sample Results 16
QC Sample Results 51
QC Association Summary 61
Chain of Custody 64
Receipt Checklists 69

Job ID: 180-108704-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-108704-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 7/24/2020 8:45 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperatures of the 3 coolers at receipt time were 2.6º C, 3.5º C and 4.2º C.

Two Amber liters and two out of four 250 amber glass container labels for the following sample did not match the information listed on the Chain-of-Custody (COC): OFW0100R (180-108704-2). The container labels list an id of OFW0100N, while the COC lists OFW0100R. The sample collection time matches sample two and the id on the COC was used.

SEMIVILATILES
An incorrect volume of surrogate spiking solution was inadvertently added the following samples: OFW0100N (180-108704-1). Percent recoveries are based on the amount spiked.

DRO
Due to the concentration of DRO detected, sample OFW0300N (180-108704-4) was analyzed at a dilution. The reporting limit has been adjusted accordingly.

DIOXINS
The following samples went through Gel-Permeation Cleanup procedure, based on EPA method 3640A:
OFW0100N (180-108704-1), OFW0100R (180-108704-2), OFW0200N (180-108704-3), OFW0300N (180-108704-4) and OFW0500N (180-108704-5)

Samples OFW0100N (180-108704-1), OFW0100R (180-108704-2), OFW0200N (180-108704-3), OFW0300N (180-108704-4) and OFW0500N (180-108704-5) were analyzed at a dilution. The reporting limits have been adjusted accordingly.

Ion abundance ratios are outside criteria for the Isotope Dilution Analyte (IDA) associated with the following sample: OFW0300N (180-108704-4).

Polychlorinated biphenyls, Total was detected in method blank MB 140-41399/7-A at a level exceeding the reporting limit. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

Several analytes were detected in method blank MB 140-41399/7-A at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the

Job ID: 180-108704-1 (Continued)

Laboratory: Eurofins TestAmerica, Pittsburgh (Continued)

MDL and/or RL, the result has been flagged.

METALS

Calcium and Zinc were detected in method blank MB 180-323777/1-A at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged. Refer to the QC report for details.

TOTAL SUSPENDED SOLIDS

No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Qualifiers

GC/MS Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Dioxin

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
C	The compound co-eluted with other compounds
C108	The compound co-eluted with PCB-108
C110	The compound co-eluted with PCB-110
C12	The compound co-eluted with PCB-12
C128	The compound co-eluted with PCB-128
C129	The compound co-eluted with PCB-129
C134	The compound co-eluted with PCB-134
C135	The compound co-eluted with PCB-135
C139	The compound co-eluted with PCB-139
C147	The compound co-eluted with PCB-147
C153	The compound co-eluted with PCB-153
C156	The compound co-eluted with PCB-156
C171	The compound co-eluted with PCB-171
C18	The compound co-eluted with PCB-18
C180	The compound co-eluted with PCB-180
C183	The compound co-eluted with PCB-183
C198	The compound co-eluted with PCB-198
C20	The compound co-eluted with PCB-20
C21	The compound co-eluted with PCB-21
C26	The compound co-eluted with PCB-26
C40	The compound co-eluted with PCB-40
C43	The compound co-eluted with PCB-43
C44	The compound co-eluted with PCB-44
C45	The compound co-eluted with PCB-45
C49	The compound co-eluted with PCB-49
C50	The compound co-eluted with PCB-50
C59	The compound co-eluted with PCB-59
C61	The compound co-eluted with PCB-61
C83	The compound co-eluted with PCB-83
C85	The compound co-eluted with PCB-85
C86	The compound co-eluted with PCB-86
C88	The compound co-eluted with PCB-88
C90	The compound co-eluted with PCB-90
C93	The compound co-eluted with PCB-93
C98	The compound co-eluted with PCB-98
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
q	The reported result is the estimated maximum possible concentration of this analyte, quantitated using the theoretical ion ratio. The measured ion ratio does not meet qualitative identification criteria and indicates a possible interference.

Metals

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid

Glossary (Continued)

Abbreviation	These commonly used abbreviations may or may not be present in this report.
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	01-01-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-15-20
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-20

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Canton

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	State	2927	02-23-21
Connecticut	State	PH-0590	12-31-21
Florida	NELAP	E87225	06-30-21
Georgia	State	4062	02-23-21
Illinois	NELAP	004498	07-31-20
Iowa	State	421	06-01-21
Kansas	NELAP	E-10336	04-30-21
Kentucky (UST)	State	112225	02-23-21
Kentucky (WW)	State	KY98016	12-31-20
Minnesota	NELAP	OH00048	12-31-20
Minnesota (Petrofund)	State	3506	08-01-21
New Jersey	NELAP	OH001	06-30-21
New York	NELAP	10975	03-31-21
Ohio VAP	State	CL0024	06-05-21
Oregon	NELAP	4062	02-24-21
Pennsylvania	NELAP	68-00340	08-31-20
Texas	NELAP	T104704517-18-10	08-31-20
USDA	US Federal Programs	P330-18-00281	09-17-21
Virginia	NELAP	010101	09-14-20
Washington	State	C971	01-12-21
West Virginia DEP	State	210	12-31-20

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Knoxville

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
	AFCEE	N/A	
ANAB	Dept. of Defense ELAP	L2311	02-13-22
ANAB	Dept. of Energy	L2311.01	02-13-22
ANAB	ISO/IEC 17025	L2311	02-13-22
ANAB	ISO/IEC 17025	L2311	02-14-22
Arkansas DEQ	State	88-0688	06-17-21
California	State	2423	06-30-21
Colorado	State	TN00009	02-28-21
Connecticut	State	PH-0223	09-30-21
Florida	NELAP	E87177	07-01-21
Georgia (DW)	State	906	12-11-22
Hawaii	State	NA	12-11-21
Kansas	NELAP	E-10349	11-01-20
Kentucky (DW)	State	90101	01-01-21
Louisiana	NELAP	LA110001	12-31-12 *
Louisiana	NELAP	83979	06-30-21
Louisiana (DW)	State	LA019	12-31-20
Maryland	State	277	03-31-21
Michigan	State	9933	12-11-22
Nevada	State	TN00009	08-31-20
New Hampshire	NELAP	299919	01-17-21
New Jersey	NELAP	TN001	07-01-21
New York	NELAP	10781	03-31-21
North Carolina (DW)	State	21705	07-31-21
North Carolina (WW/SW)	State	64	12-31-20
Ohio VAP	State	CL0059	06-02-23
Oklahoma	State	9415	09-01-20
Oregon	NELAP	TNI0189	01-02-21
Pennsylvania	NELAP	68-00576	12-31-20
Tennessee	State	02014	12-11-22
Texas	NELAP	T104704380-18-12	08-31-20
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-19-00236	08-20-22
Utah	NELAP	TN00009	07-31-20 *
Virginia	NELAP	460176	09-15-20
Washington	State	C593	01-19-21
West Virginia (DW)	State	9955C	01-01-21
West Virginia DEP	State	345	05-01-21
Wisconsin	State	998044300	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-108704-1	OFW0100N	Water	07/22/20 16:25	07/24/20 08:45	
180-108704-2	OFW0100R	Water	07/22/20 16:30	07/24/20 08:45	
180-108704-3	OFW0200N	Water	07/22/20 16:40	07/24/20 08:45	
180-108704-4	OFW0300N	Water	07/22/20 16:50	07/24/20 08:45	
180-108704-5	OFW0500N	Water	07/22/20 17:30	07/24/20 08:45	

Method Summary

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8270D LL	Semivolatile Organic Compounds by GC/MS - Low Level	SW846	TAL PIT
8015D	Diesel Range Organics (DRO) (GC)	SW846	TAL CAN
1668C	Chlorinated Biphenyl Congeners (HRGC/HRMS)	EPA	TAL KNX
EPA 6020A	Metals (ICP/MS)	SW846	TAL PIT
EPA 7470A	Mercury (CVAA)	SW846	TAL PIT
SM 2540D	Solids, Total Suspended (TSS)	SM	TAL PIT
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	TAL PIT
3510C LVI	Liquid-Liquid Extraction (Separatory Funnel) LVI	SW846	TAL CAN
3520C	Liquid-Liquid Extraction (Continuous)	SW846	TAL PIT
7470A	Preparation, Mercury	SW846	TAL PIT
HRMS-Sepf	Separatory Funnel (Liquid-Liquid) Extraction	EPA	TAL KNX

Protocol References:

EPA = US Environmental Protection Agency

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0100N
Lab Sample ID: 180-108704-1
Date Collected: 07/22/20 16:25
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			310 mL	250 uL	323155	07/27/20 11:53	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	323410	07/29/20 16:14	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			250 mL	5 mL	444506	07/28/20 06:30	MDH	TAL CAN
Total/NA	Analysis	8015D		1			444816	07/29/20 19:12	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1045.5 mL	20 uL	41399	07/29/20 09:50	SSS	TAL KNX
Total/NA	Analysis	1668C		2			41630	08/05/20 13:28	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324024	08/01/20 21:10	NAM	TAL PIT
	Instrument ID: DORY									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324170	08/03/20 21:40	NAM	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	323724	07/31/20 05:35	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			324008	08/03/20 10:29	RJR	TAL PIT
	Instrument ID: HGZ									
Total/NA	Analysis	SM 2540D		1	600 mL	1000 mL	323013	07/25/20 13:18	AGP	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0100R
Lab Sample ID: 180-108704-2
Date Collected: 07/22/20 16:30
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			300 mL	250 uL	323155	07/27/20 11:57	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	323410	07/29/20 16:40	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			240 mL	5 mL	444506	07/28/20 06:30	MDH	TAL CAN
Total/NA	Analysis	8015D		1			444816	07/29/20 19:39	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1023.5 mL	20 uL	41399	07/29/20 09:50	SSS	TAL KNX
Total/NA	Analysis	1668C		2			41630	08/05/20 14:29	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324024	08/01/20 21:14	NAM	TAL PIT
	Instrument ID: DORY									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324170	08/03/20 21:44	NAM	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	323724	07/31/20 05:35	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			324008	08/03/20 10:30	RJR	TAL PIT
	Instrument ID: HGZ									

Lab Chronicle

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0100R
Lab Sample ID: 180-108704-2
Date Collected: 07/22/20 16:30
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	SM 2540D		1	450 mL	1000 mL	323013	07/25/20 13:18	AGP	TAL PIT

Client Sample ID: OFW0200N
Lab Sample ID: 180-108704-3
Date Collected: 07/22/20 16:40
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			290 mL	250 uL	323155	07/27/20 11:57	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	323410	07/29/20 17:05	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			240 mL	5 mL	444506	07/28/20 06:30	MDH	TAL CAN
Total/NA	Analysis	8015D		1			444816	07/29/20 20:07	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1011 mL	20 uL	41399	07/29/20 09:50	SSS	TAL KNX
Total/NA	Analysis	1668C		2			41630	08/05/20 15:31	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324024	08/01/20 21:17	NAM	TAL PIT
	Instrument ID: DORY									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324170	08/03/20 21:47	NAM	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	323724	07/31/20 05:35	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			324008	08/03/20 10:31	RJR	TAL PIT
	Instrument ID: HGZ									
Total/NA	Analysis	SM 2540D		1	750 mL	1000 mL	323013	07/25/20 13:18	AGP	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0300N
Lab Sample ID: 180-108704-4
Date Collected: 07/22/20 16:50
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			290 mL	250 uL	323155	07/27/20 11:57	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	323410	07/29/20 17:30	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			240 mL	5 mL	444506	07/28/20 06:30	MDH	TAL CAN
Total/NA	Analysis	8015D		5			444889	07/30/20 12:04	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1021.3 mL	20 uL	41399	07/29/20 09:50	SSS	TAL KNX
Total/NA	Analysis	1668C		5			41619	08/05/20 07:51	PMP	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324024	08/01/20 21:21	NAM	TAL PIT
	Instrument ID: DORY									

Lab Chronicle

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0300N
Lab Sample ID: 180-108704-4
Date Collected: 07/22/20 16:50
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324170	08/03/20 21:51	NAM	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	323724	07/31/20 05:35	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			324008	08/03/20 10:32	RJR	TAL PIT
	Instrument ID: HGZ									
Total/NA	Analysis	SM 2540D		1	250 mL	1000 mL	323013	07/25/20 13:18	AGP	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0500N
Lab Sample ID: 180-108704-5
Date Collected: 07/22/20 17:30
Matrix: Water
Date Received: 07/24/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			310 mL	250 uL	323155	07/27/20 11:57	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	323410	07/29/20 17:55	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			240 mL	5 mL	444506	07/28/20 06:30	MDH	TAL CAN
Total/NA	Analysis	8015D		1			444816	07/29/20 21:02	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1026.7 mL	20 uL	41399	07/29/20 09:50	SSS	TAL KNX
Total/NA	Analysis	1668C		2			41630	08/05/20 16:32	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324024	08/01/20 21:24	NAM	TAL PIT
	Instrument ID: DORY									
Total Recoverable	Prep	3005A			50 mL	50 mL	323777	07/31/20 08:03	TJO	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			324170	08/03/20 22:01	NAM	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	323724	07/31/20 05:35	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			324008	08/03/20 10:33	RJR	TAL PIT
	Instrument ID: HGZ									
Total/NA	Analysis	SM 2540D		1	400 mL	1000 mL	323013	07/25/20 13:18	AGP	TAL PIT
	Instrument ID: NOEQUIP									

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-108704-1
Project/Site: Pepco Benning Road Facility

Analyst References:

Lab: TAL CAN
- Batch Type: Prep
  - MDH = Matthew Howell
- Batch Type: Analysis
  - LKG = Lucas Grossman

Lab: TAL KNX
- Batch Type: Prep
  - SSS = Samuel Stockton
- Batch Type: Analysis
  - JMN = Jon Nordquist
  - PMP = Trish Parsly

Lab: TAL PIT
- Batch Type: Prep
  - BJT = Bill Trout
  - RJR = Ron Rosenbaum
  - TJO = Tyler Oliver
- Batch Type: Analysis
  - AGP = Angela Partridge
  - NAM = Nicole Marfisi
  - RJR = Ron Rosenbaum
  - VVP = Vincent Piccolino

Client Sample ID: OFW0100N

Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.15	0.052	ug/L		07/27/20 11:53	07/29/20 16:14	1
Acenaphthylene	ND		0.15	0.052	ug/L		07/27/20 11:53	07/29/20 16:14	1
Anthracene	ND		0.15	0.040	ug/L		07/27/20 11:53	07/29/20 16:14	1
Benzo[a]anthracene	ND		0.15	0.060	ug/L		07/27/20 11:53	07/29/20 16:14	1
Benzo[b]fluoranthene	ND		0.15	0.078	ug/L		07/27/20 11:53	07/29/20 16:14	1
Benzo[k]fluoranthene	ND		0.15	0.071	ug/L		07/27/20 11:53	07/29/20 16:14	1
Benzo[g,h,i]perylene	ND		0.15	0.056	ug/L		07/27/20 11:53	07/29/20 16:14	1
Benzo[a]pyrene	ND		0.15	0.043	ug/L		07/27/20 11:53	07/29/20 16:14	1
Chrysene	ND		0.15	0.065	ug/L		07/27/20 11:53	07/29/20 16:14	1
Dibenz(a,h)anthracene	ND		0.15	0.058	ug/L		07/27/20 11:53	07/29/20 16:14	1
Fluoranthene	ND		0.15	0.048	ug/L		07/27/20 11:53	07/29/20 16:14	1
Fluorene	ND		0.15	0.056	ug/L		07/27/20 11:53	07/29/20 16:14	1
Indeno[1,2,3-cd]pyrene	ND		0.15	0.069	ug/L		07/27/20 11:53	07/29/20 16:14	1
Naphthalene	ND		0.15	0.048	ug/L		07/27/20 11:53	07/29/20 16:14	1
Phenanthrene	**0.061**	**J**	0.15	0.044	ug/L		07/27/20 11:53	07/29/20 16:14	1
Pyrene	ND		0.15	0.044	ug/L		07/27/20 11:53	07/29/20 16:14	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*88*		*23 - 105*	*07/27/20 11:53*	*07/29/20 16:14*	*1*
Nitrobenzene-d5 (Surr)	*81*		*28 - 111*	*07/27/20 11:53*	*07/29/20 16:14*	*1*
Terphenyl-d14 (Surr)	*78*		*20 - 126*	*07/27/20 11:53*	*07/29/20 16:14*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**1900**		500	230	ug/L		07/28/20 06:30	07/29/20 19:12	1
ORO C24-C40	**2800**		500	230	ug/L		07/28/20 06:30	07/29/20 19:12	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*81*		*52 - 121*	*07/28/20 06:30*	*07/29/20 19:12*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.088**	**B q**	0.077	0.00066	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-2	**0.015**	**J B**	0.077	0.00078	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-3	**0.052**	**J B**	0.077	0.00089	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-4	**0.020**	**J q**	0.11	0.0035	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-5	ND		0.077	0.0029	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-6	**0.0098**	**J q**	0.077	0.0025	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-7	ND		0.077	0.0026	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-8	**0.044**	**J**	0.11	0.0023	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-9	ND		0.077	0.0026	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-10	ND		0.077	0.0028	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-11	**0.34**	**B**	0.11	0.0025	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-12	**0.0088**	**J C q**	0.15	0.0026	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-13	**0.0088**	**J C12 q**	0.15	0.0026	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-14	ND		0.077	0.0022	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-15	**0.040**	**J**	0.077	0.0027	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-16	**0.040**	**J**	0.077	0.00094	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-17	**0.028**	**J q**	0.077	0.00084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-18	**0.073**	**J C**	0.15	0.00074	ng/L		07/29/20 09:50	08/05/20 13:28	2

Client Sample ID: OFW0100N
Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.0070	J	0.077	0.0010	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-20	0.17	C B	0.15	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-21	0.091	J C B	0.15	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-22	0.069	J	0.077	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-23	ND		0.077	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-24	0.0019	J	0.077	0.00071	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-25	0.011	J	0.077	0.0016	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-26	0.024	J C	0.15	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-27	0.0058	J	0.077	0.00061	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-28	0.17	B C20	0.15	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-29	0.024	J C26	0.15	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-30	0.073	J C18	0.15	0.00074	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-31	0.13	B	0.077	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-32	0.028	J	0.077	0.00059	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-33	0.091	J B C21	0.15	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-34	ND		0.077	0.0019	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-35	0.012	J B	0.077	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-36	ND		0.077	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-37	0.084	B	0.077	0.0018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-38	ND		0.077	0.0019	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-39	ND		0.077	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-40	0.13	J C	0.23	0.0084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-41	0.13	J C40	0.23	0.0084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-42	0.055	J	0.077	0.0084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-43	ND	C	0.15	0.0079	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-44	0.27	C B	0.23	0.0074	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-45	0.032	J C B	0.15	0.0088	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-46	0.012	J	0.077	0.011	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-47	0.27	B C44	0.23	0.0074	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-48	0.038	J q	0.077	0.0084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-49	0.13	J C	0.15	0.0068	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-50	0.018	J C q	0.15	0.0081	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-51	0.032	J C45 B	0.15	0.0088	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-52	0.41		0.077	0.0083	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-53	0.018	J C50 q	0.15	0.0081	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-54	ND		0.077	0.00020	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-55	0.011	J	0.077	0.0061	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-56	0.17		0.077	0.0061	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-57	ND		0.077	0.0062	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-58	ND		0.077	0.0063	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-59	0.017	J C B	0.23	0.0059	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-60	0.088		0.077	0.0062	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-61	0.88	C B	0.31	0.0058	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-62	0.017	J B C59	0.23	0.0059	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-63	0.0074	J q	0.077	0.0057	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-64	0.11		0.077	0.0056	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-65	0.27	B C44	0.23	0.0074	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-66	0.32		0.077	0.0058	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-67	0.0088	J q	0.077	0.0054	ng/L		07/29/20 09:50	08/05/20 13:28	2

Client Sample ID: OFW0100N

Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.077	0.0055	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-69	**0.13**	**J C49**	0.15	0.0068	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-70	**0.88**	**C61 B**	0.31	0.0058	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-71	**0.13**	**J C40**	0.23	0.0084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-72	ND		0.077	0.0061	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-73	ND	C43	0.15	0.0079	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-74	**0.88**	**C61 B**	0.31	0.0058	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-75	**0.017**	**J B C59**	0.23	0.0059	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-76	**0.88**	**C61 B**	0.31	0.0058	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-77	**0.13**		0.077	0.0061	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-78	ND		0.077	0.0063	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-79	**0.017**	**J q**	0.077	0.0054	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-80	ND		0.077	0.0053	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-81	ND		0.077	0.0056	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-82	**0.23**	**B**	0.077	0.00054	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-83	**0.77**	**C B**	0.15	0.00050	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-84	**0.33**		0.077	0.00055	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-85	**0.27**	**C B**	0.23	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-86	**1.1**	**C B**	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-87	**1.1**	**B C86**	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-88	**0.11**	**J C q**	0.15	0.00049	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-89	**0.0092**	**J q**	0.077	0.00053	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-90	**1.6**	**C B**	0.23	0.00041	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-91	**0.11**	**J C88 q**	0.15	0.00049	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-92	**0.23**		0.077	0.00046	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-93	**0.0090**	**J C**	0.15	0.00047	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-94	**0.0025**	**J q**	0.077	0.00053	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-95	**0.89**	**B**	0.077	0.00051	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-96	**0.0034**	**J**	0.077	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-97	**1.1**	**B C86**	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-98	**0.022**	**J C**	0.15	0.00046	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-99	**0.77**	**C83 B**	0.15	0.00050	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-100	**0.0090**	**J C93**	0.15	0.00047	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-101	**1.6**	**B C90**	0.23	0.00041	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-102	**0.022**	**J C98**	0.15	0.00046	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-103	**0.0043**	**J**	0.077	0.00047	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-104	ND		0.077	0.00036	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-105	**1.2**	**B**	0.077	0.0088	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-106	ND		0.077	0.0083	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-107	**0.19**	**B q**	0.077	0.0089	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-108	**0.10**	**J C B q**	0.15	0.0086	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-109	**1.1**	**B C86**	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-110	**2.0**	**C B**	0.15	0.00034	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-111	**0.0039**	**J B**	0.077	0.00033	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-112	**0.0020**	**J q**	0.077	0.00035	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-113	**1.6**	**B C90**	0.23	0.00041	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-114	**0.039**	**J B q**	0.077	0.0076	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-115	**2.0**	**B C110**	0.15	0.00034	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-116	**0.27**	**C85 B**	0.23	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2

Client Sample ID: OFW0100N
Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.27	C85 B	0.23	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-118	2.5	B	0.077	0.0067	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-119	1.1	B C86	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-120	0.0047	J q	0.077	0.00034	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-121	ND		0.077	0.00035	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-122	0.038	J B q	0.077	0.0096	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-123	0.035	J B	0.077	0.0077	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-124	0.10	J B q C108	0.15	0.0086	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-125	1.1	B C86	0.46	0.00040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-126	0.078	B	0.077	0.011	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-127	ND		0.077	0.0083	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-128	0.76	C B	0.15	0.028	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-129	4.6	C B	0.31	0.029	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-130	0.28		0.077	0.038	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-131	0.049	J q	0.077	0.040	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-132	1.4		0.077	0.037	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-133	0.053	J	0.077	0.036	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-134	0.25	C	0.15	0.038	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-135	0.71	C	0.15	0.00067	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-136	0.23		0.077	0.00048	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-137	0.23	q	0.077	0.033	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-138	4.6	B C129	0.31	0.029	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-139	0.066	J C q	0.15	0.032	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-140	0.066	J C139 q	0.15	0.032	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-141	0.97		0.077	0.034	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-142	ND		0.077	0.036	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-143	0.25	C134	0.15	0.038	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-144	0.090		0.077	0.00060	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-145	ND		0.077	0.00046	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-146	0.55		0.077	0.032	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-147	3.9	C	0.15	0.036	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-148	0.0022	J q	0.077	0.00064	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-149	3.9	C147	0.15	0.036	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-150	ND		0.077	0.00044	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-151	0.71	C135	0.15	0.00067	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-152	ND		0.077	0.00047	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-153	3.8	C B	0.15	0.025	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-154	0.015	J	0.077	0.00052	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-155	ND		0.077	0.00044	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-156	0.57	C B	0.15	0.028	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-157	0.57	C156 B	0.15	0.028	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-158	0.51		0.077	0.023	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-159	0.054	J B	0.077	0.024	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-160	4.6	B C129	0.31	0.029	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-161	ND		0.077	0.024	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-162	0.041	J B q	0.077	0.024	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-163	4.6	B C129	0.31	0.029	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-164	0.28		0.077	0.025	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-165	ND		0.077	0.027	ng/L		07/29/20 09:50	08/05/20 13:28	2

Client Sample ID: OFW0100N
Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.76	C128 B	0.15	0.028	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-167	0.17	B	0.077	0.018	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-168	3.8	B C153	0.15	0.025	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-169	0.051	J B q	0.077	0.021	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-170	1.3	B	0.077	0.0014	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-171	0.27	C B	0.15	0.0010	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-172	0.19		0.077	0.0010	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-173	0.27	C171 B	0.15	0.0010	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-174	1.6	B	0.077	0.00094	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-175	0.036	J q	0.077	0.00091	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-176	0.17		0.077	0.00069	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-177	0.68	B	0.077	0.00097	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-178	0.32		0.077	0.00098	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-179	0.76		0.077	0.00073	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-180	3.0	C B	0.15	0.00076	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-181	ND		0.077	0.00091	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-182	ND		0.077	0.00087	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-183	1.0	C B	0.15	0.00089	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-184	ND		0.077	0.00074	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-185	1.0	B C183	0.15	0.00089	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-186	ND		0.077	0.00072	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-187	1.9	B	0.077	0.00084	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-188	ND		0.077	0.00055	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-189	0.032	J B q	0.077	0.0087	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-190	0.20	B	0.077	0.00066	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-191	0.039	J B q	0.077	0.00068	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-192	ND		0.077	0.00076	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-193	3.0	C180 B	0.15	0.00076	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-194	1.2	B	0.077	0.012	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-195	0.41	B	0.077	0.013	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-196	0.58	B	0.077	0.0019	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-197	0.036	J B q	0.077	0.0014	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-198	1.4	C B	0.15	0.0019	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-199	1.4	C198 B	0.15	0.0019	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-200	0.14	B	0.077	0.0013	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-201	0.16		0.077	0.0013	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-202	0.28		0.077	0.0015	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-203	0.79	B	0.077	0.0017	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-204	ND		0.077	0.0014	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-205	0.052	J B	0.077	0.0098	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-206	0.44		0.077	0.013	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-207	0.050	J	0.077	0.0091	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-208	0.083		0.077	0.0092	ng/L		07/29/20 09:50	08/05/20 13:28	2
PCB-209	0.023	J B q	0.077	0.0060	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Monochlorobiphenyls	0.16	B q	0.077	0.00078	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Dichlorobiphenyls	0.46	B q	0.15	0.0027	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Trichlorobiphenyls	0.77	B q	0.15	0.0014	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Tetrachlorobiphenyls	2.9	B q	0.31	0.0065	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Pentachlorobiphenyls	12	B q	0.46	0.0031	ng/L		07/29/20 09:50	08/05/20 13:28	2

Client Sample ID: OFW0100N

Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	20	B q	0.31	0.022	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Heptachlorobiphenyls	11	B q	0.15	0.0012	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Octachlorobiphenyls	5.0	B q	0.15	0.0042	ng/L		07/29/20 09:50	08/05/20 13:28	2
Total Nonachlorobiphenyls	0.57		0.077	0.010	ng/L		07/29/20 09:50	08/05/20 13:28	2
Polychlorinated biphenyls, Total	53	B q	0.46	0.0064	ng/L		07/29/20 09:50	08/05/20 13:28	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*66*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-3L	*68*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-4L	*75*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-15L	*79*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-19L	*88*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-37L	*83*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-54L	*81*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-77L	*62*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-81L	*67*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-104L	*80*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-105L	*86*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-114L	*99*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-118L	*102*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-123L	*103*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-126L	*73*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-155L	*78*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-156L	*70*	*C*	*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-157L	*70*	*C156*	*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-167L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-169L	*71*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-170L	*73*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-188L	*118*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-189L	*80*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-202L	*94*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-205L	*68*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-206L	*61*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-208L	*70*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-209L	*66*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*98*		*5 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-111L	*70*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*
PCB-178L	*117*		*10 - 145*	*07/29/20 09:50*	*08/05/20 13:28*	*2*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	570		30	13	ug/L		07/31/20 08:03	08/01/20 21:10	1
Arsenic	0.99	J	1.0	0.31	ug/L		07/31/20 08:03	08/01/20 21:10	1
Barium	19		10	1.6	ug/L		07/31/20 08:03	08/01/20 21:10	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:10	1
Cadmium	0.27	J	1.0	0.22	ug/L		07/31/20 08:03	08/01/20 21:10	1
Calcium	11000	B	500	130	ug/L		07/31/20 08:03	08/01/20 21:10	1
Chromium	3.6		2.0	1.5	ug/L		07/31/20 08:03	08/03/20 21:40	1
Cobalt	0.89		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 21:10	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0100N
Date Collected: 07/22/20 16:25
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-1
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	17		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 21:10	1
Iron	1500		50	20	ug/L		07/31/20 08:03	08/01/20 21:10	1
Silver	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:10	1
Potassium	3200		500	160	ug/L		07/31/20 08:03	08/01/20 21:10	1
Magnesium	1100		500	83	ug/L		07/31/20 08:03	08/01/20 21:10	1
Manganese	36		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 21:10	1
Sodium	5000		500	350	ug/L		07/31/20 08:03	08/01/20 21:10	1
Nickel	3.0		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 21:10	1
Lead	9.7		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 21:10	1
Antimony	1.2	J	2.0	0.38	ug/L		07/31/20 08:03	08/01/20 21:10	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 21:10	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 21:10	1
Vanadium	4.0		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 21:10	1
Zinc	110	B	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 21:10	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:29	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	33		0.83	0.83	mg/L			07/25/20 13:18	1

Client Sample ID: OFW0100R

Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.16	0.054	ug/L		07/27/20 11:57	07/29/20 16:40	1
Acenaphthylene	ND		0.16	0.054	ug/L		07/27/20 11:57	07/29/20 16:40	1
Anthracene	ND		0.16	0.041	ug/L		07/27/20 11:57	07/29/20 16:40	1
Benzo[a]anthracene	ND		0.16	0.063	ug/L		07/27/20 11:57	07/29/20 16:40	1
Benzo[b]fluoranthene	ND		0.16	0.081	ug/L		07/27/20 11:57	07/29/20 16:40	1
Benzo[k]fluoranthene	ND		0.16	0.073	ug/L		07/27/20 11:57	07/29/20 16:40	1
Benzo[g,h,i]perylene	ND		0.16	0.058	ug/L		07/27/20 11:57	07/29/20 16:40	1
Benzo[a]pyrene	ND		0.16	0.044	ug/L		07/27/20 11:57	07/29/20 16:40	1
Chrysene	ND		0.16	0.068	ug/L		07/27/20 11:57	07/29/20 16:40	1
Dibenz(a,h)anthracene	ND		0.16	0.060	ug/L		07/27/20 11:57	07/29/20 16:40	1
Fluoranthene	ND		0.16	0.050	ug/L		07/27/20 11:57	07/29/20 16:40	1
Fluorene	ND		0.16	0.058	ug/L		07/27/20 11:57	07/29/20 16:40	1
Indeno[1,2,3-cd]pyrene	ND		0.16	0.071	ug/L		07/27/20 11:57	07/29/20 16:40	1
Naphthalene	ND		0.16	0.049	ug/L		07/27/20 11:57	07/29/20 16:40	1
Phenanthrene	**0.058**	**J**	0.16	0.046	ug/L		07/27/20 11:57	07/29/20 16:40	1
Pyrene	ND		0.16	0.045	ug/L		07/27/20 11:57	07/29/20 16:40	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*54*		*23 - 105*	*07/27/20 11:57*	*07/29/20 16:40*	*1*
Nitrobenzene-d5 (Surr)	*57*		*28 - 111*	*07/27/20 11:57*	*07/29/20 16:40*	*1*
Terphenyl-d14 (Surr)	*33*		*20 - 126*	*07/27/20 11:57*	*07/29/20 16:40*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**1800**		520	240	ug/L		07/28/20 06:30	07/29/20 19:39	1
ORO C24-C40	**2700**		520	240	ug/L		07/28/20 06:30	07/29/20 19:39	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*79*		*52 - 121*	*07/28/20 06:30*	*07/29/20 19:39*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.10**	**B**	0.078	0.00070	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-2	**0.014**	**J B**	0.078	0.00076	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-3	**0.053**	**J B**	0.078	0.00077	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-4	**0.018**	**J**	0.12	0.0032	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-5	**0.0028**	**J q**	0.078	0.0027	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-6	**0.010**	**J q**	0.078	0.0024	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-7	ND		0.078	0.0024	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-8	**0.048**	**J**	0.12	0.0022	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-9	**0.0035**	**J q**	0.078	0.0025	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-10	ND		0.078	0.0026	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-11	**0.38**	**B**	0.12	0.0023	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-12	**0.015**	**J C**	0.16	0.0024	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-13	**0.015**	**J C12**	0.16	0.0024	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-14	ND		0.078	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-15	**0.047**	**J**	0.078	0.0026	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-16	**0.042**	**J**	0.078	0.00093	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-17	**0.034**	**J**	0.078	0.00083	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-18	**0.081**	**J C**	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 14:29	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.0068	J q	0.078	0.0010	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-20	0.18	C B	0.16	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-21	0.11	J C B	0.16	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-22	0.076	J	0.078	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-23	ND		0.078	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-24	0.0015	J q	0.078	0.00070	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-25	0.011	J	0.078	0.0018	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-26	0.027	J C	0.16	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-27	0.0055	J q	0.078	0.00061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-28	0.18	B C20	0.16	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-29	0.027	J C26	0.16	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-30	0.081	J C18	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-31	0.15	B	0.078	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-32	0.028	J	0.078	0.00058	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-33	0.11	J B C21	0.16	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-34	ND		0.078	0.0021	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-35	0.011	J B q	0.078	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-36	ND		0.078	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-37	0.092	B	0.078	0.0020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-38	ND		0.078	0.0021	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-39	ND		0.078	0.0019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-40	0.20	J C	0.23	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-41	0.20	J C40	0.23	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-42	0.076	J	0.078	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-43	ND	C	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-44	0.40	C B	0.23	0.0099	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-45	0.043	J C B	0.16	0.012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-46	0.018	J	0.078	0.014	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-47	0.40	B C44	0.23	0.0099	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-48	0.057	J	0.078	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-49	0.19	C	0.16	0.0092	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-50	0.030	J C	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-51	0.043	J C45 B	0.16	0.012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-52	0.62		0.078	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-53	0.030	J C50	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-54	ND		0.078	0.00026	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-55	0.013	J q	0.078	0.0082	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-56	0.23		0.078	0.0082	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-57	ND		0.078	0.0083	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-58	ND		0.078	0.0084	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-59	0.026	J C B	0.23	0.0079	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-60	0.13		0.078	0.0083	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-61	1.4	C B	0.31	0.0078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-62	0.026	J B C59	0.23	0.0079	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-63	0.013	J q	0.078	0.0076	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-64	0.17		0.078	0.0075	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-65	0.40	B C44	0.23	0.0099	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-66	0.47		0.078	0.0078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-67	0.012	J	0.078	0.0072	ng/L		07/29/20 09:50	08/05/20 14:29	2

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.078	0.0073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-69	**0.19**	**C49**	0.16	0.0092	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-70	**1.4**	**C61 B**	0.31	0.0078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-71	**0.20**	**J C40**	0.23	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-72	ND		0.078	0.0081	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-73	ND	C43	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-74	**1.4**	**C61 B**	0.31	0.0078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-75	**0.026**	**J B C59**	0.23	0.0079	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-76	**1.4**	**C61 B**	0.31	0.0078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-77	**0.17**		0.078	0.0082	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-78	ND		0.078	0.0084	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-79	**0.020**	**J**	0.078	0.0073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-80	ND		0.078	0.0071	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-81	ND		0.078	0.0074	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-82	**0.22**	**B**	0.078	0.00080	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-83	**0.77**	**C B**	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-84	**0.38**		0.078	0.00081	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-85	**0.26**	**C B**	0.23	0.00059	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-86	**1.2**	**C B**	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-87	**1.2**	**B C86**	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-88	**0.15**	**J C**	0.16	0.00072	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-89	**0.013**	**J**	0.078	0.00078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-90	**1.7**	**C B**	0.23	0.00061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-91	**0.15**	**J C88**	0.16	0.00072	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-92	**0.27**		0.078	0.00069	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-93	**0.0063**	**J C q**	0.16	0.00069	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-94	ND		0.078	0.00078	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-95	**1.1**	**B**	0.078	0.00076	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-96	**0.0037**	**J q**	0.078	0.00059	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-97	**1.2**	**B C86**	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-98	**0.026**	**J C q**	0.16	0.00067	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-99	**0.77**	**C83 B**	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-100	**0.0063**	**J C93 q**	0.16	0.00069	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-101	**1.7**	**B C90**	0.23	0.00061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-102	**0.026**	**J C98 q**	0.16	0.00067	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-103	ND		0.078	0.00069	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-104	ND		0.078	0.00053	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-105	**1.5**	**B**	0.078	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-106	ND		0.078	0.010	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-107	**0.27**	**B**	0.078	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-108	**0.14**	**J C B**	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-109	**1.2**	**B C86**	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-110	**1.9**	**C B**	0.16	0.00050	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-111	ND		0.078	0.00049	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-112	**0.0068**	**J q**	0.078	0.00051	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-113	**1.7**	**B C90**	0.23	0.00061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-114	**0.071**	**J B**	0.078	0.0094	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-115	**1.9**	**B C110**	0.16	0.00050	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-116	**0.26**	**C85 B**	0.23	0.00059	ng/L		07/29/20 09:50	08/05/20 14:29	2

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.26	C85 B	0.23	0.00059	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-118	3.2	B	0.078	0.0088	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-119	1.2	B C86	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-120	ND		0.078	0.00050	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-121	ND		0.078	0.00051	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-122	0.050	J B q	0.078	0.012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-123	0.027	J B q	0.078	0.0098	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-124	0.14	J B C108	0.16	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-125	1.2	B C86	0.47	0.00060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-126	0.076	J B	0.078	0.014	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-127	ND		0.078	0.010	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-128	1.0	C B	0.16	0.041	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-129	6.2	C B	0.31	0.043	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-130	0.38		0.078	0.056	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-131	0.071	J	0.078	0.059	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-132	1.8		0.078	0.055	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-133	0.056	J	0.078	0.053	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-134	0.29	C	0.16	0.056	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-135	0.76	C	0.16	0.0018	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-136	0.28		0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-137	0.30		0.078	0.048	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-138	6.2	B C129	0.31	0.043	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-139	0.069	J C q	0.16	0.047	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-140	0.069	J C139 q	0.16	0.047	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-141	1.3		0.078	0.050	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-142	ND		0.078	0.053	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-143	0.29	C134	0.16	0.056	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-144	0.087		0.078	0.0016	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-145	ND		0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-146	0.69		0.078	0.047	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-147	4.8	C	0.16	0.054	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-148	ND		0.078	0.0017	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-149	4.8	C147	0.16	0.054	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-150	0.0023	J q	0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-151	0.76	C135	0.16	0.0018	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-152	0.0035	J	0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-153	4.9	C B	0.16	0.037	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-154	0.010	J q	0.078	0.0014	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-155	ND		0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-156	0.73	C B	0.16	0.040	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-157	0.73	C156 B	0.16	0.040	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-158	0.64		0.078	0.034	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-159	0.065	J B q	0.078	0.035	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-160	6.2	B C129	0.31	0.043	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-161	ND		0.078	0.035	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-162	0.065	J B	0.078	0.035	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-163	6.2	B C129	0.31	0.043	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-164	0.41		0.078	0.037	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-165	ND		0.078	0.040	ng/L		07/29/20 09:50	08/05/20 14:29	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	1.0	C128 B	0.16	0.041	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-167	0.23	B	0.078	0.028	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-168	4.9	B C153	0.16	0.037	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-169	0.10	B q	0.078	0.031	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-170	1.7	B	0.078	0.0085	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-171	0.37	C B	0.16	0.0068	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-172	0.26		0.078	0.0067	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-173	0.37	C171 B	0.16	0.0068	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-174	2.1	B	0.078	0.0063	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-175	0.073	J	0.078	0.0061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-176	0.22		0.078	0.0046	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-177	0.90	B	0.078	0.0065	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-178	0.41		0.078	0.0066	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-179	1.0		0.078	0.0049	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-180	4.1	C B	0.16	0.0051	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-181	ND		0.078	0.0061	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-182	ND		0.078	0.0059	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-183	1.3	C B	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-184	ND		0.078	0.0050	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-185	1.3	B C183	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-186	ND		0.078	0.0049	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-187	2.6	B	0.078	0.0057	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-188	ND		0.078	0.0039	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-189	0.080	B	0.078	0.036	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-190	0.25	B	0.078	0.0044	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-191	0.049	J B q	0.078	0.0046	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-192	ND		0.078	0.0051	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-193	4.1	C180 B	0.16	0.0051	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-194	1.4	B	0.078	0.023	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-195	0.17	B	0.078	0.025	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-196	0.79	B	0.078	0.0093	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-197	0.076	J B	0.078	0.0071	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-198	1.9	C B	0.16	0.0094	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-199	1.9	C198 B	0.16	0.0094	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-200	0.20	B	0.078	0.0063	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-201	0.24		0.078	0.0065	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-202	0.37		0.078	0.0073	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-203	1.1	B	0.078	0.0084	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-204	ND		0.078	0.0071	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-205	0.061	J B	0.078	0.020	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-206	0.54		0.078	0.017	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-207	0.059	J	0.078	0.019	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-208	0.11		0.078	0.032	ng/L		07/29/20 09:50	08/05/20 14:29	2
PCB-209	0.024	J B q	0.078	0.0064	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Monochlorobiphenyls	0.17	B	0.078	0.00074	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Dichlorobiphenyls	0.52	B q	0.16	0.0025	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Trichlorobiphenyls	0.86	B q	0.16	0.0016	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Tetrachlorobiphenyls	4.3	B q	0.31	0.0087	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Pentachlorobiphenyls	13	B q	0.47	0.0039	ng/L		07/29/20 09:50	08/05/20 14:29	2

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	25	B q	0.31	0.032	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Heptachlorobiphenyls	15	B q	0.16	0.0071	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Octachlorobiphenyls	6.3	B	0.16	0.012	ng/L		07/29/20 09:50	08/05/20 14:29	2
Total Nonachlorobiphenyls	0.71		0.078	0.023	ng/L		07/29/20 09:50	08/05/20 14:29	2
Polychlorinated biphenyls, Total	67	B q	0.47	0.011	ng/L		07/29/20 09:50	08/05/20 14:29	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*72*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-3L	*76*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-4L	*80*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-15L	*81*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-19L	*92*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-37L	*85*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-54L	*85*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-77L	*49*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-81L	*56*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-104L	*96*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-105L	*92*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-114L	*103*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-118L	*102*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-123L	*106*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-126L	*78*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-155L	*81*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-156L	*72*	*C*	*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-157L	*72*	*C156*	*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-167L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-169L	*70*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-170L	*78*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-188L	*117*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-189L	*31*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-202L	*89*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-205L	*82*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-206L	*84*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-208L	*32*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-209L	*79*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*103*		*5 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-111L	*62*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*
PCB-178L	*115*		*10 - 145*	*07/29/20 09:50*	*08/05/20 14:29*	*2*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	710		30	13	ug/L		07/31/20 08:03	08/01/20 21:14	1
Arsenic	1.1		1.0	0.31	ug/L		07/31/20 08:03	08/01/20 21:14	1
Barium	20		10	1.6	ug/L		07/31/20 08:03	08/01/20 21:14	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:14	1
Cadmium	0.23	J	1.0	0.22	ug/L		07/31/20 08:03	08/01/20 21:14	1
Calcium	11000	B	500	130	ug/L		07/31/20 08:03	08/01/20 21:14	1
Chromium	3.5		2.0	1.5	ug/L		07/31/20 08:03	08/03/20 21:44	1
Cobalt	0.98		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 21:14	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0100R
Date Collected: 07/22/20 16:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-2
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	17		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 21:14	1
Iron	1700		50	20	ug/L		07/31/20 08:03	08/01/20 21:14	1
Silver	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:14	1
Potassium	3300		500	160	ug/L		07/31/20 08:03	08/01/20 21:14	1
Magnesium	1200		500	83	ug/L		07/31/20 08:03	08/01/20 21:14	1
Manganese	37		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 21:14	1
Sodium	4900		500	350	ug/L		07/31/20 08:03	08/01/20 21:14	1
Nickel	3.1		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 21:14	1
Lead	11		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 21:14	1
Antimony	1.1	J	2.0	0.38	ug/L		07/31/20 08:03	08/01/20 21:14	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 21:14	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 21:14	1
Vanadium	4.3		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 21:14	1
Zinc	130	B	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 21:14	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:30	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	31		1.1	1.1	mg/L			07/25/20 13:18	1

Client Sample ID: OFW0200N

Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.16	0.056	ug/L		07/27/20 11:57	07/29/20 17:05	1
Acenaphthylene	ND		0.16	0.056	ug/L		07/27/20 11:57	07/29/20 17:05	1
Anthracene	ND		0.16	0.042	ug/L		07/27/20 11:57	07/29/20 17:05	1
Benzo[a]anthracene	ND		0.16	0.065	ug/L		07/27/20 11:57	07/29/20 17:05	1
Benzo[b]fluoranthene	ND		0.16	0.084	ug/L		07/27/20 11:57	07/29/20 17:05	1
Benzo[k]fluoranthene	ND		0.16	0.076	ug/L		07/27/20 11:57	07/29/20 17:05	1
Benzo[g,h,i]perylene	ND		0.16	0.059	ug/L		07/27/20 11:57	07/29/20 17:05	1
Benzo[a]pyrene	ND		0.16	0.046	ug/L		07/27/20 11:57	07/29/20 17:05	1
Chrysene	ND		0.16	0.070	ug/L		07/27/20 11:57	07/29/20 17:05	1
Dibenz(a,h)anthracene	ND		0.16	0.062	ug/L		07/27/20 11:57	07/29/20 17:05	1
Fluoranthene	**0.088**	**J**	0.16	0.052	ug/L		07/27/20 11:57	07/29/20 17:05	1
Fluorene	ND		0.16	0.059	ug/L		07/27/20 11:57	07/29/20 17:05	1
Indeno[1,2,3-cd]pyrene	ND		0.16	0.073	ug/L		07/27/20 11:57	07/29/20 17:05	1
Naphthalene	ND		0.16	0.051	ug/L		07/27/20 11:57	07/29/20 17:05	1
Phenanthrene	**0.071**	**J**	0.16	0.047	ug/L		07/27/20 11:57	07/29/20 17:05	1
Pyrene	ND		0.16	0.047	ug/L		07/27/20 11:57	07/29/20 17:05	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*63*		*23 - 105*	*07/27/20 11:57*	*07/29/20 17:05*	*1*
Nitrobenzene-d5 (Surr)	*66*		*28 - 111*	*07/27/20 11:57*	*07/29/20 17:05*	*1*
Terphenyl-d14 (Surr)	*56*		*20 - 126*	*07/27/20 11:57*	*07/29/20 17:05*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**840**		520	240	ug/L		07/28/20 06:30	07/29/20 20:07	1
ORO C24-C40	**1000**		520	240	ug/L		07/28/20 06:30	07/29/20 20:07	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*78*		*52 - 121*	*07/28/20 06:30*	*07/29/20 20:07*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.014**	**J q B**	0.079	0.00061	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-2	**0.0051**	**J B**	0.079	0.00067	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-3	**0.0087**	**J q B**	0.079	0.00068	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-4	**0.024**	**J q**	0.12	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-5	ND		0.079	0.0020	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-6	**0.0063**	**J q**	0.079	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-7	ND		0.079	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-8	**0.033**	**J**	0.12	0.0016	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-9	ND		0.079	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-10	ND		0.079	0.0020	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-11	**0.45**	**B**	0.12	0.0017	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-12	**0.011**	**J C**	0.16	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-13	**0.011**	**J C12**	0.16	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-14	ND		0.079	0.0015	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-15	**0.058**	**J**	0.079	0.0018	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-16	**0.018**	**J q**	0.079	0.00091	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-17	**0.021**	**J q**	0.079	0.00082	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-18	**0.036**	**J q C**	0.16	0.00072	ng/L		07/29/20 09:50	08/05/20 15:31	2

Client Sample ID: OFW0200N
Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.0078	J	0.079	0.0010	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-20	0.18	C B	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-21	0.049	J C B	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-22	0.059	J	0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-23	ND		0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-24	0.0011	J	0.079	0.00069	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-25	0.010	J	0.079	0.0012	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-26	0.018	J C	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-27	0.0033	J q	0.079	0.00060	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-28	0.18	C20 B	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-29	0.018	J C26	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-30	0.036	J q C18	0.16	0.00072	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-31	0.10	B	0.079	0.0012	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-32	0.025	J	0.079	0.00057	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-33	0.049	J C21 B	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-34	ND		0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-35	0.028	J B	0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-36	ND		0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-37	0.089	B	0.079	0.0013	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-38	ND		0.079	0.0014	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-39	ND		0.079	0.0012	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-40	0.077	J C	0.24	0.0038	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-41	0.077	J C40	0.24	0.0038	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-42	0.031	J	0.079	0.0038	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-43	ND	C	0.16	0.0035	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-44	0.13	J C B	0.24	0.0033	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-45	0.024	J C B	0.16	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-46	0.0083	J	0.079	0.0048	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-47	0.13	J C44 B	0.24	0.0033	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-48	0.016	J	0.079	0.0038	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-49	0.069	J C	0.16	0.0031	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-50	0.014	J C	0.16	0.0037	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-51	0.024	J C45 B	0.16	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-52	0.16		0.079	0.0037	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-53	0.014	J C50	0.16	0.0037	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-54	0.0018	J	0.079	0.00036	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-55	0.0047	J q	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-56	0.078	J	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-57	ND		0.079	0.0028	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-58	ND		0.079	0.0028	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-59	0.011	J C B	0.24	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-60	0.040	J	0.079	0.0028	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-61	0.28	J C B	0.32	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-62	0.011	J C59 B	0.24	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-63	0.0036	J q	0.079	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-64	0.061	J	0.079	0.0025	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-65	0.13	J C44 B	0.24	0.0033	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-66	0.16		0.079	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-67	0.0046	J q	0.079	0.0024	ng/L		07/29/20 09:50	08/05/20 15:31	2

Client Sample ID: OFW0200N
Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.079	0.0025	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-69	**0.069**	**J C49**	0.16	0.0031	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-70	**0.28**	**J C61 B**	0.32	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-71	**0.077**	**J C40**	0.24	0.0038	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-72	ND		0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-73	ND	C43	0.16	0.0035	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-74	**0.28**	**J C61 B**	0.32	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-75	**0.011**	**J C59 B**	0.24	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-76	**0.28**	**J C61 B**	0.32	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-77	**0.048**	**J**	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-78	ND		0.079	0.0028	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-79	**0.0035**	**J q**	0.079	0.0024	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-80	ND		0.079	0.0024	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-81	ND		0.079	0.0025	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-82	**0.068**	**J B**	0.079	0.00086	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-83	**0.24**	**C B**	0.16	0.00079	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-84	**0.095**	**q**	0.079	0.00087	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-85	**0.088**	**J C B**	0.24	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-86	**0.38**	**J C B**	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-87	**0.38**	**J C86 B**	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-88	**0.052**	**J C**	0.16	0.00078	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-89	**0.0047**	**J q**	0.079	0.00085	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-90	**0.47**	**C B**	0.24	0.00065	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-91	**0.052**	**J C88**	0.16	0.00078	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-92	**0.075**	**J**	0.079	0.00074	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-93	**0.0048**	**J q C**	0.16	0.00075	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-94	**0.0018**	**J q**	0.079	0.00085	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-95	**0.32**	**B**	0.079	0.00082	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-96	**0.0029**	**J**	0.079	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-97	**0.38**	**J C86 B**	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-98	**0.010**	**J C**	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-99	**0.24**	**C83 B**	0.16	0.00079	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-100	**0.0048**	**J q C93**	0.16	0.00075	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-101	**0.47**	**C90 B**	0.24	0.00065	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-102	**0.010**	**J C98**	0.16	0.00073	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-103	ND		0.079	0.00075	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-104	ND		0.079	0.00057	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-105	**0.27**	**B**	0.079	0.0029	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-106	ND		0.079	0.0030	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-107	**0.043**	**J B**	0.079	0.0032	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-108	**0.026**	**J C B**	0.16	0.0031	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-109	**0.38**	**J C86 B**	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-110	**0.64**	**C B**	0.16	0.00054	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-111	ND		0.079	0.00053	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-112	ND		0.079	0.00055	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-113	**0.47**	**C90 B**	0.24	0.00065	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-114	**0.011**	**J q B**	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-115	**0.64**	**C110 B**	0.16	0.00054	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-116	**0.088**	**J C85 B**	0.24	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0200N
Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.088	J C85 B	0.24	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-118	0.58	B	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-119	0.38	J C86 B	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-120	ND		0.079	0.00053	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-121	ND		0.079	0.00055	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-122	0.0095	J q B	0.079	0.0035	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-123	0.012	J B	0.079	0.0029	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-124	0.026	J C108 B	0.16	0.0031	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-125	0.38	J C86 B	0.47	0.00064	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-126	0.0091	J q B	0.079	0.0036	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-127	ND		0.079	0.0030	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-128	0.19	C B	0.16	0.0067	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-129	1.4	C B	0.32	0.0069	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-130	0.071	J q	0.079	0.0091	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-131	ND		0.079	0.0095	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-132	0.43		0.079	0.0089	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-133	ND		0.079	0.0086	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-134	0.056	J C	0.16	0.0090	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-135	0.33	C	0.16	0.0015	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-136	0.10		0.079	0.0011	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-137	0.043	J	0.079	0.0077	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-138	1.4	C129 B	0.32	0.0069	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-139	0.015	J q C	0.16	0.0076	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-140	0.015	J q C139	0.16	0.0076	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-141	0.32		0.079	0.0080	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-142	ND		0.079	0.0085	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-143	0.056	J C134	0.16	0.0090	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-144	0.042	J	0.079	0.0014	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-145	ND		0.079	0.0010	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-146	0.19		0.079	0.0076	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-147	1.2	C	0.16	0.0087	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-148	ND		0.079	0.0014	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-149	1.2	C147	0.16	0.0087	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-150	ND		0.079	0.00098	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-151	0.33	C135	0.16	0.0015	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-152	ND		0.079	0.0011	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-153	1.2	C B	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-154	0.0077	J q	0.079	0.0012	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-155	ND		0.079	0.00098	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-156	0.13	J C B	0.16	0.0070	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-157	0.13	J C156 B	0.16	0.0070	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-158	0.14		0.079	0.0054	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-159	0.013	J B	0.079	0.0057	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-160	1.4	C129 B	0.32	0.0069	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-161	ND		0.079	0.0057	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-162	ND		0.079	0.0056	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-163	1.4	C129 B	0.32	0.0069	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-164	0.095		0.079	0.0060	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-165	ND		0.079	0.0065	ng/L		07/29/20 09:50	08/05/20 15:31	2

Client Sample ID: OFW0200N
Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.19	C128 B	0.16	0.0067	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-167	0.052	J B	0.079	0.0041	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-168	1.2	C153 B	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-169	ND		0.079	0.0050	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-170	0.48	B	0.079	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-171	0.11	J C B	0.16	0.0030	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-172	0.077	J	0.079	0.0030	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-173	0.11	J C171 B	0.16	0.0030	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-174	0.49	B	0.079	0.0028	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-175	0.021	J	0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-176	0.059	J	0.079	0.0020	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-177	0.25	B	0.079	0.0029	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-178	0.11		0.079	0.0029	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-179	0.21		0.079	0.0022	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-180	0.93	C B	0.16	0.0023	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-181	ND		0.079	0.0027	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-182	0.0066	J q	0.079	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-183	0.33	C B	0.16	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-184	ND		0.079	0.0022	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-185	0.33	C183 B	0.16	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-186	ND		0.079	0.0022	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-187	0.59	B	0.079	0.0025	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-188	ND		0.079	0.0017	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-189	0.016	J B	0.079	0.0048	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-190	0.067	J B	0.079	0.0020	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-191	0.013	J q B	0.079	0.0020	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-192	ND		0.079	0.0023	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-193	0.93	C180 B	0.16	0.0023	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-194	0.38	B	0.079	0.015	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-195	0.16	B	0.079	0.016	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-196	0.18	B	0.079	0.0052	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-197	0.016	J q B	0.079	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-198	0.55	C B	0.16	0.0053	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-199	0.55	C198 B	0.16	0.0053	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-200	0.040	J B	0.079	0.0035	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-201	0.064	J	0.079	0.0036	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-202	0.12		0.079	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-203	0.33	B	0.079	0.0047	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-204	ND		0.079	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-205	0.025	J B	0.079	0.012	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-206	0.85		0.079	0.0084	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-207	0.073	J	0.079	0.0056	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-208	0.24		0.079	0.0055	ng/L		07/29/20 09:50	08/05/20 15:31	2
PCB-209	0.17	B	0.079	0.0040	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Monochlorobiphenyls	0.028	J q B	0.079	0.00065	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Dichlorobiphenyls	0.58	q B	0.16	0.0019	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Trichlorobiphenyls	0.65	q B	0.16	0.0011	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Tetrachlorobiphenyls	1.2	q B	0.32	0.0029	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Pentachlorobiphenyls	3.4	q B	0.47	0.0015	ng/L		07/29/20 09:50	08/05/20 15:31	2

Client Sample ID: OFW0200N

Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	6.0	q B	0.32	0.0054	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Heptachlorobiphenyls	3.8	q B	0.16	0.0026	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Octachlorobiphenyls	1.9	q B	0.16	0.0071	ng/L		07/29/20 09:50	08/05/20 15:31	2
Total Nonachlorobiphenyls	1.2		0.079	0.0065	ng/L		07/29/20 09:50	08/05/20 15:31	2
Polychlorinated biphenyls, Total	19	q B	0.47	0.0037	ng/L		07/29/20 09:50	08/05/20 15:31	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*61*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-3L	*67*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-4L	*76*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-15L	*81*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-19L	*92*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-37L	*92*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-54L	*89*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-77L	*84*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-81L	*86*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-104L	*80*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-105L	*93*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-114L	*94*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-118L	*93*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-123L	*93*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-126L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-155L	*84*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-156L	*72*	*C*	*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-157L	*72*	*C156*	*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-167L	*79*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-169L	*66*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-170L	*78*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-188L	*124*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-189L	*106*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-202L	*103*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-205L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-206L	*85*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-208L	*100*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-209L	*89*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*100*		*5 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-111L	*90*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*
PCB-178L	*130*		*10 - 145*	*07/29/20 09:50*	*08/05/20 15:31*	*2*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	530		30	13	ug/L		07/31/20 08:03	08/01/20 21:17	1
Arsenic	1.1		1.0	0.31	ug/L		07/31/20 08:03	08/01/20 21:17	1
Barium	15		10	1.6	ug/L		07/31/20 08:03	08/01/20 21:17	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:17	1
Cadmium	0.30	J	1.0	0.22	ug/L		07/31/20 08:03	08/01/20 21:17	1
Calcium	8700	B	500	130	ug/L		07/31/20 08:03	08/01/20 21:17	1
Chromium	3.0		2.0	1.5	ug/L		07/31/20 08:03	08/03/20 21:47	1
Cobalt	0.89		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 21:17	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0200N
Date Collected: 07/22/20 16:40
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-3
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	24		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 21:17	1
Iron	1200		50	20	ug/L		07/31/20 08:03	08/01/20 21:17	1
Silver	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:17	1
Potassium	2600		500	160	ug/L		07/31/20 08:03	08/01/20 21:17	1
Magnesium	1600		500	83	ug/L		07/31/20 08:03	08/01/20 21:17	1
Manganese	52		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 21:17	1
Sodium	5400		500	350	ug/L		07/31/20 08:03	08/01/20 21:17	1
Nickel	4.5		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 21:17	1
Lead	20		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 21:17	1
Antimony	1.9	J	2.0	0.38	ug/L		07/31/20 08:03	08/01/20 21:17	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 21:17	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 21:17	1
Vanadium	8.0		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 21:17	1
Zinc	150	B	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 21:17	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:31	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	29		0.67	0.67	mg/L			07/25/20 13:18	1

Client Sample ID: OFW0300N

Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.16	0.056	ug/L		07/27/20 11:57	07/29/20 17:30	1
Acenaphthylene	ND		0.16	0.056	ug/L		07/27/20 11:57	07/29/20 17:30	1
Anthracene	ND		0.16	0.042	ug/L		07/27/20 11:57	07/29/20 17:30	1
Benzo[a]anthracene	ND		0.16	0.065	ug/L		07/27/20 11:57	07/29/20 17:30	1
Benzo[b]fluoranthene	ND		0.16	0.084	ug/L		07/27/20 11:57	07/29/20 17:30	1
Benzo[k]fluoranthene	ND		0.16	0.076	ug/L		07/27/20 11:57	07/29/20 17:30	1
Benzo[g,h,i]perylene	**0.075**	**J**	0.16	0.059	ug/L		07/27/20 11:57	07/29/20 17:30	1
Benzo[a]pyrene	ND		0.16	0.046	ug/L		07/27/20 11:57	07/29/20 17:30	1
Chrysene	ND		0.16	0.070	ug/L		07/27/20 11:57	07/29/20 17:30	1
Dibenz(a,h)anthracene	ND		0.16	0.062	ug/L		07/27/20 11:57	07/29/20 17:30	1
Fluoranthene	**0.077**	**J**	0.16	0.052	ug/L		07/27/20 11:57	07/29/20 17:30	1
Fluorene	ND		0.16	0.059	ug/L		07/27/20 11:57	07/29/20 17:30	1
Indeno[1,2,3-cd]pyrene	ND		0.16	0.073	ug/L		07/27/20 11:57	07/29/20 17:30	1
Naphthalene	ND		0.16	0.051	ug/L		07/27/20 11:57	07/29/20 17:30	1
Phenanthrene	**0.088**	**J**	0.16	0.047	ug/L		07/27/20 11:57	07/29/20 17:30	1
Pyrene	**0.15**	**J**	0.16	0.047	ug/L		07/27/20 11:57	07/29/20 17:30	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*54*		*23 - 105*	*07/27/20 11:57*	*07/29/20 17:30*	*1*
Nitrobenzene-d5 (Surr)	*66*		*28 - 111*	*07/27/20 11:57*	*07/29/20 17:30*	*1*
Terphenyl-d14 (Surr)	*54*		*20 - 126*	*07/27/20 11:57*	*07/29/20 17:30*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**8200**		2600	1200	ug/L		07/28/20 06:30	07/30/20 12:04	5
ORO C24-C40	**7200**		2600	1200	ug/L		07/28/20 06:30	07/30/20 12:04	5

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*75*		*52 - 121*	*07/28/20 06:30*	*07/30/20 12:04*	*5*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.016**	**J B**	0.20	0.0012	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-2	ND		0.20	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-3	**0.013**	**J B**	0.20	0.0018	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-4	ND		0.29	0.012	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-5	ND		0.20	0.010	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-6	ND		0.20	0.0089	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-7	ND		0.20	0.0091	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-8	**0.021**	**J q**	0.29	0.0082	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-9	ND		0.20	0.0093	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-10	ND		0.20	0.0099	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-11	**2.0**	**B**	0.29	0.0087	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-12	ND	C	0.39	0.0090	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-13	ND	C12	0.39	0.0090	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-14	ND		0.20	0.0076	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-15	**0.031**	**J q**	0.20	0.0099	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-16	**0.014**	**J q**	0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-17	**0.019**	**J q**	0.20	0.0011	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-18	**0.034**	**J C q**	0.39	0.00099	ng/L		07/29/20 09:50	08/05/20 07:51	5

Client Sample ID: OFW0300N
Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	ND		0.20	0.0014	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-20	**0.14**	**J C B**	0.39	0.0050	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-21	**0.071**	**J C B**	0.39	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-22	**0.053**	**J**	0.20	0.0051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-23	ND		0.20	0.0051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-24	ND		0.20	0.00095	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-25	**0.0091**	**J q**	0.20	0.0046	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-26	**0.021**	**J C**	0.39	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-27	ND		0.20	0.00082	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-28	**0.14**	**J B C20**	0.39	0.0050	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-29	**0.021**	**J C26**	0.39	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-30	**0.034**	**J C18 q**	0.39	0.00099	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-31	**0.11**	**J B q**	0.20	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-32	**0.012**	**J q**	0.20	0.00079	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-33	**0.071**	**J B C21**	0.39	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-34	ND		0.20	0.0053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-35	**0.015**	**J B q**	0.20	0.0051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-36	ND		0.20	0.0049	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-37	**0.046**	**J B q**	0.20	0.0051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-38	ND		0.20	0.0053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-39	ND		0.20	0.0048	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-40	**0.18**	**J C**	0.59	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-41	**0.18**	**J C40**	0.59	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-42	ND		0.20	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-43	ND	C	0.39	0.037	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-44	**0.27**	**J C B q**	0.59	0.035	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-45	ND	C	0.39	0.042	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-46	ND		0.20	0.051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-47	**0.27**	**J B C44 q**	0.59	0.035	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-48	**0.068**	**J**	0.20	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-49	**0.16**	**J C**	0.39	0.033	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-50	ND	C	0.39	0.039	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-51	ND	C45	0.39	0.042	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-52	**0.54**		0.20	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-53	ND	C50	0.39	0.039	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-54	ND		0.20	0.00083	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-55	ND		0.20	0.029	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-56	**0.13**	**J**	0.20	0.029	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-57	ND		0.20	0.029	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-58	ND		0.20	0.030	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-59	ND	C	0.59	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-60	**0.061**	**J q**	0.20	0.030	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-61	**0.68**	**J C B**	0.78	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-62	ND	C59	0.59	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-63	ND		0.20	0.027	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-64	**0.14**	**J**	0.20	0.027	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-65	**0.27**	**J B C44 q**	0.59	0.035	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-66	**0.25**		0.20	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-67	ND		0.20	0.026	ng/L		07/29/20 09:50	08/05/20 07:51	5

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0300N
Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.20	0.026	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-69	**0.16**	**J C49**	0.39	0.033	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-70	**0.68**	**J C61 B**	0.78	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-71	**0.18**	**J C40**	0.59	0.040	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-72	ND		0.20	0.029	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-73	ND	C43	0.39	0.037	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-74	**0.68**	**J C61 B**	0.78	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-75	ND	C59	0.59	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-76	**0.68**	**J C61 B**	0.78	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-77	**0.061**	**J**	0.20	0.031	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-78	ND		0.20	0.030	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-79	ND		0.20	0.026	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-80	ND		0.20	0.025	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-81	ND		0.20	0.025	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-82	**0.046**	**J B q**	0.20	0.0021	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-83	**0.021**	**J C B q**	0.39	0.0019	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-84	**0.11**	**J**	0.20	0.0021	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-85	**0.051**	**J C B q**	0.59	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-86	**0.32**	**J C B**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-87	**0.32**	**J B C86**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-88	**0.064**	**J C**	0.39	0.0019	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-89	ND		0.20	0.0020	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-90	**0.47**	**J C B**	0.59	0.0016	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-91	**0.064**	**J C88**	0.39	0.0019	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-92	**0.077**	**J**	0.20	0.0018	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-93	ND	C	0.39	0.0018	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-94	ND		0.20	0.0020	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-95	**0.36**	**B q**	0.20	0.0020	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-96	ND		0.20	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-97	**0.32**	**J B C86**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-98	ND	C	0.39	0.0017	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-99	**0.021**	**J C83 B q**	0.39	0.0019	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-100	ND	C93	0.39	0.0018	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-101	**0.47**	**J B C90**	0.59	0.0016	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-102	ND	C98	0.39	0.0017	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-103	ND		0.20	0.0018	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-104	ND		0.20	0.0014	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-105	**0.29**	**B**	0.20	0.036	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-106	ND		0.20	0.033	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-107	ND		0.20	0.035	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-108	ND	C	0.39	0.034	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-109	**0.32**	**J B C86**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-110	**0.50**	**C B**	0.39	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-111	ND		0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-112	**0.11**	**J q**	0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-113	**0.47**	**J B C90**	0.59	0.0016	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-114	ND		0.20	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-115	**0.50**	**B C110**	0.39	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-116	**0.051**	**J C85 B q**	0.59	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5

Client Sample ID: OFW0300N

Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	**0.051**	**J C85 B q**	0.59	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-118	**0.63**	**B**	0.20	0.028	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-119	**0.32**	**J B C86**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-120	ND		0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-121	ND		0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-122	ND		0.20	0.038	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-123	ND		0.20	0.029	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-124	ND	C108	0.39	0.034	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-125	**0.32**	**J B C86**	1.2	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-126	ND		0.20	0.042	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-127	ND		0.20	0.033	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-128	**0.14**	**J C B**	0.39	0.053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-129	**1.2**	**C B**	0.78	0.054	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-130	ND		0.20	0.072	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-131	ND		0.20	0.075	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-132	**0.33**		0.20	0.070	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-133	ND		0.20	0.068	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-134	ND	C	0.39	0.071	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-135	**0.21**	**J C q**	0.39	0.0014	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-136	**0.085**	**J**	0.20	0.00099	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-137	ND		0.20	0.061	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-138	**1.2**	**B C129**	0.78	0.054	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-139	ND	C	0.39	0.060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-140	ND	C139	0.39	0.060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-141	**0.19**	**J q**	0.20	0.063	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-142	ND		0.20	0.068	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-143	ND	C134	0.39	0.071	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-144	**0.038**	**J**	0.20	0.0012	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-145	ND		0.20	0.00094	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-146	ND		0.20	0.060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-147	**0.84**	**C**	0.39	0.068	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-148	ND		0.20	0.0013	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-149	**0.84**	**C147**	0.39	0.068	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-150	ND		0.20	0.00090	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-151	**0.21**	**J C135 q**	0.39	0.0014	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-152	ND		0.20	0.00097	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-153	**0.98**	**C B**	0.39	0.047	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-154	**0.0064**	**J q**	0.20	0.0011	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-155	ND		0.20	0.00090	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-156	**0.098**	**J C B q**	0.39	0.052	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-157	**0.098**	**J C156 B q**	0.39	0.052	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-158	**0.12**	**J**	0.20	0.043	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-159	ND		0.20	0.045	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-160	**1.2**	**B C129**	0.78	0.054	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-161	**0.094**	**J q**	0.20	0.045	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-162	ND		0.20	0.044	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-163	**1.2**	**B C129**	0.78	0.054	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-164	ND		0.20	0.048	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-165	ND		0.20	0.051	ng/L		07/29/20 09:50	08/05/20 07:51	5

Client Sample ID: OFW0300N
Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	**0.14**	**J C128 B**	0.39	0.053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-167	ND		0.20	0.036	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-168	**0.98**	**B C153**	0.39	0.047	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-169	ND		0.20	0.039	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-170	**0.22**	**B q**	0.20	0.0073	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-171	**0.084**	**J C B**	0.39	0.0060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-172	**0.052**	**J**	0.20	0.0060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-173	**0.084**	**J C171 B**	0.39	0.0060	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-174	**0.27**	**B**	0.20	0.0056	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-175	ND		0.20	0.0055	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-176	**0.024**	**J q**	0.20	0.0041	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-177	**0.12**	**J B q**	0.20	0.0058	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-178	**0.068**	**J q**	0.20	0.0059	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-179	**0.18**	**J**	0.20	0.0044	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-180	**0.60**	**C B q**	0.39	0.0046	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-181	ND		0.20	0.0054	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-182	ND		0.20	0.0052	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-183	**0.24**	**J C B**	0.39	0.0053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-184	ND		0.20	0.0045	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-185	**0.24**	**J B C183**	0.39	0.0053	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-186	ND		0.20	0.0043	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-187	**0.40**	**B**	0.20	0.0051	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-188	ND		0.20	0.0035	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-189	ND		0.20	0.052	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-190	**0.049**	**J B q**	0.20	0.0039	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-191	ND		0.20	0.0041	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-192	ND		0.20	0.0046	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-193	**0.60**	**C180 B q**	0.39	0.0046	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-194	**0.14**	**J B q**	0.20	0.059	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-195	ND		0.20	0.065	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-196	**0.077**	**J B q**	0.20	0.010	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-197	ND		0.20	0.0080	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-198	**0.25**	**J C B q**	0.39	0.011	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-199	**0.25**	**J C198 B q**	0.39	0.011	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-200	**0.029**	**J B q**	0.20	0.0071	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-201	ND		0.20	0.0073	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-202	**0.040**	**J q**	0.20	0.0082	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-203	**0.17**	**J B**	0.20	0.0095	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-204	ND		0.20	0.0080	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-205	ND		0.20	0.050	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-206	**0.17**	**J q**	0.20	0.041	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-207	ND		0.20	0.042	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-208	ND		0.20	0.062	ng/L		07/29/20 09:50	08/05/20 07:51	5
PCB-209	**0.074**	**J B**	0.20	0.031	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Monochlorobiphenyls	**0.029**	**J B**	0.20	0.0015	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Dichlorobiphenyls	**2.1**	**B q**	0.39	0.0093	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Trichlorobiphenyls	**0.54**	**B q**	0.39	0.0036	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Tetrachlorobiphenyls	**2.5**	**B q**	0.78	0.031	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Pentachlorobiphenyls	**3.0**	**B q**	1.2	0.012	ng/L		07/29/20 09:50	08/05/20 07:51	5

Client Sample ID: OFW0300N

Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	4.3	B q	0.78	0.041	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Heptachlorobiphenyls	2.3	B q	0.39	0.0073	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Octachlorobiphenyls	0.71	B q	0.39	0.022	ng/L		07/29/20 09:50	08/05/20 07:51	5
Total Nonachlorobiphenyls	0.17	J q	0.20	0.048	ng/L		07/29/20 09:50	08/05/20 07:51	5
Polychlorinated biphenyls, Total	16	B q	1.2	0.023	ng/L		07/29/20 09:50	08/05/20 07:51	5

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*83*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-3L	*81*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-4L	*75*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-15L	*65*	*q*	*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-19L	*79*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-37L	*67*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-54L	*62*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-77L	*34*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-81L	*36*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-104L	*84*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-105L	*62*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-114L	*76*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-118L	*74*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-123L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-126L	*51*	*q*	*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-155L	*60*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-156L	*56*	*C*	*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-157L	*56*	*C156*	*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-167L	*59*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-169L	*57*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-170L	*64*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-188L	*87*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-189L	*40*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-202L	*78*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-205L	*58*	*q*	*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-206L	*72*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-208L	*37*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-209L	*67*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*103*		*5 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-111L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*
PCB-178L	*115*		*10 - 145*	*07/29/20 09:50*	*08/05/20 07:51*	*5*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	650		30	13	ug/L		07/31/20 08:03	08/01/20 21:21	1
Arsenic	2.1		1.0	0.31	ug/L		07/31/20 08:03	08/01/20 21:21	1
Barium	28		10	1.6	ug/L		07/31/20 08:03	08/01/20 21:21	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:21	1
Cadmium	0.25	J	1.0	0.22	ug/L		07/31/20 08:03	08/01/20 21:21	1
Calcium	28000	B	500	130	ug/L		07/31/20 08:03	08/01/20 21:21	1
Chromium	5.1		2.0	1.5	ug/L		07/31/20 08:03	08/03/20 21:51	1
Cobalt	2.5		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 21:21	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0300N
Date Collected: 07/22/20 16:50
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-4
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	47		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 21:21	1
Iron	2200		50	20	ug/L		07/31/20 08:03	08/01/20 21:21	1
Silver	0.20	J	1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:21	1
Potassium	14000		500	160	ug/L		07/31/20 08:03	08/01/20 21:21	1
Magnesium	2600		500	83	ug/L		07/31/20 08:03	08/01/20 21:21	1
Manganese	100		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 21:21	1
Sodium	18000		500	350	ug/L		07/31/20 08:03	08/01/20 21:21	1
Nickel	8.8		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 21:21	1
Lead	48		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 21:21	1
Antimony	2.2		2.0	0.38	ug/L		07/31/20 08:03	08/01/20 21:21	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 21:21	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 21:21	1
Vanadium	9.1		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 21:21	1
Zinc	300	B	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 21:21	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:32	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	98		2.0	2.0	mg/L			07/25/20 13:18	1

Client Sample ID: OFW0500N

Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.15	0.052	ug/L		07/27/20 11:57	07/29/20 17:55	1
Acenaphthylene	ND		0.15	0.052	ug/L		07/27/20 11:57	07/29/20 17:55	1
Anthracene	ND		0.15	0.040	ug/L		07/27/20 11:57	07/29/20 17:55	1
Benzo[a]anthracene	**0.085**	**J**	0.15	0.060	ug/L		07/27/20 11:57	07/29/20 17:55	1
Benzo[b]fluoranthene	**0.13**	**J**	0.15	0.078	ug/L		07/27/20 11:57	07/29/20 17:55	1
Benzo[k]fluoranthene	**0.15**		0.15	0.071	ug/L		07/27/20 11:57	07/29/20 17:55	1
Benzo[g,h,i]perylene	**0.17**		0.15	0.056	ug/L		07/27/20 11:57	07/29/20 17:55	1
Benzo[a]pyrene	**0.069**	**J**	0.15	0.043	ug/L		07/27/20 11:57	07/29/20 17:55	1
Chrysene	**0.14**	**J**	0.15	0.065	ug/L		07/27/20 11:57	07/29/20 17:55	1
Dibenz(a,h)anthracene	**0.17**		0.15	0.058	ug/L		07/27/20 11:57	07/29/20 17:55	1
Fluoranthene	ND		0.15	0.048	ug/L		07/27/20 11:57	07/29/20 17:55	1
Fluorene	ND		0.15	0.056	ug/L		07/27/20 11:57	07/29/20 17:55	1
Indeno[1,2,3-cd]pyrene	**0.16**		0.15	0.069	ug/L		07/27/20 11:57	07/29/20 17:55	1
Naphthalene	ND		0.15	0.048	ug/L		07/27/20 11:57	07/29/20 17:55	1
Phenanthrene	**0.074**	**J**	0.15	0.044	ug/L		07/27/20 11:57	07/29/20 17:55	1
Pyrene	ND		0.15	0.044	ug/L		07/27/20 11:57	07/29/20 17:55	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*62*		*23 - 105*	*07/27/20 11:57*	*07/29/20 17:55*	*1*
Nitrobenzene-d5 (Surr)	*61*		*28 - 111*	*07/27/20 11:57*	*07/29/20 17:55*	*1*
Terphenyl-d14 (Surr)	*67*		*20 - 126*	*07/27/20 11:57*	*07/29/20 17:55*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**2000**		520	240	ug/L		07/28/20 06:30	07/29/20 21:02	1
ORO C24-C40	**2800**		520	240	ug/L		07/28/20 06:30	07/29/20 21:02	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*75*		*52 - 121*	*07/28/20 06:30*	*07/29/20 21:02*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.0033**	**J B**	0.078	0.00053	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-2	**0.0024**	**J q B**	0.078	0.00061	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-3	**0.0027**	**J B**	0.078	0.00067	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-4	ND		0.12	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-5	ND		0.078	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-6	ND		0.078	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-7	ND		0.078	0.0025	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-8	**0.0092**	**J q**	0.12	0.0022	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-9	ND		0.078	0.0025	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-10	ND		0.078	0.0027	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-11	**0.25**	**B**	0.12	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-12	ND	C	0.16	0.0025	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-13	ND	C12	0.16	0.0025	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-14	ND		0.078	0.0021	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-15	**0.013**	**J q**	0.078	0.0026	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-16	**0.0057**	**J**	0.078	0.0010	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-17	**0.0064**	**J**	0.078	0.00089	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-18	**0.014**	**J C**	0.16	0.00079	ng/L		07/29/20 09:50	08/05/20 16:32	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0500N
Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	ND		0.078	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-20	**0.033**	**J C B**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-21	**0.015**	**J q C B**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-22	**0.012**	**J**	0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-23	ND		0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-24	ND		0.078	0.00075	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-25	**0.0021**	**J q**	0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-26	**0.0042**	**J q C**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-27	ND		0.078	0.00065	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-28	**0.033**	**J C20 B**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-29	**0.0042**	**J q C26**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-30	**0.014**	**J C18**	0.16	0.00079	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-31	**0.028**	**J B**	0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-32	**0.0046**	**J q**	0.078	0.00062	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-33	**0.015**	**J q C21 B**	0.16	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-34	ND		0.078	0.0014	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-35	**0.0020**	**J q B**	0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-36	ND		0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-37	**0.016**	**J B**	0.078	0.0013	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-38	ND		0.078	0.0014	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-39	ND		0.078	0.0012	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-40	**0.019**	**J q C**	0.23	0.0050	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-41	**0.019**	**J q C40**	0.23	0.0050	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-42	**0.0063**	**J q**	0.078	0.0050	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-43	ND	C	0.16	0.0047	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-44	**0.041**	**J C B**	0.23	0.0044	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-45	**0.0064**	**J q C B**	0.16	0.0052	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-46	ND		0.078	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-47	**0.041**	**J C44 B**	0.23	0.0044	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-48	**0.0070**	**J**	0.078	0.0050	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-49	**0.014**	**J q C**	0.16	0.0040	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-50	ND	C	0.16	0.0048	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-51	**0.0064**	**J q C45 B**	0.16	0.0052	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-52	**0.048**	**J**	0.078	0.0049	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-53	ND	C50	0.16	0.0048	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-54	ND		0.078	0.00040	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-55	ND		0.078	0.0036	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-56	**0.018**	**J**	0.078	0.0036	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-57	ND		0.078	0.0037	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-58	ND		0.078	0.0037	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-59	ND	C	0.23	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-60	**0.011**	**J**	0.078	0.0037	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-61	**0.072**	**J C B**	0.31	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-62	ND	C59	0.23	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-63	ND		0.078	0.0034	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-64	**0.013**	**J q**	0.078	0.0033	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-65	**0.041**	**J C44 B**	0.23	0.0044	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-66	**0.032**	**J**	0.078	0.0034	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-67	ND		0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2

Client Sample ID: OFW0500N
Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-69	**0.014**	**J q C49**	0.16	0.0040	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-70	**0.072**	**J C61 B**	0.31	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-71	**0.019**	**J q C40**	0.23	0.0050	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-72	ND		0.078	0.0036	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-73	ND	C43	0.16	0.0047	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-74	**0.072**	**J C61 B**	0.31	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-75	ND	C59	0.23	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-76	**0.072**	**J C61 B**	0.31	0.0035	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-77	**0.011**	**J q**	0.078	0.0036	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-78	ND		0.078	0.0037	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-79	ND		0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-80	ND		0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-81	ND		0.078	0.0033	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-82	**0.018**	**J q B**	0.078	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-83	**0.052**	**J q C B**	0.16	0.00098	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-84	**0.025**	**J q**	0.078	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-85	**0.023**	**J C B**	0.23	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-86	**0.081**	**J q C B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-87	**0.081**	**J q C86 B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-88	**0.011**	**J q C**	0.16	0.00097	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-89	ND		0.078	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-90	**0.12**	**J C B**	0.23	0.00082	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-91	**0.011**	**J q C88**	0.16	0.00097	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-92	**0.018**	**J**	0.078	0.00092	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-93	**0.0016**	**J q C**	0.16	0.00093	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-94	ND		0.078	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-95	**0.081**	**B**	0.078	0.0010	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-96	ND		0.078	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-97	**0.081**	**J q C86 B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-98	ND	C	0.16	0.00090	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-99	**0.052**	**J q C83 B**	0.16	0.00098	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-100	**0.0016**	**J q C93**	0.16	0.00093	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-101	**0.12**	**J C90 B**	0.23	0.00082	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-102	ND	C98	0.16	0.00090	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-103	ND		0.078	0.00093	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-104	ND		0.078	0.00071	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-105	**0.054**	**J B**	0.078	0.0029	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-106	ND		0.078	0.0029	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-107	**0.0069**	**J q B**	0.078	0.0031	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-108	**0.0062**	**J q C B**	0.16	0.0030	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-109	**0.081**	**J q C86 B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-110	**0.19**	**C B**	0.16	0.00068	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-111	ND		0.078	0.00065	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-112	ND		0.078	0.00069	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-113	**0.12**	**J C90 B**	0.23	0.00082	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-114	ND		0.078	0.0027	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-115	**0.19**	**C110 B**	0.16	0.00068	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-116	**0.023**	**J C85 B**	0.23	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2

Client Sample ID: OFW0500N
Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	**0.023**	**J C85 B**	0.23	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-118	**0.13**	**B**	0.078	0.0026	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-119	**0.081**	**J q C86 B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-120	ND		0.078	0.00067	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-121	ND		0.078	0.00068	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-122	ND		0.078	0.0034	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-123	ND		0.078	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-124	**0.0062**	**J q C108 B**	0.16	0.0030	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-125	**0.081**	**J q C86 B**	0.47	0.00080	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-126	ND		0.078	0.0033	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-127	ND		0.078	0.0029	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-128	**0.033**	**J C B**	0.16	0.0061	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-129	**0.26**	**J C B**	0.31	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-130	**0.014**	**J q**	0.078	0.0083	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-131	ND		0.078	0.0086	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-132	**0.081**		0.078	0.0081	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-133	ND		0.078	0.0078	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-134	ND	C	0.16	0.0082	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-135	**0.046**	**J q C**	0.16	0.00078	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-136	**0.016**	**J**	0.078	0.00056	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-137	**0.013**	**J**	0.078	0.0071	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-138	**0.26**	**J C129 B**	0.31	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-139	ND	C	0.16	0.0070	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-140	ND	C139	0.16	0.0070	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-141	**0.053**	**J**	0.078	0.0073	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-142	ND		0.078	0.0078	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-143	ND	C134	0.16	0.0082	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-144	**0.0071**	**J**	0.078	0.00071	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-145	ND		0.078	0.00054	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-146	**0.033**	**J**	0.078	0.0069	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-147	**0.18**	**C**	0.16	0.0079	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-148	ND		0.078	0.00076	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-149	**0.18**	**C147**	0.16	0.0079	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-150	ND		0.078	0.00051	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-151	**0.046**	**J q C135**	0.16	0.00078	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-152	ND		0.078	0.00055	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-153	**0.18**	**C B**	0.16	0.0055	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-154	ND		0.078	0.00061	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-155	ND		0.078	0.00052	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-156	**0.021**	**J C B**	0.16	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-157	**0.021**	**J C156 B**	0.16	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-158	**0.023**	**J**	0.078	0.0049	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-159	ND		0.078	0.0052	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-160	**0.26**	**J C129 B**	0.31	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-161	ND		0.078	0.0052	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-162	ND		0.078	0.0051	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-163	**0.26**	**J C129 B**	0.31	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-164	**0.017**	**J**	0.078	0.0055	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-165	ND		0.078	0.0059	ng/L		07/29/20 09:50	08/05/20 16:32	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0500N
Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.033	J C128 B	0.16	0.0061	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-167	0.0082	J q B	0.078	0.0038	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-168	0.18	C153 B	0.16	0.0055	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-169	ND		0.078	0.0046	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-170	0.059	J B	0.078	0.0042	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-171	0.015	J q C B	0.16	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-172	0.010	J q	0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-173	0.015	J q C171 B	0.16	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-174	0.059	J B	0.078	0.0030	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-175	0.0034	J q	0.078	0.0029	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-176	0.0055	J q	0.078	0.0022	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-177	0.032	J B	0.078	0.0031	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-178	0.011	J	0.078	0.0032	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-179	0.030	J	0.078	0.0023	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-180	0.12	J C B	0.16	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-181	ND		0.078	0.0029	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-182	ND		0.078	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-183	0.040	J C B	0.16	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-184	ND		0.078	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-185	0.040	J C183 B	0.16	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-186	ND		0.078	0.0023	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-187	0.060	J q B	0.078	0.0027	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-188	ND		0.078	0.0018	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-189	ND		0.078	0.0049	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-190	0.0086	J q B	0.078	0.0021	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-191	ND		0.078	0.0022	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-192	ND		0.078	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-193	0.12	J C180 B	0.16	0.0024	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-194	0.025	J q B	0.078	0.010	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-195	ND		0.078	0.011	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-196	0.023	J B	0.078	0.0059	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-197	ND		0.078	0.0045	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-198	0.039	J q C B	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-199	0.039	J q C198 B	0.16	0.0060	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-200	ND		0.078	0.0040	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-201	ND		0.078	0.0041	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-202	ND		0.078	0.0046	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-203	0.019	J q B	0.078	0.0053	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-204	ND		0.078	0.0045	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-205	ND		0.078	0.0088	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-206	0.024	J q	0.078	0.0078	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-207	ND		0.078	0.0058	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-208	ND		0.078	0.0062	ng/L		07/29/20 09:50	08/05/20 16:32	2
PCB-209	0.010	J B	0.078	0.0048	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Monochlorobiphenyls	0.0084	J q B	0.078	0.00061	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Dichlorobiphenyls	0.27	q B	0.16	0.0026	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Trichlorobiphenyls	0.14	J q B	0.16	0.0011	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Tetrachlorobiphenyls	0.30	J q B	0.31	0.0039	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Pentachlorobiphenyls	0.82	q B	0.47	0.0015	ng/L		07/29/20 09:50	08/05/20 16:32	2

Client Sample ID: OFW0500N

Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	0.99	q B	0.31	0.0048	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Heptachlorobiphenyls	0.45	q B	0.16	0.0028	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Octachlorobiphenyls	0.11	J q B	0.16	0.0063	ng/L		07/29/20 09:50	08/05/20 16:32	2
Total Nonachlorobiphenyls	0.024	J q	0.078	0.0066	ng/L		07/29/20 09:50	08/05/20 16:32	2
Polychlorinated biphenyls, Total	3.1	q B	0.47	0.0038	ng/L		07/29/20 09:50	08/05/20 16:32	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*60*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-3L	*66*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-4L	*69*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-15L	*70*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-19L	*76*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-37L	*72*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-54L	*66*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-77L	*67*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-81L	*67*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-104L	*61*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-105L	*69*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-114L	*74*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-118L	*75*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-123L	*74*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-126L	*65*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-155L	*67*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-156L	*62*	*C*	*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-157L	*62*	*C156*	*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-167L	*65*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-169L	*58*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-170L	*59*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-188L	*93*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-189L	*73*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-202L	*82*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-205L	*62*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-206L	*69*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-208L	*68*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-209L	*69*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*104*		*5 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-111L	*96*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*
PCB-178L	*127*		*10 - 145*	*07/29/20 09:50*	*08/05/20 16:32*	*2*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	260		30	13	ug/L		07/31/20 08:03	08/01/20 21:24	1
Arsenic	1.4		1.0	0.31	ug/L		07/31/20 08:03	08/01/20 21:24	1
Barium	21		10	1.6	ug/L		07/31/20 08:03	08/01/20 21:24	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:24	1
Cadmium	ND		1.0	0.22	ug/L		07/31/20 08:03	08/01/20 21:24	1
Calcium	18000	B	500	130	ug/L		07/31/20 08:03	08/01/20 21:24	1
Chromium	9.7		2.0	1.5	ug/L		07/31/20 08:03	08/03/20 22:01	1
Cobalt	0.68		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 21:24	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-108704-1

Client Sample ID: OFW0500N
Date Collected: 07/22/20 17:30
Date Received: 07/24/20 08:45

Lab Sample ID: 180-108704-5
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	20		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 21:24	1
Iron	650		50	20	ug/L		07/31/20 08:03	08/01/20 21:24	1
Silver	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 21:24	1
Potassium	5500		500	160	ug/L		07/31/20 08:03	08/01/20 21:24	1
Magnesium	1800		500	83	ug/L		07/31/20 08:03	08/01/20 21:24	1
Manganese	30		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 21:24	1
Sodium	12000		500	350	ug/L		07/31/20 08:03	08/01/20 21:24	1
Nickel	4.1		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 21:24	1
Lead	5.5		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 21:24	1
Antimony	1.3	J	2.0	0.38	ug/L		07/31/20 08:03	08/01/20 21:24	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 21:24	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 21:24	1
Vanadium	10		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 21:24	1
Zinc	74	B	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 21:24	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:33	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	17		1.3	1.3	mg/L			07/25/20 13:18	1

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: MB 180-323155/1-A
Matrix: Water
Analysis Batch: 323469

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 323155

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.19	0.065	ug/L		07/27/20 11:53	07/29/20 12:14	1
Acenaphthylene	ND		0.19	0.065	ug/L		07/27/20 11:53	07/29/20 12:14	1
Anthracene	ND		0.19	0.049	ug/L		07/27/20 11:53	07/29/20 12:14	1
Benzo[a]anthracene	ND		0.19	0.075	ug/L		07/27/20 11:53	07/29/20 12:14	1
Benzo[b]fluoranthene	ND		0.19	0.097	ug/L		07/27/20 11:53	07/29/20 12:14	1
Benzo[k]fluoranthene	ND		0.19	0.088	ug/L		07/27/20 11:53	07/29/20 12:14	1
Benzo[g,h,i]perylene	ND		0.19	0.069	ug/L		07/27/20 11:53	07/29/20 12:14	1
Benzo[a]pyrene	ND		0.19	0.053	ug/L		07/27/20 11:53	07/29/20 12:14	1
Chrysene	ND		0.19	0.081	ug/L		07/27/20 11:53	07/29/20 12:14	1
Dibenz(a,h)anthracene	ND		0.19	0.072	ug/L		07/27/20 11:53	07/29/20 12:14	1
Fluoranthene	ND		0.19	0.060	ug/L		07/27/20 11:53	07/29/20 12:14	1
Fluorene	ND		0.19	0.069	ug/L		07/27/20 11:53	07/29/20 12:14	1
Indeno[1,2,3-cd]pyrene	ND		0.19	0.085	ug/L		07/27/20 11:53	07/29/20 12:14	1
Naphthalene	ND		0.19	0.059	ug/L		07/27/20 11:53	07/29/20 12:14	1
Phenanthrene	ND		0.19	0.055	ug/L		07/27/20 11:53	07/29/20 12:14	1
Pyrene	ND		0.19	0.054	ug/L		07/27/20 11:53	07/29/20 12:14	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*80*		*23 - 105*	*07/27/20 11:53*	*07/29/20 12:14*	*1*
Nitrobenzene-d5 (Surr)	*80*		*28 - 111*	*07/27/20 11:53*	*07/29/20 12:14*	*1*
Terphenyl-d14 (Surr)	*81*		*20 - 126*	*07/27/20 11:53*	*07/29/20 12:14*	*1*

Lab Sample ID: LCS 180-323155/2-A
Matrix: Water
Analysis Batch: 323469

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 323155

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	20.0	14.5		ug/L		73	50 - 100
Acenaphthylene	20.0	14.7		ug/L		73	51 - 100
Anthracene	20.0	15.4		ug/L		77	53 - 100
Benzo[a]anthracene	20.0	15.5		ug/L		77	51 - 100
Benzo[b]fluoranthene	20.0	14.5		ug/L		73	45 - 100
Benzo[k]fluoranthene	20.0	15.4		ug/L		77	49 - 100
Benzo[g,h,i]perylene	20.0	14.7		ug/L		73	51 - 100
Benzo[a]pyrene	20.0	16.1		ug/L		80	51 - 100
Chrysene	20.0	15.4		ug/L		77	51 - 100
Dibenz(a,h)anthracene	20.0	15.0		ug/L		75	50 - 100
Fluoranthene	20.0	16.5		ug/L		83	54 - 100
Fluorene	20.0	14.8		ug/L		74	53 - 100
Indeno[1,2,3-cd]pyrene	20.0	14.9		ug/L		75	50 - 100
Naphthalene	20.0	14.3		ug/L		72	55 - 100
Phenanthrene	20.0	14.9		ug/L		74	51 - 100
Pyrene	20.0	16.4		ug/L		82	47 - 100

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*71*		*23 - 105*
Nitrobenzene-d5 (Surr)	*70*		*28 - 111*
Terphenyl-d14 (Surr)	*80*		*20 - 126*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Lab Sample ID: MB 240-444506/6-A
Matrix: Water
Analysis Batch: 444816

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 444506

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	ND		500	230	ug/L		07/28/20 06:30	07/29/20 21:30	1
ORO C24-C40	ND		500	230	ug/L		07/28/20 06:30	07/29/20 21:30	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*82*		*52 - 121*	*07/28/20 06:30*	*07/29/20 21:30*	*1*

Lab Sample ID: LCS 240-444506/7-A
Matrix: Water
Analysis Batch: 444816

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 444506

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Diesel Range Organics [C10 - C28]	2000	1690		ug/L		85	56 - 120

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
o-Terphenyl	*82*		*52 - 121*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Lab Sample ID: MB 140-41399/7-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41399

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.00143	J q	0.040	0.00025	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-2	0.00172	J q	0.040	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-3	0.00124	J q	0.040	0.00035	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-4	ND		0.060	0.0057	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-5	ND		0.040	0.0049	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-6	ND		0.040	0.0043	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-7	ND		0.040	0.0044	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-8	ND		0.060	0.0040	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-9	ND		0.040	0.0045	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-10	ND		0.040	0.0048	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-11	0.0142	J q	0.060	0.0042	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-12	ND	C	0.080	0.0043	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-13	ND	C12	0.080	0.0043	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-14	ND		0.040	0.0037	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-15	ND		0.040	0.0048	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-16	ND		0.040	0.00066	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-17	ND		0.040	0.00059	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-18	ND	C	0.080	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-19	ND		0.040	0.00072	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-20	0.00246	J q C	0.080	0.00061	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-21	0.00287	J C	0.080	0.00059	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-22	ND		0.040	0.00062	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-23	ND		0.040	0.00062	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-24	ND		0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41399/7-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41399

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-25	ND		0.040	0.00056	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-26	ND	C	0.080	0.00060	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-27	ND		0.040	0.00043	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-28	0.00246	J q C20	0.080	0.00061	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-29	ND	C26	0.080	0.00060	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-30	ND	C18	0.080	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-31	0.00266	J q	0.040	0.00059	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-32	ND		0.040	0.00041	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-33	0.00287	J C21	0.080	0.00059	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-34	ND		0.040	0.00064	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-35	0.00116	J q	0.040	0.00062	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-36	ND		0.040	0.00060	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-37	0.00230	J	0.040	0.00062	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-38	ND		0.040	0.00065	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-39	ND		0.040	0.00058	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-40	ND	C	0.12	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-41	ND	C40	0.12	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-42	ND		0.040	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-43	ND	C	0.080	0.00099	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-44	0.0665	J C	0.12	0.00093	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-45	0.00658	J C	0.080	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-46	ND		0.040	0.0013	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-47	0.0665	J C44	0.12	0.00093	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-48	ND		0.040	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-49	ND	C	0.080	0.00086	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-50	ND	C	0.080	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-51	0.00658	J C45	0.080	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-52	ND		0.040	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-53	ND	C50	0.080	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-54	ND		0.040	0.00017	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-55	ND		0.040	0.00076	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-56	ND		0.040	0.00077	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-57	ND		0.040	0.00078	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-58	ND		0.040	0.00079	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-59	0.00207	J C	0.12	0.00074	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-60	ND		0.040	0.00078	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-61	0.00644	J C	0.16	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-62	0.00207	J C59	0.12	0.00074	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-63	ND		0.040	0.00071	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-64	ND		0.040	0.00070	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-65	0.0665	J C44	0.12	0.00093	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-66	ND		0.040	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-67	ND		0.040	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-68	0.0101	J	0.040	0.00069	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-69	ND	C49	0.080	0.00086	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-70	0.00644	J C61	0.16	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-71	ND	C40	0.12	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-72	ND		0.040	0.00076	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-73	ND	C43	0.080	0.00099	ng/L		07/29/20 09:50	08/04/20 15:05	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41399/7-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41399

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-74	0.00644	J C61	0.16	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-75	0.00207	J C59	0.12	0.00074	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-76	0.00644	J C61	0.16	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-77	ND		0.040	0.00072	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-78	0.00141	J q	0.040	0.00079	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-79	ND		0.040	0.00068	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-80	ND		0.040	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-81	ND		0.040	0.00074	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-82	0.00138	J	0.040	0.00034	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-83	0.00250	J q C	0.080	0.00031	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-84	ND		0.040	0.00035	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-85	0.00338	J q C	0.12	0.00025	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-86	0.00496	J q C	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-87	0.00496	J q C86	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-88	ND	C	0.080	0.00031	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-89	ND		0.040	0.00034	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-90	0.00352	J C	0.12	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-91	ND	C88	0.080	0.00031	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-92	ND		0.040	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-93	ND	C	0.080	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-94	ND		0.040	0.00034	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-95	0.00170	J q	0.040	0.00033	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-96	ND		0.040	0.00025	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-97	0.00496	J q C86	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-98	ND	C	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-99	0.00250	J q C83	0.080	0.00031	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-100	ND	C93	0.080	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-101	0.00352	J C90	0.12	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-102	ND	C98	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-103	ND		0.040	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-104	ND		0.040	0.00023	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-105	0.00263	J	0.040	0.00048	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-106	0.00103	J q	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-107	0.00121	J q	0.040	0.00054	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-108	0.00275	J q C	0.080	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-109	0.00496	J q C86	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-110	0.00494	J q C	0.080	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-111	0.00102	J	0.040	0.00021	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-112	ND		0.040	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-113	0.00352	J C90	0.12	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-114	0.00136	J	0.040	0.00047	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-115	0.00494	J q C110	0.080	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-116	0.00338	J q C85	0.12	0.00025	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-117	0.00338	J q C85	0.12	0.00025	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-118	0.00434	J q	0.040	0.00047	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-119	0.00496	J q C86	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-120	ND		0.040	0.00021	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-121	ND		0.040	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-122	0.00192	J	0.040	0.00058	ng/L		07/29/20 09:50	08/04/20 15:05	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41399/7-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41399

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-123	0.00114	J q	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-124	0.00275	J q C108	0.080	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-125	0.00496	J q C86	0.24	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-126	0.00234	J q	0.040	0.00054	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-127	0.00210	J	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-128	0.00318	J q C	0.080	0.00075	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-129	0.00996	J C	0.16	0.00077	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-130	ND		0.040	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-131	ND		0.040	0.0011	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-132	ND		0.040	0.00099	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-133	ND		0.040	0.00096	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-134	ND	C	0.080	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-135	ND	C	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-136	ND		0.040	0.00021	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-137	ND		0.040	0.00087	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-138	0.00996	J C129	0.16	0.00077	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-139	ND	C	0.080	0.00086	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-140	ND	C139	0.080	0.00086	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-141	ND		0.040	0.00090	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-142	ND		0.040	0.00096	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-143	ND	C134	0.080	0.0010	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-144	ND		0.040	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-145	ND		0.040	0.00020	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-146	ND		0.040	0.00085	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-147	ND	C	0.080	0.00097	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-148	ND		0.040	0.00028	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-149	ND	C147	0.080	0.00097	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-150	ND		0.040	0.00019	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-151	ND	C135	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-152	ND		0.040	0.00020	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-153	0.00371	J q C	0.080	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-154	ND		0.040	0.00023	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-155	ND		0.040	0.00019	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-156	0.00516	J C	0.080	0.00079	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-157	0.00516	J C156	0.080	0.00079	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-158	ND		0.040	0.00061	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-159	0.00190	J	0.040	0.00064	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-160	0.00996	J C129	0.16	0.00077	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-161	ND		0.040	0.00064	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-162	0.00110	J q	0.040	0.00063	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-163	0.00996	J C129	0.16	0.00077	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-164	ND		0.040	0.00068	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-165	ND		0.040	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-166	0.00318	J q C128	0.080	0.00075	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-167	0.00231	J q	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-168	0.00371	J q C153	0.080	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-169	0.00409	J	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-170	0.00236	J q	0.040	0.00079	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-171	0.00352	J C	0.080	0.00076	ng/L		07/29/20 09:50	08/04/20 15:05	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41399/7-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41399

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-172	ND		0.040	0.00075	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-173	0.00352	J C171	0.080	0.00076	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-174	0.00202	J q	0.040	0.00071	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-175	ND		0.040	0.00069	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-176	ND		0.040	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-177	0.00172	J q	0.040	0.00073	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-178	ND		0.040	0.00074	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-179	ND		0.040	0.00055	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-180	0.00372	J q C	0.080	0.00057	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-181	0.00192	J q	0.040	0.00068	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-182	ND		0.040	0.00066	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-183	0.00303	J q C	0.080	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-184	ND		0.040	0.00056	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-185	0.00303	J q C183	0.080	0.00067	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-186	ND		0.040	0.00055	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-187	0.00291	J	0.040	0.00064	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-188	ND		0.040	0.00048	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-189	0.00528	J	0.040	0.00044	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-190	0.00217	J q	0.040	0.00050	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-191	0.00174	J q	0.040	0.00052	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-192	ND		0.040	0.00058	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-193	0.00372	J q C180	0.080	0.00057	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-194	0.00530	J	0.040	0.00021	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-195	0.00214	J q	0.040	0.00023	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-196	0.00130	J q	0.040	0.00028	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-197	0.00176	J	0.040	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-198	0.00191	J q C	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-199	0.00191	J q C198	0.080	0.00029	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-200	0.000542	J q	0.040	0.00019	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-201	ND		0.040	0.00020	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-202	ND		0.040	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-203	0.00156	J q	0.040	0.00026	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-204	ND		0.040	0.00022	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-205	0.00524	J q	0.040	0.00018	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-206	ND		0.040	0.0034	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-207	ND		0.040	0.0023	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-208	ND		0.040	0.0023	ng/L		07/29/20 09:50	08/04/20 15:05	1
PCB-209	0.00374	J q	0.040	0.00013	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Monochlorobiphenyls	0.00439	J q	0.040	0.00030	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Dichlorobiphenyls	0.0142	J q	0.080	0.0045	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Trichlorobiphenyls	0.0115	J q	0.080	0.00059	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Tetrachlorobiphenyls	0.0931	J q	0.16	0.00082	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Pentachlorobiphenyls	0.0442	J q	0.24	0.00035	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Hexachlorobiphenyls	0.0314	J q	0.16	0.00064	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Heptachlorobiphenyls	0.0304	J q	0.080	0.00062	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Octachlorobiphenyls	0.0198	J q	0.080	0.00023	ng/L		07/29/20 09:50	08/04/20 15:05	1
Total Nonachlorobiphenyls	ND		0.040	0.0034	ng/L		07/29/20 09:50	08/04/20 15:05	1
Polychlorinated biphenyls, Total	0.253	q	0.24	0.0013	ng/L		07/29/20 09:50	08/04/20 15:05	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-1L	86		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-3L	84		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-4L	77		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-15L	77		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-19L	92		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-37L	93		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-54L	94		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-77L	91		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-81L	87		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-104L	82		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-105L	98		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-114L	95		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-118L	94		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-123L	92		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-126L	94		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-155L	83		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-156L	91	C	10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-157L	91	C156	10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-167L	91		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-169L	95		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-170L	89		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-188L	92		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-189L	100		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-202L	102		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-205L	83		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-206L	86		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-208L	89		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-209L	78		10 - 145	07/29/20 09:50	08/04/20 15:05	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	100		5 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-111L	97		10 - 145	07/29/20 09:50	08/04/20 15:05	1
PCB-178L	102		10 - 145	07/29/20 09:50	08/04/20 15:05	1

Lab Sample ID: LCS 140-41399/6-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 41399

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1	1.00	0.896		ng/L		90	60 - 135
PCB-3	1.00	0.925		ng/L		92	60 - 135
PCB-4	1.00	1.01		ng/L		101	60 - 135
PCB-15	1.00	1.13		ng/L		113	60 - 135
PCB-19	1.00	1.13		ng/L		113	60 - 135
PCB-37	1.00	1.06		ng/L		106	60 - 135
PCB-54	1.00	0.997		ng/L		100	60 - 135
PCB-77	1.00	1.04		ng/L		104	60 - 135
PCB-81	1.00	0.921		ng/L		92	60 - 135
PCB-104	1.00	1.08		ng/L		108	60 - 135
PCB-105	1.00	1.07		ng/L		107	60 - 135
PCB-114	1.00	1.14		ng/L		114	60 - 135

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-41399/6-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 41399

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
PCB-118			1.00	1.11		ng/L		111	60 - 135		
PCB-123			1.00	1.09		ng/L		109	60 - 135		
PCB-126			1.00	1.14		ng/L		114	60 - 135		
PCB-155			1.00	1.04		ng/L		104	60 - 135		
PCB-156			2.00	2.12	C	ng/L		106	60 - 135		
PCB-157			2.00	2.12	C156	ng/L		106	60 - 135		
PCB-167			1.00	1.09		ng/L		109	60 - 135		
PCB-169			1.00	0.966		ng/L		97	60 - 135		
PCB-188			1.00	0.998		ng/L		100	60 - 135		
PCB-189			1.00	1.08		ng/L		108	60 - 135		
PCB-202			1.00	0.912		ng/L		91	60 - 135		
PCB-205			1.00	1.12		ng/L		112	60 - 135		
PCB-206			1.00	0.889		ng/L		89	60 - 135		
PCB-208			1.00	0.893		ng/L		89	60 - 135		
PCB-209			1.00	0.837		ng/L		84	60 - 135		

Isotope Dilution	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-1L	*91*		*15 - 145*
PCB-3L	*87*		*15 - 145*
PCB-4L	*84*		*15 - 145*
PCB-15L	*83*		*15 - 145*
PCB-19L	*95*		*15 - 145*
PCB-37L	*95*		*15 - 145*
PCB-54L	*96*		*15 - 145*
PCB-77L	*91*		*40 - 145*
PCB-81L	*90*		*40 - 145*
PCB-104L	*85*		*40 - 145*
PCB-105L	*98*		*40 - 145*
PCB-114L	*96*		*40 - 145*
PCB-118L	*94*		*40 - 145*
PCB-123L	*94*		*40 - 145*
PCB-126L	*95*		*40 - 145*
PCB-155L	*85*		*40 - 145*
PCB-156L	*92*	*C*	*40 - 145*
PCB-157L	*92*	*C156*	*40 - 145*
PCB-167L	*94*		*40 - 145*
PCB-169L	*96*		*40 - 145*
PCB-170L	*88*		*40 - 145*
PCB-188L	*96*		*40 - 145*
PCB-189L	*101*		*40 - 145*
PCB-202L	*101*		*40 - 145*
PCB-205L	*82*		*40 - 145*
PCB-206L	*83*		*40 - 145*
PCB-208L	*88*		*40 - 145*
PCB-209L	*77*		*40 - 145*

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-28L	*97*		*15 - 145*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-41399/6-A
Matrix: Water
Analysis Batch: 41606

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 41399

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-111L	*95*		*40 - 145*
PCB-178L	*102*		*40 - 145*

Method: EPA 6020A - Metals (ICP/MS)

Lab Sample ID: MB 180-323777/1-A
Matrix: Water
Analysis Batch: 324024

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 323777

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	ND		30	13	ug/L		07/31/20 08:03	08/01/20 20:28	1
Arsenic	ND		1.0	0.31	ug/L		07/31/20 08:03	08/01/20 20:28	1
Barium	ND		10	1.6	ug/L		07/31/20 08:03	08/01/20 20:28	1
Beryllium	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 20:28	1
Cadmium	ND		1.0	0.22	ug/L		07/31/20 08:03	08/01/20 20:28	1
Calcium	187	J	500	130	ug/L		07/31/20 08:03	08/01/20 20:28	1
Chromium	ND		2.0	1.5	ug/L		07/31/20 08:03	08/01/20 20:28	1
Cobalt	ND		0.50	0.13	ug/L		07/31/20 08:03	08/01/20 20:28	1
Copper	ND		2.0	0.63	ug/L		07/31/20 08:03	08/01/20 20:28	1
Iron	ND		50	20	ug/L		07/31/20 08:03	08/01/20 20:28	1
Silver	ND		1.0	0.18	ug/L		07/31/20 08:03	08/01/20 20:28	1
Potassium	ND		500	160	ug/L		07/31/20 08:03	08/01/20 20:28	1
Magnesium	ND		500	83	ug/L		07/31/20 08:03	08/01/20 20:28	1
Manganese	ND		5.0	0.87	ug/L		07/31/20 08:03	08/01/20 20:28	1
Sodium	ND		500	350	ug/L		07/31/20 08:03	08/01/20 20:28	1
Nickel	ND		1.0	0.34	ug/L		07/31/20 08:03	08/01/20 20:28	1
Lead	ND		1.0	0.13	ug/L		07/31/20 08:03	08/01/20 20:28	1
Antimony	ND		2.0	0.38	ug/L		07/31/20 08:03	08/01/20 20:28	1
Selenium	ND		5.0	1.5	ug/L		07/31/20 08:03	08/01/20 20:28	1
Thallium	ND		1.0	0.15	ug/L		07/31/20 08:03	08/01/20 20:28	1
Vanadium	ND		1.0	0.99	ug/L		07/31/20 08:03	08/01/20 20:28	1
Zinc	4.00	J	5.0	3.2	ug/L		07/31/20 08:03	08/01/20 20:28	1

Lab Sample ID: LCS 180-323777/2-A
Matrix: Water
Analysis Batch: 324024

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 323777

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Aluminum	5000	4850		ug/L		97	80 - 120
Arsenic	1000	985		ug/L		98	80 - 120
Barium	1000	985		ug/L		99	80 - 120
Beryllium	500	495		ug/L		99	80 - 120
Cadmium	500	490		ug/L		98	80 - 120
Calcium	25000	27700		ug/L		111	80 - 120
Chromium	500	490		ug/L		98	80 - 120
Cobalt	500	488		ug/L		98	80 - 120
Copper	500	480		ug/L		96	80 - 120
Iron	5000	5020		ug/L		100	80 - 120
Silver	250	244		ug/L		98	80 - 120

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 180-323777/2-A
Matrix: Water
Analysis Batch: 324024

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 323777

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Potassium	25000	24700		ug/L		99	80 - 120
Magnesium	25000	24900		ug/L		99	80 - 120
Manganese	500	485		ug/L		97	80 - 120
Sodium	25000	24100		ug/L		97	80 - 120
Nickel	500	478		ug/L		96	80 - 120
Lead	500	494		ug/L		99	80 - 120
Antimony	250	256		ug/L		102	80 - 120
Selenium	1000	994		ug/L		99	80 - 120
Thallium	1000	991		ug/L		99	80 - 120
Vanadium	500	486		ug/L		97	80 - 120
Zinc	250	248		ug/L		99	80 - 120

Method: EPA 7470A - Mercury (CVAA)

Lab Sample ID: MB 180-323724/1-A
Matrix: Water
Analysis Batch: 324008

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 323724

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		07/31/20 05:35	08/03/20 10:16	1

Lab Sample ID: LCS 180-323724/2-A
Matrix: Water
Analysis Batch: 324008

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 323724

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Mercury	2.50	2.66		ug/L		106	80 - 120

Method: SM 2540D - Solids, Total Suspended (TSS)

Lab Sample ID: MB 180-323013/2
Matrix: Water
Analysis Batch: 323013

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	ND		0.50	0.50	mg/L			07/25/20 13:18	1

Lab Sample ID: LCS 180-323013/1
Matrix: Water
Analysis Batch: 323013

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Suspended Solids	84.7	96.0		mg/L		113	80 - 120

GC/MS Semi VOA

Prep Batch: 323155

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	3520C	
180-108704-2	OFW0100R	Total/NA	Water	3520C	
180-108704-3	OFW0200N	Total/NA	Water	3520C	
180-108704-4	OFW0300N	Total/NA	Water	3520C	
180-108704-5	OFW0500N	Total/NA	Water	3520C	
MB 180-323155/1-A	Method Blank	Total/NA	Water	3520C	
LCS 180-323155/2-A	Lab Control Sample	Total/NA	Water	3520C	

Analysis Batch: 323410

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	EPA 8270D LL	323155
180-108704-2	OFW0100R	Total/NA	Water	EPA 8270D LL	323155
180-108704-3	OFW0200N	Total/NA	Water	EPA 8270D LL	323155
180-108704-4	OFW0300N	Total/NA	Water	EPA 8270D LL	323155
180-108704-5	OFW0500N	Total/NA	Water	EPA 8270D LL	323155

Analysis Batch: 323469

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 180-323155/1-A	Method Blank	Total/NA	Water	EPA 8270D LL	323155
LCS 180-323155/2-A	Lab Control Sample	Total/NA	Water	EPA 8270D LL	323155

GC Semi VOA

Prep Batch: 444506

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	3510C LVI	
180-108704-2	OFW0100R	Total/NA	Water	3510C LVI	
180-108704-3	OFW0200N	Total/NA	Water	3510C LVI	
180-108704-4	OFW0300N	Total/NA	Water	3510C LVI	
180-108704-5	OFW0500N	Total/NA	Water	3510C LVI	
MB 240-444506/6-A	Method Blank	Total/NA	Water	3510C LVI	
LCS 240-444506/7-A	Lab Control Sample	Total/NA	Water	3510C LVI	

Analysis Batch: 444816

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	8015D	444506
180-108704-2	OFW0100R	Total/NA	Water	8015D	444506
180-108704-3	OFW0200N	Total/NA	Water	8015D	444506
180-108704-5	OFW0500N	Total/NA	Water	8015D	444506
MB 240-444506/6-A	Method Blank	Total/NA	Water	8015D	444506
LCS 240-444506/7-A	Lab Control Sample	Total/NA	Water	8015D	444506

Analysis Batch: 444889

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-4	OFW0300N	Total/NA	Water	8015D	444506

Specialty Organics

Prep Batch: 41399

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	HRMS-Sepf	
180-108704-2	OFW0100R	Total/NA	Water	HRMS-Sepf	

Specialty Organics (Continued)

Prep Batch: 41399 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-3	OFW0200N	Total/NA	Water	HRMS-Sepf	
180-108704-4	OFW0300N	Total/NA	Water	HRMS-Sepf	
180-108704-5	OFW0500N	Total/NA	Water	HRMS-Sepf	
MB 140-41399/7-A	Method Blank	Total/NA	Water	HRMS-Sepf	
LCS 140-41399/6-A	Lab Control Sample	Total/NA	Water	HRMS-Sepf	

Analysis Batch: 41606

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 140-41399/7-A	Method Blank	Total/NA	Water	1668C	41399
LCS 140-41399/6-A	Lab Control Sample	Total/NA	Water	1668C	41399

Analysis Batch: 41619

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-4	OFW0300N	Total/NA	Water	1668C	41399

Analysis Batch: 41630

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	1668C	41399
180-108704-2	OFW0100R	Total/NA	Water	1668C	41399
180-108704-3	OFW0200N	Total/NA	Water	1668C	41399
180-108704-5	OFW0500N	Total/NA	Water	1668C	41399

Metals

Prep Batch: 323724

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	7470A	
180-108704-2	OFW0100R	Total/NA	Water	7470A	
180-108704-3	OFW0200N	Total/NA	Water	7470A	
180-108704-4	OFW0300N	Total/NA	Water	7470A	
180-108704-5	OFW0500N	Total/NA	Water	7470A	
MB 180-323724/1-A	Method Blank	Total/NA	Water	7470A	
LCS 180-323724/2-A	Lab Control Sample	Total/NA	Water	7470A	

Prep Batch: 323777

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total Recoverable	Water	3005A	
180-108704-2	OFW0100R	Total Recoverable	Water	3005A	
180-108704-3	OFW0200N	Total Recoverable	Water	3005A	
180-108704-4	OFW0300N	Total Recoverable	Water	3005A	
180-108704-5	OFW0500N	Total Recoverable	Water	3005A	
MB 180-323777/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 180-323777/2-A	Lab Control Sample	Total Recoverable	Water	3005A	

Analysis Batch: 324008

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	EPA 7470A	323724
180-108704-2	OFW0100R	Total/NA	Water	EPA 7470A	323724
180-108704-3	OFW0200N	Total/NA	Water	EPA 7470A	323724
180-108704-4	OFW0300N	Total/NA	Water	EPA 7470A	323724
180-108704-5	OFW0500N	Total/NA	Water	EPA 7470A	323724

Metals (Continued)

Analysis Batch: 324008 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 180-323724/1-A	Method Blank	Total/NA	Water	EPA 7470A	323724
LCS 180-323724/2-A	Lab Control Sample	Total/NA	Water	EPA 7470A	323724

Analysis Batch: 324024

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total Recoverable	Water	EPA 6020A	323777
180-108704-2	OFW0100R	Total Recoverable	Water	EPA 6020A	323777
180-108704-3	OFW0200N	Total Recoverable	Water	EPA 6020A	323777
180-108704-4	OFW0300N	Total Recoverable	Water	EPA 6020A	323777
180-108704-5	OFW0500N	Total Recoverable	Water	EPA 6020A	323777
MB 180-323777/1-A	Method Blank	Total Recoverable	Water	EPA 6020A	323777
LCS 180-323777/2-A	Lab Control Sample	Total Recoverable	Water	EPA 6020A	323777

Analysis Batch: 324170

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total Recoverable	Water	EPA 6020A	323777
180-108704-2	OFW0100R	Total Recoverable	Water	EPA 6020A	323777
180-108704-3	OFW0200N	Total Recoverable	Water	EPA 6020A	323777
180-108704-4	OFW0300N	Total Recoverable	Water	EPA 6020A	323777
180-108704-5	OFW0500N	Total Recoverable	Water	EPA 6020A	323777

General Chemistry

Analysis Batch: 323013

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-108704-1	OFW0100N	Total/NA	Water	SM 2540D	
180-108704-2	OFW0100R	Total/NA	Water	SM 2540D	
180-108704-3	OFW0200N	Total/NA	Water	SM 2540D	
180-108704-4	OFW0300N	Total/NA	Water	SM 2540D	
180-108704-5	OFW0500N	Total/NA	Water	SM 2540D	
MB 180-323013/2	Method Blank	Total/NA	Water	SM 2540D	
LCS 180-323013/1	Lab Control Sample	Total/NA	Water	SM 2540D	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: Qiang Huang	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-62216-12590.1
Client Contact: Mr. Robert Kennedy	Phone: 240 - 374 - 8920	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 1 of 1
Company: AECOM				Job #:
Address: 250 Apollo Drive	Due Date Requested:			
City: Chelmsford	TAT Requested (days): Standard			
State, Zip: MA, 01824				
Phone:	PO #: 126546			
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site: Pepco Benning Road	SSOW#:			

Analysis Requested

Preservation Codes:
A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)
Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C - PCB Congeners	8270D - PAHs	6020A - TAL Metals 6010C	2540 - TSS	8015D - TPH DRO/ORO	Total Number of containers	Special Instructions/Note:
			Preservation Code:										
OFW0100N	7/22/20	1675	G	W			X	X	X	X	X		
OFW0100R	7/22/20	1630	G	W			X	X	X	X	X		
OFW0200N	7/22/20	1640	G	W			X	X	X	X	X		
OFW0300N	7/22/20	1650	G	W			X	X	X	X	X		
OFW0500N	7/22/20	1730	G	W			X	X	X	X	X		

180-108704 Chain of Custody

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		7-23-20 1300	AECOM		7/23/20 1800	ETA
2		7/23/20 1700	ETA		7-24-20	ETA/PT
3		Date/Time:	Company		Date/Time: 8:45	Company

Custody Seals Intact: Δ Yes Δ No | Custody Seal No.:

Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Do Not Lift Using This Tag



ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 23JUL20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

56BJ3/C6A6/B766

FedEx Express

2 of 3
MPS# 0263 7710 7630 5408
Mstr# 7710 7630 5614

FRI - 24 JUL 10:30A
PRIORITY OVERNIGHT

0201

15238
PIT
PA-US

NA AGCA

Uncorrected temp 4.2 °C
Thermometer ID 14
CF 0 Initials

PT-WI-SR-001 effective 7/26/13

Part # 156297-435 RRDW2 EXP 05/21

DO NOT LIFT USING



ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 23JUL20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

FedEx Express

3 of 3
MPS# 0263 7710 7630 5338
Mstr# 7710 7630 5614

FRI - 24 JUL 10:30A
PRIORITY OVERNIGHT
0201

NA AGCA
15238
PA-US PIT

Uncorrected temp 2.6 °C
Thermometer ID 14
CF 0 Initials MY

T-WI-SR-001 effective 7/26/13

Part # 156297-435 RRDW2 EXP 05/20



ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 23JUL20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

FedEx Express

1 of 3
TRK# 0201 7710 7630 5614
MASTER

FRI - 24 JUL 10:30A
PRIORITY OVERNIGHT

NA AGCA
15238
PA-US PIT

Uncorrected temp 3.5 °C
Thermometer ID 14
CF 0 Initials MY

PT-WI-SR-001 effective 7/26/13

Part # 156297-435 RRDW2 EXP 05/20

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-404629.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-108704-1
Address: 5815 Middlebrook Pike, ,	Due Date Requested: 8/7/2020			
City: Knoxville	TAT Requested (days):			
State, Zip: TN, 37921				
Phone: 865-291-3000(Tel) 865-584-4315(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C/1668_P_Sep PCB Congeners	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
OFW0100N (180-108704-1)	7/22/20	16:25 Eastern		Water			X	2	AU ND
OFW0100R (180-108704-2)	7/22/20	16:30 Eastern		Water			X	2	
OFW0200N (180-108704-3)	7/22/20	16:40 Eastern		Water			X	2	
OFW0300N (180-108704-4)	7/22/20	16:50 Eastern		Water			X	2	
OFW0500N (180-108704-5)	7/22/20	17:30 Eastern		Water			X	2	

CUSTODY SEALS INTACT
RECEIVED AT CT 0.7/CT 0.7C
ARD 7.28.20
COOLER FEDEX # 168951818897 PD

180-108704 Chain of Custody

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be p TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

currently
fins

Possible Hazard Identification	Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
Unconfirmed	☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:		
Relinquished by:	Date/Time: 7/27/20 1DES	Company: IND	Received by:	Date/Time: 7.28.20 10:20	Company: ETA FW X
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: ∆ Yes ∆ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Loc: 180
108704

EUROFINS/TESTAMERICA KNOXVILLE SAMPLE RECEIPT/CONDITION UPON RECEIPT ANOMALY CHECKLIST **Log In Number:**

Review Items	Yes	No	NA	If No, what was the problem?
1. Are the shipping containers intact?	✓		✓	☐ **Containers, Broken**
2. Were ambient air containers received intact?			✓	☐ Checked in lab
3. The coolers/containers custody seal if present, is it intact?	✓			☐ Yes ☐ NA
4. Is the cooler temperature within limits? (> freezing temp. of water to 6 °C, VOST: 10°C) Thermometer ID : SC68 Correction factor: 0.0	✓			☐ **Cooler Out of Temp, Client Contacted, Proceed/Cancel** ☐ **Cooler Out of Temp, Same Day Receipt**
5. Were all of the sample containers received intact?	✓			☐ **Containers, Broken**
6. Were samples received in appropriate containers?	✓			☐ **Containers, Improper; Client Contacted; Proceed/Cancel**
7. Do sample container labels match COC? (IDs, Dates, Times)	✓			☐ **COC & Samples Do Not Match** ☐ **COC Incorrect/Incomplete** ☐ **COC Not Received**
8. Were all of the samples listed on the COC received?	✓			☐ **Sample Received, Not on COC** ☐ **Sample on COC, Not Received**
9. Is the date/time of sample collection noted?	✓			☐ **COC; No Date/Time; Client Contacted**
10. Was the sampler identified on the COC?			✓	☐ **Sampler Not Listed on COC**
11. Is the client and project name/# identified?	✓			☐ **COC Incorrect/Incomplete**
12. Are tests/parameters listed for each sample?	✓			☐ **COC No tests on COC**
13. Is the matrix of the samples noted?	✓			☐ **COC Incorrect/Incomplete**
14. Was COC relinquished? (Signed/Dated/Timed)	✓			☐ **COC Incorrect/Incomplete**
15. Were samples received within holding time?	✓			☐ **Holding Time - Receipt**
16. Were samples received with correct chemical preservative (excluding Encore)?			✓	☐ **pH Adjusted, pH Included (See box 16A)** ☐ **Incorrect Preservative**
17. Were VOA samples received without headspace?			✓	☐ **Headspace (VOA only)**
18. Did you check for residual chlorine, if necessary? (e.g. 1613B, 1668) Chlorine test strip lot number: 8178 2021/04	✓			☐ **Residual Chlorine**
19. For 1613B water samples is pH<9?			✓	☐ If no, notify lab to adjust
20. For rad samples was sample activity info. Provided?			✓	☐ Project missing info

Comments/Actions Taken

Labeling Verified by: **Date:**

pH test strip lot number:

	Box 16A: pH Preservation	Box 18A: Residual Chlorine
Preservative:		
Lot Number:		
Exp Date:		
Analyst:		
Date:		
Time:		

Project #: _____ PM Instructions: _____

Sample Receiving Associate: _____ Date: 7.28.20

QA026R32.doc, 062719

8/7/2020

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-108704-1

Login Number: 108704
List Number: 1
Creator: Watson, Debbie

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	False	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-109612-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
9/2/2020 12:46:34 PM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS

Review your project results through TotalAccess

Have a Question? Ask The Expert

Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 4
Certification Summary 6
Sample Summary 9
Method Summary 10
Lab Chronicle 11
Client Sample Results 12
QC Sample Results 19
QC Association Summary 30
Chain of Custody 32
Receipt Checklists 36

Job ID: 180-109612-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-109612-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 08/14/2020; the samples arrived in good condition, properly preserved and on ice. The temperature of the coolers at receipt was 2.9 C.

SEMIVOLATILES
The matrix spike of sample OFW0400N (180-109612-1) recovered outside of the control limits for several analytes.

DRO
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

PCB CONGENERS
Several analytes were detected in method blank MB 140-41958/13-A at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

The laboratory control sample (LCS) for batch 140-41958 recovered outside control limits for the following analytes: PCB-104, PCB-155. These analytes were biased high in the LCS but were not detected above the reporting limit in the associated samples; therefore, the data have been reported as is with no adverse affects to data quality.

METALS
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

TOTAL SUSPENDED SOLIDS
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Qualifiers

GC/MS Semi VOA

Qualifier	Qualifier Description
F1	MS and/or MSD recovery exceeds control limits.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

GC Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Dioxin

Qualifier	Qualifier Description
*	LCS or LCSD is outside acceptance limits.
B	Compound was found in the blank and sample.
C	The compound co-eluted with other compounds
C108	The compound co-eluted with PCB-108
C110	The compound co-eluted with PCB-110
C12	The compound co-eluted with PCB-12
C128	The compound co-eluted with PCB-128
C129	The compound co-eluted with PCB-129
C134	The compound co-eluted with PCB-134
C135	The compound co-eluted with PCB-135
C139	The compound co-eluted with PCB-139
C147	The compound co-eluted with PCB-147
C153	The compound co-eluted with PCB-153
C156	The compound co-eluted with PCB-156
C171	The compound co-eluted with PCB-171
C18	The compound co-eluted with PCB-18
C180	The compound co-eluted with PCB-180
C183	The compound co-eluted with PCB-183
C198	The compound co-eluted with PCB-198
C20	The compound co-eluted with PCB-20
C21	The compound co-eluted with PCB-21
C26	The compound co-eluted with PCB-26
C40	The compound co-eluted with PCB-40
C43	The compound co-eluted with PCB-43
C44	The compound co-eluted with PCB-44
C45	The compound co-eluted with PCB-45
C49	The compound co-eluted with PCB-49
C50	The compound co-eluted with PCB-50
C59	The compound co-eluted with PCB-59
C61	The compound co-eluted with PCB-61
C83	The compound co-eluted with PCB-83
C85	The compound co-eluted with PCB-85
C86	The compound co-eluted with PCB-86
C88	The compound co-eluted with PCB-88
C90	The compound co-eluted with PCB-90
C93	The compound co-eluted with PCB-93
C98	The compound co-eluted with PCB-98
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
q	The reported result is the estimated maximum possible concentration of this analyte, quantitated using the theoretical ion ratio. The measured ion ratio does not meet qualitative identification criteria and indicates a possible interference.

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Definitions/Glossary

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	01-01-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-15-20
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-20

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Canton

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	State	2927	02-23-21
Connecticut	State	PH-0590	12-31-21
Florida	NELAP	E87225	06-30-21
Georgia	State	4062	02-23-21
Illinois	NELAP	004498	07-31-20 *
Iowa	State	421	06-01-21
Kansas	NELAP	E-10336	04-30-21
Kentucky (UST)	State	112225	02-23-21
Kentucky (WW)	State	KY98016	12-31-20
Minnesota	NELAP	OH00048	12-31-20
Minnesota (Petrofund)	State	3506	08-01-21
New Jersey	NELAP	OH001	06-30-21
New York	NELAP	10975	03-31-21
Ohio VAP	State	CL0024	06-05-21
Oregon	NELAP	4062	02-24-21
Pennsylvania	NELAP	68-00340	08-31-20
Texas	NELAP	T104704517-18-10	08-31-20
USDA	US Federal Programs	P330-18-00281	09-17-21
Virginia	NELAP	010101	09-14-20
Washington	State	C971	01-12-21
West Virginia DEP	State	210	12-31-20

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Knoxville

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
	AFCEE	N/A	
ANAB	Dept. of Defense ELAP	L2311	02-13-22
ANAB	Dept. of Energy	L2311.01	02-13-22
ANAB	ISO/IEC 17025	L2311	02-13-22
ANAB	ISO/IEC 17025	L2311	02-14-22
Arkansas DEQ	State	88-0688	06-17-21
California	State	2423	06-30-21
Colorado	State	TN00009	02-28-21
Connecticut	State	PH-0223	09-30-21
Florida	NELAP	E87177	07-01-21
Georgia (DW)	State	906	12-11-22
Hawaii	State	NA	12-11-21
Kansas	NELAP	E-10349	11-01-20
Kentucky (DW)	State	90101	01-01-21
Louisiana	NELAP	LA110001	12-31-12 *
Louisiana	NELAP	83979	06-30-21
Louisiana (DW)	State	LA019	12-31-20
Maryland	State	277	03-31-21
Michigan	State	9933	12-11-22
Nevada	State	TN00009	07-31-21
New Hampshire	NELAP	299919	01-17-21
New Jersey	NELAP	TN001	07-01-21
New York	NELAP	10781	03-31-21
North Carolina (DW)	State	21705	07-31-21
North Carolina (WW/SW)	State	64	12-31-20
Ohio VAP	State	CL0059	06-02-23
Oklahoma	State	9415	08-31-20
Oregon	NELAP	TNI0189	01-02-21
Pennsylvania	NELAP	68-00576	12-31-20
Tennessee	State	02014	12-11-22
Texas	NELAP	T104704380-18-12	08-31-20
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-19-00236	08-20-22
Utah	NELAP	TN00009	07-31-21
Virginia	NELAP	460176	09-15-20
Washington	State	C593	01-19-21
West Virginia (DW)	State	9955C	01-01-21
West Virginia DEP	State	345	05-01-21
Wisconsin	State	998044300	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-109612-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-109612-1	OFW0400N	Water	08/13/20 08:50	08/14/20 09:00	

Method Summary

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8270D LL	Semivolatile Organic Compounds by GC/MS - Low Level	SW846	TAL PIT
8015D	Diesel Range Organics (DRO) (GC)	SW846	TAL CAN
1668C	Chlorinated Biphenyl Congeners (HRGC/HRMS)	EPA	TAL KNX
EPA 6020A	Metals (ICP/MS)	SW846	TAL PIT
EPA 7470A	Mercury (CVAA)	SW846	TAL PIT
SM 2540D	Solids, Total Suspended (TSS)	SM	TAL PIT
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	TAL PIT
3510C LVI	Liquid-Liquid Extraction (Separatory Funnel) LVI	SW846	TAL CAN
3520C	Liquid-Liquid Extraction (Continuous)	SW846	TAL PIT
7470A	Preparation, Mercury	SW846	TAL PIT
HRMS-Sepf	Separatory Funnel (Liquid-Liquid) Extraction	EPA	TAL KNX

Protocol References:

EPA = US Environmental Protection Agency

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-109612-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0400N
Lab Sample ID: 180-109612-1
Date Collected: 08/13/20 08:50
Matrix: Water
Date Received: 08/14/20 09:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			320 mL	250 uL	326164	08/19/20 09:22	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	326981	08/25/20 15:32	VVP	TAL PIT
	Instrument ID: CH732									
Total/NA	Prep	3510C LVI			260 mL	5 mL	447423	08/17/20 09:11	MDH	TAL CAN
Total/NA	Analysis	8015D		1			447510	08/17/20 18:40	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1014.6 mL	20 uL	41958	08/19/20 15:50	SMA	TAL KNX
Total/NA	Analysis	1668C		1			42160	08/26/20 19:13	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	326168	08/19/20 09:29	KEM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			327802	08/29/20 15:40	RSK	TAL PIT
	Instrument ID: DORY									
Total/NA	Prep	7470A			50 mL	50 mL	326779	08/24/20 05:16	RJR	TAL PIT
Total/NA	Analysis	EPA 7470A		1			326852	08/24/20 10:47	RJR	TAL PIT
	Instrument ID: HGZ									
Total/NA	Analysis	SM 2540D		1	1000 mL	1000 mL	325702	08/15/20 10:59	AGP	TAL PIT
	Instrument ID: NOEQUIP									

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396
TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Analyst References:

Lab: TAL CAN
- Batch Type: Prep
  - MDH = Matthew Howell
- Batch Type: Analysis
  - LKG = Lucas Grossman

Lab: TAL KNX
- Batch Type: Prep
  - SMA = Syed Ahmed
- Batch Type: Analysis
  - JMN = Jon Nordquist

Lab: TAL PIT
- Batch Type: Prep
  - BJT = Bill Trout
  - KEM = Kimberly Mahoney
  - RJR = Ron Rosenbaum
- Batch Type: Analysis
  - AGP = Angela Partridge
  - RJR = Ron Rosenbaum
  - RSK = Robert Kurtz
  - VVP = Vincent Piccolino

Client Sample ID: OFW0400N

Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND	F1	0.15	0.051	ug/L		08/19/20 09:22	08/25/20 15:32	1
Acenaphthylene	ND		0.15	0.051	ug/L		08/19/20 09:22	08/25/20 15:32	1
Anthracene	ND	F1	0.15	0.038	ug/L		08/19/20 09:22	08/25/20 15:32	1
Benzo[a]anthracene	ND	F1	0.15	0.059	ug/L		08/19/20 09:22	08/25/20 15:32	1
Benzo[b]fluoranthene	ND	F1	0.15	0.076	ug/L		08/19/20 09:22	08/25/20 15:32	1
Benzo[k]fluoranthene	ND	F1	0.15	0.069	ug/L		08/19/20 09:22	08/25/20 15:32	1
Benzo[g,h,i]perylene	ND	F1	0.15	0.054	ug/L		08/19/20 09:22	08/25/20 15:32	1
Benzo[a]pyrene	ND	F1	0.15	0.041	ug/L		08/19/20 09:22	08/25/20 15:32	1
Chrysene	ND	F1	0.15	0.063	ug/L		08/19/20 09:22	08/25/20 15:32	1
Dibenz(a,h)anthracene	ND	F1	0.15	0.056	ug/L		08/19/20 09:22	08/25/20 15:32	1
Fluoranthene	ND	F1	0.15	0.047	ug/L		08/19/20 09:22	08/25/20 15:32	1
Fluorene	ND	F1	0.15	0.054	ug/L		08/19/20 09:22	08/25/20 15:32	1
Indeno[1,2,3-cd]pyrene	ND	F1	0.15	0.066	ug/L		08/19/20 09:22	08/25/20 15:32	1
Naphthalene	ND		0.15	0.046	ug/L		08/19/20 09:22	08/25/20 15:32	1
Phenanthrene	**0.058**	**J F1**	0.15	0.043	ug/L		08/19/20 09:22	08/25/20 15:32	1
Pyrene	ND	F1	0.15	0.042	ug/L		08/19/20 09:22	08/25/20 15:32	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*58*		*23 - 105*	*08/19/20 09:22*	*08/25/20 15:32*	*1*
Nitrobenzene-d5 (Surr)	*68*		*28 - 111*	*08/19/20 09:22*	*08/25/20 15:32*	*1*
Terphenyl-d14 (Surr)	*44*		*20 - 126*	*08/19/20 09:22*	*08/25/20 15:32*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**330**	**J**	480	220	ug/L		08/17/20 09:11	08/17/20 18:40	1
ORO C24-C40	**560**		480	220	ug/L		08/17/20 09:11	08/17/20 18:40	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*84*		*52 - 121*	*08/17/20 09:11*	*08/17/20 18:40*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.0063**	**J B**	0.039	0.00040	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-2	**0.0035**	**J B q**	0.039	0.00049	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-3	**0.0048**	**J B q**	0.039	0.00058	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-4	**0.011**	**J**	0.059	0.0041	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-5	ND		0.039	0.0033	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-6	**0.0033**	**J q**	0.039	0.0029	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-7	ND		0.039	0.0030	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-8	**0.020**	**J q**	0.059	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-9	ND		0.039	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-10	ND		0.039	0.0033	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-11	**0.098**	**B**	0.059	0.0029	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-12	**0.0071**	**J C q**	0.079	0.0030	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-13	**0.0071**	**J C12 q**	0.079	0.0030	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-14	ND		0.039	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-15	**0.022**	**J**	0.039	0.0032	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-16	**0.0087**	**J**	0.039	0.0014	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-17	**0.0082**	**J q**	0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-18	**0.016**	**J C q**	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-109612-1

Client Sample ID: OFW0400N
Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	ND		0.039	0.0015	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-20	**0.051**	**J C B**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-21	**0.022**	**J C**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-22	**0.022**	**J**	0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-23	ND		0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-24	ND		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-25	**0.0038**	**J q**	0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-26	**0.0077**	**J C**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-27	ND		0.039	0.00092	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-28	**0.051**	**J B C20**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-29	**0.0077**	**J C26**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-30	**0.016**	**J C18 q**	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-31	**0.037**	**J B**	0.039	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-32	**0.011**	**J**	0.039	0.00088	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-33	**0.022**	**J C21**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-34	ND		0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-35	ND		0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-36	ND		0.039	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-37	**0.031**	**J**	0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-38	ND		0.039	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-39	ND		0.039	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-40	**0.028**	**J C q**	0.12	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-41	**0.028**	**J q C40**	0.12	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-42	**0.015**	**J**	0.039	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-43	ND	C	0.079	0.0026	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-44	**0.044**	**J C B**	0.12	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-45	ND	C	0.079	0.0029	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-46	ND		0.039	0.0035	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-47	**0.044**	**J B C44**	0.12	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-48	**0.0073**	**J q**	0.039	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-49	**0.023**	**J C**	0.079	0.0023	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-50	**0.0064**	**J C**	0.079	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-51	ND	C45	0.079	0.0029	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-52	**0.059**	**B**	0.039	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-53	**0.0064**	**J C50**	0.079	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-54	ND		0.039	0.00086	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-55	**0.0039**	**J q**	0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-56	**0.032**	**J**	0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-57	ND		0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-58	ND		0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-59	**0.0045**	**J C q**	0.12	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-60	**0.020**	**J**	0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-61	**0.093**	**J C B**	0.16	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-62	**0.0045**	**J C59 q**	0.12	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-63	ND		0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-64	**0.034**	**J**	0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-65	**0.044**	**J B C44**	0.12	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-66	**0.058**		0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-67	ND		0.039	0.0018	ng/L		08/19/20 15:50	08/26/20 19:13	1

Client Sample ID: OFW0400N
Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.039	0.0018	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-69	**0.023**	**J C49**	0.079	0.0023	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-70	**0.093**	**J C61 B**	0.16	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-71	**0.028**	**J q C40**	0.12	0.0028	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-72	ND		0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-73	ND	C43	0.079	0.0026	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-74	**0.093**	**J C61 B**	0.16	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-75	**0.0045**	**J C59 q**	0.12	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-76	**0.093**	**J C61 B**	0.16	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-77	**0.014**	**J**	0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-78	ND		0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-79	ND		0.039	0.0018	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-80	ND		0.039	0.0018	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-81	ND		0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-82	**0.027**	**J q**	0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-83	**0.086**	**C**	0.079	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-84	**0.051**		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-85	**0.037**	**J C B**	0.12	0.00081	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-86	**0.11**	**J C B**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-87	**0.11**	**J B C86**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-88	**0.023**	**J C**	0.079	0.00099	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-89	ND		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-90	**0.15**	**C B**	0.12	0.00083	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-91	**0.023**	**J C88**	0.079	0.00099	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-92	**0.031**	**J**	0.039	0.00094	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-93	**0.0034**	**J C q**	0.079	0.00095	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-94	ND		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-95	**0.14**	**B**	0.039	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-96	ND		0.039	0.00081	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-97	**0.11**	**J B C86**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-98	**0.0056**	**J C q**	0.079	0.00092	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-99	**0.086**	**C83**	0.079	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-100	**0.0034**	**J C93 q**	0.079	0.00095	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-101	**0.15**	**B C90**	0.12	0.00083	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-102	**0.0056**	**J C98 q**	0.079	0.00092	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-103	ND		0.039	0.00094	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-104	ND	*	0.039	0.00072	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-105	**0.064**		0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-106	ND		0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-107	**0.011**	**J**	0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-108	**0.0067**	**J C q**	0.079	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-109	**0.11**	**J B C86**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-110	**0.31**	**C B**	0.079	0.00069	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-111	ND		0.039	0.00066	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-112	**0.0012**	**J**	0.039	0.00070	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-113	**0.15**	**B C90**	0.12	0.00083	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-114	ND		0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-115	**0.31**	**B C110**	0.079	0.00069	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-116	**0.037**	**J C85 B**	0.12	0.00081	ng/L		08/19/20 15:50	08/26/20 19:13	1

Client Sample ID: OFW0400N
Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	**0.037**	**J C85 B**	0.12	0.00081	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-118	**0.14**	**B**	0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-119	**0.11**	**J B C86**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-120	ND		0.039	0.00068	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-121	ND		0.039	0.00070	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-122	ND		0.039	0.0023	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-123	**0.0032**	**J q**	0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-124	**0.0067**	**J q C108**	0.079	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-125	**0.11**	**J B C86**	0.24	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-126	**0.0027**	**J q**	0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-127	ND		0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-128	**0.065**	**J C q**	0.079	0.0030	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-129	**0.41**	**C B**	0.16	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-130	**0.024**	**J q**	0.039	0.0040	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-131	ND		0.039	0.0042	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-132	**0.14**		0.039	0.0039	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-133	ND		0.039	0.0038	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-134	**0.020**	**J C q**	0.079	0.0040	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-135	**0.15**	**C**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-136	**0.043**		0.039	0.00084	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-137	**0.015**	**J q**	0.039	0.0034	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-138	**0.41**	**B C129**	0.16	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-139	**0.0099**	**J C**	0.079	0.0034	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-140	**0.0099**	**J C139**	0.079	0.0034	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-141	**0.084**		0.039	0.0036	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-142	ND		0.039	0.0038	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-143	**0.020**	**J C134 q**	0.079	0.0040	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-144	**0.019**	**J q**	0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-145	ND		0.039	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-146	**0.056**	**B**	0.039	0.0034	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-147	**0.33**	**C B**	0.079	0.0039	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-148	ND		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-149	**0.33**	**B C147**	0.079	0.0039	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-150	ND		0.039	0.00076	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-151	**0.15**	**C135**	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-152	ND		0.039	0.00082	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-153	**0.26**	**C B**	0.079	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-154	**0.0027**	**J q**	0.039	0.00091	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-155	ND	*	0.039	0.00076	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-156	**0.043**	**J C**	0.079	0.0032	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-157	**0.043**	**J C156**	0.079	0.0032	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-158	**0.048**		0.039	0.0024	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-159	**0.0043**	**J**	0.039	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-160	**0.41**	**B C129**	0.16	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-161	ND		0.039	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-162	ND		0.039	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-163	**0.41**	**B C129**	0.16	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-164	**0.027**	**J q**	0.039	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-165	ND		0.039	0.0029	ng/L		08/19/20 15:50	08/26/20 19:13	1

Client Sample ID: OFW0400N
Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.065	J C128 q	0.079	0.0030	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-167	0.017	J	0.039	0.0019	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-168	0.26	B C153	0.079	0.0027	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-169	ND		0.039	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-170	0.13		0.039	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-171	0.043	J C	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-172	0.026	J	0.039	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-173	0.043	J C171	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-174	0.13		0.039	0.00098	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-175	0.0071	J	0.039	0.00095	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-176	0.015	J	0.039	0.00072	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-177	0.080		0.039	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-178	0.028	J	0.039	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-179	0.054		0.039	0.00076	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-180	0.25	C B	0.079	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-181	ND		0.039	0.00095	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-182	ND		0.039	0.00092	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-183	0.086	C B	0.079	0.00093	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-184	ND		0.039	0.00078	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-185	0.086	B C183	0.079	0.00093	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-186	ND		0.039	0.00076	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-187	0.15		0.039	0.00088	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-188	ND		0.039	0.00066	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-189	0.0054	J	0.039	0.0017	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-190	0.027	J	0.039	0.00069	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-191	0.0051	J q	0.039	0.00072	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-192	ND		0.039	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-193	0.25	C180 B	0.079	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-194	0.064		0.039	0.0024	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-195	0.037	J	0.039	0.0026	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-196	0.030	J	0.039	0.0010	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-197	ND		0.039	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-198	0.067	J C B	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-199	0.067	J C198 B	0.079	0.0011	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-200	0.0069	J	0.039	0.00071	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-201	0.0060	J q	0.039	0.00073	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-202	0.0084	J q	0.039	0.00081	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-203	0.035	J	0.039	0.00094	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-204	ND		0.039	0.00080	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-205	ND		0.039	0.0020	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-206	0.032	J	0.039	0.0061	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-207	ND		0.039	0.0041	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-208	ND		0.039	0.0041	ng/L		08/19/20 15:50	08/26/20 19:13	1
PCB-209	0.014	J	0.039	0.0014	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Monochlorobiphenyls	0.015	J B q	0.039	0.00049	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Dichlorobiphenyls	0.16	B q	0.079	0.0031	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Trichlorobiphenyls	0.22	B q	0.079	0.0012	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Tetrachlorobiphenyls	0.44	B q	0.16	0.0022	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Pentachlorobiphenyls	1.2	B q	0.24	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1

Client Sample ID: OFW0400N
Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	1.8	B q	0.16	0.0025	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Heptachlorobiphenyls	1.0	B q	0.079	0.00092	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Octachlorobiphenyls	0.25	B q	0.079	0.0013	ng/L		08/19/20 15:50	08/26/20 19:13	1
Total Nonachlorobiphenyls	0.032	J	0.039	0.0048	ng/L		08/19/20 15:50	08/26/20 19:13	1
Polychlorinated biphenyls, Total	5.1	B q	0.24	0.0021	ng/L		08/19/20 15:50	08/26/20 19:13	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*68*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-3L	*66*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-4L	*68*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-15L	*68*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-19L	*73*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-37L	*77*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-54L	*78*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-77L	*73*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-81L	*72*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-104L	*67*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-105L	*71*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-114L	*71*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-118L	*72*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-123L	*71*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-126L	*73*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-155L	*69*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-156L	*67*	*C*	*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-157L	*67*	*C156*	*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-167L	*69*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-169L	*66*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-170L	*67*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-188L	*73*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-189L	*75*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-202L	*81*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-205L	*59*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-206L	*65*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-208L	*74*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-209L	*62*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*95*		*5 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-111L	*94*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*
PCB-178L	*100*		*10 - 145*	*08/19/20 15:50*	*08/26/20 19:13*	*1*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	380		30	13	ug/L		08/19/20 09:29	08/29/20 15:40	1
Arsenic	2.1		1.0	0.31	ug/L		08/19/20 09:29	08/29/20 15:40	1
Barium	12		10	1.6	ug/L		08/19/20 09:29	08/29/20 15:40	1
Beryllium	ND		1.0	0.18	ug/L		08/19/20 09:29	08/29/20 15:40	1
Cadmium	ND		1.0	0.22	ug/L		08/19/20 09:29	08/29/20 15:40	1
Calcium	14000		500	130	ug/L		08/19/20 09:29	08/29/20 15:40	1
Chromium	2.1		2.0	1.5	ug/L		08/19/20 09:29	08/29/20 15:40	1
Cobalt	0.52		0.50	0.13	ug/L		08/19/20 09:29	08/29/20 15:40	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-109612-1

Client Sample ID: OFW0400N

Date Collected: 08/13/20 08:50
Date Received: 08/14/20 09:00

Lab Sample ID: 180-109612-1

Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	**8.2**		2.0	0.63	ug/L		08/19/20 09:29	08/29/20 15:40	1
Iron	**720**		50	20	ug/L		08/19/20 09:29	08/29/20 15:40	1
Silver	ND		1.0	0.18	ug/L		08/19/20 09:29	08/29/20 15:40	1
Potassium	**2000**		500	160	ug/L		08/19/20 09:29	08/29/20 15:40	1
Magnesium	**3300**		500	83	ug/L		08/19/20 09:29	08/29/20 15:40	1
Manganese	**21**		5.0	0.87	ug/L		08/19/20 09:29	08/29/20 15:40	1
Sodium	**7900**		500	350	ug/L		08/19/20 09:29	08/29/20 15:40	1
Nickel	**6.8**		1.0	0.34	ug/L		08/19/20 09:29	08/29/20 15:40	1
Lead	**3.4**		1.0	0.13	ug/L		08/19/20 09:29	08/29/20 15:40	1
Antimony	**0.51**	**J**	2.0	0.38	ug/L		08/19/20 09:29	08/29/20 15:40	1
Selenium	ND		5.0	1.5	ug/L		08/19/20 09:29	08/29/20 15:40	1
Thallium	ND		1.0	0.15	ug/L		08/19/20 09:29	08/29/20 15:40	1
Vanadium	**29**		1.0	0.99	ug/L		08/19/20 09:29	08/29/20 15:40	1
Zinc	**36**		5.0	3.2	ug/L		08/19/20 09:29	08/29/20 15:40	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		08/24/20 05:16	08/24/20 10:47	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	**17**		0.50	0.50	mg/L			08/15/20 10:59	1

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: MB 180-326164/1-A
Matrix: Water
Analysis Batch: 326981

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 326164

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.19	0.065	ug/L		08/19/20 09:22	08/25/20 12:51	1
Acenaphthylene	ND		0.19	0.065	ug/L		08/19/20 09:22	08/25/20 12:51	1
Anthracene	ND		0.19	0.049	ug/L		08/19/20 09:22	08/25/20 12:51	1
Benzo[a]anthracene	ND		0.19	0.075	ug/L		08/19/20 09:22	08/25/20 12:51	1
Benzo[b]fluoranthene	ND		0.19	0.097	ug/L		08/19/20 09:22	08/25/20 12:51	1
Benzo[k]fluoranthene	ND		0.19	0.088	ug/L		08/19/20 09:22	08/25/20 12:51	1
Benzo[g,h,i]perylene	ND		0.19	0.069	ug/L		08/19/20 09:22	08/25/20 12:51	1
Benzo[a]pyrene	ND		0.19	0.053	ug/L		08/19/20 09:22	08/25/20 12:51	1
Chrysene	ND		0.19	0.081	ug/L		08/19/20 09:22	08/25/20 12:51	1
Dibenz(a,h)anthracene	ND		0.19	0.072	ug/L		08/19/20 09:22	08/25/20 12:51	1
Fluoranthene	ND		0.19	0.060	ug/L		08/19/20 09:22	08/25/20 12:51	1
Fluorene	ND		0.19	0.069	ug/L		08/19/20 09:22	08/25/20 12:51	1
Indeno[1,2,3-cd]pyrene	ND		0.19	0.085	ug/L		08/19/20 09:22	08/25/20 12:51	1
Naphthalene	ND		0.19	0.059	ug/L		08/19/20 09:22	08/25/20 12:51	1
Phenanthrene	ND		0.19	0.055	ug/L		08/19/20 09:22	08/25/20 12:51	1
Pyrene	ND		0.19	0.054	ug/L		08/19/20 09:22	08/25/20 12:51	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*67*		*23 - 105*	*08/19/20 09:22*	*08/25/20 12:51*	*1*
Nitrobenzene-d5 (Surr)	*67*		*28 - 111*	*08/19/20 09:22*	*08/25/20 12:51*	*1*
Terphenyl-d14 (Surr)	*67*		*20 - 126*	*08/19/20 09:22*	*08/25/20 12:51*	*1*

Lab Sample ID: LCS 180-326164/2-A
Matrix: Water
Analysis Batch: 326981

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 326164

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	20.0	15.1		ug/L		75	50 - 100
Acenaphthylene	20.0	14.8		ug/L		74	51 - 100
Anthracene	20.0	15.5		ug/L		77	53 - 100
Benzo[a]anthracene	20.0	15.3		ug/L		77	51 - 100
Benzo[b]fluoranthene	20.0	15.8		ug/L		79	45 - 100
Benzo[k]fluoranthene	20.0	15.8		ug/L		79	49 - 100
Benzo[g,h,i]perylene	20.0	16.4		ug/L		82	51 - 100
Benzo[a]pyrene	20.0	16.2		ug/L		81	51 - 100
Chrysene	20.0	16.1		ug/L		81	51 - 100
Dibenz(a,h)anthracene	20.0	16.2		ug/L		81	50 - 100
Fluoranthene	20.0	15.7		ug/L		78	54 - 100
Fluorene	20.0	14.8		ug/L		74	53 - 100
Indeno[1,2,3-cd]pyrene	20.0	16.4		ug/L		82	50 - 100
Naphthalene	20.0	14.1		ug/L		71	55 - 100
Phenanthrene	20.0	14.9		ug/L		74	51 - 100
Pyrene	20.0	16.5		ug/L		83	47 - 100

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*74*		*23 - 105*
Nitrobenzene-d5 (Surr)	*78*		*28 - 111*
Terphenyl-d14 (Surr)	*85*		*20 - 126*

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: 180-109612-1 MS
Matrix: Water
Analysis Batch: 326981

Client Sample ID: OFW0400N
Prep Type: Total/NA
Prep Batch: 326164

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	ND	F1	15.6	16.7	F1	ug/L		107	50 - 100
Acenaphthylene	ND		15.6	15.4		ug/L		99	51 - 100
Anthracene	ND	F1	15.6	16.7	F1	ug/L		107	53 - 100
Benzo[a]anthracene	ND	F1	15.6	18.2	F1	ug/L		117	51 - 100
Benzo[b]fluoranthene	ND	F1	15.6	17.7	F1	ug/L		113	45 - 100
Benzo[k]fluoranthene	ND	F1	15.6	18.0	F1	ug/L		115	49 - 100
Benzo[g,h,i]perylene	ND	F1	15.6	20.8	F1	ug/L		133	51 - 100
Benzo[a]pyrene	ND	F1	15.6	16.3	F1	ug/L		104	51 - 100
Chrysene	ND	F1	15.6	19.2	F1	ug/L		123	51 - 100
Dibenz(a,h)anthracene	ND	F1	15.6	21.2	F1	ug/L		136	50 - 100
Fluoranthene	ND	F1	15.6	18.6	F1	ug/L		119	54 - 100
Fluorene	ND	F1	15.6	18.3	F1	ug/L		117	53 - 100
Indeno[1,2,3-cd]pyrene	ND	F1	15.6	20.7	F1	ug/L		132	50 - 100
Naphthalene	ND		15.6	13.1		ug/L		84	55 - 100
Phenanthrene	0.058	J F1	15.6	18.3	F1	ug/L		117	51 - 100
Pyrene	ND	F1	15.6	18.4	F1	ug/L		117	47 - 100

Surrogate	*MS %Recovery*	*MS Qualifier*	*Limits*
2-Fluorobiphenyl	*61*		*23 - 105*
Nitrobenzene-d5 (Surr)	*67*		*28 - 111*
Terphenyl-d14 (Surr)	*44*		*20 - 126*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Lab Sample ID: MB 240-447423/3-A
Matrix: Water
Analysis Batch: 447510

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 447423

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	ND		500	230	ug/L		08/17/20 09:11	08/17/20 17:45	1
ORO C24-C40	ND		500	230	ug/L		08/17/20 09:11	08/17/20 17:45	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*85*		*52 - 121*	*08/17/20 09:11*	*08/17/20 17:45*	*1*

Lab Sample ID: LCS 240-447423/4-A
Matrix: Water
Analysis Batch: 447510

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 447423

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Diesel Range Organics [C10 - C28]			2000	1800		ug/L		90	56 - 120

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
o-Terphenyl	*87*		*52 - 121*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.00228	J q	0.040	0.00025	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-2	0.00261	J q	0.040	0.00031	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-3	0.00269	J	0.040	0.00037	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-4	ND		0.060	0.0042	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-5	ND		0.040	0.0036	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-6	ND		0.040	0.0032	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-7	ND		0.040	0.0033	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-8	ND		0.060	0.0030	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-9	ND		0.040	0.0034	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-10	ND		0.040	0.0036	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-11	0.00889	J q	0.060	0.0031	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-12	ND	C	0.080	0.0032	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-13	ND	C12	0.080	0.0032	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-14	ND		0.040	0.0028	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-15	ND		0.040	0.0036	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-16	ND		0.040	0.00085	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-17	ND		0.040	0.00076	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-18	ND	C	0.080	0.00067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-19	ND		0.040	0.00094	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-20	0.00215	J C	0.080	0.00055	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-21	ND	C	0.080	0.00054	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-22	ND		0.040	0.00057	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-23	ND		0.040	0.00056	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-24	ND		0.040	0.00064	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-25	ND		0.040	0.00051	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-26	ND	C	0.080	0.00054	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-27	ND		0.040	0.00056	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-28	0.00215	J C20	0.080	0.00055	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-29	ND	C26	0.080	0.00054	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-30	ND	C18	0.080	0.00067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-31	0.00188	J q	0.040	0.00054	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-32	ND		0.040	0.00053	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-33	ND	C21	0.080	0.00054	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-34	ND		0.040	0.00058	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-35	ND		0.040	0.00057	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-36	ND		0.040	0.00055	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-37	ND		0.040	0.00056	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-38	ND		0.040	0.00059	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-39	ND		0.040	0.00053	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-40	ND	C	0.12	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-41	ND	C40	0.12	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-42	ND		0.040	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-43	ND	C	0.080	0.00085	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-44	0.00900	J C	0.12	0.00080	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-45	ND	C	0.080	0.00095	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-46	ND		0.040	0.0011	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-47	0.00900	J C44	0.12	0.00080	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-48	ND		0.040	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-49	ND	C	0.080	0.00074	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-50	ND	C	0.080	0.00088	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-51	ND	C45	0.080	0.00095	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-52	0.00140	J q	0.040	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-53	ND	C50	0.080	0.00088	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-54	ND		0.040	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-55	ND		0.040	0.00066	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-56	ND		0.040	0.00066	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-57	ND		0.040	0.00067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-58	ND		0.040	0.00068	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-59	ND	C	0.12	0.00064	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-60	ND		0.040	0.00067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-61	0.00210	J q C	0.16	0.00063	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-62	ND	C59	0.12	0.00064	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-63	ND		0.040	0.00061	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-64	ND		0.040	0.00060	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-65	0.00900	J C44	0.12	0.00080	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-66	ND		0.040	0.00063	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-67	ND		0.040	0.00058	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-68	0.00163	J	0.040	0.00059	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-69	ND	C49	0.080	0.00074	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-70	0.00210	J q C61	0.16	0.00063	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-71	ND	C40	0.12	0.00090	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-72	ND		0.040	0.00065	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-73	ND	C43	0.080	0.00085	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-74	0.00210	J q C61	0.16	0.00063	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-75	ND	C59	0.12	0.00064	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-76	0.00210	J q C61	0.16	0.00063	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-77	ND		0.040	0.00065	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-78	ND		0.040	0.00068	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-79	ND		0.040	0.00059	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-80	ND		0.040	0.00057	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-81	ND		0.040	0.00060	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-82	ND		0.040	0.00030	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-83	ND	C	0.080	0.00027	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-84	ND		0.040	0.00030	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-85	0.00167	J q C	0.12	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-86	0.00271	J C	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-87	0.00271	J C86	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-88	ND	C	0.080	0.00027	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-89	ND		0.040	0.00029	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-90	0.00321	J C	0.12	0.00023	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-91	ND	C88	0.080	0.00027	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-92	ND		0.040	0.00026	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-93	ND	C	0.080	0.00026	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-94	ND		0.040	0.00029	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-95	0.00195	J q	0.040	0.00028	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-96	ND		0.040	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-97	0.00271	J C86	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-98	ND	C	0.080	0.00025	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-99	ND	C83	0.080	0.00027	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-100	ND	C93	0.080	0.00026	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-101	0.00321	J C90	0.12	0.00023	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-102	ND	C98	0.080	0.00025	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-103	ND		0.040	0.00026	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-104	ND		0.040	0.00020	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-105	ND		0.040	0.00040	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-106	ND		0.040	0.00043	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-107	ND		0.040	0.00046	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-108	ND	C	0.080	0.00044	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-109	0.00271	J C86	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-110	0.00243	J C	0.080	0.00019	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-111	ND		0.040	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-112	ND		0.040	0.00019	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-113	0.00321	J C90	0.12	0.00023	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-114	ND		0.040	0.00040	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-115	0.00243	J C110	0.080	0.00019	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-116	0.00167	J q C85	0.12	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-117	0.00167	J q C85	0.12	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-118	0.00107	J q	0.040	0.00039	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-119	0.00271	J C86	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-120	ND		0.040	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-121	ND		0.040	0.00019	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-122	ND		0.040	0.00049	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-123	ND		0.040	0.00043	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-124	ND	C108	0.080	0.00044	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-125	0.00271	J C86	0.24	0.00022	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-126	ND		0.040	0.00047	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-127	ND		0.040	0.00043	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-128	ND	C	0.080	0.00037	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-129	0.00201	J C	0.16	0.00038	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-130	ND		0.040	0.00050	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-131	ND		0.040	0.00052	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-132	ND		0.040	0.00049	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-133	ND		0.040	0.00047	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-134	ND	C	0.080	0.00050	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-135	ND	C	0.080	0.00021	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-136	ND		0.040	0.00015	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-137	ND		0.040	0.00043	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-138	0.00201	J C129	0.16	0.00038	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-139	ND	C	0.080	0.00042	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-140	ND	C139	0.080	0.00042	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-141	ND		0.040	0.00044	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-142	ND		0.040	0.00047	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-143	ND	C134	0.080	0.00050	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-144	ND		0.040	0.00019	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-145	ND		0.040	0.00015	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-146	0.000829	J q	0.040	0.00042	ng/L		08/19/20 15:50	08/26/20 15:08	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-147	0.000817	J q C	0.080	0.00048	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-148	ND		0.040	0.00021	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-149	0.000817	J q C147	0.080	0.00048	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-150	ND		0.040	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-151	ND	C135	0.080	0.00021	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-152	ND		0.040	0.00015	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-153	0.00126	J q C	0.080	0.00033	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-154	ND		0.040	0.00017	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-155	ND		0.040	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-156	ND	C	0.080	0.00040	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-157	ND	C156	0.080	0.00040	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-158	ND		0.040	0.00030	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-159	ND		0.040	0.00032	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-160	0.00201	J C129	0.16	0.00038	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-161	ND		0.040	0.00031	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-162	ND		0.040	0.00031	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-163	0.00201	J C129	0.16	0.00038	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-164	ND		0.040	0.00033	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-165	ND		0.040	0.00036	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-166	ND	C128	0.080	0.00037	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-167	ND		0.040	0.00024	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-168	0.00126	J q C153	0.080	0.00033	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-169	ND		0.040	0.00025	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-170	ND		0.040	0.00017	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-171	ND	C	0.080	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-172	ND		0.040	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-173	ND	C171	0.080	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-174	ND		0.040	0.00017	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-175	ND		0.040	0.00017	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-176	ND		0.040	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-177	ND		0.040	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-178	ND		0.040	0.00018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-179	ND		0.040	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-180	0.00202	J q C	0.080	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-181	ND		0.040	0.00017	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-182	ND		0.040	0.00016	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-183	0.00201	J C	0.080	0.00016	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-184	ND		0.040	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-185	0.00201	J C183	0.080	0.00016	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-186	ND		0.040	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-187	ND		0.040	0.00015	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-188	ND		0.040	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-189	ND		0.040	0.00031	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-190	ND		0.040	0.00012	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-191	ND		0.040	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-192	ND		0.040	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-193	0.00202	J q C180	0.080	0.00014	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-194	ND		0.040	0.00029	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-195	ND		0.040	0.00032	ng/L		08/19/20 15:50	08/26/20 15:08	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-196	ND		0.040	0.000087	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-197	ND		0.040	0.000067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-198	0.000803	J C	0.080	0.000089	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-199	0.000803	J C198	0.080	0.000089	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-200	ND		0.040	0.000059	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-201	ND		0.040	0.000061	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-202	ND		0.040	0.000068	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-203	ND		0.040	0.000079	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-204	ND		0.040	0.000067	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-205	0.00127	J	0.040	0.00025	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-206	ND		0.040	0.0018	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-207	ND		0.040	0.0013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-208	ND		0.040	0.0013	ng/L		08/19/20 15:50	08/26/20 15:08	1
PCB-209	ND		0.040	0.00023	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Monochlorobiphenyls	0.00758	J q	0.040	0.00031	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Dichlorobiphenyls	0.00889	J q	0.080	0.0034	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Trichlorobiphenyls	0.00403	J q	0.080	0.00061	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Tetrachlorobiphenyls	0.0141	J q	0.16	0.00071	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Pentachlorobiphenyls	0.0130	J q	0.24	0.00030	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Hexachlorobiphenyls	0.00492	J q	0.16	0.00033	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Heptachlorobiphenyls	0.00403	J q	0.080	0.00016	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Octachlorobiphenyls	0.00207	J	0.080	0.00013	ng/L		08/19/20 15:50	08/26/20 15:08	1
Total Nonachlorobiphenyls	ND		0.040	0.0018	ng/L		08/19/20 15:50	08/26/20 15:08	1
Polychlorinated biphenyls, Total	0.0587	J q	0.24	0.00085	ng/L		08/19/20 15:50	08/26/20 15:08	1

Isotope Dilution	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*62*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-3L	*61*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-4L	*66*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-15L	*70*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-19L	*68*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-37L	*76*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-54L	*73*		*5 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-77L	*79*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-81L	*77*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-104L	*56*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-105L	*81*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-114L	*77*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-118L	*78*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-123L	*75*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-126L	*76*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-155L	*58*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-156L	*79*	*C*	*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-157L	*79*	*C156*	*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-167L	*80*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-169L	*82*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-170L	*78*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-188L	*69*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*
PCB-189L	*81*		*10 - 145*	*08/19/20 15:50*	*08/26/20 15:08*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-41958/13-A
Matrix: Water
Analysis Batch: 42160

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 41958

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-202L	85		10 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-205L	71		10 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-206L	75		10 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-208L	78		10 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-209L	70		10 - 145	08/19/20 15:50	08/26/20 15:08	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	90		5 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-111L	89		10 - 145	08/19/20 15:50	08/26/20 15:08	1
PCB-178L	94		10 - 145	08/19/20 15:50	08/26/20 15:08	1

Lab Sample ID: LCS 140-41958/12-A
Matrix: Water
Analysis Batch: 42191

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 41958

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1	1.00	0.983		ng/L		98	60 - 135
PCB-3	1.00	1.02		ng/L		102	60 - 135
PCB-4	1.00	1.16		ng/L		116	60 - 135
PCB-15	1.00	1.34		ng/L		134	60 - 135
PCB-19	1.00	1.26		ng/L		126	60 - 135
PCB-37	1.00	1.12		ng/L		112	60 - 135
PCB-54	1.00	1.15		ng/L		115	60 - 135
PCB-77	1.00	1.04		ng/L		104	60 - 135
PCB-81	1.00	1.08		ng/L		108	60 - 135
PCB-104	1.00	1.42	*	ng/L		142	60 - 135
PCB-105	1.00	1.11		ng/L		111	60 - 135
PCB-114	1.00	1.24		ng/L		124	60 - 135
PCB-118	1.00	1.17		ng/L		117	60 - 135
PCB-123	1.00	1.29		ng/L		129	60 - 135
PCB-126	1.00	1.18		ng/L		118	60 - 135
PCB-155	1.00	1.43	*	ng/L		143	60 - 135
PCB-156	2.00	2.32	C	ng/L		116	60 - 135
PCB-157	2.00	2.32	C156	ng/L		116	60 - 135
PCB-167	1.00	1.17		ng/L		117	60 - 135
PCB-169	1.00	1.05		ng/L		105	60 - 135
PCB-188	1.00	1.23		ng/L		123	60 - 135
PCB-189	1.00	1.13		ng/L		113	60 - 135
PCB-202	1.00	0.988		ng/L		99	60 - 135
PCB-205	1.00	1.21		ng/L		121	60 - 135
PCB-206	1.00	0.885		ng/L		88	60 - 135
PCB-208	1.00	0.912		ng/L		91	60 - 135
PCB-209	1.00	0.683		ng/L		68	60 - 135

Isotope Dilution	LCS %Recovery	LCS Qualifier	Limits
PCB-1L	78		15 - 145
PCB-3L	77		15 - 145
PCB-4L	69		15 - 145

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-41958/12-A
Matrix: Water
Analysis Batch: 42191

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 41958

Isotope Dilution	LCS %Recovery	LCS Qualifier	Limits
PCB-15L	66		15 - 145
PCB-19L	77		15 - 145
PCB-37L	79		15 - 145
PCB-54L	68		15 - 145
PCB-77L	80		40 - 145
PCB-81L	77		40 - 145
PCB-104L	59		40 - 145
PCB-105L	83		40 - 145
PCB-114L	80		40 - 145
PCB-118L	79		40 - 145
PCB-123L	77		40 - 145
PCB-126L	80		40 - 145
PCB-155L	56		40 - 145
PCB-156L	79	C	40 - 145
PCB-157L	79	C156	40 - 145
PCB-167L	81		40 - 145
PCB-169L	85		40 - 145
PCB-170L	78		40 - 145
PCB-188L	70		40 - 145
PCB-189L	83		40 - 145
PCB-202L	81		40 - 145
PCB-205L	68		40 - 145
PCB-206L	70		40 - 145
PCB-208L	67		40 - 145
PCB-209L	66		40 - 145

Surrogate	LCS %Recovery	LCS Qualifier	Limits
PCB-28L	94		15 - 145
PCB-111L	88		40 - 145
PCB-178L	95		40 - 145

Method: EPA 6020A - Metals (ICP/MS)

Lab Sample ID: MB 180-326168/1-A
Matrix: Water
Analysis Batch: 327802

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 326168

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	ND		30	13	ug/L		08/19/20 09:29	08/29/20 15:30	1
Arsenic	ND		1.0	0.31	ug/L		08/19/20 09:29	08/29/20 15:30	1
Barium	ND		10	1.6	ug/L		08/19/20 09:29	08/29/20 15:30	1
Beryllium	ND		1.0	0.18	ug/L		08/19/20 09:29	08/29/20 15:30	1
Cadmium	ND		1.0	0.22	ug/L		08/19/20 09:29	08/29/20 15:30	1
Calcium	ND		500	130	ug/L		08/19/20 09:29	08/29/20 15:30	1
Chromium	ND		2.0	1.5	ug/L		08/19/20 09:29	08/29/20 15:30	1
Cobalt	ND		0.50	0.13	ug/L		08/19/20 09:29	08/29/20 15:30	1
Copper	ND		2.0	0.63	ug/L		08/19/20 09:29	08/29/20 15:30	1
Iron	ND		50	20	ug/L		08/19/20 09:29	08/29/20 15:30	1
Silver	ND		1.0	0.18	ug/L		08/19/20 09:29	08/29/20 15:30	1

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Lab Sample ID: MB 180-326168/1-A
Matrix: Water
Analysis Batch: 327802

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 326168

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Potassium	ND		500	160	ug/L		08/19/20 09:29	08/29/20 15:30	1
Magnesium	ND		500	83	ug/L		08/19/20 09:29	08/29/20 15:30	1
Manganese	ND		5.0	0.87	ug/L		08/19/20 09:29	08/29/20 15:30	1
Sodium	ND		500	350	ug/L		08/19/20 09:29	08/29/20 15:30	1
Nickel	ND		1.0	0.34	ug/L		08/19/20 09:29	08/29/20 15:30	1
Lead	ND		1.0	0.13	ug/L		08/19/20 09:29	08/29/20 15:30	1
Antimony	ND		2.0	0.38	ug/L		08/19/20 09:29	08/29/20 15:30	1
Selenium	ND		5.0	1.5	ug/L		08/19/20 09:29	08/29/20 15:30	1
Thallium	ND		1.0	0.15	ug/L		08/19/20 09:29	08/29/20 15:30	1
Vanadium	ND		1.0	0.99	ug/L		08/19/20 09:29	08/29/20 15:30	1
Zinc	ND		5.0	3.2	ug/L		08/19/20 09:29	08/29/20 15:30	1

Lab Sample ID: LCS 180-326168/2-A
Matrix: Water
Analysis Batch: 327802

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 326168

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Aluminum	5000	4820		ug/L		96	80 - 120
Arsenic	1000	1000		ug/L		100	80 - 120
Barium	1000	1060		ug/L		106	80 - 120
Beryllium	500	482		ug/L		96	80 - 120
Cadmium	500	487		ug/L		97	80 - 120
Calcium	25000	27700		ug/L		111	80 - 120
Chromium	500	509		ug/L		102	80 - 120
Cobalt	500	484		ug/L		97	80 - 120
Copper	500	487		ug/L		97	80 - 120
Iron	5000	4930		ug/L		99	80 - 120
Silver	250	246		ug/L		99	80 - 120
Potassium	25000	24900		ug/L		99	80 - 120
Magnesium	25000	24900		ug/L		100	80 - 120
Manganese	500	487		ug/L		97	80 - 120
Sodium	25000	24400		ug/L		97	80 - 120
Nickel	500	495		ug/L		99	80 - 120
Lead	500	500		ug/L		100	80 - 120
Antimony	250	265		ug/L		106	80 - 120
Selenium	1000	1030		ug/L		103	80 - 120
Thallium	1000	1020		ug/L		102	80 - 120
Vanadium	500	498		ug/L		100	80 - 120
Zinc	250	249		ug/L		100	80 - 120

Method: EPA 7470A - Mercury (CVAA)

Lab Sample ID: MB 180-326779/1-A
Matrix: Water
Analysis Batch: 326852

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 326779

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		08/24/20 05:16	08/24/20 10:28	1

Method: EPA 7470A - Mercury (CVAA) (Continued)

Lab Sample ID: LCS 180-326779/2-A
Matrix: Water
Analysis Batch: 326852

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 326779

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Mercury	2.50	2.59		ug/L		103	80 - 120

Method: SM 2540D - Solids, Total Suspended (TSS)

Lab Sample ID: MB 180-325702/2
Matrix: Water
Analysis Batch: 325702

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	ND		0.50	0.50	mg/L			08/15/20 10:59	1

Lab Sample ID: LCS 180-325702/1
Matrix: Water
Analysis Batch: 325702

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Suspended Solids	84.7	90.0		mg/L		106	80 - 120

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-109612-1

GC/MS Semi VOA

Prep Batch: 326164

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	3520C	
MB 180-326164/1-A	Method Blank	Total/NA	Water	3520C	
LCS 180-326164/2-A	Lab Control Sample	Total/NA	Water	3520C	
180-109612-1 MS	OFW0400N	Total/NA	Water	3520C	

Analysis Batch: 326981

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	EPA 8270D LL	326164
MB 180-326164/1-A	Method Blank	Total/NA	Water	EPA 8270D LL	326164
LCS 180-326164/2-A	Lab Control Sample	Total/NA	Water	EPA 8270D LL	326164
180-109612-1 MS	OFW0400N	Total/NA	Water	EPA 8270D LL	326164

GC Semi VOA

Prep Batch: 447423

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	3510C LVI	
MB 240-447423/3-A	Method Blank	Total/NA	Water	3510C LVI	
LCS 240-447423/4-A	Lab Control Sample	Total/NA	Water	3510C LVI	

Analysis Batch: 447510

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	8015D	447423
MB 240-447423/3-A	Method Blank	Total/NA	Water	8015D	447423
LCS 240-447423/4-A	Lab Control Sample	Total/NA	Water	8015D	447423

Specialty Organics

Prep Batch: 41958

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	HRMS-Sepf	
MB 140-41958/13-A	Method Blank	Total/NA	Water	HRMS-Sepf	
LCS 140-41958/12-A	Lab Control Sample	Total/NA	Water	HRMS-Sepf	

Analysis Batch: 42160

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	1668C	41958
MB 140-41958/13-A	Method Blank	Total/NA	Water	1668C	41958

Analysis Batch: 42191

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 140-41958/12-A	Lab Control Sample	Total/NA	Water	1668C	41958

Metals

Prep Batch: 326168

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total Recoverable	Water	3005A	
MB 180-326168/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 180-326168/2-A	Lab Control Sample	Total Recoverable	Water	3005A	

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-109612-1

Metals

Prep Batch: 326779

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	7470A	
MB 180-326779/1-A	Method Blank	Total/NA	Water	7470A	
LCS 180-326779/2-A	Lab Control Sample	Total/NA	Water	7470A	

Analysis Batch: 326852

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	EPA 7470A	326779
MB 180-326779/1-A	Method Blank	Total/NA	Water	EPA 7470A	326779
LCS 180-326779/2-A	Lab Control Sample	Total/NA	Water	EPA 7470A	326779

Analysis Batch: 327802

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total Recoverable	Water	EPA 6020A	326168
MB 180-326168/1-A	Method Blank	Total Recoverable	Water	EPA 6020A	326168
LCS 180-326168/2-A	Lab Control Sample	Total Recoverable	Water	EPA 6020A	326168

General Chemistry

Analysis Batch: 325702

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-109612-1	OFW0400N	Total/NA	Water	SM 2540D	
MB 180-325702/2	Method Blank	Total/NA	Water	SM 2540D	
LCS 180-325702/1	Lab Control Sample	Total/NA	Water	SM 2540D	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: Qiang Huang	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-62216-12590.1
Client Contact: Mr. Robert Kennedy	Phone: 240-374-8920	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 1 of 1
Company: AECOM				Job #:
Address: 250 Apollo Drive	Due Date Requested:			
City: Chelmsford	TAT Requested (days): Standard.			
State, Zip: MA, 01824				
Phone:	PO #: 126546			
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site: Pepco Benning Rd.	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)

Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C - PCB Congeners	8270D - PAHs	6020A - TAL Metal 6020/7470	2540 - TSS	8015D - TPH DRO/ORO	Total Number of containers	Special Instructions/Note:
			Preservation Code:										
OFW0400N	8/13/20	0850	G	W			X	X	X	X	X		

180-109612 Chain of Custody


Possible Hazard Identification	Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological	☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months
Deliverable Requested: I, II, III, IV, Other (specify)	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Qiang Huang	8/13/20 1200			8/13/20 1700	BTA Balt
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
	8/13/20 1700	BTA Balt		8/14/20 900	BTA Balt
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019



FZ 10:30 A
8306
08.14

ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 13AUG20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

568J2/7709/B766

FedEx Express

FRI - 14 AUG 10:30A
PRIORITY OVERNIGHT

TRK# 0201 7712 5678 8306

15238
PIT

NA AGCA
PA-US

Uncorrected Temp 2.9 °C
Thermometer ID 14
CF 0 Initials JJ
PT-WI-SR-001 effective 11/8/18

Part # 156297-435 RRDW2 EXP 08/21

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

180-109612 Chain of Custody

Eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L		J: 180-407250.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-109612-1
Address: 5815 Middlebrook Pike, ,	Due Date Requested: 8/28/2020			Preservation Codes:
City: Knoxville	TAT Requested (days):			A - HCL M - Hexane B - NaOH N - None C - Zn Acetate O - AsNaO2 D - Nitric Acid P - Na2O4S E - NaHSO4 Q - Na2SO3 F - MeOH R - Na2S2O3 G - Amchlor S - H2SO4 H - Ascorbic Acid T - TSP Dodecahydrate I - Ice U - Acetone J - DI Water V - MCAA K - EDTA W - pH 4-5 L - EDA Z - other (specify) Other:
State, Zip: TN, 37921				
Phone: 865-291-3000(Tel) 865-584-4315(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C/1668_P_Sep PCB Congeners	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
OFW0400N (180-109612-1)	8/13/20	08:50 Eastern		Water			X	2	

RT: 2.1°C CT: 2.1°C, 1 Cooler
Fedex Po, RC-NO, Custody seal intact
trk# 1689 5102 2661
KW 8/15/20

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification *Unconfirmed*	***Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*** ☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:		Date:	Time:	Method of Shipment:		
Relinquished by:	Date/Time: 8/14/20 1700	Company: NT	Received by:	Date/Time: 8/15/20 1010	Company: ETA	
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company	
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company	

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Loc: 180

EUROFINS/TESTAMERICA KNOXVILLE SAMPLE RECEIPT/CONDITION UPON RECEIPT ANOMALY CHECKLIST

Log In Number: 109612

Review Items	Yes	No	NA	If No, what was the problem?
1. Are the shipping containers intact?	✓			☐ **Containers, Broken**
2. Were ambient air containers received intact?			✓	☐ Checked in lab
3. The coolers/containers custody seal if present, is it intact?	✓			☐ Yes ☐ NA
4. Is the cooler temperature within limits? (> freezing temp. of water to 6 °C, VOST: 10°C) Thermometer ID : SC68 Correction factor: 0.0	✓			☐ **Cooler Out of Temp, Client Contacted, Proceed/Cancel** ☐ **Cooler Out of Temp, Same Day Receipt**
5. Were all of the sample containers received intact?	✓			☐ **Containers, Broken**
6. Were samples received in appropriate containers?	✓			☐ **Containers, Improper; Client Contacted; Proceed/Cancel**
7. Do sample container labels match COC? (IDs, Dates, Times)	✓			☐ **COC & Samples Do Not Match** ☐ **COC Incorrect/Incomplete** ☐ **COC Not Received**
8. Were all of the samples listed on the COC received?	✓			☐ **Sample Received, Not on COC** ☐ **Sample on COC, Not Received**
9. Is the date/time of sample collection noted?	✓			☐ **COC; No Date/Time; Client Contacted**
10. Was the sampler identified on the COC?			✓	☐ **Sampler Not Listed on COC**
11. Is the client and project name/# identified?	✓			☐ **COC Incorrect/Incomplete**
12. Are tests/parameters listed for each sample?	✓			☐ **COC No tests on COC**
13. Is the matrix of the samples noted?	✓			☐ **COC Incorrect/Incomplete**
14. Was COC relinquished? (Signed/Dated/Timed)	✓			☐ **COC Incorrect/Incomplete**
15. Were samples received within holding time?	✓			☐ **Holding Time - Receipt**
16. Were samples received with correct chemical preservative (excluding Encore)?			✓	☐ **pH Adjusted, pH Included (See box 16A)** ☐ **Incorrect Preservative**
17. Were VOA samples received without headspace?			✓	☐ **Headspace (VOA only)**
18. Did you check for residual chlorine, if necessary? (e.g. 1613B, 1668) Chlorine test strip lot number: 8178 2021/04	✓			☐ **Residual Chlorine**
19. For 1613B water samples is pH<9?			✓	☐ If no, notify lab to adjust
20. For rad samples was sample activity info. Provided?			✓	☐ Project missing info

Comments/Actions Taken

Labeling Verified by: **Date:**

pH test strip lot number:

	Box 16A: pH Preservation	Box 18A: Residual Chlorine
Preservative:		
Lot Number:		
Exp Date:		
Analyst:		
Date:		
Time:		

Project #: _____ PM Instructions: _____

Sample Receiving Associate: _____ Date: 8/15/20

QA026R32.doc, 062719

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-109612-1

Login Number: 109612
List Number: 1
Creator: Say, Thomas C

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-111218-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
10/23/2020 9:38:06 AM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 4
Certification Summary 6
Sample Summary 9
Method Summary 10
Lab Chronicle 11
Client Sample Results 14
QC Sample Results 47
QC Association Summary 55
Chain of Custody 57
Receipt Checklists 64

Job ID: 180-111218-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-111218-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 09/19/2020; the samples arrived in good condition, properly preserved and on ice. The temperature of the coolers at receipt was 2.9 C.

1668A
The samples were sent through the Gel-Permeation Cleanup procedure, based on EPA method 3640A

Samples STS0300N (180-111218-1), STS0200N (180-111218-2) and STS0100N (180-111218-3) were analyzed at a dilution. The reporting limits have been adjusted accordingly.

Several analytes were detected in method blank MB 140-43261/19-B at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

GRAIN SIZE
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

SPECIFIC GRAVITY
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

TOTAL ORGANIC CARBON
Please note that the reporting limit for Lloyd Kahn TOC analysis is a nominal value and does not reflect adjustments in sample mass processed on an individual basis..

PERCENT SOLIDS
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

PARTICLE SIZE DISTRIBUTION VIA LASER LIGHT SCATTERING
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Qualifiers

Dioxin

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
C	The compound co-eluted with other compounds
C108	The compound co-eluted with PCB-108
C110	The compound co-eluted with PCB-110
C12	The compound co-eluted with PCB-12
C128	The compound co-eluted with PCB-128
C129	The compound co-eluted with PCB-129
C134	The compound co-eluted with PCB-134
C135	The compound co-eluted with PCB-135
C139	The compound co-eluted with PCB-139
C147	The compound co-eluted with PCB-147
C153	The compound co-eluted with PCB-153
C156	The compound co-eluted with PCB-156
C171	The compound co-eluted with PCB-171
C18	The compound co-eluted with PCB-18
C180	The compound co-eluted with PCB-180
C183	The compound co-eluted with PCB-183
C198	The compound co-eluted with PCB-198
C20	The compound co-eluted with PCB-20
C21	The compound co-eluted with PCB-21
C26	The compound co-eluted with PCB-26
C40	The compound co-eluted with PCB-40
C43	The compound co-eluted with PCB-43
C44	The compound co-eluted with PCB-44
C45	The compound co-eluted with PCB-45
C49	The compound co-eluted with PCB-49
C50	The compound co-eluted with PCB-50
C59	The compound co-eluted with PCB-59
C61	The compound co-eluted with PCB-61
C83	The compound co-eluted with PCB-83
C85	The compound co-eluted with PCB-85
C86	The compound co-eluted with PCB-86
C88	The compound co-eluted with PCB-88
C90	The compound co-eluted with PCB-90
C93	The compound co-eluted with PCB-93
C98	The compound co-eluted with PCB-98
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
q	The reported result is the estimated maximum possible concentration of this analyte, quantitated using the theoretical ion ratio. The measured ion ratio does not meet qualitative identification criteria and indicates a possible interference.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)

Glossary (Continued)

Abbreviation	These commonly used abbreviations may or may not be present in this report.
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	10-12-20
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20
Florida	NELAP	E871008	10-12-20
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	10-12-20
Kansas	NELAP	E-10350	10-12-20
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	10-12-20
Louisiana	NELAP	04041	10-12-20
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	10-12-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	10-12-20
New Jersey	NELAP	PA005	10-12-20
New York	NELAP	11182	10-12-20
North Carolina (WW/SW)	State	434	01-01-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	10-12-20
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	10-12-20
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	10-12-20
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-21

Laboratory: Eurofins Calscience LLC

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	Los Angeles County Sanitation Districts	10109	09-30-21
California	SCAQMD LAP	17LA0919	11-30-20
California	State	2944	09-30-21
Guam	State	20-003R	10-31-20
Nevada	State	CA00111	07-31-21
Oregon	NELAP	CA300001	01-29-21
USDA	US Federal Programs	P330-20-00034	02-10-23
Washington	State	C916-18	10-11-21

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Burlington

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
ANAB	Dept. of Defense ELAP	L2336	02-25-23
Connecticut	State	PH-0751	09-30-21
DE Haz. Subst. Cleanup Act (HSCA)	State	N/A	05-16-21
Florida	NELAP	E87467	06-30-21
Minnesota	NELAP	050-999-436	12-31-20
New Hampshire	NELAP	2006	12-18-20
New Jersey	NELAP	VT972	06-30-21
New York	NELAP	10391	04-01-21
Pennsylvania	NELAP	68-00489	04-30-21
Rhode Island	State	LAO00298	12-30-20
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-17-00272	08-09-20 *
Vermont	State	VT4000	12-31-20
Virginia	NELAP	460209	12-14-20
Wisconsin	State	399133350	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Knoxville

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
	AFCEE	N/A	
ANAB	Dept. of Defense ELAP	L2311	02-13-22
ANAB	Dept. of Energy	L2311.01	02-13-22
ANAB	ISO/IEC 17025	L2311	02-13-22
ANAB	ISO/IEC 17025	L2311	02-14-22
Arkansas DEQ	State	88-0688	06-17-21
California	State	2423	06-30-21
Colorado	State	TN00009	02-28-21
Connecticut	State	PH-0223	09-30-21
Florida	NELAP	E87177	07-01-21
Georgia (DW)	State	906	12-11-22
Hawaii	State	NA	12-11-21
Kansas	NELAP	E-10349	11-01-20
Kentucky (DW)	State	90101	01-01-21
Louisiana	NELAP	LA110001	12-31-12 *
Louisiana	NELAP	83979	06-30-21
Louisiana (DW)	State	LA019	12-31-20
Maryland	State	277	03-31-21
Michigan	State	9933	12-11-22
Nevada	State	TN00009	07-31-21
New Hampshire	NELAP	299919	01-17-21
New Jersey	NELAP	TN001	07-01-21
New York	NELAP	10781	03-31-21
North Carolina (DW)	State	21705	07-31-21
North Carolina (WW/SW)	State	64	12-31-20
Ohio VAP	State	CL0059	06-02-23
Oklahoma	State	9415	08-31-21
Oregon	NELAP	TNI0189	01-02-21
Pennsylvania	NELAP	68-00576	12-31-20
Tennessee	State	02014	12-11-22
Texas	NELAP	T104704380-18-12	08-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-19-00236	08-20-22
Utah	NELAP	TN00009	07-31-21
Virginia	NELAP	460176	09-14-21
Washington	State	C593	01-19-21
West Virginia (DW)	State	9955C	01-01-21
West Virginia DEP	State	345	05-01-21
Wisconsin	State	998044300	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-111218-1	STS0300N	Sediment	09/17/20 11:55	09/19/20 11:00	
180-111218-2	STS0200N	Sediment	09/17/20 12:20	09/19/20 11:00	
180-111218-3	STS0100N	Sediment	09/17/20 12:35	09/19/20 11:00	
180-111218-4	SEE0101N	Sediment	09/17/20 13:15	09/19/20 11:00	
180-111218-5	SEE0201N	Sediment	09/17/20 13:45	09/19/20 11:00	
180-111218-6	SEE0301N	Sediment	09/17/20 14:02	09/19/20 11:00	
180-111218-7	STS0300N	Solid	09/17/20 11:55	09/19/20 11:00	
180-111218-8	STS0200N	Solid	09/17/20 12:20	09/19/20 11:00	
180-111218-9	STS0100N	Solid	09/17/20 12:35	09/19/20 11:00	

Method Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
1668C	Chlorinated Biphenyl Congeners (HRGC/HRMS)	EPA	TAL KNX
2540G	SM 2540G	SM22	TAL PIT
ASTM D5057-90	Specific Gravity and Bulk Density (Screening)	ASTM	TAL PIT
EPA-Lloyd Kahn	Organic Carbon, Total (TOC)	EPA	TAL PIT
D422	Grain Size	ASTM	TAL BUR
D4464	Particle Size Distribution of Catalytic Material (Laser light scattering)	ASTM	ECL 1
HRMS-Sox	Soxhlet Extraction	EPA	TAL KNX
Split	Split Factor Determination	None	TAL KNX

Protocol References:

ASTM = ASTM International
EPA = US Environmental Protection Agency
None = None
SM22 = Standard Methods For The Examination Of Water And Wastewater, 22nd Edition

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494
TAL BUR = Eurofins TestAmerica, Burlington, 30 Community Drive, Suite 11, South Burlington, VT 05403, TEL (802)660-1990
TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: STS0300N
Lab Sample ID: 180-111218-1
Date Collected: 09/17/20 11:55
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			331732	09/29/20 21:22	PMH	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:28	TAM	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: STS0300N
Lab Sample ID: 180-111218-1
Date Collected: 09/17/20 11:55
Matrix: Sediment
Date Received: 09/19/20 11:00
Percent Solids: 44.5

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			20.72 g	20 mL	43261	10/03/20 06:25	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43349	10/07/20 12:39	ALS	TAL KNX
Total/NA	Analysis	1668C		2			43723	10/21/20 15:46	JMN	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			331767	09/29/20 16:30	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: STS0200N
Lab Sample ID: 180-111218-2
Date Collected: 09/17/20 12:20
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			331732	09/29/20 21:22	PMH	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:30	TAM	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: STS0200N
Lab Sample ID: 180-111218-2
Date Collected: 09/17/20 12:20
Matrix: Sediment
Date Received: 09/19/20 11:00
Percent Solids: 43.7

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			20.12 g	20 mL	43261	10/03/20 06:25	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43349	10/07/20 12:39	ALS	TAL KNX
Total/NA	Analysis	1668C		2			43723	10/21/20 16:47	JMN	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			331767	09/29/20 16:47	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: STS0100N
Lab Sample ID: 180-111218-3
Date Collected: 09/17/20 12:35
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			331732	09/29/20 21:22	PMH	TAL PIT
	Instrument ID: NOEQUIP									

Lab Chronicle

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: STS0100N
Lab Sample ID: 180-111218-3
Date Collected: 09/17/20 12:35
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:32	TAM	TAL PIT

Client Sample ID: STS0100N
Lab Sample ID: 180-111218-3
Date Collected: 09/17/20 12:35
Matrix: Sediment
Date Received: 09/19/20 11:00
Percent Solids: 40.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			20.18 g	20 mL	43261	10/03/20 06:25	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43349	10/07/20 12:39	ALS	TAL KNX
Total/NA	Analysis	1668C		2			43723	10/21/20 19:54	JMN	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			331767	09/29/20 17:43	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: SEE0101N
Lab Sample ID: 180-111218-4
Date Collected: 09/17/20 13:15
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:33	TAM	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			159682	09/30/20 20:32	CPF	TAL BUR
	Instrument ID: D422_import									

Client Sample ID: SEE0201N
Lab Sample ID: 180-111218-5
Date Collected: 09/17/20 13:45
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:35	TAM	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			159682	09/30/20 20:34	CPF	TAL BUR
	Instrument ID: D422_import									

Client Sample ID: SEE0301N
Lab Sample ID: 180-111218-6
Date Collected: 09/17/20 14:02
Matrix: Sediment
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	ASTM D5057-90		1	50 g	50 mL	331888	09/30/20 18:36	TAM	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			159682	09/30/20 20:36	CPF	TAL BUR
	Instrument ID: D422_import									

Lab Chronicle

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: STS0300N
Lab Sample ID: 180-111218-7
Date Collected: 09/17/20 11:55
Matrix: Solid
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			103533	10/21/20 13:26	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Client Sample ID: STS0200N
Lab Sample ID: 180-111218-8
Date Collected: 09/17/20 12:20
Matrix: Solid
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			103533	10/21/20 13:30	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Client Sample ID: STS0100N
Lab Sample ID: 180-111218-9
Date Collected: 09/17/20 12:35
Matrix: Solid
Date Received: 09/19/20 11:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			103533	10/21/20 13:40	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

TAL BUR = Eurofins TestAmerica, Burlington, 30 Community Drive, Suite 11, South Burlington, VT 05403, TEL (802)660-1990

TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Analyst References:

Lab: ECL 1
- Batch Type: Analysis
  - C4LT = Jordan Stratford

Lab: TAL BUR
- Batch Type: Analysis
  - CPF = Fred Cota

Lab: TAL KNX
- Batch Type: Cleanup
  - ALS = Allan Sudderth
- Batch Type: Prep
  - CLI = Crystal Ivey
- Batch Type: Analysis
  - JMN = Jon Nordquist

Lab: TAL PIT
- Batch Type: Analysis
  - DLF = Donald Ferguson
  - PMH = Paloma Hoelzle
  - TAM = Tessa Mastalski

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.17		0.022	0.00056	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-2	0.024		0.022	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-3	0.069		0.022	0.00089	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-4	0.96		0.043	0.0036	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-5	0.027	q	0.022	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-6	0.29		0.022	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-7	0.065		0.022	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-8	1.3		0.043	0.0023	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-9	0.076		0.022	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-10	0.042	q	0.022	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-11	0.19	B	0.043	0.0024	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-12	0.11	C	0.043	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-13	0.11	C12	0.043	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-14	ND		0.022	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-15	0.84		0.022	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-16	1.0		0.022	0.00065	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-17	1.5		0.022	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-18	2.5	C B	0.043	0.00051	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-19	0.52		0.022	0.00072	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-20	3.8	C B	0.043	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-21	1.6	C B	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-22	1.2		0.022	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-23	0.0033	J	0.022	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-24	0.059		0.022	0.00049	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-25	0.39		0.022	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-26	0.68	C	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-27	0.36		0.022	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-28	3.8	B C20	0.043	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-29	0.68	C26	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-30	2.5	C18 B	0.043	0.00051	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-31	3.0	B	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-32	1.1		0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-33	1.6	B C21	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-34	0.017	J	0.022	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-35	0.053		0.022	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-36	0.0038	J	0.022	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-37	0.86		0.022	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-38	ND		0.022	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-39	0.016	J	0.022	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-40	2.1	C	0.065	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-41	2.1	C40	0.065	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-42	0.94		0.022	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-43	0.14	C	0.043	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-44	3.8	C B	0.065	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-45	0.93	C	0.043	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-46	0.27		0.022	0.0060	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-47	3.8	B C44	0.065	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-48	0.67		0.022	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-49	2.3	C	0.043	0.0039	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	0.73	C	0.043	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-51	0.93	C45	0.043	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-52	4.3	B	0.022	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-53	0.73	C50	0.043	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-54	0.034		0.022	0.00028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-55	0.048	q	0.022	0.0035	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-56	1.1		0.022	0.0035	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-57	0.019	J	0.022	0.0035	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-58	0.010	J q	0.022	0.0036	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-59	0.34	C	0.065	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-60	0.57		0.022	0.0035	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-61	4.2	C B	0.087	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-62	0.34	C59	0.065	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-63	0.11		0.022	0.0032	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-64	1.5		0.022	0.0032	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-65	3.8	B C44	0.065	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-66	2.6		0.022	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-67	0.077		0.022	0.0030	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-68	0.020	J q	0.022	0.0031	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-69	2.3	C49	0.043	0.0039	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-70	4.2	C61 B	0.087	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-71	2.1	C40	0.065	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-72	0.033		0.022	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-73	0.14	C43	0.043	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-74	4.2	C61 B	0.087	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-75	0.34	C59	0.065	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-76	4.2	C61 B	0.087	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-77	0.28		0.022	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-78	ND		0.022	0.0036	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-79	0.022	q	0.022	0.0031	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-80	ND		0.022	0.0030	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-81	0.0090	J q	0.022	0.0032	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-82	0.55		0.022	0.00050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-83	2.3	C B	0.043	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-84	1.0		0.022	0.00050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-85	0.84	C B	0.065	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-86	2.6	C B	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-87	2.6	B C86	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-88	0.71	C	0.043	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-89	0.051	q	0.022	0.00049	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-90	4.0	C B	0.065	0.00038	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-91	0.71	C88	0.043	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-92	0.69		0.022	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-93	0.13	C	0.043	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-94	0.046		0.022	0.00049	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-95	3.5	B	0.022	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-96	0.055		0.022	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-97	2.6	B C86	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-98	0.18	C	0.043	0.00042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	2.3	C83 B	0.043	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-100	0.13	C93	0.043	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-101	4.0	B C90	0.065	0.00038	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-102	0.18	C98	0.043	0.00042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-103	0.042		0.022	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-104	0.0030	J	0.022	0.00033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-105	1.5		0.022	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-106	ND		0.022	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-107	0.24		0.022	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-108	0.13	C	0.043	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-109	2.6	B C86	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-110	4.8	C B	0.043	0.00031	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-111	ND		0.022	0.00030	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-112	0.016	J	0.022	0.00032	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-113	4.0	B C90	0.065	0.00038	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-114	0.080		0.022	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-115	4.8	B C110	0.043	0.00031	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-116	0.84	C85 B	0.065	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-117	0.84	C85 B	0.065	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-118	3.3	B	0.022	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-119	2.6	B C86	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-120	0.0086	J q	0.022	0.00031	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-121	ND		0.022	0.00032	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-122	0.072		0.022	0.0054	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-123	0.088		0.022	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-124	0.13	C108	0.043	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-125	2.6	B C86	0.13	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-126	0.011	J	0.022	0.0052	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-127	ND		0.022	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-128	0.77	C	0.043	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-129	5.6	C B	0.087	0.0053	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-130	0.30		0.022	0.0070	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-131	0.061		0.022	0.0073	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-132	1.7		0.022	0.0068	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-133	0.069		0.022	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-134	0.28	C	0.043	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-135	1.7	C	0.043	0.00042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-136	0.58		0.022	0.00030	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-137	0.21		0.022	0.0060	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-138	5.6	B C129	0.087	0.0053	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-139	0.076	C	0.043	0.0059	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-140	0.076	C139	0.043	0.0059	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-141	1.1		0.022	0.0062	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-142	ND		0.022	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-143	0.28	C134	0.043	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-144	0.20		0.022	0.00038	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-145	0.0026	J q	0.022	0.00029	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-146	0.72		0.022	0.0058	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-147	4.7	C B	0.043	0.0067	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.0067	J	0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-149	4.7	B C147	0.043	0.0067	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-150	0.0071	J	0.022	0.00028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-151	1.7	C135	0.043	0.00042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-152	0.0054	J	0.022	0.00030	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-153	4.4	C B	0.043	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-154	0.050		0.022	0.00033	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-155	ND		0.022	0.00028	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-156	0.52	C	0.043	0.0055	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-157	0.52	C156	0.043	0.0055	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-158	0.53		0.022	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-159	0.045		0.022	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-160	5.6	B C129	0.087	0.0053	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-161	0.0051	J q	0.022	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-162	0.010	J q	0.022	0.0043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-163	5.6	B C129	0.087	0.0053	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-164	0.38		0.022	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-165	ND		0.022	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-166	0.77	C128	0.043	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-167	0.18		0.022	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-168	4.4	B C153	0.043	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-169	0.017	J B q	0.022	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-170	1.5		0.022	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-171	0.38	C	0.043	0.00066	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-172	0.25		0.022	0.00065	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-173	0.38	C171	0.043	0.00066	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-174	1.6		0.022	0.00061	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-175	0.055		0.022	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-176	0.17		0.022	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-177	0.88		0.022	0.00063	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-178	0.32		0.022	0.00064	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-179	0.67		0.022	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-180	3.3	C B	0.043	0.00050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-181	ND		0.022	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-182	0.011	J q	0.022	0.00057	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-183	1.0	C B	0.043	0.00058	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-184	ND		0.022	0.00048	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-185	1.0	B C183	0.043	0.00058	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-186	ND		0.022	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-187	1.9	B	0.022	0.00055	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-188	ND		0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-189	0.053		0.022	0.0024	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-190	0.29		0.022	0.00043	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-191	0.063		0.022	0.00045	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-192	ND		0.022	0.00050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-193	3.3	C180 B	0.043	0.00050	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-194	0.83		0.022	0.0020	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-195	0.33		0.022	0.0022	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-196	0.35		0.022	0.00053	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	0.024	q	0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-198	0.95	C	0.043	0.00054	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-199	0.95	C198	0.043	0.00054	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-200	0.094		0.022	0.00036	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-201	0.092		0.022	0.00037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-202	0.19		0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-203	0.58		0.022	0.00048	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-204	ND		0.022	0.00041	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-205	0.044		0.022	0.0017	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-206	0.66		0.022	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-207	0.060		0.022	0.0018	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-208	0.20		0.022	0.0018	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
PCB-209	0.37		0.022	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Monochlorobiphenyls	0.26		0.022	0.00072	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Dichlorobiphenyls	3.9	B q	0.043	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Trichlorobiphenyls	19	B	0.043	0.0019	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Tetrachlorobiphenyls	27	B q	0.087	0.0037	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Pentachlorobiphenyls	27	B q	0.13	0.0018	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Hexachlorobiphenyls	24	B q	0.087	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Heptachlorobiphenyls	12	B q	0.043	0.00064	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Octachlorobiphenyls	3.5	q	0.043	0.00085	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Total Nonachlorobiphenyls	0.92		0.022	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2
Polychlorinated biphenyls, Total	120	B q	0.13	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 15:46	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*61*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-3L	*58*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-4L	*69*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-15L	*76*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-19L	*85*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-37L	*77*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-54L	*90*		*5 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-77L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-81L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-104L	*79*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-105L	*85*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-114L	*84*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-118L	*84*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-123L	*83*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-126L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-155L	*86*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-156L	*81*	*C*	*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-157L	*81*	*C156*	*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-167L	*83*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-169L	*87*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-170L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-188L	*86*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-189L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-202L	*94*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*
PCB-205L	*70*		*10 - 145*	*10/03/20 06:25*	*10/21/20 15:46*	*2*

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0300N
Date Collected: 09/17/20 11:55
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-1
Matrix: Sediment
Percent Solids: 44.5

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-206L	76		10 - 145	10/03/20 06:25	10/21/20 15:46	2
PCB-208L	80		10 - 145	10/03/20 06:25	10/21/20 15:46	2
PCB-209L	77		10 - 145	10/03/20 06:25	10/21/20 15:46	2

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	89		5 - 145	10/03/20 06:25	10/21/20 15:46	2
PCB-111L	94		10 - 145	10/03/20 06:25	10/21/20 15:46	2
PCB-178L	98		10 - 145	10/03/20 06:25	10/21/20 15:46	2

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	55.5		0.1	0.1	%			09/29/20 21:22	1
Bulk Density	1.4		0.010	0.010	g/cc			09/30/20 18:28	1
Total Organic Carbon - Duplicates	31000		2200	1700	mg/Kg	☼		09/29/20 16:30	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-2
Matrix: Sediment
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.091		0.023	0.00065	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-2	0.023		0.023	0.00078	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-3	0.054		0.023	0.00088	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-4	0.87		0.045	0.0034	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-5	0.023		0.023	0.0029	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-6	0.27		0.023	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-7	0.051	q	0.023	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-8	1.2		0.045	0.0023	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-9	0.076		0.023	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-10	0.041	q	0.023	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-11	0.39	B	0.045	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-12	0.13	C	0.045	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-13	0.13	C12	0.045	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-14	ND		0.023	0.0022	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-15	1.0		0.023	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-16	0.82		0.023	0.00075	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-17	1.3		0.023	0.00067	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-18	2.2	C B	0.045	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-19	0.48		0.023	0.00082	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-20	4.2	C B	0.045	0.0041	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-21	1.7	C B	0.045	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-22	1.3		0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-23	0.0044	J	0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-24	0.052		0.023	0.00056	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-25	0.43		0.023	0.0038	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-26	0.75	C	0.045	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-27	0.35		0.023	0.00049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-28	4.2	B C20	0.045	0.0041	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-29	0.75	C26	0.045	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-30	2.2	C18 B	0.045	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-31	3.2	B	0.045	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-32	1.1		0.023	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-33	1.7	B C21	0.045	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-34	0.019	J	0.023	0.0043	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-35	0.064		0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-36	ND		0.023	0.0040	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-37	1.1		0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-38	ND		0.023	0.0043	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-39	0.019	J	0.023	0.0039	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-40	2.3	C	0.068	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-41	2.3	C40	0.068	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-42	1.1		0.023	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-43	0.18	C	0.045	0.0062	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-44	4.5	C B	0.068	0.0058	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-45	0.89	C	0.045	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-46	0.27		0.023	0.0084	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-47	4.5	B C44	0.068	0.0058	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-48	0.77		0.023	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-49	2.9	C	0.045	0.0054	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-2
Matrix: Sediment
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	0.80	C	0.045	0.0064	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-51	0.89	C45	0.045	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-52	6.0	B	0.023	0.0065	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-53	0.80	C50	0.045	0.0064	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-54	0.027		0.023	0.00033	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-55	0.099		0.023	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-56	1.5		0.023	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-57	0.025		0.023	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-58	0.016	J q	0.023	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-59	0.40	C	0.068	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-60	0.78		0.023	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-61	6.3	C B	0.091	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-62	0.40	C59	0.068	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-63	0.16		0.023	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-64	1.8		0.023	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-65	4.5	B C44	0.068	0.0058	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-66	3.7		0.023	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-67	0.10		0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-68	0.024	q	0.023	0.0043	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-69	2.9	C49	0.045	0.0054	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-70	6.3	C61 B	0.091	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-71	2.3	C40	0.068	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-72	0.044		0.023	0.0048	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-73	0.18	C43	0.045	0.0062	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-74	6.3	C61 B	0.091	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-75	0.40	C59	0.068	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-76	6.3	C61 B	0.091	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-77	0.39		0.023	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-78	ND		0.023	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-79	0.047		0.023	0.0043	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-80	ND		0.023	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-81	0.015	J	0.023	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-82	1.1		0.023	0.00092	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-83	4.8	C B	0.045	0.00084	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-84	2.0		0.023	0.00093	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-85	1.7	C B	0.068	0.00068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-86	5.6	C B	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-87	5.6	B C86	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-88	1.2	C	0.045	0.00083	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-89	0.094		0.023	0.00090	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-90	8.1	C B	0.068	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-91	1.2	C88	0.045	0.00083	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-92	1.4		0.023	0.00079	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-93	0.12	C q	0.045	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-94	0.050	q	0.023	0.00090	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-95	6.4	B	0.023	0.00087	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-96	0.062	q	0.023	0.00068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-97	5.6	B C86	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-98	0.27	C	0.045	0.00078	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-2
Matrix: Sediment
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	4.8	C83 B	0.045	0.00084	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-100	0.12	C93 q	0.045	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-101	8.1	B C90	0.068	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-102	0.27	C98	0.045	0.00078	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-103	0.060		0.023	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-104	ND		0.023	0.00061	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-105	3.9		0.023	0.0066	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-106	ND		0.023	0.0068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-107	0.63		0.023	0.0072	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-108	0.36	C	0.045	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-109	5.6	B C86	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-110	10	C B	0.045	0.00058	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-111	ND		0.023	0.00056	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-112	0.027		0.023	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-113	8.1	B C90	0.068	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-114	0.20		0.023	0.0063	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-115	10	B C110	0.045	0.00058	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-116	1.7	C85 B	0.068	0.00068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-117	1.7	C85 B	0.068	0.00068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-118	8.4	B	0.023	0.0063	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-119	5.6	B C86	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-120	0.022	J	0.023	0.00057	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-121	ND		0.023	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-122	0.15	q	0.023	0.0078	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-123	0.20		0.023	0.0067	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-124	0.36	C108	0.045	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-125	5.6	B C86	0.14	0.00069	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-126	0.024		0.023	0.0072	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-127	0.0086	J q	0.023	0.0067	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-128	1.8	C	0.045	0.0092	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-129	12	C B	0.091	0.0095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-130	0.71		0.023	0.013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-131	0.16		0.023	0.013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-132	3.9		0.023	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-133	0.14		0.023	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-134	0.65	C	0.045	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-135	3.1	C	0.045	0.00095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-136	1.1		0.023	0.00068	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-137	0.57		0.023	0.011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-138	12	B C129	0.091	0.0095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-139	0.20	C	0.045	0.011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-140	0.20	C139	0.045	0.011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-141	2.2		0.023	0.011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-142	ND		0.023	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-143	0.65	C134	0.045	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-144	0.37		0.023	0.00086	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-145	0.0053	J q	0.023	0.00065	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-146	1.5		0.023	0.010	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-147	9.6	C B	0.045	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-2
Matrix: Sediment
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.0096	J	0.023	0.00091	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-149	9.6	B C147	0.045	0.012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-150	0.012	J	0.023	0.00062	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-151	3.1	C135	0.045	0.00095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-152	0.0069	J q	0.023	0.00067	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-153	8.9	C B	0.045	0.0083	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-154	0.095		0.023	0.00074	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-155	ND		0.023	0.00062	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-156	1.3	C	0.045	0.0097	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-157	1.3	C156	0.045	0.0097	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-158	1.2		0.023	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-159	0.076		0.023	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-160	12	B C129	0.091	0.0095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-161	ND		0.023	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-162	0.025	q	0.023	0.0078	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-163	12	B C129	0.091	0.0095	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-164	0.81		0.023	0.0084	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-165	ND		0.023	0.0090	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-166	1.8	C128	0.045	0.0092	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-167	0.40		0.023	0.0061	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-168	8.9	B C153	0.045	0.0083	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-169	0.026	B q	0.023	0.0064	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-170	2.6		0.023	0.0019	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-171	0.74	C	0.045	0.0017	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-172	0.42		0.023	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-173	0.74	C171	0.045	0.0017	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-174	2.6		0.023	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-175	0.095		0.023	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-176	0.30		0.023	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-177	1.4		0.023	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-178	0.54		0.023	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-179	1.1		0.023	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-180	5.2	C B	0.045	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-181	0.028		0.023	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-182	0.010	J q	0.023	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-183	1.7	C B	0.045	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-184	ND		0.023	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-185	1.7	B C183	0.045	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-186	ND		0.023	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-187	3.2	B	0.023	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-188	ND		0.023	0.0010	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-189	0.090		0.023	0.0038	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-190	0.51		0.023	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-191	0.11		0.023	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-192	ND		0.023	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-193	5.2	C180 B	0.045	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-194	1.4		0.023	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-195	0.54		0.023	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-196	0.57		0.023	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2

Client Sample ID: STS0200N
Lab Sample ID: 180-111218-2
Date Collected: 09/17/20 12:20
Matrix: Sediment
Date Received: 09/19/20 11:00
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	**0.042**		0.023	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-198	**1.5**	**C**	0.045	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-199	**1.5**	**C198**	0.045	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-200	**0.14**		0.023	0.0010	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-201	**0.15**		0.023	0.0010	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-202	**0.30**		0.023	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-203	**0.93**		0.023	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-204	ND		0.023	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-205	**0.071**		0.023	0.0038	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-206	**1.1**		0.023	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-207	**0.10**		0.023	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-208	**0.32**		0.023	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
PCB-209	**0.57**		0.023	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Monochlorobiphenyls	**0.17**		0.023	0.00077	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Dichlorobiphenyls	**4.1**	**B q**	0.045	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Trichlorobiphenyls	**19**	**B**	0.045	0.0029	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Tetrachlorobiphenyls	**35**	**B q**	0.091	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Pentachlorobiphenyls	**57**	**B q**	0.14	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Hexachlorobiphenyls	**51**	**B q**	0.091	0.0073	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Heptachlorobiphenyls	**21**	**B q**	0.045	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Octachlorobiphenyls	**5.6**		0.045	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Total Nonachlorobiphenyls	**1.5**		0.023	0.0038	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2
Polychlorinated biphenyls, Total	**190**	**B q**	0.14	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 16:47	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*63*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-3L	*59*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-4L	*74*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-15L	*77*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-19L	*87*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-37L	*80*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-54L	*88*		*5 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-77L	*80*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-81L	*78*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-104L	*87*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-105L	*88*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-114L	*89*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-118L	*88*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-123L	*86*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-126L	*84*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-155L	*89*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-156L	*83*	*C*	*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-157L	*83*	*C156*	*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-167L	*86*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-169L	*88*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-170L	*84*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-188L	*97*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-189L	*85*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-202L	*101*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*
PCB-205L	*73*		*10 - 145*	*10/03/20 06:25*	*10/21/20 16:47*	*2*

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-2
Matrix: Sediment
Percent Solids: 43.7

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-206L	80		10 - 145	10/03/20 06:25	10/21/20 16:47	2
PCB-208L	80		10 - 145	10/03/20 06:25	10/21/20 16:47	2
PCB-209L	83		10 - 145	10/03/20 06:25	10/21/20 16:47	2

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	91		5 - 145	10/03/20 06:25	10/21/20 16:47	2
PCB-111L	91		10 - 145	10/03/20 06:25	10/21/20 16:47	2
PCB-178L	103		10 - 145	10/03/20 06:25	10/21/20 16:47	2

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	56.3		0.1	0.1	%			09/29/20 21:22	1
Bulk Density	1.4		0.010	0.010	g/cc			09/30/20 18:30	1
Total Organic Carbon - Duplicates	38000		2300	1700	mg/Kg	☼		09/29/20 16:47	1

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.13		0.025	0.00084	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-2	0.033		0.025	0.00099	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-3	0.080		0.025	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-4	1.0		0.049	0.0036	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-5	0.024	J q	0.025	0.0029	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-6	0.39		0.025	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-7	0.072		0.025	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-8	1.5		0.049	0.0024	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-9	0.097		0.025	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-10	0.055		0.025	0.0029	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-11	0.34	B	0.049	0.0025	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-12	0.19	C	0.049	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-13	0.19	C12	0.049	0.0026	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-14	ND		0.025	0.0022	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-15	1.4		0.025	0.0028	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-16	1.2		0.025	0.00075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-17	1.8		0.025	0.00067	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-18	3.1	C B	0.049	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-19	0.64		0.025	0.00082	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-20	7.5	C B	0.049	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-21	2.5	C B	0.049	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-22	2.3		0.025	0.0052	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-23	0.0052	J q	0.025	0.0052	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-24	0.077		0.025	0.00057	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-25	0.75		0.025	0.0047	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-26	1.3	C	0.049	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-27	0.47		0.025	0.00049	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-28	7.5	B C20	0.049	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-29	1.3	C26	0.049	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-30	3.1	C18 B	0.049	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-31	5.2	B	0.049	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-32	1.8		0.025	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-33	2.5	B C21	0.049	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-34	0.037		0.025	0.0054	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-35	0.11		0.025	0.0053	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-36	ND		0.025	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-37	2.2		0.025	0.0052	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-38	ND		0.025	0.0055	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-39	0.033		0.025	0.0049	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-40	3.9	C	0.074	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-41	3.9	C40	0.074	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-42	1.9		0.025	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-43	0.26	C	0.049	0.010	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-44	7.4	C B	0.074	0.0096	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-45	1.6	C	0.049	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-46	0.46		0.025	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-47	7.4	B C44	0.074	0.0096	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-48	1.3		0.025	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-49	4.7	C	0.049	0.0088	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	1.3	C	0.049	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-51	1.6	C45	0.049	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-52	9.0	B	0.025	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-53	1.3	C50	0.049	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-54	0.055		0.025	0.00047	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-55	0.14		0.025	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-56	2.7		0.025	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-57	0.055		0.025	0.0080	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-58	0.028		0.025	0.0081	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-59	0.68	C	0.074	0.0077	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-60	1.4		0.025	0.0080	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-61	10	C B	0.099	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-62	0.68	C59	0.074	0.0077	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-63	0.26		0.025	0.0073	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-64	3.0		0.025	0.0072	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-65	7.4	B C44	0.074	0.0096	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-66	6.4		0.025	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-67	0.20		0.025	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-68	0.056		0.025	0.0071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-69	4.7	C49	0.049	0.0088	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-70	10	C61 B	0.099	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-71	3.9	C40	0.074	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-72	0.084		0.025	0.0078	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-73	0.26	C43	0.049	0.010	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-74	10	C61 B	0.099	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-75	0.68	C59	0.074	0.0077	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-76	10	C61 B	0.099	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-77	0.69		0.025	0.0075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-78	ND		0.025	0.0081	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-79	0.065		0.025	0.0070	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-80	ND		0.025	0.0069	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-81	0.026		0.025	0.0076	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-82	1.2		0.025	0.00095	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-83	5.6	C B	0.049	0.00086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-84	2.4		0.025	0.00096	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-85	1.8	C B	0.074	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-86	6.3	C B	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-87	6.3	B C86	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-88	1.5	C	0.049	0.00086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-89	0.12		0.025	0.00093	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-90	10	C B	0.074	0.00072	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-91	1.5	C88	0.049	0.00086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-92	1.9		0.025	0.00081	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-93	0.22	C	0.049	0.00082	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-94	0.093		0.025	0.00093	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-95	8.6	B	0.025	0.00090	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-96	0.10		0.025	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-97	6.3	B C86	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-98	0.37	C	0.049	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	5.6	C83 B	0.049	0.00086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-100	0.22	C93	0.049	0.00082	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-101	10	B C90	0.074	0.00072	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-102	0.37	C98	0.049	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-103	0.12		0.025	0.00082	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-104	ND		0.025	0.00062	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-105	3.5		0.025	0.0083	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-106	ND		0.025	0.0086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-107	0.72		0.025	0.0092	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-108	0.37	C	0.049	0.0088	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-109	6.3	B C86	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-110	11	C B	0.049	0.00060	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-111	ND		0.025	0.00058	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-112	0.040		0.025	0.00061	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-113	10	B C90	0.074	0.00072	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-114	0.20		0.025	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-115	11	B C110	0.049	0.00060	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-116	1.8	C85 B	0.074	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-117	1.8	C85 B	0.074	0.00070	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-118	8.4	B	0.025	0.0079	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-119	6.3	B C86	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-120	0.032		0.025	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-121	ND		0.025	0.00060	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-122	0.16		0.025	0.010	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-123	0.16	q	0.025	0.0085	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-124	0.37	C108	0.049	0.0088	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-125	6.3	B C86	0.15	0.00071	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-126	0.034		0.025	0.0097	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-127	ND		0.025	0.0086	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-128	2.1	C	0.049	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-129	16	C B	0.099	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-130	0.92		0.025	0.019	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-131	0.18		0.025	0.019	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-132	5.2		0.025	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-133	0.26		0.025	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-134	0.87	C	0.049	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-135	5.3	C	0.049	0.00083	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-136	1.8		0.025	0.00060	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-137	0.56		0.025	0.016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-138	16	B C129	0.099	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-139	0.23	C	0.049	0.016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-140	0.23	C139	0.049	0.016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-141	3.5		0.025	0.017	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-142	ND		0.025	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-143	0.87	C134	0.049	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-144	0.63		0.025	0.00075	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-145	0.0053	J	0.025	0.00057	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-146	2.6		0.025	0.016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-147	16	C B	0.049	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.029		0.025	0.00080	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-149	16	B C147	0.049	0.018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-150	0.026		0.025	0.00055	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-151	5.3	C135	0.049	0.00083	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-152	0.012	J	0.025	0.00059	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-153	14	C B	0.049	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-154	0.19		0.025	0.00065	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-155	ND		0.025	0.00055	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-156	1.5	C	0.049	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-157	1.5	C156	0.049	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-158	1.6		0.025	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-159	0.16		0.025	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-160	16	B C129	0.099	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-161	0.016	J	0.025	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-162	0.044		0.025	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-163	16	B C129	0.099	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-164	1.1		0.025	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-165	ND		0.025	0.013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-166	2.1	C128	0.049	0.014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-167	0.52		0.025	0.0090	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-168	14	B C153	0.049	0.012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-169	0.061	B q	0.025	0.0096	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-170	5.1		0.025	0.0018	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-171	1.4	C	0.049	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-172	0.85		0.025	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-173	1.4	C171	0.049	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-174	5.3		0.025	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-175	0.20		0.025	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-176	0.64		0.025	0.0010	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-177	2.9		0.025	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-178	1.1		0.025	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-179	2.5		0.025	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-180	11	C B	0.049	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-181	0.032		0.025	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-182	0.043		0.025	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-183	3.6	C B	0.049	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-184	ND		0.025	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-185	3.6	B C183	0.049	0.0013	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-186	ND		0.025	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-187	6.5	B	0.025	0.0012	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-188	ND		0.025	0.00087	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-189	0.17		0.025	0.0046	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-190	0.89		0.025	0.00097	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-191	0.21		0.025	0.0010	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-192	ND		0.025	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-193	11	C180 B	0.049	0.0011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-194	2.9		0.025	0.0060	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-195	1.1		0.025	0.0065	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-196	1.2		0.025	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	0.096		0.025	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-198	2.9	C	0.049	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-199	2.9	C198	0.049	0.0021	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-200	0.32		0.025	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-201	0.32		0.025	0.0015	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-202	0.57		0.025	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-203	1.8		0.025	0.0019	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-204	ND		0.025	0.0016	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-205	0.15		0.025	0.0050	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-206	1.4		0.025	0.0068	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-207	0.14		0.025	0.0044	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-208	0.37		0.025	0.0042	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
PCB-209	0.56		0.025	0.0023	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Monochlorobiphenyls	0.24		0.025	0.00098	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Dichlorobiphenyls	5.1	B q	0.049	0.0027	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Trichlorobiphenyls	31	B q	0.049	0.0036	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Tetrachlorobiphenyls	58	B	0.099	0.0084	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Pentachlorobiphenyls	65	B q	0.15	0.0033	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Hexachlorobiphenyls	75	B q	0.099	0.011	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Heptachlorobiphenyls	42	B	0.049	0.0014	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Octachlorobiphenyls	11		0.049	0.0029	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Total Nonachlorobiphenyls	1.9		0.025	0.0051	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2
Polychlorinated biphenyls, Total	290	B q	0.15	0.0045	ng/g	☼	10/03/20 06:25	10/21/20 19:54	2

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*62*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-3L	*62*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-4L	*76*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-15L	*80*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-19L	*86*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-37L	*79*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-54L	*84*		*5 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-77L	*79*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-81L	*79*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-104L	*83*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-105L	*88*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-114L	*90*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-118L	*88*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-123L	*87*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-126L	*80*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-155L	*87*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-156L	*79*	*C*	*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-157L	*79*	*C156*	*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-167L	*83*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-169L	*83*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-170L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-188L	*97*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-189L	*85*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-202L	*100*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*
PCB-205L	*72*		*10 - 145*	*10/03/20 06:25*	*10/21/20 19:54*	*2*

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0100N
Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-3
Matrix: Sediment
Percent Solids: 40.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-206L	77		10 - 145	10/03/20 06:25	10/21/20 19:54	2
PCB-208L	77		10 - 145	10/03/20 06:25	10/21/20 19:54	2
PCB-209L	80		10 - 145	10/03/20 06:25	10/21/20 19:54	2

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	92		5 - 145	10/03/20 06:25	10/21/20 19:54	2
PCB-111L	93		10 - 145	10/03/20 06:25	10/21/20 19:54	2
PCB-178L	104		10 - 145	10/03/20 06:25	10/21/20 19:54	2

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	59.8		0.1	0.1	%			09/29/20 21:22	1
Bulk Density	1.4		0.010	0.010	g/cc			09/30/20 18:32	1
Total Organic Carbon - Duplicates	37000		2500	1900	mg/Kg	☼		09/29/20 17:43	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: SEE0101N
Date Collected: 09/17/20 13:15
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-4
Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bulk Density	1.7		0.010	0.010	g/cc			09/30/20 18:33	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size 0.375 inch - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size #4 - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size #10 - Percent Finer	100.0				% Passing			09/30/20 20:32	1
Sieve Size #20 - Percent Finer	99.5				% Passing			09/30/20 20:32	1
Sieve Size #40 - Percent Finer	97.7				% Passing			09/30/20 20:32	1
Sieve Size #60 - Percent Finer	96.0				% Passing			09/30/20 20:32	1
Sieve Size #80 - Percent Finer	95.2				% Passing			09/30/20 20:32	1
Sieve Size #100 - Percent Finer	94.1				% Passing			09/30/20 20:32	1
Sieve Size #200 - Percent Finer	91.0				% Passing			09/30/20 20:32	1
Hydrometer Reading 1 - Percent Finer	71.7				% Passing			09/30/20 20:32	1
Hydrometer Reading 2 - Percent Finer	61.3				% Passing			09/30/20 20:32	1
Hydrometer Reading 3 - Percent Finer	52.1				% Passing			09/30/20 20:32	1
Hydrometer Reading 4 - Percent Finer	45.2				% Passing			09/30/20 20:32	1
Hydrometer Reading 5 - Percent Finer	38.3				% Passing			09/30/20 20:32	1
Hydrometer Reading 6 - Percent Finer	29.0				% Passing			09/30/20 20:32	1
Hydrometer Reading 7 - Percent Finer	21.0				% Passing			09/30/20 20:32	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: SEE0201N
Date Collected: 09/17/20 13:45
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-5
Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bulk Density	1.5		0.010	0.010	g/cc			09/30/20 18:35	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size 0.375 inch - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size #4 - Percent Finer	100.0				% Passing			09/30/20 20:34	1
Sieve Size #10 - Percent Finer	98.5				% Passing			09/30/20 20:34	1
Sieve Size #20 - Percent Finer	96.7				% Passing			09/30/20 20:34	1
Sieve Size #40 - Percent Finer	93.9				% Passing			09/30/20 20:34	1
Sieve Size #60 - Percent Finer	90.8				% Passing			09/30/20 20:34	1
Sieve Size #80 - Percent Finer	88.4				% Passing			09/30/20 20:34	1
Sieve Size #100 - Percent Finer	86.7				% Passing			09/30/20 20:34	1
Sieve Size #200 - Percent Finer	82.4				% Passing			09/30/20 20:34	1
Hydrometer Reading 1 - Percent Finer	78.3				% Passing			09/30/20 20:34	1
Hydrometer Reading 2 - Percent Finer	71.8				% Passing			09/30/20 20:34	1
Hydrometer Reading 3 - Percent Finer	61.4				% Passing			09/30/20 20:34	1
Hydrometer Reading 4 - Percent Finer	52.3				% Passing			09/30/20 20:34	1
Hydrometer Reading 5 - Percent Finer	41.9				% Passing			09/30/20 20:34	1
Hydrometer Reading 6 - Percent Finer	31.5				% Passing			09/30/20 20:34	1
Hydrometer Reading 7 - Percent Finer	19.7				% Passing			09/30/20 20:34	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: SEE0301N
Date Collected: 09/17/20 14:02
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-6
Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Bulk Density	2.1		0.010	0.010	g/cc			09/30/20 18:36	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size 0.375 inch - Percent Finer	100.0				% Passing			09/30/20 20:36	1
Sieve Size #4 - Percent Finer	80.5				% Passing			09/30/20 20:36	1
Sieve Size #10 - Percent Finer	74.9				% Passing			09/30/20 20:36	1
Sieve Size #20 - Percent Finer	69.4				% Passing			09/30/20 20:36	1
Sieve Size #40 - Percent Finer	58.2				% Passing			09/30/20 20:36	1
Sieve Size #60 - Percent Finer	48.5				% Passing			09/30/20 20:36	1
Sieve Size #80 - Percent Finer	44.6				% Passing			09/30/20 20:36	1
Sieve Size #100 - Percent Finer	42.1				% Passing			09/30/20 20:36	1
Sieve Size #200 - Percent Finer	36.4				% Passing			09/30/20 20:36	1
Hydrometer Reading 1 - Percent Finer	33.2				% Passing			09/30/20 20:36	1
Hydrometer Reading 2 - Percent Finer	30.1				% Passing			09/30/20 20:36	1
Hydrometer Reading 3 - Percent Finer	24.3				% Passing			09/30/20 20:36	1
Hydrometer Reading 4 - Percent Finer	21.1				% Passing			09/30/20 20:36	1
Hydrometer Reading 5 - Percent Finer	18.0				% Passing			09/30/20 20:36	1
Hydrometer Reading 6 - Percent Finer	13.5				% Passing			09/30/20 20:36	1
Hydrometer Reading 7 - Percent Finer	9.7				% Passing			09/30/20 20:36	1

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: STS0300N
Lab Sample ID: 180-111218-7
Date Collected: 09/17/20 11:55
Matrix: Solid
Date Received: 09/19/20 11:00

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**6.96**		0.01	0.01	%			10/21/20 13:26	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			10/21/20 13:26	1
Fine Sand (0.125 to 0.25mm)	**17.67**		0.01	0.01	%			10/21/20 13:26	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			10/21/20 13:26	1
Medium Sand (0.25 to 0.5 mm)	**1.86**		0.01	0.01	%			10/21/20 13:26	1
Silt (0.00391 to 0.0625mm)	**56.12**		0.01	0.01	%			10/21/20 13:26	1
Total Silt and Clay (0 to 0.0626mm)	**63.08**		0.01	0.01	%			10/21/20 13:26	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			10/21/20 13:26	1
Very Fine Sand (0.0625 to 0.125 mm)	**17.39**		0.01	0.01	%			10/21/20 13:26	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0200N
Date Collected: 09/17/20 12:20
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-8
Matrix: Solid

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**7.42**		0.01	0.01	%			10/21/20 13:30	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			10/21/20 13:30	1
Fine Sand (0.125 to 0.25mm)	**12.41**		0.01	0.01	%			10/21/20 13:30	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			10/21/20 13:30	1
Medium Sand (0.25 to 0.5 mm)	**2.22**		0.01	0.01	%			10/21/20 13:30	1
Silt (0.00391 to 0.0625mm)	**61.97**		0.01	0.01	%			10/21/20 13:30	1
Total Silt and Clay (0 to 0.0626mm)	**69.39**		0.01	0.01	%			10/21/20 13:30	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			10/21/20 13:30	1
Very Fine Sand (0.0625 to 0.125 mm)	**15.98**		0.01	0.01	%			10/21/20 13:30	1

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-111218-1

Client Sample ID: STS0100N

Date Collected: 09/17/20 12:35
Date Received: 09/19/20 11:00

Lab Sample ID: 180-111218-9

Matrix: Solid

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**9.48**		0.01	0.01	%			10/21/20 13:40	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			10/21/20 13:40	1
Fine Sand (0.125 to 0.25mm)	**7.30**		0.01	0.01	%			10/21/20 13:40	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			10/21/20 13:40	1
Medium Sand (0.25 to 0.5 mm)	ND		0.01	0.01	%			10/21/20 13:40	1
Silt (0.00391 to 0.0625mm)	**70.72**		0.01	0.01	%			10/21/20 13:40	1
Total Silt and Clay (0 to 0.0626mm)	**80.20**		0.01	0.01	%			10/21/20 13:40	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			10/21/20 13:40	1
Very Fine Sand (0.0625 to 0.125 mm)	**12.50**		0.01	0.01	%			10/21/20 13:40	1

PARTICLE SIZE SUMMARY

(ASTM D422 / D4464M)


AECOM

Date Sampled:	09/17/20
Date Received:	09/22/20
Work Order No:	180-111218
Date Analyzed:	10/21/20
Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
STS0300N		Very Fine Sand	0.066

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	1.86	17.67	17.39	56.12	6.96	63.08



V 3.0

PARTICLE SIZE SUMMARY

(ASTM D422 / D4464M)


AECOM

Date Sampled:	09/17/20
Date Received:	09/22/20
Work Order No:	180-111218
Date Analyzed:	10/21/20
Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
STS0200N		Silt	0.057

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	2.22	12.41	15.98	61.97	7.42	69.39



V 3.0

PARTICLE SIZE SUMMARY


(ASTM D422 / D4464M)

AECOM		Date Sampled:	09/17/20
		Date Received:	09/22/20
		Work Order No:	180-111218
		Date Analyzed:	10/21/20
		Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
STS0100N		Silt	0.039

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	0.00	7.30	12.50	70.72	9.48	80.20



V 3.0


Particle Size of Soils by ASTM D422

Sample ID:	SEE0101N	**Percent Solids:**	54.5%	**Date Received:**	9/19/2020
Lab ID:	180-111218-A-4	**Specific Gravity:**	2.650	**Start Date:**	9/30/2020
				End Date:	10/7/2020

Shape (> #10): na

Non-soil material: na

Hardness (> #10): na



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	100.0	0.0
#4	4750	100.0	0.0
#10	2000	100.0	0.0
#20	850	99.5	0.5
#40	425	97.7	1.8
#60	250	96.0	1.7
#80	180	95.2	0.8
#100	150	94.1	1.1
#200	75	91.0	3.1
Hyd1	25.9	71.7	19.3
Hyd2	17.7	61.3	10.4
Hyd3	10.8	52.1	9.2
Hyd4	7.7	45.2	6.9
Hyd5	5.8	38.3	6.9
Hyd6	2.9	29.0	9.3
Hyd7	1.3	21.0	8.0

Soil Classification	Percent of sample
Gravel	0.0
Sand	9.0
Coarse Sand	0.0
Medium Sand	2.3
Fine Sand	6.7
Silt	52.7
Clay	38.3


Particle Size of Soils by ASTM D422

Sample ID:	SEE0201N	**Percent Solids:**	53.7%	**Date Received:**	9/19/2020
Lab ID:	180-111218-A-5	**Specific Gravity:**	2.650	**Start Date:**	9/30/2020
				End Date:	10/7/2020

Shape (> #10): na

Non-soil material: plant

Hardness (> #10): na



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	100.0	0.0
#4	4750	100.0	0.0
#10	2000	98.5	1.5
#20	850	96.7	1.8
#40	425	93.9	2.8
#60	250	90.8	3.1
#80	180	88.4	2.4
#100	150	86.7	1.7
#200	75	82.4	4.3
Hyd1	26.4	78.3	4.1
Hyd2	17.4	71.8	6.5
Hyd3	10.7	61.4	10.4
Hyd4	7.9	52.3	9.1
Hyd5	5.7	41.9	10.4
Hyd6	3	31.5	10.4
Hyd7	1.3	19.7	11.8

Soil Classification	Percent of sample
Gravel	0.0
Sand	17.6
Coarse Sand	1.5
Medium Sand	4.6
Fine Sand	11.5
Silt	40.5
Clay	41.9


Particle Size of Soils by ASTM D422

Sample ID:	SEE0301N	**Percent Solids:**	74.2%	**Date Received:**	9/19/2020
Lab ID:	180-111218-A-6	**Specific Gravity:**	2.650	**Start Date:**	9/30/2020
				End Date:	10/7/2020

Shape (> #10): angular

Non-soil material: plant, glass

Hardness (> #10): hard



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	100.0	0.0
#4	4750	80.5	19.5
#10	2000	74.9	5.6
#20	850	69.4	5.5
#40	425	58.2	11.2
#60	250	48.5	9.7
#80	180	44.6	3.9
#100	150	42.1	2.5
#200	75	36.4	5.7
Hyd1	28.2	33.2	3.2
Hyd2	18.5	30.1	3.1
Hyd3	11.3	24.3	5.8
Hyd4	8.3	21.1	3.2
Hyd5	6.2	18.0	3.1
Hyd6	3.1	13.5	4.5
Hyd7	1.3	9.7	3.8

Soil Classification	Percent of sample
Gravel	19.5
Sand	44.1
Coarse Sand	5.6
Medium Sand	16.7
Fine Sand	21.8
Silt	18.4
Clay	18.0

Sediment Grain Size - D422

Client	
Client Sample ID	SEE0101N
Lab Sample ID	180-111218-A-4

Date Received	9/19/2020
Start Date	09/30/2020 20:32
End Date	10/07/2020 13:20

Dry Weight Determination

Tin Weight	0.98	g
Wet Sample + Tin	23.23	g
Dry Sample + Tin	13.11	g
% Moisture	45.48	%

Non-soil material:	na
Shape (> #10):	na
Hardness (> #10):	na

Date/Time in oven	09/30/2020 20:34
Date/Time out of oven	10/01/2020 16:05

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	47.82	175.43	127.61
Sample Weight (Oven Dried)			69.6

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			0
Sample <#10			69.6
% Passing #10			54.5

Hydrometer Data	
Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500			0.00	g	100.0	Gravel	
#4	4750			0.00	g	100.0	Gravel	
#10	2000			0.00	g	100.0	Sand	Coarse
#20	850	373.62	373.96	0.34	g	99.5	Sand	Medium
#40	425	361.96	363.21	1.25	g	97.7	Sand	Medium
#60	250	351.98	353.19	1.21	g	96.0	Sand	Fine
#80	180	318.91	319.45	0.54	g	95.2	Sand	Fine
#100	150	328.17	328.92	0.75	g	94.1	Sand	Fine
#200	75	314.14	316.27	2.13	g	91.0	Sand	Fine
				0.00	g	91.0		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	69.6

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0340	20.5	25.9	71.7	Silt	
5	5	1.0295	20.5	17.7	61.3	Silt	
15	15	1.0255	20.5	10.8	52.1	Silt	
30	32	1.0225	20.5	7.7	45.2	Silt	
60	60	1.0195	20.5	5.8	38.3	Silt	
250	259	1.0155	20.5	2.9	29	Clay	
1440	1406	1.0120	20.5	1.3	21	Clay	

Sediment Grain Size - D422

Client	
Client Sample ID	SEE0201N
Lab Sample ID	180-111218-A-5

Date Received	9/19/2020
Start Date	09/30/2020 20:34
End Date	10/07/2020 13:28

Dry Weight Determination

Tin Weight	0.99	g
Wet Sample + Tin	26.17	g
Dry Sample + Tin	14.51	g
% Moisture	46.31	%

Non-soil material:	plant
Shape (> #10):	na
Hardness (> #10):	na

Date/Time in oven	09/30/2020 20:36
Date/Time out of oven	10/01/2020 16:05

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	44.05	158.97	114.92
Sample Weight (Oven Dried)			61.7

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			0.91
Sample <#10			60.8
% Passing #10			52.9

Hydrometer Data

Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500			0.00	g	100.0	Gravel	
#4	4750			0.00	g	100.0	Gravel	
#10	2000	462.61	463.52	0.91	g	98.5	Sand	Coarse
#20	850	378.33	379.43	1.10	g	96.7	Sand	Medium
#40	425	366.26	367.96	1.70	g	93.9	Sand	Medium
#60	250	347.91	349.81	1.90	g	90.8	Sand	Fine
#80	180	337.55	339.05	1.50	g	88.4	Sand	Fine
#100	150	327.89	328.95	1.06	g	86.7	Sand	Fine
#200	75	312.66	315.31	2.65	g	82.4	Sand	Fine
				0.00	g	82.4		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	61.7

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0330	20.5	26.4	78.3	Silt	
5	5	1.0305	20.5	17.4	71.8	Silt	
15	15	1.0265	20.5	10.7	61.4	Silt	
30	30	1.0230	20.5	7.9	52.3	Silt	
60	63	1.0190	20.5	5.7	41.9	Silt	
250	253	1.0150	20.5	3	31.5	Clay	
1440	1400	1.0105	20.5	1.3	19.7	Clay	

Sediment Grain Size - D422

Client	
Client Sample ID	SEE0301N
Lab Sample ID	180-111218-A-6

Date Received	9/19/2020
Start Date	09/30/2020 20:36
End Date	10/07/2020 13:32

Dry Weight Determination

Tin Weight	0.98	g
Wet Sample + Tin	27.61	g
Dry Sample + Tin	20.75	g
% Moisture	25.76	%

Non-soil material:	plant, glass
Shape (> #10):	angular
Hardness (> #10):	hard
Date/Time in oven	09/30/2020 20:38
Date/Time out of oven	10/01/2020 16:05

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	47.85	216.97	169.12
Sample Weight (Oven Dried)			126

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			31.5
Sample <#10			94.5
% Passing #10			55.9

Hydrometer Data

Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500			0.00	g	100.0	Gravel	
#4	4750	487.98	512.50	24.52	g	80.5	Gravel	
#10	2000	462.61	469.62	7.01	g	74.9	Sand	Coarse
#20	850	373.62	380.57	6.95	g	69.4	Sand	Medium
#40	425	361.96	376.03	14.07	g	58.2	Sand	Medium
#60	250	351.98	364.22	12.24	g	48.5	Sand	Fine
#80	180	318.91	323.78	4.87	g	44.6	Sand	Fine
#100	150	328.17	331.30	3.13	g	42.1	Sand	Fine
#200	75	314.14	321.36	7.22	g	36.4	Sand	Fine
				0.00	g	36.4		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	126

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0290	20.5	28.2	33.2	Silt	
5	5	1.0265	20.5	18.5	30.1	Silt	
15	15	1.0220	20.5	11.3	24.3	Silt	
30	30	1.0195	20.5	8.3	21.1	Silt	
60	57	1.0170	20.5	6.2	18	Silt	
250	247	1.0135	20.5	3.1	13.5	Clay	
1440	1394	1.0105	20.5	1.3	9.67	Clay	

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	ND		0.010	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-2	ND		0.010	0.00014	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-3	ND		0.010	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-4	ND		0.020	0.0016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-5	ND		0.010	0.0015	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-6	ND		0.010	0.0013	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-7	ND		0.010	0.0014	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-8	ND		0.020	0.0012	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-9	ND		0.010	0.0014	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-10	ND		0.010	0.0015	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-11	0.00361	J q	0.020	0.0013	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-12	ND	C	0.020	0.0013	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-13	ND	C12	0.020	0.0013	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-14	ND		0.010	0.0011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-15	ND		0.010	0.0017	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-16	ND		0.010	0.00030	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-17	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-18	0.000776	J C q	0.020	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-19	ND		0.010	0.00033	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-20	0.00121	J C	0.020	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-21	0.000452	J C	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-22	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-23	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-24	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-25	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-26	ND	C	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-27	ND		0.010	0.00020	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-28	0.00121	J C20	0.020	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-29	ND	C26	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-30	0.000776	J C18 q	0.020	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-31	0.000879	J q	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-32	ND		0.010	0.00019	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-33	0.000452	J C21	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-34	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-35	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-36	ND		0.010	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-37	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-38	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-39	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-40	ND	C	0.030	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-41	ND	C40	0.030	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-42	ND		0.010	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-43	ND	C	0.020	0.00034	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-44	0.00224	J C	0.030	0.00032	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-45	ND	C	0.020	0.00038	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-46	ND		0.010	0.00046	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-47	0.00224	J C44	0.030	0.00032	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-48	ND		0.010	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-49	ND	C	0.020	0.00029	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-50	ND	C	0.020	0.00035	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-51	ND	C45	0.020	0.00038	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-52	0.000685	J q	0.010	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-53	ND	C50	0.020	0.00035	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-54	ND		0.010	0.000053	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-55	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-56	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-57	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-58	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-59	ND	C	0.030	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-60	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-61	0.00125	J C	0.040	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-62	ND	C59	0.030	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-63	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-64	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-65	0.00224	J C44	0.030	0.00032	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-66	ND		0.010	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-67	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-68	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-69	ND	C49	0.020	0.00029	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-70	0.00125	J C61	0.040	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-71	ND	C40	0.030	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-72	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-73	ND	C43	0.020	0.00034	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-74	0.00125	J C61	0.040	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-75	ND	C59	0.030	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-76	0.00125	J C61	0.040	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-77	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-78	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-79	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-80	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-81	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-82	ND		0.010	0.000095	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-83	0.000666	J C	0.020	0.000086	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-84	ND		0.010	0.000096	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-85	0.000277	J C q	0.030	0.000070	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-86	0.000612	J C q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-87	0.000612	J C86 q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-88	ND	C	0.020	0.000086	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-89	ND		0.010	0.000093	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-90	0.000934	J C	0.030	0.000072	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-91	ND	C88	0.020	0.000086	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-92	ND		0.010	0.000081	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-93	ND	C	0.020	0.000082	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-94	ND		0.010	0.000093	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-95	0.000584	J q	0.010	0.000090	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-96	ND		0.010	0.000070	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-97	0.000612	J C86 q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-98	ND	C	0.020	0.000080	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-99	0.000666	J C83	0.020	0.000086	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-100	ND	C93	0.020	0.000082	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-101	0.000934	J C90	0.030	0.000072	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-102	ND	C98	0.020	0.000080	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-103	ND		0.010	0.000082	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-104	ND		0.010	0.000062	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-105	ND		0.010	0.00015	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-106	ND		0.010	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-107	ND		0.010	0.00017	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-108	ND	C	0.020	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-109	0.000612	J C86 q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-110	0.000797	J C	0.020	0.000060	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-111	ND		0.010	0.000058	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-112	ND		0.010	0.000061	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-113	0.000934	J C90	0.030	0.000072	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-114	ND		0.010	0.00014	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-115	0.000797	J C110	0.020	0.000060	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-116	0.000277	J C85 q	0.030	0.000070	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-117	0.000277	J C85 q	0.030	0.000070	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-118	0.000652	J	0.010	0.00015	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-119	0.000612	J C86 q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-120	ND		0.010	0.000059	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-121	ND		0.010	0.000060	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-122	ND		0.010	0.00019	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-123	ND		0.010	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-124	ND	C108	0.020	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-125	0.000612	J C86 q	0.060	0.000071	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-126	ND		0.010	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-127	ND		0.010	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-128	ND	C	0.020	0.00020	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-129	0.000796	J C	0.040	0.00021	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-130	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-131	ND		0.010	0.00028	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-132	ND		0.010	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-133	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-134	ND	C	0.020	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-135	ND	C	0.020	0.000077	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-136	ND		0.010	0.000056	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-137	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-138	0.000796	J C129	0.040	0.00021	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-139	ND	C	0.020	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-140	ND	C139	0.020	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-141	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-142	ND		0.010	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-143	ND	C134	0.020	0.00027	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-144	ND		0.010	0.000070	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-145	ND		0.010	0.000053	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-146	ND		0.010	0.00023	ng/g		10/03/20 06:25	10/21/20 14:45	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-147	0.000716	J C q	0.020	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-148	ND		0.010	0.000075	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-149	0.000716	J C147 q	0.020	0.00026	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-150	ND		0.010	0.000051	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-151	ND	C135	0.020	0.000077	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-152	ND		0.010	0.000054	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-153	0.000590	J C q	0.020	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-154	ND		0.010	0.000060	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-155	ND		0.010	0.000051	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-156	ND	C	0.020	0.00022	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-157	ND	C156	0.020	0.00022	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-158	ND		0.010	0.00016	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-159	ND		0.010	0.00017	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-160	0.000796	J C129	0.040	0.00021	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-161	ND		0.010	0.00017	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-162	ND		0.010	0.00017	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-163	0.000796	J C129	0.040	0.00021	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-164	ND		0.010	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-165	ND		0.010	0.00019	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-166	ND	C128	0.020	0.00020	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-167	ND		0.010	0.00013	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-168	0.000590	J C153 q	0.020	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-169	0.000150	J q	0.010	0.00014	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-170	ND		0.010	0.00012	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-171	ND	C	0.020	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-172	ND		0.010	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-173	ND	C171	0.020	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-174	ND		0.010	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-175	ND		0.010	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-176	ND		0.010	0.000078	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-177	ND		0.010	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-178	ND		0.010	0.00011	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-179	ND		0.010	0.000083	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-180	0.000615	J C	0.020	0.000087	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-181	ND		0.010	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-182	ND		0.010	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-183	0.000572	J C q	0.020	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-184	ND		0.010	0.000085	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-185	0.000572	J C183 q	0.020	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-186	ND		0.010	0.000082	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-187	0.000327	J	0.010	0.000096	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-188	ND		0.010	0.000074	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-189	ND		0.010	0.00024	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-190	ND		0.010	0.000075	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-191	ND		0.010	0.000078	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-192	ND		0.010	0.000087	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-193	0.000615	J C180	0.020	0.000087	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-194	ND		0.010	0.00033	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-195	ND		0.010	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-196	ND		0.010	0.00012	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-197	ND		0.010	0.000089	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-198	ND	C	0.020	0.00012	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-199	ND	C198	0.020	0.00012	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-200	ND		0.010	0.000079	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-201	ND		0.010	0.000081	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-202	ND		0.010	0.000090	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-203	ND		0.010	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-204	ND		0.010	0.000089	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-205	ND		0.010	0.00028	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-206	ND		0.010	0.00069	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-207	ND		0.010	0.00050	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-208	ND		0.010	0.00052	ng/g		10/03/20 06:25	10/21/20 14:45	1
PCB-209	ND		0.010	0.00038	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Monochlorobiphenyls	ND		0.010	0.00018	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Dichlorobiphenyls	0.00361	J q	0.020	0.0014	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Trichlorobiphenyls	0.00332	J q	0.020	0.00025	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Tetrachlorobiphenyls	0.00418	J q	0.040	0.00028	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Pentachlorobiphenyls	0.00452	J q	0.060	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Hexachlorobiphenyls	0.00225	J q	0.040	0.00017	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Heptachlorobiphenyls	0.00151	J q	0.020	0.00010	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Octachlorobiphenyls	ND		0.020	0.00036	ng/g		10/03/20 06:25	10/21/20 14:45	1
Total Nonachlorobiphenyls	ND		0.010	0.00069	ng/g		10/03/20 06:25	10/21/20 14:45	1
Polychlorinated biphenyls, Total	0.0194	J q	0.060	0.00041	ng/g		10/03/20 06:25	10/21/20 14:45	1

Isotope Dilution	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*47*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-3L	*45*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-4L	*54*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-15L	*52*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-19L	*60*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-37L	*59*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-54L	*70*		*5 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-77L	*69*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-81L	*66*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-104L	*64*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-105L	*82*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-114L	*80*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-118L	*80*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-123L	*77*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-126L	*76*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-155L	*76*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-156L	*81*	*C*	*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-157L	*81*	*C156*	*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-167L	*81*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-169L	*85*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-170L	*79*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-188L	*78*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*
PCB-189L	*75*		*10 - 145*	*10/03/20 06:25*	*10/21/20 14:45*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43261/19-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43261

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-202L	92		10 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-205L	70		10 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-206L	80		10 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-208L	78		10 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-209L	81		10 - 145	10/03/20 06:25	10/21/20 14:45	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	77		5 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-111L	82		10 - 145	10/03/20 06:25	10/21/20 14:45	1
PCB-178L	91		10 - 145	10/03/20 06:25	10/21/20 14:45	1

Lab Sample ID: LCS 140-43261/20-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43261

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1	0.500	0.411		ng/g		82	60 - 135
PCB-3	0.500	0.433		ng/g		87	60 - 135
PCB-4	0.500	0.477		ng/g		95	60 - 135
PCB-15	0.500	0.613		ng/g		123	60 - 135
PCB-19	0.500	0.523		ng/g		105	60 - 135
PCB-37	0.500	0.495		ng/g		99	60 - 135
PCB-54	0.500	0.483		ng/g		97	60 - 135
PCB-77	0.500	0.480		ng/g		96	60 - 135
PCB-81	0.500	0.475		ng/g		95	60 - 135
PCB-104	0.500	0.537		ng/g		107	60 - 135
PCB-105	0.500	0.529		ng/g		106	60 - 135
PCB-114	0.500	0.574		ng/g		115	60 - 135
PCB-118	0.500	0.546		ng/g		109	60 - 135
PCB-123	0.500	0.594		ng/g		119	60 - 135
PCB-126	0.500	0.563		ng/g		113	60 - 135
PCB-155	0.500	0.522		ng/g		104	60 - 135
PCB-156	1.00	1.08	C	ng/g		108	60 - 135
PCB-157	1.00	1.08	C156	ng/g		108	60 - 135
PCB-167	0.500	0.528		ng/g		106	60 - 135
PCB-169	0.500	0.491		ng/g		98	60 - 135
PCB-188	0.500	0.523		ng/g		105	60 - 135
PCB-189	0.500	0.552		ng/g		110	60 - 135
PCB-202	0.500	0.475		ng/g		95	60 - 135
PCB-205	0.500	0.593		ng/g		119	60 - 135
PCB-206	0.500	0.507		ng/g		101	60 - 135
PCB-208	0.500	0.529		ng/g		106	60 - 135
PCB-209	0.500	0.558		ng/g		112	60 - 135

Isotope Dilution	LCS %Recovery	LCS Qualifier	Limits
PCB-1L	51		15 - 145
PCB-3L	48		15 - 145
PCB-4L	58		15 - 145

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-43261/20-B
Matrix: Sediment
Analysis Batch: 43723

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43261

Isotope Dilution	LCS %Recovery	LCS Qualifier	Limits
PCB-15L	56		15 - 145
PCB-19L	69		15 - 145
PCB-37L	66		15 - 145
PCB-54L	76		15 - 145
PCB-77L	74		40 - 145
PCB-81L	73		40 - 145
PCB-104L	68		40 - 145
PCB-105L	82		40 - 145
PCB-114L	83		40 - 145
PCB-118L	81		40 - 145
PCB-123L	78		40 - 145
PCB-126L	79		40 - 145
PCB-155L	79		40 - 145
PCB-156L	80	C	40 - 145
PCB-157L	80	C156	40 - 145
PCB-167L	82		40 - 145
PCB-169L	86		40 - 145
PCB-170L	80		40 - 145
PCB-188L	82		40 - 145
PCB-189L	77		40 - 145
PCB-202L	97		40 - 145
PCB-205L	71		40 - 145
PCB-206L	79		40 - 145
PCB-208L	80		40 - 145
PCB-209L	82		40 - 145

Surrogate	LCS %Recovery	LCS Qualifier	Limits
PCB-28L	76		15 - 145
PCB-111L	84		40 - 145
PCB-178L	92		40 - 145

Method: 2540G - SM 2540G

Lab Sample ID: 180-111218-3 DU
Matrix: Sediment
Analysis Batch: 331732

Client Sample ID: STS0100N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Percent Moisture	59.8			59.6		%				0.3	10

Method: ASTM D5057-90 - Specific Gravity and Bulk Density (Screening)

Lab Sample ID: 180-111218-1 DU
Matrix: Sediment
Analysis Batch: 331888

Client Sample ID: STS0300N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Bulk Density	1.4			1.45		g/cc				2	20

Method: EPA-Lloyd Kahn - Organic Carbon, Total (TOC)

Lab Sample ID: MB 180-331767/4
Matrix: Sediment
Analysis Batch: 331767

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Organic Carbon - Duplicates	ND		1000	750	mg/Kg			09/29/20 13:25	1

Lab Sample ID: LCS 180-331767/5
Matrix: Sediment
Analysis Batch: 331767

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Total Organic Carbon - Duplicates			37800	33800		mg/Kg		89	75 - 125		

Specialty Organics

Prep Batch: 43261

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	HRMS-Sox	
180-111218-2	STS0200N	Total/NA	Sediment	HRMS-Sox	
180-111218-3	STS0100N	Total/NA	Sediment	HRMS-Sox	
MB 140-43261/19-B	Method Blank	Total/NA	Sediment	HRMS-Sox	
LCS 140-43261/20-B	Lab Control Sample	Total/NA	Sediment	HRMS-Sox	

Cleanup Batch: 43349

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	Split	43261
180-111218-2	STS0200N	Total/NA	Sediment	Split	43261
180-111218-3	STS0100N	Total/NA	Sediment	Split	43261
MB 140-43261/19-B	Method Blank	Total/NA	Sediment	Split	43261
LCS 140-43261/20-B	Lab Control Sample	Total/NA	Sediment	Split	43261

Analysis Batch: 43723

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	1668C	43349
180-111218-2	STS0200N	Total/NA	Sediment	1668C	43349
180-111218-3	STS0100N	Total/NA	Sediment	1668C	43349
MB 140-43261/19-B	Method Blank	Total/NA	Sediment	1668C	43349
LCS 140-43261/20-B	Lab Control Sample	Total/NA	Sediment	1668C	43349

General Chemistry

Analysis Batch: 331732

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	2540G	
180-111218-2	STS0200N	Total/NA	Sediment	2540G	
180-111218-3	STS0100N	Total/NA	Sediment	2540G	
180-111218-3 DU	STS0100N	Total/NA	Sediment	2540G	

Analysis Batch: 331767

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	EPA-Lloyd Kahn	
180-111218-2	STS0200N	Total/NA	Sediment	EPA-Lloyd Kahn	
180-111218-3	STS0100N	Total/NA	Sediment	EPA-Lloyd Kahn	
MB 180-331767/4	Method Blank	Total/NA	Sediment	EPA-Lloyd Kahn	
LCS 180-331767/5	Lab Control Sample	Total/NA	Sediment	EPA-Lloyd Kahn	

Analysis Batch: 331888

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-1	STS0300N	Total/NA	Sediment	ASTM D5057-90	
180-111218-2	STS0200N	Total/NA	Sediment	ASTM D5057-90	
180-111218-3	STS0100N	Total/NA	Sediment	ASTM D5057-90	
180-111218-4	SEE0101N	Total/NA	Sediment	ASTM D5057-90	
180-111218-5	SEE0201N	Total/NA	Sediment	ASTM D5057-90	
180-111218-6	SEE0301N	Total/NA	Sediment	ASTM D5057-90	
180-111218-1 DU	STS0300N	Total/NA	Sediment	ASTM D5057-90	

QC Association Summary

Client: AECOM
Job ID: 180-111218-1
Project/Site: Pepco Benning Road Facility

Geotechnical

Analysis Batch: 103533

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-7	STS0300N	Total/NA	Solid	D4464	
180-111218-8	STS0200N	Total/NA	Solid	D4464	
180-111218-9	STS0100N	Total/NA	Solid	D4464	

Analysis Batch: 159682

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-111218-4	SEE0101N	Total/NA	Sediment	D422	
180-111218-5	SEE0201N	Total/NA	Sediment	D422	
180-111218-6	SEE0301N	Total/NA	Sediment	D422	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: QIANG HUANG	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-63272-12755.1
Client Contact: Mr. Robert Kennedy	Phone: 240-374-8920	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 1 of 2
Company: AECOM				Job #:
Address: 250 Apollo Drive	Due Date Requested:			
City: Chelmsford	TAT Requested (days): standard.			
State, Zip: MA, 01824				
Phone:	PO #: 126546			
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	ASTM D4464 (Eurofins Calscience)	Lloyd Kahn (TOC)	EPA 1668C	Dry Density, Percent Moisture	ASTM D422	ASTM D2937	Total Number of containers	Special
Preservation Code:														
STS0300N	9/17/20	1155	C	S			X	X	X	X			3	
STS0200N	9/17/20	1220	C	S			X	X	X	X			3	
STS0100N	9/17/20	1235	C	S			X	X	X	X			3	
SEE0101N	9/17/20	1315	C	S							X	X	2	
SEE0201N	9/17/20	1345	C	S							X	X	2	
SEE0301N	9/17/20	1402	C	S							X	X	2	

180-111218 Chain of Custody

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1	QIANG HUANG	9/18/2020 1015			9/18/20 10:15	EAB&A
2		9/18/20 1700	EAB&A		9-19-20	EAB&A
3		Date/Time:	Company	Received by:	Date/Time: 11:00	Company

Custody Seals Intact: Δ Yes Δ No | Custody Seal No.: | Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019



Do Not Lift Using This T

5 A
12:00 3370
09.19

RI 639
ST 18

ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 18SEP20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238

(412) 963-7058 REF: AECOM PEPCO BENNING

INV:
PO: DEPT:

568J61545/B766

FedEx Express

SATURDAY 12:00P
PRIORITY OVERNIGHT

TRK# 0201 7715 7050 3370

15238
PA-US PIT

XO AGCA

PT-WI-SR-001 effective 7/26/13

Uncorrected temp 2.9 °C
Thermometer ID TM

CF 0 Initials TB

Part # 156297-435 RRDW2 EB 0741

180-111218 Waybill

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-412108.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-111218-1
Address: 5815 Middlebrook Pike, ,	Due Date Requested: 10/5/2020			Preservation Codes:
City: Knoxville	TAT Requested (days):			A - HCL M - Hexane B - NaOH N - None C - Zn Acetate O - AsNaO2 D - Nitric Acid P - Na2O4S E - NaHSO4 Q - Na2SO3 F - MeOH R - Na2S2O3 G - Amchlor S - H2SO4 H - Ascorbic Acid T - TSP Dodecahydrate I - Ice U - Acetone J - DI Water V - MCAA K - EDTA W - pH 4-5 L - EDA Z - other (specify) Other:
State, Zip: TN, 37921				
Phone: 865-291-3000(Tel) 865-584-4315(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Screen_1668/Screen_PCB_P_S	1668C/1668_P_Sox Standard 209 List with Coelutions for Re	Total Number of containers	Special Instructions/Note:
			Preservation Code:							
STS0300N (180-111218-1)	9/17/20	11:55 Eastern		Sediment			X	X	1	
STS0200N (180-111218-2)	9/17/20	12:20 Eastern		Sediment			X	X	1	
STS0100N (180-111218-3)	9/17/20	12:35 Eastern		Sediment			X	X	1	

180-111218 Chain of Custody

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sampl ...ded chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	*Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
	09/21/2020 1806	ETA PHL		9-22-20 10:20	ETA KNT
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Loc: 180
111218

EUROFINS/TESTAMERICA KNOXVILLE SAMPLE RECEIPT/CONDITION UPON RECEIPT ANOMALY CHECKLIST

Log In Number:

Review Items	Yes	No	NA	If No, what was the problem?
1. Are the shipping containers intact?	✓		✓	☐ Containers, Broken
2. Were ambient air containers received intact?			✓	☐ Checked in lab
3. The coolers/containers custody seal if present, is it intact?	✓			☐ Yes ☐ NA
4. Is the cooler temperature within limits? (> freezing temp. of water to 6 °C, VOST: 10°C) Thermometer ID : S168 Correction factor: 0.0	✓ ✓			☐ Cooler Out of Temp, Client Contacted, Proceed/Cancel ☐ Cooler Out of Temp, Same Day Receipt
5. Were all of the sample containers received intact?	✓			☐ Containers, Broken
6. Were samples received in appropriate containers?	✓			☐ Containers, Improper; Client Contacted; Proceed/Cancel
7. Do sample container labels match COC? (IDs, Dates, Times)	✓			☐ COC & Samples Do Not Match ☐ COC Incorrect/Incomplete ☐ COC Not Received
8. Were all of the samples listed on the COC received?	✓			☐ Sample Received, Not on COC ☐ Sample on COC, Not Received
9. Is the date/time of sample collection noted?	✓			☐ COC; No Date/Time; Client Contacted
10. Was the sampler identified on the COC?			✓	☐ Sampler Not Listed on COC
11. Is the client and project name/# identified?	✓			☐ COC Incorrect/Incomplete
12. Are tests/parameters listed for each sample?	✓			☐ COC No tests on COC
13. Is the matrix of the samples noted?	✓			☐ COC Incorrect/Incomplete
14. Was COC relinquished? (Signed/Dated/Timed)	✓			☐ COC Incorrect/Incomplete
15. Were samples received within holding time?	✓			☐ Holding Time - Receipt
16. Were samples received with correct chemical preservative (excluding Encore)?			✓ ✓	☐ pH Adjusted, pH Included (See box 16A) ☐ Incorrect Preservative
17. Were VOA samples received without headspace?			✓	☐ Headspace (VOA only)
18. Did you check for residual chlorine, if necessary? (e.g. 1613B, 1668) Chlorine test strip lot number:			✓	☐ Residual Chlorine
19. For 1613B water samples is pH<9?			✓	☐ If no, notify lab to adjust
20. For rad samples was sample activity info. Provided?			✓	☐ Project missing info

Comments/Actions Taken

CUSTODY SEALS INTACT
RECEIVED AT RT 0.6, 0.2 / CT 0.6, 0.2°C
DM 9-22-20
2 COOLERS FEDEX #1689 5102 9346 em PD

Labeling Verified by: **Date:**

pH test strip lot number:

Box 16A: pH Preservation	Box 18A: Residual Chlorine
Preservative:	
Lot Number:	
Exp Date:	
Analyst:	
Date:	
Time:	

Project #: _____ PM Instructions: _____

Sample Receiving Associate: _____ Date: 9-22-20

QA026R32.doc, 062719

10/23/2020

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

180-111218 Chain of Custody

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	COC No: 180-412105.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):	Job #: 180-111218-1
Address: 30 Community Drive, Suite 11,	Due Date Requested: 10/1/2020		
City: South Burlington	TAT Requested (days):		
State, Zip: VT, 05403			
Phone: 802-660-1990(Tel) 802-660-1919(Fax)	PO #:		
Email:	WO #:		
Project Name: Pepco Benning Road Facility	Project #: 18022565		
Site:	SSOW#:		

Analysis Requested

Preservation Codes:

A - HCL
B - NaOH
C - Zn Acetate
D - Nitric Acid
E - NaHSO4
F - MeOH
G - Amchlor
H - Ascorbic Acid
I - Ice
J - DI Water
K - EDTA
L - EDA
M - Hexane
N - None
O - AsNaO2
P - Na2O4S
Q - Na2SO3
R - Na2S2O3
S - H2SO4
T - TSP Dodecahydrate
U - Acetone
V - MCAA
W - pH 4-5
Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	D422/ Grain Size (Sieve and Hydrometer)	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
SEE0101N (180-111218-4)	9/17/20	13:15 Eastern		Sediment			X	1	
SEE0201N (180-111218-5)	9/17/20	13:45 Eastern		Sediment			X	1	
SEE0301N (180-111218-6)	9/17/20	14:02 Eastern		Sediment			X	1	

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification *Unconfirmed*	***Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*** ☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:		Date:	Time:	Method of Shipment:		
Relinquished by:	Date/Time: 09/21/2020 1800	Company EDA FIL	Received by:	Date/Time: 9/22/2020 1040	Company TMBCH	
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company	
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company	

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

ORIGIN ID:AGCA (412) 963-7058
PITTSBURGH SAMPLE RECEIVING
EUROFINS TESTAMERICA PITTSBURGH
301 ALPHA DRIVE

PITTSBURGH, PA 152381330
UNITED STATES US

SHIP DATE: 21SEP20
ACTWGT: 45.00 LB MAN
CAD: 741733/CAFE3406

BILL RECIPIENT

TO SHIPPING/RECEIVING
TESTAMERICA LABORATORIES, INC.
30 COMMUNITY DRIVE
SUITE 11
SOUTH BURLINGTON VT 05403

(802) 660-1990 REF: 8180-64194
PO: YES DEPT: SAMPLE RECEIVING

FedEx Express

2 of 3
MPS# 0263 1689 5102 9324
Mstr# 1689 5102 9313 0201

TUE - 22 SEP 10:30A
PRIORITY OVERNIGHT

NL BTVA

05403
VT-US BTV

ORIGIN ID:AGCA (412) 963-7058
PITTSBURGH SAMPLE RECEIVING
EUROFINS TESTAMERICA PITTSBURGH
301 ALPHA DRIVE

PITTSBURGH, PA 152381330
UNITED STATES US

SHIP DATE: 21SEP20
ACTWGT: 45.00 LB MAN
CAD: 741733/CAFE3406

BILL RECIPIENT

TO SHIPPING/RECEIVING
TESTAMERICA LABORATORIES, INC.
30 COMMUNITY DRIVE
SUITE 11
SOUTH BURLINGTON VT 05403

(802) 660-1990 REF: 8180-64194
PO: YES DEPT: SAMPLE RECEIVING

FedEx Express

3 of 3
MPS# 0263 1689 5102 9335
Mstr# 1689 5102 9313 0201

TUE - 22 SEP 10:30A
PRIORITY OVERNIGHT

NL BTVA

0540
VT-US BTV

1 of 3
TRK# 0201 1689 5102 9313
MASTER

TUE - 22 SEP 10:30A
PRIORITY OVERNIGHT

NL BTVA

05403
VT-US BTV

ORIGIN ID:AGCA (412) 963-7058
PITTSBURGH SAMPLE RECEIVING
EUROFINS TESTAMERICA PITTSBURGH
301 ALPHA DRIVE

PITTSBURGH, PA 152381330
UNITED STATES US

SHIP DATE: 21SEP20
ACTWGT: 45.00 LB MAN
CAD: 741733/CAFE3406

BILL RECIPIENT

TO SHIPPING/RECEIVING
TESTAMERICA LABORATORIES, INC.
30 COMMUNITY DRIVE
SUITE 11
SOUTH BURLINGTON VT 05403

(802) 660-1990 REF: 8180-64194
PO: YES DEPT: SAMPLE RECEIVING

FedEx Express

eurofins

Environment Testing
TestAmerica

10/23/2020

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-412131.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: Eurofins Calscience LLC		Accreditations Required (See note):		Job #: 180-111218-1
Address: 7440 Lincoln Way,	Due Date Requested: 10/1/2020			
City: Garden Grove	TAT Requested (days):			
State, Zip: CA, 92841				
Phone: 714-895-5494(Tel) 714-894-7501(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	SUB (ASTM D4464)/ ASTM D4464	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
STS0300N (180-111218-1)	9/17/20	11:55 Eastern		Sediment			X	1	ICO is $88
STS0200N (180-111218-2)	9/17/20	12:20 Eastern		Sediment			X	1	ICO is $88
STS0100N (180-111218-3)	9/17/20	12:35 Eastern		Sediment			X	1	ICO is $88

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	*Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		9/21/20 1800	ETACH		09/22/2020 1030	
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks: 2.1/2.7 SW

Ver: 01/16/2019

10/23/2020

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-111218-1

Login Number: 111218
List Number: 1
Creator: Watson, Debbie

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-111218-1

Login Number: 111218
List Number: 4
Creator: Stratford, Jordan

List Source: Eurofins Calscience
List Creation: 10/21/20 12:31 PM

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-111218-1

Login Number: 111218
List Number: 3
Creator: Jaffe, Nat S

List Source: Eurofins TestAmerica, Burlington
List Creation: 09/22/20 01:24 PM

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	Lab does not accept radioactive samples.
The cooler's custody seal, if present, is intact.	True	Seal present with no number.
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	0.2ºC, 0.7ºC, 0.7ºC
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	Received project as a subcontract.
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	N/A	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-112434-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
11/10/2020 9:19:28 AM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 6
Certification Summary 8
Sample Summary 11
Method Summary 12
Lab Chronicle 13
Client Sample Results 18
QC Sample Results 66
QC Association Summary 80
Chain of Custody 84
Receipt Checklists 94

Job ID: 180-112434-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-112434-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 10/17/2020 9:30 AM; the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 3 coolers at receipt time were 2.4º C, 15.1º C and 17.8º C.

SEMIVOLATILES
Due to the concentration of target compounds detected and/or matrix, the samples were analyzed at a dilution. The reporting limits have been adjusted accordingly. The samples had the surrogates diluted out.

The matrix spike duplicate of sample 0FS0300N (180-112434-2) recovered outside of the control limits for Benzo[k]fluoranthene. The relative percent difference between the matrix spike and the matrix spike duplicate was outside of the control limits for Benzo[k]fluoranthene.

The continuing calibration verification (CCV) analyzed in 180-334654 was outside the method criteria for the following analyte: 2,4,6-Tribromophenol(surr). As indicated in the reference method, sample analysis may proceed; however, any detection for the affected analyte(s) is considered estimated.

DRO
Due to the concentration of DRO/ORO detected, the samples were analyzed at a dilution. The reporting limits have been adjusted accordingly.

Several analytes were detected in method blank MB 140-43801/12-B at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged. Refer to the QC report for details.

PCB COMGENERS
Due to the concentration of target compounds detected and/or matrix, the samples were analyzed at a dilution. The reporting limits have been adjusted accordingly. The samples had the surrogates diluted out.

One or more ion abundance ratios are outside criteria for the Isotope Dilution Analyte (IDA) associated with the following samples: 0FS0300N (180-112434-2) and 0FS0100N (180-112434-4).

Job ID: 180-112434-1 (Continued)

Laboratory: Eurofins TestAmerica, Pittsburgh (Continued)

An ion abundance ratio(s) is outside criteria for the Internal Standard(s) associated with the following sample: 0FS0300N (180-112434-2).

DIOXINS

Reported OCDD and/or OCDF analytes that are flagged with the “E” qualifier exceed the upper calibration range of the instrument. Per the method, dilutions are not required to bring these analytes within the calibration range.

The Isotope Dilution Analyte (IDA) recovery associated with the following samples is below the method recommended limit: 0FS0300N (180-112434-2) and 0FS0400N (180-112434-6). Generally, data quality is not considered affected if the IDA signal-to-noise ratio is greater than 10:1, which is achieved for all IDA in the sample(s).

The bracketing continuing calibration verification (CCV) associated with batch 140-44180 has analytes with percent difference values that are between the method criteria of 30% to 35% deviation from the initial calibration curve. Per method guidelines, an average relative response factor (RRF) is calculated from the bracketing CCV and is used to quantitate the Isotope Dilution Analyte (IDA) recovery in the associated samples.

The Isotope Dilution Analyte (IDA) recovery associated with the following sample is below the method recommended limit: 0FS0300N (180-112434-2). Generally, data quality is not considered affected if the IDA signal-to-noise ratio is greater than 10:1, which is achieved for all IDA in the sample(s).

Several analytes were detected in method blank MB 140-43808/20-A at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

Several analytes were detected in method blank MB 140-43801/12-B at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

METALS

The method blank for batch 180-335170 contained nickel above the reporting limit (RL). Associated samples were not re-extracted and/or re-analyzed because results were greater than 10X the value found in the method blank.

Calcium was detected in method blank MB 180-335170/1-A at a level that was above the method detection limit but below the reporting limit. The value should be considered an estimate, and has been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

Mercury was detected in method blank MB 180-334165/1-A at a level that was above the method detection limit but below the reporting limit. The value should be considered an estimate, and has been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged. Refer to the QC report for details.

The aluminum concentrations found in the continuing calibration blanks (CCB) were greater than the reporting limit. All associated samples bracketed by these CCB's had aluminum concentrations at least 10x greater than the CCB concentrations. All associated results have been flagged with a "^" qualifier.

GRAIN SIZE

No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

GENERAL CHEMISTRY

The following samples are mats: SMS0100N-MAT, SMS0200N-MAT, and SM0300N-MAT. The laboratory was instructed to rinse sediment off of the mats using a squirt bottle of water. This approach yielded minimal success. The laboratory then submersed the mat in a bucket of water and "washed" the mat by hand. This processed was performed three times. The "wash" water was then placed in baking dishes and placed into a drying oven. After the sample was completely dry, the amount of dried sediment was weighed. The results are as follows:
SMS0100N-MAT- 263.8 grams
SMS0200N-MAT- 415.8 grams

Job ID: 180-112434-1 (Continued)

Laboratory: Eurofins TestAmerica, Pittsburgh (Continued)

SM0300N-MAT- 471.8 grams

Please note that the reporting limit for Lloyd Kahn TOC analysis is a nominal value and does not reflect adjustments in sample mass processed on an individual basis.

Qualifiers

GC/MS Semi VOA

Qualifier	Qualifier Description
D	Surrogate or matrix spike recoveries were not obtained because the extract was diluted for analysis; also compounds analyzed at a dilution may be flagged with a D.
F1	MS and/or MSD recovery exceeds control limits.
F2	MS/MSD RPD exceeds control limits
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
X	Surrogate recovery exceeds control limits

GC Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Dioxin

Qualifier	Qualifier Description
*5	Isotope dilution analyte is outside acceptance limits.
B	Compound was found in the blank and sample.
C	The compound co-eluted with other compounds
C108	The compound co-eluted with PCB-108
C110	The compound co-eluted with PCB-110
C12	The compound co-eluted with PCB-12
C128	The compound co-eluted with PCB-128
C129	The compound co-eluted with PCB-129
C134	The compound co-eluted with PCB-134
C135	The compound co-eluted with PCB-135
C139	The compound co-eluted with PCB-139
C147	The compound co-eluted with PCB-147
C153	The compound co-eluted with PCB-153
C156	The compound co-eluted with PCB-156
C171	The compound co-eluted with PCB-171
C18	The compound co-eluted with PCB-18
C180	The compound co-eluted with PCB-180
C183	The compound co-eluted with PCB-183
C198	The compound co-eluted with PCB-198
C20	The compound co-eluted with PCB-20
C21	The compound co-eluted with PCB-21
C26	The compound co-eluted with PCB-26
C40	The compound co-eluted with PCB-40
C43	The compound co-eluted with PCB-43
C44	The compound co-eluted with PCB-44
C45	The compound co-eluted with PCB-45
C49	The compound co-eluted with PCB-49
C50	The compound co-eluted with PCB-50
C59	The compound co-eluted with PCB-59
C61	The compound co-eluted with PCB-61
C83	The compound co-eluted with PCB-83
C85	The compound co-eluted with PCB-85
C86	The compound co-eluted with PCB-86
C88	The compound co-eluted with PCB-88
C90	The compound co-eluted with PCB-90
C93	The compound co-eluted with PCB-93
C98	The compound co-eluted with PCB-98
E	Result exceeded calibration range.
I	Value is EMPC (estimated maximum possible concentration).
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Qualifiers (Continued)

Dioxin (Continued)

Qualifier	Qualifier Description
q	The reported result is the estimated maximum possible concentration of this analyte, quantitated using the theoretical ion ratio. The measured ion ratio does not meet qualitative identification criteria and indicates a possible interference.

Metals

Qualifier	Qualifier Description
^	ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA, DLCK or MRL standard: Instrument related QC is outside acceptance limits.
B	Compound was found in the blank and sample.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20 *
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	12-31-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-14-21
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-21

Laboratory: Eurofins TestAmerica, Burlington

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
ANAB	Dept. of Defense ELAP	L2336	02-25-23
Connecticut	State	PH-0751	09-30-21
DE Haz. Subst. Cleanup Act (HSCA)	State	N/A	05-16-21
Florida	NELAP	E87467	06-30-21
Minnesota	NELAP	050-999-436	12-31-20
New Hampshire	NELAP	2006	12-18-20
New Jersey	NELAP	VT972	06-30-21
New York	NELAP	10391	04-01-21
Pennsylvania	NELAP	68-00489	04-30-21
Rhode Island	State	LAO00298	12-30-20
US Fish & Wildlife	US Federal Programs	058448	07-31-21
Vermont	State	VT4000	12-31-20
Virginia	NELAP	460209	12-14-20
Wisconsin	State	399133350	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Canton

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	State	2927	02-23-21
Connecticut	State	PH-0590	12-31-21
Florida	NELAP	E87225	06-30-21
Georgia	State	4062	02-23-21
Illinois	NELAP	004498	07-31-21
Iowa	State	421	06-01-21
Kansas	NELAP	E-10336	04-30-21
Kentucky (UST)	State	112225	02-23-21
Kentucky (WW)	State	KY98016	12-31-20
Minnesota	NELAP	OH00048	12-31-20
Minnesota (Petrofund)	State	3506	08-01-21
New Jersey	NELAP	OH001	06-30-21
New York	NELAP	10975	03-31-21
Ohio VAP	State	CL0024	06-05-21
Oregon	NELAP	4062	02-24-21
Pennsylvania	NELAP	68-00340	08-31-21
Texas	NELAP	T104704517-18-10	08-31-21
USDA	US Federal Programs	P330-18-00281	09-17-21
Virginia	NELAP	010101	09-14-21
Washington	State	C971	01-12-21
West Virginia DEP	State	210	12-31-20

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Knoxville

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
	AFCEE	N/A	
ANAB	Dept. of Defense ELAP	L2311	02-13-22
ANAB	Dept. of Energy	L2311.01	02-13-22
ANAB	ISO/IEC 17025	L2311	02-13-22
ANAB	ISO/IEC 17025	L2311	02-14-22
Arkansas DEQ	State	88-0688	06-17-21
California	State	2423	06-30-21
Colorado	State	TN00009	02-28-21
Connecticut	State	PH-0223	09-30-21
Florida	NELAP	E87177	07-01-21
Georgia (DW)	State	906	12-11-22
Hawaii	State	NA	12-11-21
Kansas	NELAP	E-10349	11-01-20 *
Kentucky (DW)	State	90101	01-01-21
Louisiana	NELAP	LA110001	12-31-12 *
Louisiana	NELAP	83979	06-30-21
Louisiana (DW)	State	LA019	12-31-20
Maryland	State	277	03-31-21
Michigan	State	9933	12-11-22
Nevada	State	TN00009	07-31-21
New Hampshire	NELAP	299919	01-17-21
New Jersey	NELAP	TN001	07-01-21
New York	NELAP	10781	03-31-21
North Carolina (DW)	State	21705	07-31-21
North Carolina (WW/SW)	State	64	12-31-20
Ohio VAP	State	CL0059	06-02-23
Oklahoma	State	9415	08-31-21
Oregon	NELAP	TNI0189	01-02-21
Pennsylvania	NELAP	68-00576	12-31-20
Tennessee	State	02014	12-11-22
Texas	NELAP	T104704380-18-12	08-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-19-00236	08-20-22
Utah	NELAP	TN00009	07-31-21
Virginia	NELAP	460176	09-14-21
Washington	State	C593	01-19-21
West Virginia (DW)	State	9955C	01-01-21
West Virginia DEP	State	345	05-01-21
Wisconsin	State	998044300	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-112434-1	SMS0100N	Sediment	10/15/20 12:15	10/17/20 09:30	
180-112434-2	0FS0300N	Sediment	10/15/20 13:00	10/17/20 09:30	
180-112434-3	SMS0200N	Sediment	10/15/20 13:55	10/17/20 09:30	
180-112434-4	0FS0100N	Sediment	10/15/20 14:00	10/17/20 09:30	
180-112434-5	SMS0300N	Sediment	10/15/20 15:00	10/17/20 09:30	
180-112434-6	0FS0400N	Sediment	10/15/20 15:15	10/17/20 09:30	

Method Summary

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8270D LL	Semivolatile Organic Compounds by GC/MS - Low Level	SW846	TAL PIT
8015C	Nonhalogenated Organics using GC/FID -Modified (Diesel Range Organics)	SW846	TAL CAN
1668C	Chlorinated Biphenyl Congeners (HRGC/HRMS)	EPA	TAL KNX
8290A	Dioxins and Furans (HRGC/HRMS)	SW846	TAL KNX
EPA 6020A	Metals (ICP/MS)	SW846	TAL PIT
EPA 7471B	Mercury (CVAA)	SW846	TAL PIT
2540G	SM 2540G	SM22	TAL PIT
EPA-Lloyd Kahn	Organic Carbon, Total (TOC)	EPA	TAL PIT
D422	Grain Size	ASTM	TAL BUR
3050B	Preparation, Metals	SW846	TAL PIT
3540C	Soxhlet Extraction	SW846	TAL CAN
3541	Automated Soxhlet Extraction (Low Level)	SW846	TAL PIT
7471B	Preparation, Mercury	SW846	TAL PIT
8290	Soxhlet Extraction of Dioxins and Furans	SW846	TAL KNX
HRMS-Sox	Soxhlet Extraction	EPA	TAL KNX
Split	Split Factor Determination	None	TAL KNX

Protocol References:

ASTM = ASTM International
EPA = US Environmental Protection Agency
None = None
SM22 = Standard Methods For The Examination Of Water And Wastewater, 22nd Edition
SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL BUR = Eurofins TestAmerica, Burlington, 30 Community Drive, Suite 11, South Burlington, VT 05403, TEL (802)660-1990
TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396
TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0100N
Lab Sample ID: 180-112434-1
Date Collected: 10/15/20 12:15
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			160516	10/22/20 22:01	CPF	TAL BUR
	Instrument ID: D422_import									

Client Sample ID: SMS0100N
Lab Sample ID: 180-112434-1
Date Collected: 10/15/20 12:15
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 31.8

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			20.09 g	20 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		10			44136	11/03/20 02:24	LKM	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			334869	10/24/20 14:24	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: 0FS0300N
Lab Sample ID: 180-112434-2
Date Collected: 10/15/20 13:00
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: 0FS0300N
Lab Sample ID: 180-112434-2
Date Collected: 10/15/20 13:00
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 69.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.5 g	0.50 mL	334547	10/23/20 12:09	JAS	TAL PIT
Total/NA	Analysis	EPA 8270D LL		25	1 mL	1 mL	334654	10/24/20 15:04	VVP	TAL PIT
	Instrument ID: CH731									
Total/NA	Prep	3540C			18.62 g	5 mL	457770	10/26/20 13:07	SDE	TAL CAN
Total/NA	Analysis	8015C		10			457876	10/27/20 14:59	LKG	TAL CAN
	Instrument ID: A2HP5F									
Total/NA	Prep	HRMS-Sox			20.02 g	20 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		10			44136	11/03/20 03:25	LKM	TAL KNX
	Instrument ID: M1D									
Total/NA	Prep	8290			20.51 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44206	11/05/20 07:12	PMP	TAL KNX
	Instrument ID: D12C									
Total/NA	Prep	8290			20.51 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44180	11/04/20 15:45	MSD	TAL KNX
	Instrument ID: D2A									

Client Sample ID: 0FS0300N
Lab Sample ID: 180-112434-2
Date Collected: 10/15/20 13:00
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 69.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335640	11/02/20 19:08	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.01 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335795	11/03/20 18:28	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.01 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335951	11/04/20 19:02	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.01 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			336056	11/05/20 10:59	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	7471B			1.36 g	100 mL	334165	10/21/20 08:22	MM1	TAL PIT
Total/NA	Analysis	EPA 7471B		1			334475	10/22/20 13:55	KEM	TAL PIT
	Instrument ID: HGY									

Client Sample ID: SMS0200N
Lab Sample ID: 180-112434-3
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			160516	10/22/20 22:03	CPF	TAL BUR
	Instrument ID: D422_import									

Client Sample ID: SMS0200N
Lab Sample ID: 180-112434-3
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 27.3

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			20.27 g	20 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		10			44136	11/03/20 04:27	LKM	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			335026	10/27/20 16:46	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: 0FS0100N
Lab Sample ID: 180-112434-4
Date Collected: 10/15/20 14:00
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									

Lab Chronicle

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0FS0100N
Lab Sample ID: 180-112434-4
Date Collected: 10/15/20 14:00
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 75.8

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.1 g	0.50 mL	334547	10/23/20 12:09	JAS	TAL PIT
Total/NA	Analysis	EPA 8270D LL		40	1 mL	1 mL	334654	10/24/20 16:21	VVP	TAL PIT
	Instrument ID: CH731									
Total/NA	Prep	3540C			29.99 g	5 mL	457770	10/26/20 13:07	SDE	TAL CAN
Total/NA	Analysis	8015C		10			457876	10/27/20 15:27	LKG	TAL CAN
	Instrument ID: A2HP5F									
Total/NA	Prep	HRMS-Sox			20.06 g	20 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		10			44136	11/03/20 05:28	LKM	TAL KNX
	Instrument ID: M1D									
Total/NA	Prep	8290			20.58 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44206	11/05/20 07:45	PMP	TAL KNX
	Instrument ID: D12C									
Total/NA	Prep	8290			20.58 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44180	11/04/20 16:46	MSD	TAL KNX
	Instrument ID: D2A									
Total/NA	Prep	3050B			2.04 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335640	11/02/20 19:11	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.04 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335795	11/03/20 18:30	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.04 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335951	11/04/20 19:05	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.04 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			336056	11/05/20 11:02	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	7471B			1.61 g	100 mL	334165	10/21/20 08:22	MM1	TAL PIT
Total/NA	Analysis	EPA 7471B		1			334475	10/22/20 13:56	KEM	TAL PIT
	Instrument ID: HGY									

Client Sample ID: SMS0300N
Lab Sample ID: 180-112434-5
Date Collected: 10/15/20 15:00
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	D422		1			160516	10/22/20 22:05	CPF	TAL BUR
	Instrument ID: D422_import									

Lab Chronicle

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0300N
Lab Sample ID: 180-112434-5
Date Collected: 10/15/20 15:00
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 33.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	HRMS-Sox			4.10 g	10 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	100 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		1			44166	11/04/20 03:11	PMP	TAL KNX
	Instrument ID: M1D									
Total/NA	Analysis	EPA-Lloyd Kahn		1			335026	10/27/20 17:03	DLF	TAL PIT
	Instrument ID: FLASHEA									

Client Sample ID: 0FS0400N
Lab Sample ID: 180-112434-6
Date Collected: 10/15/20 15:15
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: 0FS0400N
Lab Sample ID: 180-112434-6
Date Collected: 10/15/20 15:15
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 71.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.1 g	0.50 mL	334547	10/23/20 12:09	JAS	TAL PIT
Total/NA	Analysis	EPA 8270D LL		40	1 mL	1 mL	334654	10/24/20 16:47	VVP	TAL PIT
	Instrument ID: CH731									
Total/NA	Prep	3540C			18.41 g	5 mL	457770	10/26/20 13:07	SDE	TAL CAN
Total/NA	Analysis	8015C		2			458086	10/28/20 10:32	LKG	TAL CAN
	Instrument ID: A2HP5F									
Total/NA	Prep	HRMS-Sox			20.31 g	20 mL	43801	10/23/20 04:33	CLI	TAL KNX
Total/NA	Cleanup	Split			10 mL	50 uL	43973	10/28/20 10:07	EDD	TAL KNX
Total/NA	Analysis	1668C		10			44136	11/03/20 07:31	LKM	TAL KNX
	Instrument ID: M1D									
Total/NA	Prep	8290			20.51 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44206	11/05/20 08:19	PMP	TAL KNX
	Instrument ID: D12C									
Total/NA	Prep	8290			20.51 g	20 uL	43808	10/23/20 08:34	SSS	TAL KNX
Total/NA	Analysis	8290A		1			44180	11/04/20 17:48	MSD	TAL KNX
	Instrument ID: D2A									
Total/NA	Prep	3050B			2.03 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335640	11/02/20 19:13	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.03 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335795	11/03/20 18:33	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	3050B			2.03 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			335951	11/04/20 19:07	RJR	TAL PIT
	Instrument ID: NEMO									

Lab Chronicle

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: 0FS0400N

Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6

Matrix: Sediment
Percent Solids: 71.2

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.03 g	100 mL	335170	10/29/20 08:20	KHM	TAL PIT
Total/NA	Analysis	EPA 6020A		1			336056	11/05/20 11:04	RJR	TAL PIT
	Instrument ID: NEMO									
Total/NA	Prep	7471B			1.48 g	100 mL	334165	10/21/20 08:22	MM1	TAL PIT
Total/NA	Analysis	EPA 7471B		1			334475	10/22/20 13:57	KEM	TAL PIT
	Instrument ID: HGY									

Laboratory References:

TAL BUR = Eurofins TestAmerica, Burlington, 30 Community Drive, Suite 11, South Burlington, VT 05403, TEL (802)660-1990
TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396
TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Analyst References:

Lab: TAL BUR
- Batch Type: Analysis
  - CPF = Fred Cota

Lab: TAL CAN
- Batch Type: Prep
  - SDE = Steve Earle
- Batch Type: Analysis
  - LKG = Lucas Grossman

Lab: TAL KNX
- Batch Type: Cleanup
  - EDD = Erica Dinkins
- Batch Type: Prep
  - CLI = Crystal Ivey
  - SSS = Samuel Stockton
- Batch Type: Analysis
  - LKM = Linda McWhirter
  - MSD = Melissa Davidson
  - PMP = Trish Parsly

Lab: TAL PIT
- Batch Type: Prep
  - JAS = Jeremy Stundon
  - KHM = Kyle Mucroski
  - MM1 = Mary Beth Miller
- Batch Type: Analysis
  - DLF = Donald Ferguson
  - KEM = Kimberly Mahoney
  - KPO = Kiera O'Neil
  - RJR = Ron Rosenbaum
  - VVP = Vincent Piccolino

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1
Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.34	B	0.16	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-2	0.045	J q	0.16	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-3	0.24	B	0.16	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-4	1.2		0.31	0.029	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-5	0.065	J q	0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-6	0.80		0.16	0.019	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-7	0.14	J	0.16	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-8	3.5		0.31	0.018	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-9	0.18	q	0.16	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-10	0.071	J q	0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-11	2.2	B	0.31	0.019	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-12	0.47	C	0.31	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-13	0.47	C12	0.31	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-14	ND		0.16	0.017	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-15	4.7		0.16	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-16	2.1		0.16	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-17	2.4		0.16	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-18	5.3	C	0.31	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-19	0.77		0.16	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-20	15	C B	0.31	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-21	5.3	C B	0.31	0.015	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-22	4.5		0.16	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-23	ND		0.16	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-24	0.095	J q	0.16	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-25	1.1		0.16	0.015	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-26	2.0	C B	0.31	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-27	0.63		0.16	0.0046	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-28	15	B C20	0.31	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-29	2.0	C26 B	0.31	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-30	5.3	C18	0.31	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-31	9.7	B	0.31	0.015	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-32	2.7	B	0.16	0.0044	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-33	5.3	B C21	0.31	0.015	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-34	ND		0.16	0.017	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-35	0.30		0.16	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-36	ND		0.16	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-37	6.3		0.16	0.016	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-38	ND		0.16	0.017	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-39	ND		0.16	0.015	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-40	6.2	C	0.47	0.034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-41	6.2	C40	0.47	0.034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-42	2.9		0.16	0.035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-43	0.32	C	0.31	0.032	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-44	11	C B	0.47	0.030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-45	2.4	C	0.31	0.036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-46	0.69		0.16	0.044	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-47	11	B C44	0.47	0.030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-48	1.7		0.16	0.034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-49	7.1	C	0.31	0.028	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1
Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	1.8	C	0.31	0.033	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-51	2.4	C45	0.31	0.036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-52	14		0.16	0.034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-53	1.8	C50	0.31	0.033	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-54	0.058	J	0.16	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-55	0.31		0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-56	5.1		0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-57	ND		0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-58	0.033	J	0.16	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-59	1.1	C	0.47	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-60	2.5		0.16	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-61	17	C	0.63	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-62	1.1	C59	0.47	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-63	0.37		0.16	0.023	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-64	4.7		0.16	0.023	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-65	11	B C44	0.47	0.030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-66	11		0.16	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-67	0.34		0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-68	0.082	J q	0.16	0.023	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-69	7.1	C49	0.31	0.028	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-70	17	C61	0.63	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-71	6.2	C40	0.47	0.034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-72	0.12	J	0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-73	0.32	C43	0.31	0.032	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-74	17	C61	0.63	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-75	1.1	C59	0.47	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-76	17	C61	0.63	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-77	2.0		0.16	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-78	ND		0.16	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-79	0.13	J q	0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-80	ND		0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-81	0.048	J q	0.16	0.022	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-82	2.9		0.16	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-83	13	C	0.31	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-84	5.3		0.16	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-85	4.4	C B	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-86	15	C	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-87	15	C86	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-88	3.6	C	0.31	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-89	0.18		0.16	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-90	26	C B	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-91	3.6	C88	0.31	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-92	4.7		0.16	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-93	0.50	C	0.31	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-94	0.18		0.16	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-95	21		0.16	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-96	0.17		0.16	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-97	15	C86	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-98	0.58	C q	0.31	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1
Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	13	C83	0.31	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-100	0.50	C93	0.31	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-101	26	B C90	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-102	0.58	C98 q	0.31	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-103	0.19	q	0.16	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-104	ND		0.16	0.0026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-105	8.0		0.16	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-106	ND		0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-107	1.6		0.16	0.027	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-108	0.81	C	0.31	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-109	15	C86	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-110	31	C B	0.31	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-111	ND		0.16	0.0024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-112	0.12	J	0.16	0.0026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-113	26	B C90	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-114	0.32	q	0.16	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-115	31	B C110	0.31	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-116	4.4	C85 B	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-117	4.4	C85 B	0.47	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-118	19		0.16	0.024	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-119	15	C86	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-120	0.085	J	0.16	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-121	ND		0.16	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-122	0.37		0.16	0.029	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-123	0.35	q	0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-124	0.81	C108	0.31	0.026	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-125	15	C86	0.94	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-126	0.11	J q	0.16	0.027	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-127	ND		0.16	0.025	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-128	5.4	C	0.31	0.044	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-129	46	C B	0.63	0.046	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-130	2.6		0.16	0.060	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-131	0.33	q	0.16	0.063	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-132	13		0.16	0.059	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-133	0.56		0.16	0.057	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-134	2.2	C	0.31	0.060	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-135	18	C	0.31	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-136	5.4		0.16	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-137	1.4		0.16	0.052	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-138	46	B C129	0.63	0.046	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-139	0.45	C	0.31	0.051	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-140	0.45	C139	0.31	0.051	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-141	10		0.16	0.053	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-142	ND		0.16	0.057	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-143	2.2	C134	0.31	0.060	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-144	1.9		0.16	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-145	ND		0.16	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-146	7.0		0.16	0.050	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-147	42	C B	0.31	0.058	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1
Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.043	J	0.16	0.0044	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-149	42	B C147	0.31	0.058	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-150	0.042	J q	0.16	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-151	18	C135	0.31	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-152	ND		0.16	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-153	39	C	0.31	0.040	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-154	0.37	q	0.16	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-155	ND		0.16	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-156	3.8	C B	0.31	0.048	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-157	3.8	C156 B	0.31	0.048	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-158	4.0		0.16	0.036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-159	0.49		0.16	0.038	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-160	46	B C129	0.63	0.046	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-161	ND		0.16	0.038	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-162	0.14	J	0.16	0.037	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-163	46	B C129	0.63	0.046	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-164	3.1		0.16	0.040	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-165	ND		0.16	0.043	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-166	5.4	C128	0.31	0.044	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-167	1.6		0.16	0.029	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-168	39	C153	0.31	0.040	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-169	ND		0.16	0.029	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-170	18		0.16	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-171	5.4	C	0.31	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-172	3.3		0.16	0.0075	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-173	5.4	C171	0.31	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-174	20		0.16	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-175	0.72		0.16	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-176	2.2		0.16	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-177	11		0.16	0.0072	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-178	4.0		0.16	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-179	8.4		0.16	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-180	41	C	0.31	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-181	0.072	J q	0.16	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-182	0.091	J q	0.16	0.0065	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-183	13	C	0.31	0.0067	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-184	ND		0.16	0.0056	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-185	13	C183	0.31	0.0067	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-186	ND		0.16	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-187	23		0.16	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-188	ND		0.16	0.0048	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-189	0.56		0.16	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-190	3.2		0.16	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-191	0.65	q	0.16	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-192	ND		0.16	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-193	41	C180	0.31	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-194	8.8		0.16	0.033	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-195	3.5		0.16	0.036	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-196	4.3		0.16	0.0090	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1
Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	0.25		0.16	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-198	9.9	C	0.31	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-199	9.9	C198	0.31	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-200	1.0		0.16	0.0061	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-201	0.97		0.16	0.0062	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-202	1.6		0.16	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-203	5.5		0.16	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-204	ND		0.16	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-205	0.40		0.16	0.028	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-206	4.4		0.16	0.041	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-207	0.40		0.16	0.029	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-208	1.1		0.16	0.030	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
PCB-209	1.1		0.16	0.021	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Monochlorobiphenyls	0.63	B q	0.16	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Dichlorobiphenyls	13	B q	0.31	0.021	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Trichlorobiphenyls	58	B q	0.31	0.012	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Tetrachlorobiphenyls	93	B q	0.63	0.027	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Pentachlorobiphenyls	160	B q	0.94	0.010	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Hexachlorobiphenyls	210	B q	0.63	0.035	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Heptachlorobiphenyls	150	q	0.31	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Octachlorobiphenyls	36		0.31	0.014	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Total Nonachlorobiphenyls	5.9		0.16	0.033	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10
Polychlorinated biphenyls, Total	730	B q	0.94	0.020	ng/g	☼	10/23/20 04:33	11/03/20 02:24	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*60*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-3L	*57*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-4L	*69*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-15L	*71*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-19L	*75*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-37L	*74*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-54L	*81*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-77L	*76*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-81L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-104L	*70*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-105L	*80*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-114L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-118L	*79*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-123L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-126L	*75*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-155L	*82*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-156L	*80*	*C*	*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-157L	*80*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-167L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-169L	*82*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-170L	*71*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-188L	*75*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-189L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-202L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-205L	*68*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*

Client Sample ID: SMS0100N

Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-1

Matrix: Sediment
Percent Solids: 31.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-206L	*71*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-208L	*75*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-209L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*84*		*5 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-111L	*95*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*
PCB-178L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 02:24*	*10*

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	68.2		0.1	0.1	%			10/25/20 15:07	1
Total Organic Carbon - Duplicates	85000		3100	2300	mg/Kg	☼		10/24/20 14:24	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			10/22/20 22:01	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			10/22/20 22:01	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			10/22/20 22:01	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			10/22/20 22:01	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			10/22/20 22:01	1
Sieve Size 0.375 inch - Percent Finer	95.4				% Passing			10/22/20 22:01	1
Sieve Size #4 - Percent Finer	87.6				% Passing			10/22/20 22:01	1
Sieve Size #10 - Percent Finer	82.6				% Passing			10/22/20 22:01	1
Sieve Size #20 - Percent Finer	78.9				% Passing			10/22/20 22:01	1
Sieve Size #40 - Percent Finer	74.7				% Passing			10/22/20 22:01	1
Sieve Size #60 - Percent Finer	70.7				% Passing			10/22/20 22:01	1
Sieve Size #80 - Percent Finer	68.5				% Passing			10/22/20 22:01	1
Sieve Size #100 - Percent Finer	66.6				% Passing			10/22/20 22:01	1
Sieve Size #200 - Percent Finer	62.2				% Passing			10/22/20 22:01	1
Hydrometer Reading 1 - Percent Finer	21.1				% Passing			10/22/20 22:01	1
Hydrometer Reading 2 - Percent Finer	17.9				% Passing			10/22/20 22:01	1
Hydrometer Reading 3 - Percent Finer	14.7				% Passing			10/22/20 22:01	1
Hydrometer Reading 4 - Percent Finer	13.1				% Passing			10/22/20 22:01	1
Hydrometer Reading 5 - Percent Finer	9.9				% Passing			10/22/20 22:01	1
Hydrometer Reading 6 - Percent Finer	6.7				% Passing			10/22/20 22:01	1
Hydrometer Reading 7 - Percent Finer	3.5				% Passing			10/22/20 22:01	1

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		120	34	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Acenaphthylene	ND		120	26	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Anthracene	ND		120	31	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Benzo[a]anthracene	**63**	**J**	120	53	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Benzo[b]fluoranthene	**77**	**J**	120	29	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Benzo[k]fluoranthene	**70**	**J F1 F2**	120	36	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Benzo[g,h,i]perylene	ND		120	26	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Benzo[a]pyrene	ND		120	51	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Chrysene	**95**	**J**	120	66	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Dibenz(a,h)anthracene	ND		120	76	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Fluoranthene	**98**	**J**	120	31	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Fluorene	ND		120	23	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Indeno[1,2,3-cd]pyrene	ND		120	59	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Naphthalene	ND		120	23	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Phenanthrene	**44**	**J**	120	32	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25
Pyrene	**100**	**J**	120	28	ug/Kg	☼	10/23/20 12:09	10/24/20 15:04	25

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*0*	*D X*	*37 - 107*	*10/23/20 12:09*	*10/24/20 15:04*	*25*
Nitrobenzene-d5 (Surr)	*0*	*D X*	*41 - 112*	*10/23/20 12:09*	*10/24/20 15:04*	*25*
Terphenyl-d14 (Surr)	*0*	*D X*	*32 - 115*	*10/23/20 12:09*	*10/24/20 15:04*	*25*

Method: 8015C - Nonhalogenated Organics using GC/FID -Modified (Diesel Range Organics)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
DRO C10-C20	**810**		390	180	mg/Kg	☼	10/26/20 13:07	10/27/20 14:59	10
Oil Range Organics (C20-C36)	**4400**		390	180	mg/Kg	☼	10/26/20 13:07	10/27/20 14:59	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl (Surr)	*75*		*39 - 120*	*10/26/20 13:07*	*10/27/20 14:59*	*10*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.0055**	**J B**	0.072	0.00082	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-2	ND		0.072	0.00092	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-3	**0.0043**	**J q B**	0.072	0.00097	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-4	ND		0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-5	ND		0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-6	ND		0.072	0.0096	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-7	ND		0.072	0.0098	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-8	**0.038**	**J q**	0.14	0.0089	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-9	ND		0.072	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-10	ND		0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-11	**0.82**	**B**	0.14	0.0094	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-12	ND	C	0.14	0.0097	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-13	ND	C12	0.14	0.0097	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-14	ND		0.072	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-15	**0.067**	**J q**	0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-16	**0.021**	**J q**	0.072	0.0023	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-17	**0.021**	**J q**	0.072	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-18	**0.058**	**J C**	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	ND		0.072	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-20	**0.17**	**C B**	0.14	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-21	**0.081**	**J C B**	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-22	**0.056**	**J**	0.072	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-23	ND		0.072	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-24	ND		0.072	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-25	**0.0099**	**J**	0.072	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-26	**0.022**	**J C B**	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-27	ND		0.072	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-28	**0.17**	**C20 B**	0.14	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-29	**0.022**	**J C26 B**	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-30	**0.058**	**J C18**	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-31	**0.12**	**J B**	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-32	**0.020**	**J q B**	0.072	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-33	**0.081**	**J C21 B**	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-34	ND		0.072	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-35	**0.0064**	**J q**	0.072	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-36	ND		0.072	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-37	**0.069**	**J**	0.072	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-38	ND		0.072	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-39	ND		0.072	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-40	**0.11**	**J C**	0.22	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-41	**0.11**	**J C40**	0.22	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-42	**0.044**	**J**	0.072	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-43	ND	C	0.14	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-44	**0.25**	**C B**	0.22	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-45	**0.025**	**J q C**	0.14	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-46	ND		0.072	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-47	**0.25**	**C44 B**	0.22	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-48	**0.019**	**J q**	0.072	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-49	**0.12**	**J C**	0.14	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-50	**0.019**	**J q C**	0.14	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-51	**0.025**	**J q C45**	0.14	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-52	**0.33**		0.072	0.0072	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-53	**0.019**	**J q C50**	0.14	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-54	ND		0.072	0.00085	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-55	ND		0.072	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-56	**0.069**	**J**	0.072	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-57	ND		0.072	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-58	ND		0.072	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-59	**0.017**	**J C**	0.22	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-60	**0.043**	**J**	0.072	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-61	**0.35**	**C**	0.29	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-62	**0.017**	**J C59**	0.22	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-63	ND		0.072	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-64	**0.10**		0.072	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-65	**0.25**	**C44 B**	0.22	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-66	**0.17**		0.072	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-67	ND		0.072	0.0047	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.072	0.0048	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-69	**0.12**	**J C49**	0.14	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-70	**0.35**	**C61**	0.29	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-71	**0.11**	**J C40**	0.22	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-72	ND		0.072	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-73	ND	C43	0.14	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-74	**0.35**	**C61**	0.29	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-75	**0.017**	**J C59**	0.22	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-76	**0.35**	**C61**	0.29	0.0051	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-77	**0.058**	**J**	0.072	0.0052	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-78	ND		0.072	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-79	ND		0.072	0.0047	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-80	ND		0.072	0.0046	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-81	ND		0.072	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-82	**0.090**		0.072	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-83	**0.53**	**C**	0.14	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-84	**0.17**		0.072	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-85	**0.15**	**J C B**	0.22	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-86	**0.53**	**C**	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-87	**0.53**	**C86**	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-88	**0.091**	**J C**	0.14	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-89	ND		0.072	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-90	**0.84**	**C B**	0.22	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-91	**0.091**	**J C88**	0.14	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-92	**0.11**	**q**	0.072	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-93	ND	C	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-94	ND		0.072	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-95	**0.72**		0.072	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-96	ND		0.072	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-97	**0.53**	**C86**	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-98	**0.015**	**J C**	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-99	**0.53**	**C83**	0.14	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-100	ND	C93	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-101	**0.84**	**C90 B**	0.22	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-102	**0.015**	**J C98**	0.14	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-103	ND		0.072	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-104	ND		0.072	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-105	**0.30**		0.072	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-106	ND		0.072	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-107	**0.055**	**J q**	0.072	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-108	**0.025**	**J C**	0.14	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-109	**0.53**	**C86**	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-110	**1.3**	**C B**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-111	ND		0.072	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-112	ND		0.072	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-113	**0.84**	**C90 B**	0.22	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-114	**0.0086**	**J q**	0.072	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-115	**1.3**	**C110 B**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-116	**0.15**	**J C85 B**	0.22	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.15	J C85 B	0.22	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-118	0.79		0.072	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-119	0.53	C86	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-120	0.0069	J	0.072	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-121	ND		0.072	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-122	0.010	J	0.072	0.0088	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-123	0.013	J	0.072	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-124	0.025	J C108	0.14	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-125	0.53	C86	0.43	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-126	ND		0.072	0.0085	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-127	ND		0.072	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-128	0.30	C	0.14	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-129	1.9	C B	0.29	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-130	0.11		0.072	0.016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-131	ND		0.072	0.016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-132	0.51		0.072	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-133	0.023	J	0.072	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-134	0.063	J q C	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-135	0.56	C	0.14	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-136	0.16		0.072	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-137	0.055	J q	0.072	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-138	1.9	C129 B	0.29	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-139	0.022	J q C	0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-140	0.022	J q C139	0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-141	0.25	q	0.072	0.014	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-142	ND		0.072	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-143	0.063	J q C134	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-144	0.056	J	0.072	0.0023	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-145	ND		0.072	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-146	0.30		0.072	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-147	1.5	C B	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-148	ND		0.072	0.0024	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-149	1.5	C147 B	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-150	ND		0.072	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-151	0.56	C135	0.14	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-152	ND		0.072	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-153	1.6	C	0.14	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-154	0.021	J q	0.072	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-155	ND		0.072	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-156	0.14	C B	0.14	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-157	0.14	C156 B	0.14	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-158	0.17		0.072	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-159	ND		0.072	0.0098	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-160	1.9	C129 B	0.29	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-161	ND		0.072	0.0097	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-162	ND		0.072	0.0096	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-163	1.9	C129 B	0.29	0.012	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-164	0.12		0.072	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-165	ND		0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.30	C128	0.14	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-167	0.063	J	0.072	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-168	1.6	C153	0.14	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-169	ND		0.072	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-170	0.50		0.072	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-171	0.12	J C	0.14	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-172	0.075		0.072	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-173	0.12	J C171	0.14	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-174	0.44		0.072	0.0056	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-175	0.016	J q	0.072	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-176	0.044	J	0.072	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-177	0.25		0.072	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-178	0.11		0.072	0.0058	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-179	0.19		0.072	0.0043	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-180	1.1	C	0.14	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-181	ND		0.072	0.0054	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-182	0.0052	J	0.072	0.0052	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-183	0.32	C	0.14	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-184	ND		0.072	0.0044	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-185	0.32	C183	0.14	0.0053	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-186	ND		0.072	0.0043	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-187	0.69		0.072	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-188	ND		0.072	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-189	ND		0.072	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-190	0.084		0.072	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-191	0.018	J q	0.072	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-192	ND		0.072	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-193	1.1	C180	0.14	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-194	0.19		0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-195	0.080	q	0.072	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-196	0.099		0.072	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-197	0.0088	J q	0.072	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-198	0.26	C	0.14	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-199	0.26	C198	0.14	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-200	0.019	J q	0.072	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-201	0.025	J q	0.072	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-202	0.051	J q	0.072	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-203	0.13		0.072	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-204	ND		0.072	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-205	ND		0.072	0.0097	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-206	0.16		0.072	0.013	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-207	ND		0.072	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-208	0.045	J	0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
PCB-209	0.082		0.072	0.0085	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Monochlorobiphenyls	0.0098	J q B	0.072	0.00091	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Dichlorobiphenyls	0.93	q B	0.14	0.010	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Trichlorobiphenyls	0.65	q B	0.14	0.0028	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Tetrachlorobiphenyls	1.7	q B	0.29	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Pentachlorobiphenyls	5.8	q B	0.43	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	7.9	q B	0.29	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Heptachlorobiphenyls	4.0	q	0.14	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Octachlorobiphenyls	0.86	q	0.14	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Total Nonachlorobiphenyls	0.21		0.072	0.011	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10
Polychlorinated biphenyls, Total	22	q B	0.43	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 03:25	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*74*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-3L	*68*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-4L	*80*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-15L	*67*	*q*	*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-19L	*84*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-37L	*78*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-54L	*91*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-77L	*86*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-81L	*85*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-104L	*80*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-105L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-114L	*88*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-118L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-123L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-126L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-155L	*91*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-156L	*87*	*C*	*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-157L	*87*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-167L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-169L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-170L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-188L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-189L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-202L	*99*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-205L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-206L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-208L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-209L	*83*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*87*		*5 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-111L	*96*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*
PCB-178L	*99*		*10 - 145*	*10/23/20 04:33*	*11/03/20 03:25*	*10*

Method: 8290A - Dioxins and Furans (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
2,3,7,8-TCDD	0.14	J I	0.70	0.090	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total TCDD	4.2	I	0.70	0.090	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,7,8-PeCDD	1.1	J	3.5	0.075	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total PeCDD	10	I	3.5	0.075	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,4,7,8-HxCDD	1.4	J I B	3.5	0.089	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,6,7,8-HxCDD	1.9	J	3.5	0.087	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,7,8,9-HxCDD	2.6	J	3.5	0.084	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total HxCDD	20	I B	3.5	0.087	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: 8290A - Dioxins and Furans (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2,3,4,6,7,8-HpCDD	22		3.5	0.18	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total HpCDD	48		3.5	0.18	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
OCDD	180	B	7.0	0.15	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
2,3,7,8-TCDF	0.44	J I	0.70	0.16	pg/g	☼	10/23/20 08:34	11/05/20 07:12	1
Total TCDF	13	I	0.70	0.10	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,7,8-PeCDF	0.52	J I	3.5	0.12	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
2,3,4,7,8-PeCDF	0.88	J	3.5	0.11	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total PeCDF	12	I	3.5	0.12	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,4,7,8-HxCDF	1.9	J	3.5	0.11	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,6,7,8-HxCDF	1.1	J I	3.5	0.12	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
2,3,4,6,7,8-HxCDF	0.99	J	3.5	0.12	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,7,8,9-HxCDF	ND		3.5	0.14	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total HxCDF	11	I	3.5	0.12	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,4,6,7,8-HpCDF	9.7	I B	3.5	0.22	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
1,2,3,4,7,8,9-HpCDF	0.84	J I	3.5	0.25	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
Total HpCDF	15	I B	3.5	0.23	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1
OCDF	7.1	B	7.0	0.10	pg/g	☼	10/23/20 08:34	11/04/20 15:45	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
13C-2,3,7,8-TCDD	*34*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,7,8-PeCDD	*30*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,4,7,8-HxCDD	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,6,7,8-HxCDD	*33*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,4,6,7,8-HpCDD	*37*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-OCDD	*31*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-2,3,7,8-TCDF	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-2,3,7,8-TCDF	*35*	*5	*40 - 135*	*10/23/20 08:34*	*11/05/20 07:12*	*1*
13C-1,2,3,7,8-PeCDF	*29*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-2,3,4,7,8-PeCDF	*28*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,4,7,8-HxCDF	*35*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,6,7,8-HxCDF	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-2,3,4,6,7,8-HxCDF	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,7,8,9-HxCDF	*33*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,4,6,7,8-HpCDF	*33*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-1,2,3,4,7,8,9-HpCDF	*35*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*
13C-OCDF	*33*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 15:45*	*1*

Method: EPA 6020A - Metals (ICP/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	1300	^	4.3	4.2	mg/Kg	☼	10/29/20 08:20	11/05/20 10:59	1
Arsenic	1.2		0.072	0.023	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Barium	13		0.72	0.092	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Antimony	0.63		0.14	0.032	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Beryllium	0.069	J	0.072	0.052	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Cadmium	0.13		0.072	0.012	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Calcium	18000	B	36	5.5	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Chromium	5.0		0.14	0.060	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Cobalt	1.9		0.036	0.0093	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Copper	35		0.22	0.15	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Magnesium	8700		36	11	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: 0FS0300N
Date Collected: 10/15/20 13:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-2
Matrix: Sediment
Percent Solids: 69.2

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	110		0.36	0.31	mg/Kg	☼	10/29/20 08:20	11/03/20 18:28	1
Iron	8400		3.6	3.4	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Lead	28		0.072	0.072	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Potassium	160		36	29	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Nickel	12	B	0.072	0.068	mg/Kg	☼	10/29/20 08:20	11/03/20 18:28	1
Selenium	0.088	J	0.36	0.088	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Sodium	190		36	14	mg/Kg	☼	10/29/20 08:20	11/04/20 19:02	1
Silver	0.046	J	0.072	0.020	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Thallium	0.063	J	0.072	0.050	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Vanadium	24		0.072	0.068	mg/Kg	☼	10/29/20 08:20	11/02/20 19:08	1
Zinc	47		0.36	0.35	mg/Kg	☼	10/29/20 08:20	11/03/20 18:28	1

Method: EPA 7471B - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.036	B	0.021	0.014	mg/Kg	☼	10/21/20 08:22	10/22/20 13:55	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	30.8		0.1	0.1	%			10/25/20 15:07	1
Percent Solids	69.2		0.1	0.1	%			10/25/20 15:07	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.43	B	0.18	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-2	0.14	J	0.18	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-3	0.32	B	0.18	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-4	2.2		0.36	0.033	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-5	0.13	J q	0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-6	1.6		0.18	0.022	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-7	0.26	q	0.18	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-8	7.4		0.36	0.021	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-9	0.41	q	0.18	0.024	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-10	0.099	J q	0.18	0.025	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-11	0.58	B	0.36	0.022	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-12	0.86	C	0.36	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-13	0.86	C12	0.36	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-14	ND		0.18	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-15	7.2		0.18	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-16	4.4		0.18	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-17	5.8		0.18	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-18	11	C	0.36	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-19	0.99		0.18	0.0083	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-20	32	C B	0.36	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-21	14	C B	0.36	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-22	10		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-23	ND		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-24	0.18	q	0.18	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-25	2.4		0.18	0.018	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-26	4.5	C B	0.36	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-27	1.1		0.18	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-28	32	C20 B	0.36	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-29	4.5	C26 B	0.36	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-30	11	C18	0.36	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-31	23	B	0.36	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-32	4.6	B	0.18	0.0048	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-33	14	C21 B	0.36	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-34	0.10	J	0.18	0.021	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-35	0.46		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-36	ND		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-37	13		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-38	ND		0.18	0.021	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-39	0.060	J q	0.18	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-40	12	C	0.54	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-41	12	C40	0.54	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-42	5.4		0.18	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-43	0.64	C	0.36	0.037	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-44	19	C B	0.54	0.035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-45	3.4	C	0.36	0.041	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-46	1.0		0.18	0.050	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-47	19	C44 B	0.54	0.035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-48	4.2		0.18	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-49	12	C	0.36	0.032	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	2.4	C	0.36	0.038	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-51	3.4	C45	0.36	0.041	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-52	21		0.18	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-53	2.4	C50	0.36	0.038	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-54	0.058	J	0.18	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-55	0.70		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-56	10		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-57	0.12	J	0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-58	0.061	J q	0.18	0.030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-59	2.0	C	0.54	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-60	5.0		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-61	35	C	0.72	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-62	2.0	C59	0.54	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-63	0.78		0.18	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-64	8.6		0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-65	19	C44 B	0.54	0.035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-66	22		0.18	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-67	0.81		0.18	0.025	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-68	0.072	J q	0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-69	12	C49	0.36	0.032	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-70	35	C61	0.72	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-71	12	C40	0.54	0.039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-72	0.17	J q	0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-73	0.64	C43	0.36	0.037	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-74	35	C61	0.72	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-75	2.0	C59	0.54	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-76	35	C61	0.72	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-77	3.0		0.18	0.027	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-78	ND		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-79	0.16	J q	0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-80	ND		0.18	0.025	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-81	0.073	J q	0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-82	3.7		0.18	0.0047	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-83	15	C	0.36	0.0043	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-84	6.2		0.18	0.0047	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-85	4.8	C B	0.54	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-86	17	C	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-87	17	C86	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-88	3.8	C	0.36	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-89	0.31		0.18	0.0046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-90	29	C B	0.54	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-91	3.8	C88	0.36	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-92	5.0		0.18	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-93	0.39	C	0.36	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-94	0.15	J	0.18	0.0046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-95	22		0.18	0.0044	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-96	0.20		0.18	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-97	17	C86	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-98	0.80	C	0.36	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	15	C83	0.36	0.0043	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-100	0.39	C93	0.36	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-101	29	C90 B	0.54	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-102	0.80	C98	0.36	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-103	0.24		0.18	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-104	ND		0.18	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-105	9.7		0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-106	ND		0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-107	2.1		0.18	0.030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-108	0.98	C	0.36	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-109	17	C86	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-110	33	C B	0.36	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-111	ND		0.18	0.0029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-112	0.083	J q	0.18	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-113	29	C90 B	0.54	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-114	0.53		0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-115	33	C110 B	0.36	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-116	4.8	C85 B	0.54	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-117	4.8	C85 B	0.54	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-118	23		0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-119	17	C86	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-120	0.12	J	0.18	0.0029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-121	ND		0.18	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-122	0.41		0.18	0.032	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-123	0.39		0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-124	0.98	C108	0.36	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-125	17	C86	1.1	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-126	0.21		0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-127	ND		0.18	0.028	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-128	5.4	C	0.36	0.044	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-129	48	C B	0.72	0.046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-130	2.6		0.18	0.060	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-131	0.41		0.18	0.063	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-132	14		0.18	0.059	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-133	0.65		0.18	0.057	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-134	2.1	C	0.36	0.059	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-135	19	C	0.36	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-136	5.6		0.18	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-137	1.3		0.18	0.051	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-138	48	C129 B	0.72	0.046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-139	0.40	q C	0.36	0.051	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-140	0.40	q C139	0.36	0.051	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-141	11		0.18	0.053	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-142	ND		0.18	0.057	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-143	2.1	C134	0.36	0.059	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-144	2.1		0.18	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-145	ND		0.18	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-146	7.6		0.18	0.050	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-147	45	C B	0.36	0.057	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.042	J	0.18	0.0048	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-149	45	C147 B	0.36	0.057	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-150	0.059	J	0.18	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-151	19	C135	0.36	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-152	ND		0.18	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-153	43	C	0.36	0.040	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-154	0.41		0.18	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-155	ND		0.18	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-156	4.1	C B	0.36	0.049	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-157	4.1	C156 B	0.36	0.049	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-158	4.3		0.18	0.036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-159	0.59		0.18	0.038	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-160	48	C129 B	0.72	0.046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-161	ND		0.18	0.038	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-162	0.12	J q	0.18	0.037	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-163	48	C129 B	0.72	0.046	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-164	3.4		0.18	0.040	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-165	ND		0.18	0.043	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-166	5.4	C128	0.36	0.044	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-167	1.7		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-168	43	C153	0.36	0.040	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-169	ND		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-170	19		0.18	0.012	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-171	5.5	C	0.36	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-172	3.6		0.18	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-173	5.5	C171	0.36	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-174	21		0.18	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-175	0.69		0.18	0.010	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-176	2.3		0.18	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-177	11		0.18	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-178	4.1		0.18	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-179	8.8		0.18	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-180	44	C	0.36	0.0085	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-181	0.077	J q	0.18	0.010	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-182	0.10	J	0.18	0.0098	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-183	13	C	0.36	0.010	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-184	ND		0.18	0.0083	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-185	13	C183	0.36	0.010	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-186	ND		0.18	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-187	24		0.18	0.0094	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-188	ND		0.18	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-189	0.64		0.18	0.020	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-190	3.5		0.18	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-191	0.74		0.18	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-192	ND		0.18	0.0086	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-193	44	C180	0.36	0.0085	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-194	9.6		0.18	0.035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-195	3.8		0.18	0.038	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-196	4.6		0.18	0.012	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	0.26	q	0.18	0.0089	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-198	11	C	0.36	0.012	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-199	11	C198	0.36	0.012	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-200	1.1		0.18	0.0079	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-201	1.1		0.18	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-202	1.8		0.18	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-203	6.1		0.18	0.011	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-204	ND		0.18	0.0089	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-205	0.48		0.18	0.029	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-206	3.8		0.18	0.033	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-207	0.37		0.18	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-208	0.90		0.18	0.023	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
PCB-209	0.76		0.18	0.019	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Monochlorobiphenyls	0.89	B	0.18	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Dichlorobiphenyls	21	q B	0.36	0.024	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Trichlorobiphenyls	130	q B	0.36	0.015	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Tetrachlorobiphenyls	170	q B	0.72	0.031	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Pentachlorobiphenyls	180	q B	1.1	0.012	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Hexachlorobiphenyls	220	q B	0.72	0.035	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Heptachlorobiphenyls	160	q	0.36	0.0099	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Octachlorobiphenyls	40	q	0.36	0.016	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Total Nonachlorobiphenyls	5.1		0.18	0.026	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10
Polychlorinated biphenyls, Total	930	q B	1.1	0.021	ng/g	☼	10/23/20 04:33	11/03/20 04:27	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*71*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-3L	*68*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-4L	*78*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-15L	*81*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-19L	*92*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-37L	*79*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-54L	*91*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-77L	*88*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-81L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-104L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-105L	*85*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-114L	*86*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-118L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-123L	*85*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-126L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-155L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-156L	*85*	*C*	*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-157L	*85*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-167L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-169L	*91*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-170L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-188L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-189L	*79*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-202L	*99*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-205L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*

Client Sample ID: SMS0200N
Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-3
Matrix: Sediment
Percent Solids: 27.3

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-206L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-208L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-209L	*84*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*88*		*5 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-111L	*91*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*
PCB-178L	*91*		*10 - 145*	*10/23/20 04:33*	*11/03/20 04:27*	*10*

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	72.7		0.1	0.1	%			10/25/20 15:07	1
Total Organic Carbon - Duplicates	82000		3700	2700	mg/Kg	☼		10/27/20 16:46	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size 0.375 inch - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size #4 - Percent Finer	100.0				% Passing			10/22/20 22:03	1
Sieve Size #10 - Percent Finer	97.6				% Passing			10/22/20 22:03	1
Sieve Size #20 - Percent Finer	95.0				% Passing			10/22/20 22:03	1
Sieve Size #40 - Percent Finer	91.8				% Passing			10/22/20 22:03	1
Sieve Size #60 - Percent Finer	88.5				% Passing			10/22/20 22:03	1
Sieve Size #80 - Percent Finer	86.5				% Passing			10/22/20 22:03	1
Sieve Size #100 - Percent Finer	84.3				% Passing			10/22/20 22:03	1
Sieve Size #200 - Percent Finer	79.5				% Passing			10/22/20 22:03	1
Hydrometer Reading 1 - Percent Finer	41.4				% Passing			10/22/20 22:03	1
Hydrometer Reading 2 - Percent Finer	33.2				% Passing			10/22/20 22:03	1
Hydrometer Reading 3 - Percent Finer	25.0				% Passing			10/22/20 22:03	1
Hydrometer Reading 4 - Percent Finer	20.0				% Passing			10/22/20 22:03	1
Hydrometer Reading 5 - Percent Finer	15.1				% Passing			10/22/20 22:03	1
Hydrometer Reading 6 - Percent Finer	10.1				% Passing			10/22/20 22:03	1
Hydrometer Reading 7 - Percent Finer	8.5				% Passing			10/22/20 22:03	1

Client Sample ID: 0FS0100N

Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4

Matrix: Sediment
Percent Solids: 75.8

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		180	51	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Acenaphthylene	ND		180	38	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Anthracene	ND		180	46	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Benzo[a]anthracene	**93**	**J**	180	79	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Benzo[b]fluoranthene	**130**	**J**	180	43	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Benzo[k]fluoranthene	**55**	**J**	180	53	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Benzo[g,h,i]perylene	ND		180	38	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Benzo[a]pyrene	ND		180	76	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Chrysene	**150**	**J**	180	97	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Dibenz(a,h)anthracene	ND		180	110	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Fluoranthene	**200**		180	46	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Fluorene	ND		180	34	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Indeno[1,2,3-cd]pyrene	ND		180	87	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Naphthalene	ND		180	34	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Phenanthrene	**57**	**J**	180	47	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40
Pyrene	**240**		180	42	ug/Kg	☼	10/23/20 12:09	10/24/20 16:21	40

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*0*	*D X*	*37 - 107*	*10/23/20 12:09*	*10/24/20 16:21*	*40*
Nitrobenzene-d5 (Surr)	*0*	*D X*	*41 - 112*	*10/23/20 12:09*	*10/24/20 16:21*	*40*
Terphenyl-d14 (Surr)	*0*	*D X*	*32 - 115*	*10/23/20 12:09*	*10/24/20 16:21*	*40*

Method: 8015C - Nonhalogenated Organics using GC/FID -Modified (Diesel Range Organics)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
DRO C10-C20	**160**	**J**	220	100	mg/Kg	☼	10/26/20 13:07	10/27/20 15:27	10
Oil Range Organics (C20-C36)	**1600**		220	100	mg/Kg	☼	10/26/20 13:07	10/27/20 15:27	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl (Surr)	*78*		*39 - 120*	*10/26/20 13:07*	*10/27/20 15:27*	*10*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.12**	**B**	0.066	0.00079	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-2	**0.014**	**J**	0.066	0.00094	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-3	**0.051**	**J B**	0.066	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-4	**0.073**	**J**	0.13	0.0096	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-5	ND		0.066	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-6	**0.026**	**J**	0.066	0.0069	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-7	ND		0.066	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-8	**0.13**		0.13	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-9	ND		0.066	0.0072	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-10	ND		0.066	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-11	**0.78**	**B**	0.13	0.0067	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-12	ND	C	0.13	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-13	ND	C12	0.13	0.0070	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-14	ND		0.066	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-15	**0.14**		0.066	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-16	**0.12**	**q**	0.066	0.0023	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-17	**0.12**		0.066	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-18	**0.28**	**q C**	0.13	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Client Sample ID: 0FS0100N
Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4
Matrix: Sediment
Percent Solids: 75.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.031	J q	0.066	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-20	0.54	C B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-21	0.27	C B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-22	0.21		0.066	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-23	ND		0.066	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-24	0.0050	J	0.066	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-25	0.034	J	0.066	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-26	0.078	J C B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-27	0.017	J q	0.066	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-28	0.54	C20 B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-29	0.078	J C26 B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-30	0.28	q C18	0.13	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-31	0.42	B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-32	0.12	B	0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-33	0.27	C21 B	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-34	ND		0.066	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-35	0.017	J q	0.066	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-36	ND		0.066	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-37	0.33		0.066	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-38	ND		0.066	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-39	0.0044	J q	0.066	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-40	0.52	C	0.20	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-41	0.52	C40	0.20	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-42	0.22		0.066	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-43	0.028	J C	0.13	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-44	0.77	C B	0.20	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-45	0.14	q C	0.13	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-46	0.044	J	0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-47	0.77	C44 B	0.20	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-48	0.15		0.066	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-49	0.42	C	0.13	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-50	0.10	J C	0.13	0.0084	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-51	0.14	q C45	0.13	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-52	0.91		0.066	0.0086	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-53	0.10	J C50	0.13	0.0084	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-54	ND		0.066	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-55	0.027	J	0.066	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-56	0.48		0.066	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-57	ND		0.066	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-58	ND		0.066	0.0065	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-59	0.078	J C	0.20	0.0061	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-60	0.28		0.066	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-61	1.6	C	0.26	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-62	0.078	J C59	0.20	0.0061	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-63	0.025	J	0.066	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-64	0.36		0.066	0.0058	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-65	0.77	C44 B	0.20	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-66	0.84		0.066	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-67	0.025	J	0.066	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Client Sample ID: 0FS0100N
Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4
Matrix: Sediment
Percent Solids: 75.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.066	0.0057	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-69	0.42	C49	0.13	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-70	1.6	C61	0.26	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-71	0.52	C40	0.20	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-72	ND		0.066	0.0063	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-73	0.028	J C43	0.13	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-74	1.6	C61	0.26	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-75	0.078	J C59	0.20	0.0061	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-76	1.6	C61	0.26	0.0060	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-77	0.20		0.066	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-78	ND		0.066	0.0065	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-79	0.017	J	0.066	0.0056	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-80	ND		0.066	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-81	0.0071	J	0.066	0.0061	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-82	0.32	q	0.066	0.0022	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-83	1.1	C	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-84	0.57		0.066	0.0022	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-85	0.45	C B	0.20	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-86	1.7	C	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-87	1.7	C86	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-88	0.22	C	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-89	0.017	J	0.066	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-90	2.1	C B	0.20	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-91	0.22	C88	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-92	0.34		0.066	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-93	0.012	J q C	0.13	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-94	ND		0.066	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-95	1.5		0.066	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-96	0.010	J q	0.066	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-97	1.7	C86	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-98	0.035	J q C	0.13	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-99	1.1	C83	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-100	0.012	J q C93	0.13	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-101	2.1	C90 B	0.20	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-102	0.035	J q C98	0.13	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-103	ND		0.066	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-104	ND		0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-105	1.2		0.066	0.0072	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-106	ND		0.066	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-107	0.17		0.066	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-108	0.10	J C	0.13	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-109	1.7	C86	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-110	3.2	C B	0.13	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-111	ND		0.066	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-112	0.0091	J	0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-113	2.1	C90 B	0.20	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-114	0.053	J	0.066	0.0065	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-115	3.2	C110 B	0.13	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-116	0.45	C85 B	0.20	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Client Sample ID: 0FS0100N
Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4
Matrix: Sediment
Percent Solids: 75.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.45	C85 B	0.20	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-118	2.4		0.066	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-119	1.7	C86	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-120	ND		0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-121	ND		0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-122	0.035	J	0.066	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-123	0.052	J	0.066	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-124	0.10	J C108	0.13	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-125	1.7	C86	0.39	0.0016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-126	0.022	J q	0.066	0.0075	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-127	ND		0.066	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-128	0.61	C	0.13	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-129	3.9	C B	0.26	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-130	0.23		0.066	0.017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-131	0.041	J	0.066	0.018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-132	1.2		0.066	0.017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-133	0.026	J	0.066	0.016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-134	0.17	C	0.13	0.017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-135	1.0	C	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-136	0.29		0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-137	0.19		0.066	0.015	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-138	3.9	C129 B	0.26	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-139	0.057	J C	0.13	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-140	0.057	J C139	0.13	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-141	0.75		0.066	0.015	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-142	ND		0.066	0.016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-143	0.17	C134	0.13	0.017	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-144	0.12		0.066	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-145	ND		0.066	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-146	0.45		0.066	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-147	2.8	C B	0.13	0.016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-148	ND		0.066	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-149	2.8	C147 B	0.13	0.016	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-150	ND		0.066	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-151	1.0	C135	0.13	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-152	ND		0.066	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-153	2.8	C	0.13	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-154	0.021	J	0.066	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-155	ND		0.066	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-156	0.46	C B	0.13	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-157	0.46	C156 B	0.13	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-158	0.42		0.066	0.010	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-159	0.025	J q	0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-160	3.9	C129 B	0.26	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-161	ND		0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-162	0.012	J q	0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-163	3.9	C129 B	0.26	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-164	0.26		0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-165	ND		0.066	0.012	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Client Sample ID: 0FS0100N
Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4
Matrix: Sediment
Percent Solids: 75.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.61	C128	0.13	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-167	0.14		0.066	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-168	2.8	C153	0.13	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-169	ND		0.066	0.0083	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-170	1.3		0.066	0.0049	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-171	0.32	C	0.13	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-172	0.18	q	0.066	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-173	0.32	C171	0.13	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-174	1.4		0.066	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-175	0.040	J	0.066	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-176	0.13		0.066	0.0029	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-177	0.65		0.066	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-178	0.29		0.066	0.0041	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-179	0.56		0.066	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-180	2.9	C	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-181	0.011	J q	0.066	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-182	ND		0.066	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-183	0.90	C	0.13	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-184	ND		0.066	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-185	0.90	C183	0.13	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-186	ND		0.066	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-187	1.6		0.066	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-188	ND		0.066	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-189	0.019	J q	0.066	0.0076	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-190	0.21		0.066	0.0027	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-191	0.032	J q	0.066	0.0028	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-192	ND		0.066	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-193	2.9	C180	0.13	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-194	0.81		0.066	0.012	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-195	0.31		0.066	0.013	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-196	0.40		0.066	0.0044	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-197	0.0088	J q	0.066	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-198	0.93	C	0.13	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-199	0.93	C198	0.13	0.0045	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-200	0.090		0.066	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-201	0.094		0.066	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-202	0.17		0.066	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-203	0.54		0.066	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-204	ND		0.066	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-205	0.025	J q	0.066	0.010	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-206	0.27		0.066	0.014	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-207	0.025	J q	0.066	0.010	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-208	0.050	J	0.066	0.011	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
PCB-209	0.034	J q	0.066	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Monochlorobiphenyls	0.19	B	0.066	0.00093	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Dichlorobiphenyls	1.1	B	0.13	0.0073	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Trichlorobiphenyls	2.6	q B	0.13	0.0028	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Tetrachlorobiphenyls	7.2	q B	0.26	0.0068	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Pentachlorobiphenyls	16	q B	0.39	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Client Sample ID: 0FS0100N
Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4
Matrix: Sediment
Percent Solids: 75.8

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	16	q B	0.26	0.010	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Heptachlorobiphenyls	11	q	0.13	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Octachlorobiphenyls	3.4	q	0.13	0.0059	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Total Nonachlorobiphenyls	0.35	q	0.066	0.012	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10
Polychlorinated biphenyls, Total	57	q B	0.39	0.0064	ng/g	☼	10/23/20 04:33	11/03/20 05:28	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*68*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-3L	*64*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-4L	*76*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-15L	*69*	*q*	*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-19L	*79*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-37L	*80*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-54L	*79*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-77L	*82*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-81L	*82*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-104L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-105L	*82*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-114L	*88*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-118L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-123L	*86*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-126L	*94*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-155L	*83*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-156L	*83*	*C*	*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-157L	*83*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-167L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-169L	*87*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-170L	*83*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-188L	*98*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-189L	*80*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-202L	*105*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-205L	*71*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-206L	*74*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-208L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-209L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*88*		*5 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-111L	*88*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*
PCB-178L	*102*		*10 - 145*	*10/23/20 04:33*	*11/03/20 05:28*	*10*

Method: 8290A - Dioxins and Furans (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
2,3,7,8-TCDD	0.25	J	0.64	0.071	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total TCDD	7.8	I	0.64	0.071	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,7,8-PeCDD	1.3	J	3.2	0.22	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total PeCDD	68	I	3.2	0.22	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,4,7,8-HxCDD	1.5	J B	3.2	0.075	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,6,7,8-HxCDD	3.1	J	3.2	0.090	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,7,8,9-HxCDD	3.6		3.2	0.077	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total HxCDD	34	B	3.2	0.081	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1

Client Sample ID: 0FS0100N

Date Collected: 10/15/20 14:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-4

Matrix: Sediment
Percent Solids: 75.8

Method: 8290A - Dioxins and Furans (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2,3,4,6,7,8-HpCDD	53		3.2	0.056	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total HpCDD	270		3.2	0.056	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
OCDD	460	B	6.4	0.059	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
2,3,7,8-TCDF	0.80		0.64	0.10	pg/g	☼	10/23/20 08:34	11/05/20 07:45	1
Total TCDF	17	I	0.64	0.080	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,7,8-PeCDF	0.87	J I	3.2	0.061	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
2,3,4,7,8-PeCDF	1.4	J	3.2	0.053	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total PeCDF	17	I	3.2	0.057	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,4,7,8-HxCDF	2.7	J	3.2	0.055	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,6,7,8-HxCDF	1.6	J	3.2	0.059	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
2,3,4,6,7,8-HxCDF	1.7	J	3.2	0.065	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,7,8,9-HxCDF	0.23	J	3.2	0.070	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total HxCDF	18	I	3.2	0.062	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,4,6,7,8-HpCDF	9.2	B	3.2	0.090	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
1,2,3,4,7,8,9-HpCDF	1.2	J	3.2	0.11	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
Total HpCDF	23	I B	3.2	0.10	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1
OCDF	18	B	6.4	0.050	pg/g	☼	10/23/20 08:34	11/04/20 16:46	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
13C-2,3,7,8-TCDD	*63*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,7,8-PeCDD	*56*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,4,7,8-HxCDD	*65*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,6,7,8-HxCDD	*55*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,4,6,7,8-HpCDD	*65*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-OCDD	*63*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-2,3,7,8-TCDF	*58*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-2,3,7,8-TCDF	*56*		*40 - 135*	*10/23/20 08:34*	*11/05/20 07:45*	*1*
13C-1,2,3,7,8-PeCDF	*53*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-2,3,4,7,8-PeCDF	*52*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,4,7,8-HxCDF	*60*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,6,7,8-HxCDF	*52*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-2,3,4,6,7,8-HxCDF	*52*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,7,8,9-HxCDF	*56*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,4,6,7,8-HpCDF	*62*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-1,2,3,4,7,8,9-HpCDF	*63*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*
13C-OCDF	*69*		*40 - 135*	*10/23/20 08:34*	*11/04/20 16:46*	*1*

Method: EPA 6020A - Metals (ICP/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	1400	^	3.9	3.8	mg/Kg	☼	10/29/20 08:20	11/05/20 11:02	1
Arsenic	0.55		0.065	0.021	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Barium	17		0.65	0.083	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Antimony	0.21		0.13	0.028	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Beryllium	0.050	J	0.065	0.047	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Cadmium	0.31		0.065	0.011	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Calcium	10000	B	32	4.9	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Chromium	4.9		0.13	0.054	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Cobalt	1.8		0.032	0.0084	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Copper	14		0.19	0.13	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Magnesium	3700		32	10	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0FS0100N
Lab Sample ID: 180-112434-4
Date Collected: 10/15/20 14:00
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 75.8

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	72		0.32	0.28	mg/Kg	☼	10/29/20 08:20	11/03/20 18:30	1
Iron	6300		3.2	3.1	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Lead	15		0.065	0.065	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Potassium	140		32	26	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Nickel	4.2	B	0.065	0.061	mg/Kg	☼	10/29/20 08:20	11/03/20 18:30	1
Selenium	ND		0.32	0.079	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Sodium	170		32	13	mg/Kg	☼	10/29/20 08:20	11/04/20 19:05	1
Silver	0.085		0.065	0.018	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Thallium	ND		0.065	0.045	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Vanadium	11		0.065	0.061	mg/Kg	☼	10/29/20 08:20	11/02/20 19:11	1
Zinc	98		0.32	0.31	mg/Kg	☼	10/29/20 08:20	11/03/20 18:30	1

Method: EPA 7471B - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.016	B	0.016	0.010	mg/Kg	☼	10/21/20 08:22	10/22/20 13:56	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	24.2		0.1	0.1	%			10/25/20 15:07	1
Percent Solids	75.8		0.1	0.1	%			10/25/20 15:07	1

Client Sample ID: SMS0300N

Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5

Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.77	B	0.074	0.0021	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-2	0.19		0.074	0.0025	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-3	0.50	B	0.074	0.0029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-4	3.6		0.15	0.011	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-5	0.18		0.074	0.0089	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-6	2.7		0.074	0.0078	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-7	0.40		0.074	0.0080	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-8	9.9		0.15	0.0072	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-9	0.57		0.074	0.0082	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-10	0.16		0.074	0.0088	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-11	2.4	B	0.15	0.0076	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-12	1.1	C	0.15	0.0079	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-13	1.1	C12	0.15	0.0079	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-14	ND		0.074	0.0067	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-15	9.3		0.074	0.0082	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-16	6.2		0.074	0.0024	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-17	8.8		0.074	0.0022	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-18	15	C	0.15	0.0019	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-19	1.9		0.074	0.0026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-20	37	C B	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-21	15	C B	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-22	12		0.074	0.018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-23	0.031	J	0.074	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-24	0.32		0.074	0.0018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-25	4.9		0.074	0.016	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-26	9.4	C B	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-27	1.6		0.074	0.0016	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-28	37	B C20	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-29	9.4	C26 B	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-30	15	C18	0.15	0.0019	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-31	27	B	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-32	6.6	B	0.074	0.0015	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-33	15	B C21	0.15	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-34	0.16		0.074	0.018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-35	0.70		0.074	0.018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-36	ND		0.074	0.017	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-37	14		0.074	0.018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-38	ND		0.074	0.018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-39	ND		0.074	0.016	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-40	17	C	0.22	0.040	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-41	17	C40	0.22	0.040	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-42	9.1		0.074	0.040	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-43	0.89	C	0.15	0.037	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-44	35	C B	0.22	0.035	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-45	6.3	C	0.15	0.042	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-46	1.9		0.074	0.050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-47	35	B C44	0.22	0.035	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-48	4.9		0.074	0.039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-49	27	C	0.15	0.032	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1

Client Sample ID: SMS0300N
Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5
Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-50	5.0	C	0.15	0.038	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-51	6.3	C45	0.15	0.042	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-52	48		0.074	0.039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-53	5.0	C50	0.15	0.038	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-54	0.20		0.074	0.0018	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-55	0.76		0.074	0.029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-56	12		0.074	0.029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-57	0.36		0.074	0.029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-58	0.22		0.074	0.030	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-59	2.9	C	0.22	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-60	5.5		0.074	0.029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-61	47	C	0.29	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-62	2.9	C59	0.22	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-63	1.1		0.074	0.027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-64	12		0.074	0.026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-65	35	B C44	0.22	0.035	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-66	28		0.074	0.027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-67	1.1		0.074	0.025	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-68	0.35		0.074	0.026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-69	27	C49	0.15	0.032	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-70	47	C61	0.29	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-71	17	C40	0.22	0.040	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-72	0.92		0.074	0.029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-73	0.89	C43	0.15	0.037	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-74	47	C61	0.29	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-75	2.9	C59	0.22	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-76	47	C61	0.29	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-77	3.7		0.074	0.028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-78	ND		0.074	0.030	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-79	0.27	q	0.074	0.026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-80	ND		0.074	0.025	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-81	0.13	q	0.074	0.027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-82	4.6		0.074	0.0031	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-83	24	C	0.15	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-84	14		0.074	0.0031	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-85	7.0	C B	0.22	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-86	26	C	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-87	26	C86	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-88	8.2	C	0.15	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-89	0.46		0.074	0.0030	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-90	50	C B	0.22	0.0024	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-91	8.2	C88	0.15	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-92	10		0.074	0.0027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-93	1.2	C	0.15	0.0027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-94	0.46		0.074	0.0030	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-95	53		0.074	0.0029	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-96	0.51		0.074	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-97	26	C86	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-98	1.5	C	0.15	0.0026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1

Client Sample ID: SMS0300N
Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5
Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-99	24	C83	0.15	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-100	1.2	C93	0.15	0.0027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-101	50	B C90	0.22	0.0024	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-102	1.5	C98	0.15	0.0026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-103	0.84		0.074	0.0027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-104	0.026	J q	0.074	0.0020	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-105	13		0.074	0.022	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-106	ND		0.074	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-107	3.2		0.074	0.024	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-108	1.4	C	0.15	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-109	26	C86	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-110	52	C B	0.15	0.0020	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-111	ND		0.074	0.0019	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-112	0.24		0.074	0.0020	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-113	50	B C90	0.22	0.0024	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-114	0.67		0.074	0.022	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-115	52	B C110	0.15	0.0020	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-116	7.0	C85 B	0.22	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-117	7.0	C85 B	0.22	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-118	36		0.074	0.021	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-119	26	C86	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-120	ND		0.074	0.0019	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-121	ND		0.074	0.0020	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-122	0.57		0.074	0.026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-123	0.65		0.074	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-124	1.4	C108	0.15	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-125	26	C86	0.44	0.0023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-126	0.36		0.074	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-127	ND		0.074	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-128	8.8	C	0.15	0.048	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-129	81	C B	0.29	0.050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-130	4.5		0.074	0.066	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-131	0.75		0.074	0.069	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-132	27		0.074	0.065	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-133	1.3		0.074	0.063	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-134	4.0	C	0.15	0.065	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-135	34	C	0.15	0.0039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-136	11		0.074	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-137	2.1		0.074	0.056	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-138	81	B C129	0.29	0.050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-139	0.92	C	0.15	0.056	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-140	0.92	C139	0.15	0.056	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-141	20		0.074	0.058	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-142	ND		0.074	0.062	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-143	4.0	C134	0.15	0.065	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-144	3.8		0.074	0.0036	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-145	ND		0.074	0.0027	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-146	14		0.074	0.055	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-147	86	C B	0.15	0.063	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: SMS0300N
Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5
Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-148	0.12		0.074	0.0038	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-149	86	B C147	0.15	0.063	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-150	0.15		0.074	0.0026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-151	34	C135	0.15	0.0039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-152	0.067	J	0.074	0.0028	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-153	77	C	0.15	0.044	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-154	0.94		0.074	0.0031	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-155	0.0098	J q	0.074	0.0026	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-156	6.3	C B	0.15	0.051	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-157	6.3	C156 B	0.15	0.051	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-158	7.2		0.074	0.039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-159	1.0		0.074	0.042	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-160	81	B C129	0.29	0.050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-161	ND		0.074	0.041	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-162	0.25	q	0.074	0.041	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-163	81	B C129	0.29	0.050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-164	6.0		0.074	0.044	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-165	ND		0.074	0.047	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-166	8.8	C128	0.15	0.048	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-167	2.7		0.074	0.034	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-168	77	C153	0.15	0.044	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-169	ND		0.074	0.032	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-170	32		0.074	0.0081	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-171	9.5	C	0.15	0.0077	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-172	6.0		0.074	0.0077	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-173	9.5	C171	0.15	0.0077	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-174	36		0.074	0.0072	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-175	1.4		0.074	0.0070	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-176	4.3		0.074	0.0053	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-177	19		0.074	0.0074	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-178	7.4		0.074	0.0075	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-179	16		0.074	0.0056	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-180	72	C	0.15	0.0058	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-181	ND		0.074	0.0069	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-182	0.19		0.074	0.0067	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-183	24	C	0.15	0.0068	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-184	ND		0.074	0.0057	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-185	24	C183	0.15	0.0068	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-186	ND		0.074	0.0055	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-187	42		0.074	0.0065	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-188	0.045	J q	0.074	0.0049	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-189	1.0		0.074	0.015	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-190	5.6		0.074	0.0050	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-191	1.3		0.074	0.0052	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-192	ND		0.074	0.0058	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-193	72	C180	0.15	0.0058	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-194	16		0.074	0.023	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-195	6.8		0.074	0.025	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-196	8.0		0.074	0.0087	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1

Client Sample ID: SMS0300N
Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5
Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-197	0.49	q	0.074	0.0067	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-198	18	C	0.15	0.0089	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-199	18	C198	0.15	0.0089	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-200	1.9		0.074	0.0059	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-201	1.9		0.074	0.0061	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-202	3.0		0.074	0.0068	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-203	9.8		0.074	0.0079	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-204	ND		0.074	0.0067	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-205	0.82		0.074	0.019	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-206	5.3		0.074	0.012	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-207	0.59		0.074	0.0081	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-208	1.3		0.074	0.0080	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
PCB-209	0.94		0.074	0.0039	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Monochlorobiphenyls	1.5	B	0.074	0.0025	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Dichlorobiphenyls	30	B	0.15	0.0082	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Trichlorobiphenyls	160	B	0.15	0.012	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Tetrachlorobiphenyls	270	B q	0.29	0.031	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Pentachlorobiphenyls	310	B q	0.44	0.0091	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Hexachlorobiphenyls	400	B q	0.29	0.038	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Heptachlorobiphenyls	280	q	0.15	0.0068	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Octachlorobiphenyls	67	q	0.15	0.011	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Total Nonachlorobiphenyls	7.2		0.074	0.0094	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1
Polychlorinated biphenyls, Total	1500	B q	0.44	0.014	ng/g	☼	10/23/20 04:33	11/04/20 03:11	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*67*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-3L	*68*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-4L	*74*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-15L	*80*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-19L	*89*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-37L	*79*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-54L	*92*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-77L	*76*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-81L	*76*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-104L	*83*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-105L	*85*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-114L	*86*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-118L	*86*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-123L	*85*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-126L	*83*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-155L	*84*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-156L	*83*	*C*	*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-157L	*83*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-167L	*84*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-169L	*86*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-170L	*80*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-188L	*89*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-189L	*80*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-202L	*92*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-205L	*71*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*

Client Sample ID: SMS0300N
Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-5
Matrix: Sediment
Percent Solids: 33.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-206L	*76*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-208L	*79*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-209L	*76*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*84*		*5 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-111L	*83*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*
PCB-178L	*92*		*10 - 145*	*10/23/20 04:33*	*11/04/20 03:11*	*1*

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	66.8		0.1	0.1	%			10/25/20 15:07	1
Total Organic Carbon - Duplicates	75000		3000	2200	mg/Kg	☼		10/27/20 17:03	1

Method: D422 - Grain Size

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sieve Size 3 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size 2 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size 1.5 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size 1 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size 0.75 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size 0.375 inch - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size #4 - Percent Finer	100.0				% Passing			10/22/20 22:05	1
Sieve Size #10 - Percent Finer	97.8				% Passing			10/22/20 22:05	1
Sieve Size #20 - Percent Finer	95.6				% Passing			10/22/20 22:05	1
Sieve Size #40 - Percent Finer	91.5				% Passing			10/22/20 22:05	1
Sieve Size #60 - Percent Finer	87.1				% Passing			10/22/20 22:05	1
Sieve Size #80 - Percent Finer	83.4				% Passing			10/22/20 22:05	1
Sieve Size #100 - Percent Finer	79.5				% Passing			10/22/20 22:05	1
Sieve Size #200 - Percent Finer	66.9				% Passing			10/22/20 22:05	1
Hydrometer Reading 1 - Percent Finer	39.4				% Passing			10/22/20 22:05	1
Hydrometer Reading 2 - Percent Finer	29.9				% Passing			10/22/20 22:05	1
Hydrometer Reading 3 - Percent Finer	25.1				% Passing			10/22/20 22:05	1
Hydrometer Reading 4 - Percent Finer	20.4				% Passing			10/22/20 22:05	1
Hydrometer Reading 5 - Percent Finer	15.6				% Passing			10/22/20 22:05	1
Hydrometer Reading 6 - Percent Finer	10.9				% Passing			10/22/20 22:05	1
Hydrometer Reading 7 - Percent Finer	7.3				% Passing			10/22/20 22:05	1

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		190	54	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Acenaphthylene	**44**	**J**	190	41	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Anthracene	ND		190	48	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Benzo[a]anthracene	**99**	**J**	190	84	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Benzo[b]fluoranthene	**120**	**J**	190	46	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Benzo[k]fluoranthene	ND		190	56	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Benzo[g,h,i]perylene	**150**	**J**	190	40	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Benzo[a]pyrene	**84**	**J**	190	81	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Chrysene	**110**	**J**	190	100	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Dibenz(a,h)anthracene	ND		190	120	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Fluoranthene	**120**	**J**	190	49	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Fluorene	ND		190	37	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Indeno[1,2,3-cd]pyrene	**98**	**J**	190	93	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Naphthalene	ND		190	36	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Phenanthrene	**50**	**J**	190	50	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40
Pyrene	**100**	**J**	190	44	ug/Kg	☼	10/23/20 12:09	10/24/20 16:47	40

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*0*	*D X*	*37 - 107*	*10/23/20 12:09*	*10/24/20 16:47*	*40*
Nitrobenzene-d5 (Surr)	*0*	*D X*	*41 - 112*	*10/23/20 12:09*	*10/24/20 16:47*	*40*
Terphenyl-d14 (Surr)	*0*	*D X*	*32 - 115*	*10/23/20 12:09*	*10/24/20 16:47*	*40*

Method: 8015C - Nonhalogenated Organics using GC/FID -Modified (Diesel Range Organics)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
DRO C10-C20	**35**	**J**	76	35	mg/Kg	☼	10/26/20 13:07	10/28/20 10:32	2
Oil Range Organics (C20-C36)	**540**		76	35	mg/Kg	☼	10/26/20 13:07	10/28/20 10:32	2

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl (Surr)	*86*		*39 - 120*	*10/26/20 13:07*	*10/28/20 10:32*	*2*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.047**	**J B**	0.069	0.00093	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-2	ND		0.069	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-3	**0.043**	**J B q**	0.069	0.0012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-4	**0.067**	**J q**	0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-5	ND		0.069	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-6	**0.063**	**J q**	0.069	0.0089	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-7	**0.015**	**J q**	0.069	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-8	**0.37**		0.14	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-9	ND		0.069	0.0094	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-10	ND		0.069	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-11	**0.24**	**B**	0.14	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-12	**0.056**	**J C**	0.14	0.0090	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-13	**0.056**	**J C12**	0.14	0.0090	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-14	ND		0.069	0.0077	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-15	**0.58**		0.069	0.0094	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-16	**0.076**		0.069	0.0027	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-17	**0.073**	**q**	0.069	0.0024	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-18	**0.17**	**C q**	0.14	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.017	J	0.069	0.0029	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-20	1.1	C B	0.14	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-21	0.43	C B	0.14	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-22	0.34		0.069	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-23	ND		0.069	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-24	0.0044	J	0.069	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-25	0.063	J	0.069	0.0035	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-26	0.12	J C B	0.14	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-27	0.015	J q	0.069	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-28	1.1	B C20	0.14	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-29	0.12	J C26 B	0.14	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-30	0.17	C18 q	0.14	0.0021	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-31	0.75	B	0.14	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-32	0.093	B q	0.069	0.0017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-33	0.43	B C21	0.14	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-34	ND		0.069	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-35	0.022	J	0.069	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-36	ND		0.069	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-37	0.65		0.069	0.0039	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-38	ND		0.069	0.0040	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-39	ND		0.069	0.0036	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-40	0.32	C	0.21	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-41	0.32	C40	0.21	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-42	0.13		0.069	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-43	ND	C	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-44	0.66	C B	0.21	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-45	0.10	J C	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-46	0.024	J q	0.069	0.019	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-47	0.66	B C44	0.21	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-48	0.062	J	0.069	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-49	0.36	C	0.14	0.012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-50	0.076	J C	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-51	0.10	J C45	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-52	1.2		0.069	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-53	0.076	J C50	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-54	ND		0.069	0.00058	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-55	0.029	J	0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-56	0.47		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-57	ND		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-58	ND		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-59	0.076	J C	0.21	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-60	0.25		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-61	1.8	C	0.28	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-62	0.076	J C59	0.21	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-63	0.017	J q	0.069	0.0099	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-64	0.41		0.069	0.0098	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-65	0.66	B C44	0.21	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-66	1.0		0.069	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-67	0.020	J	0.069	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.069	0.0095	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-69	**0.36**	**C49**	0.14	0.012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-70	**1.8**	**C61**	0.28	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-71	**0.32**	**C40**	0.21	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-72	ND		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-73	ND	C43	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-74	**1.8**	**C61**	0.28	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-75	**0.076**	**J C59**	0.21	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-76	**1.8**	**C61**	0.28	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-77	**0.23**		0.069	0.0098	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-78	ND		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-79	**0.014**	**J q**	0.069	0.0095	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-80	ND		0.069	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-81	ND		0.069	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-82	**0.46**		0.069	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-83	**1.7**	**C**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-84	**1.1**		0.069	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-85	**0.67**	**C B**	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-86	**2.3**	**C**	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-87	**2.3**	**C86**	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-88	**0.77**	**C**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-89	**0.024**	**J q**	0.069	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-90	**3.8**	**C B**	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-91	**0.77**	**C88**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-92	**0.76**		0.069	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-93	**0.029**	**J C q**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-94	**0.016**	**J q**	0.069	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-95	**5.3**		0.069	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-96	**0.027**	**J**	0.069	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-97	**2.3**	**C86**	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-98	**0.10**	**J C**	0.14	0.0012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-99	**1.7**	**C83**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-100	**0.029**	**J C93 q**	0.14	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-101	**3.8**	**B C90**	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-102	**0.10**	**J C98**	0.14	0.0012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-103	**0.015**	**J q**	0.069	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-104	ND		0.069	0.00096	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-105	**1.3**		0.069	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-106	ND		0.069	0.0079	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-107	**0.23**	**q**	0.069	0.0085	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-108	**0.15**	**C**	0.14	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-109	**2.3**	**C86**	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-110	**7.8**	**C B**	0.14	0.00092	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-111	ND		0.069	0.00089	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-112	**0.0094**	**J q**	0.069	0.00094	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-113	**3.8**	**B C90**	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-114	**0.058**	**J q**	0.069	0.0075	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-115	**7.8**	**B C110**	0.14	0.00092	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-116	**0.67**	**C85 B**	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.67	C85 B	0.21	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-118	3.0		0.069	0.0074	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-119	2.3	C86	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-120	0.010	J q	0.069	0.00090	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-121	ND		0.069	0.00093	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-122	0.038	J q	0.069	0.0091	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-123	0.042	J q	0.069	0.0078	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-124	0.15	C108	0.14	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-125	2.3	C86	0.41	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-126	0.021	J q	0.069	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-127	ND		0.069	0.0079	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-128	1.6	C	0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-129	12	C B	0.28	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-130	0.71		0.069	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-131	0.12	q	0.069	0.018	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-132	4.2		0.069	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-133	0.13	q	0.069	0.016	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-134	0.67	C	0.14	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-135	5.8	C	0.14	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-136	1.8		0.069	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-137	0.40		0.069	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-138	12	B C129	0.28	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-139	0.14	C	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-140	0.14	C139	0.14	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-141	2.4		0.069	0.015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-142	ND		0.069	0.016	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-143	0.67	C134	0.14	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-144	0.67		0.069	0.0018	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-145	0.0079	J q	0.069	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-146	1.7		0.069	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-147	13	C B	0.14	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-148	ND		0.069	0.0019	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-149	13	B C147	0.14	0.017	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-150	0.0086	J q	0.069	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-151	5.8	C135	0.14	0.0020	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-152	ND		0.069	0.0014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-153	8.4	C	0.14	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-154	0.056	J q	0.069	0.0015	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-155	ND		0.069	0.0013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-156	0.84	C B	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-157	0.84	C156 B	0.14	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-158	1.1		0.069	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-159	0.14		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-160	12	B C129	0.28	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-161	ND		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-162	0.029	J q	0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-163	12	B C129	0.28	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-164	0.99		0.069	0.012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-165	ND		0.069	0.012	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	1.6	C128	0.14	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-167	0.37		0.069	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-168	8.4	C153	0.14	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-169	ND		0.069	0.0081	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-170	4.5		0.069	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-171	1.3	C	0.14	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-172	0.82		0.069	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-173	1.3	C171	0.14	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-174	5.3		0.069	0.0031	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-175	0.18		0.069	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-176	0.57		0.069	0.0023	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-177	2.8		0.069	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-178	1.0		0.069	0.0033	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-179	2.2		0.069	0.0024	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-180	11	C	0.14	0.0026	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-181	ND		0.069	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-182	ND		0.069	0.0029	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-183	3.4	C	0.14	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-184	ND		0.069	0.0025	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-185	3.4	C183	0.14	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-186	ND		0.069	0.0024	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-187	6.1		0.069	0.0028	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-188	ND		0.069	0.0022	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-189	0.13		0.069	0.0075	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-190	0.81		0.069	0.0022	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-191	0.17		0.069	0.0023	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-192	ND		0.069	0.0026	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-193	11	C180	0.14	0.0026	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-194	2.2		0.069	0.013	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-195	0.91		0.069	0.014	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-196	1.1		0.069	0.0055	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-197	0.046	J q	0.069	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-198	2.5	C	0.14	0.0056	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-199	2.5	C198	0.14	0.0056	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-200	0.27		0.069	0.0037	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-201	0.23		0.069	0.0038	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-202	0.40		0.069	0.0043	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-203	1.4		0.069	0.0050	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-204	ND		0.069	0.0042	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-205	0.11		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-206	0.67		0.069	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-207	0.063	J	0.069	0.0082	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-208	0.14		0.069	0.0087	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
PCB-209	0.25		0.069	0.0072	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Monochlorobiphenyls	0.090	B q	0.069	0.0011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Dichlorobiphenyls	1.4	B q	0.14	0.0094	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Trichlorobiphenyls	3.9	B q	0.14	0.0032	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Tetrachlorobiphenyls	7.2	B q	0.28	0.011	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Pentachlorobiphenyls	30	B q	0.41	0.0034	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	57	B q	0.28	0.010	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Heptachlorobiphenyls	40		0.14	0.0030	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Octachlorobiphenyls	9.2	q	0.14	0.0067	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Total Nonachlorobiphenyls	0.87		0.069	0.0093	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10
Polychlorinated biphenyls, Total	150	B q	0.41	0.0071	ng/g	☼	10/23/20 04:33	11/03/20 07:31	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*69*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-3L	*70*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-4L	*74*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-15L	*80*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-19L	*93*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-37L	*79*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-54L	*87*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-77L	*78*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-81L	*75*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-104L	*75*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-105L	*79*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-114L	*78*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-118L	*78*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-123L	*77*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-126L	*78*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-155L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-156L	*80*	*C*	*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-157L	*80*	*C156*	*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-167L	*83*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-169L	*83*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-170L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-188L	*81*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-189L	*72*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-202L	*89*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-205L	*66*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-206L	*71*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-208L	*73*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-209L	*72*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*83*		*5 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-111L	*86*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*
PCB-178L	*88*		*10 - 145*	*10/23/20 04:33*	*11/03/20 07:31*	*10*

Method: 8290A - Dioxins and Furans (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
2,3,7,8-TCDD	1.3		0.68	0.13	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total TCDD	35	I	0.68	0.13	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,7,8-PeCDD	6.9		3.4	0.64	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total PeCDD	190	I	3.4	0.64	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,4,7,8-HxCDD	8.6	B	3.4	0.24	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,6,7,8-HxCDD	14		3.4	0.24	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,7,8,9-HxCDD	22		3.4	0.23	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total HxCDD	170	B	3.4	0.24	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1

Client Sample ID: 0FS0400N
Date Collected: 10/15/20 15:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-6
Matrix: Sediment
Percent Solids: 71.2

Method: 8290A - Dioxins and Furans (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2,3,4,6,7,8-HpCDD	190		3.4	0.16	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total HpCDD	430		3.4	0.16	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
OCDD	3700	E B	6.8	0.21	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
2,3,7,8-TCDF	2.4		0.68	0.47	pg/g	☼	10/23/20 08:34	11/05/20 08:19	1
Total TCDF	110	I	0.68	0.11	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,7,8-PeCDF	3.4		3.4	0.15	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
2,3,4,7,8-PeCDF	5.6		3.4	0.14	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total PeCDF	110	I	3.4	0.14	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,4,7,8-HxCDF	11		3.4	0.32	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,6,7,8-HxCDF	6.9	I	3.4	0.34	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
2,3,4,6,7,8-HxCDF	6.8		3.4	0.39	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,7,8,9-HxCDF	0.59	J	3.4	0.39	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total HxCDF	89	I	3.4	0.36	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,4,6,7,8-HpCDF	29	B	3.4	0.13	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
1,2,3,4,7,8,9-HpCDF	3.6		3.4	0.15	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
Total HpCDF	65	I B	3.4	0.14	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1
OCDF	46	B	6.8	0.21	pg/g	☼	10/23/20 08:34	11/04/20 17:48	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
13C-2,3,7,8-TCDD	*46*		*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,7,8-PeCDD	*42*		*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,4,7,8-HxCDD	*35*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,6,7,8-HxCDD	*37*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,4,6,7,8-HpCDD	*39*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-OCDD	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-2,3,7,8-TCDF	*42*		*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-2,3,7,8-TCDF	*41*		*40 - 135*	*10/23/20 08:34*	*11/05/20 08:19*	*1*
13C-1,2,3,7,8-PeCDF	*39*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-2,3,4,7,8-PeCDF	*37*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,4,7,8-HxCDF	*38*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,6,7,8-HxCDF	*33*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-2,3,4,6,7,8-HxCDF	*32*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,7,8,9-HxCDF	*37*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,4,6,7,8-HpCDF	*35*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-1,2,3,4,7,8,9-HpCDF	*38*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*
13C-OCDF	*37*	*5	*40 - 135*	*10/23/20 08:34*	*11/04/20 17:48*	*1*

Method: EPA 6020A - Metals (ICP/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	3900	^	4.1	4.0	mg/Kg	☼	10/29/20 08:20	11/05/20 11:04	1
Arsenic	7.6		0.069	0.022	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Barium	41		0.69	0.089	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Antimony	0.44		0.14	0.030	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Beryllium	0.46		0.069	0.050	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Cadmium	0.60		0.069	0.012	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Calcium	4600	B	35	5.3	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Chromium	21		0.14	0.058	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Cobalt	7.8		0.035	0.0090	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Copper	55		0.21	0.14	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Magnesium	3100		35	11	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1

Client: AECOM
Job ID: 180-112434-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0FS0400N
Lab Sample ID: 180-112434-6
Date Collected: 10/15/20 15:15
Matrix: Sediment
Date Received: 10/17/20 09:30
Percent Solids: 71.2

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	300		0.35	0.30	mg/Kg	☼	10/29/20 08:20	11/03/20 18:33	1
Iron	30000		3.5	3.3	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Lead	35		0.069	0.069	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Potassium	520		35	28	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Nickel	29	B	0.069	0.065	mg/Kg	☼	10/29/20 08:20	11/03/20 18:33	1
Selenium	0.33	J	0.35	0.084	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Sodium	77		35	14	mg/Kg	☼	10/29/20 08:20	11/04/20 19:07	1
Silver	0.24		0.069	0.019	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Thallium	0.13		0.069	0.048	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Vanadium	75		0.069	0.065	mg/Kg	☼	10/29/20 08:20	11/02/20 19:13	1
Zinc	1200		0.35	0.33	mg/Kg	☼	10/29/20 08:20	11/03/20 18:33	1

Method: EPA 7471B - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.084	B	0.019	0.012	mg/Kg	☼	10/21/20 08:22	10/22/20 13:57	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	28.8		0.1	0.1	%			10/25/20 15:07	1
Percent Solids	71.2		0.1	0.1	%			10/25/20 15:07	1


Particle Size of Soils by ASTM D422

Sample ID:	SMS0100N	**Percent Solids:**	28.5%	**Date Received:**	10/17/2020
Lab ID:	180-112434-A-1	**Specific Gravity:**	2.650	**Start Date:**	10/22/2020
				End Date:	10/28/2020

Shape (> #10): na

Non-soil material: plant

Hardness (> #10): na



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	95.4	4.6
#4	4750	87.6	7.8
#10	2000	82.6	5.0
#20	850	78.9	3.7
#40	425	74.7	4.2
#60	250	70.7	4.0
#80	180	68.5	2.2
#100	150	66.6	1.9
#200	75	62.2	4.4
Hyd1	35.6	21.1	41.1
Hyd2	22.7	17.9	3.2
Hyd3	13.3	14.7	3.2
Hyd4	9.4	13.1	1.6
Hyd5	6.6	9.9	3.2
Hyd6	3.3	6.7	3.2
Hyd7	1.4	3.5	3.2

Soil Classification	Percent of sample
Gravel	12.4
Sand	25.4
Coarse Sand	5.0
Medium Sand	7.9
Fine Sand	12.5
Silt	52.3
Clay	9.9

Particle Size of Soils by ASTM D422


Sample ID: SMS0200N
Lab ID: 180-112434-A-3

Percent Solids: 28.0%
Specific Gravity: 2.650

Date Received: 10/17/2020
Start Date: 10/22/2020
End Date: 10/28/2020

Shape (> #10): na

Non-soil material: plant
Hardness (> #10): na



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	100.0	0.0
#4	4750	100.0	0.0
#10	2000	97.6	2.4
#20	850	95.0	2.6
#40	425	91.8	3.2
#60	250	88.5	3.3
#80	180	86.5	2.0
#100	150	84.3	2.2
#200	75	79.5	4.8
Hyd1	33.5	41.4	38.1
Hyd2	21.8	33.2	8.2
Hyd3	12.9	25.0	8.2
Hyd4	9.2	20.0	5.0
Hyd5	6.8	15.1	4.9
Hyd6	3.3	10.1	5.0
Hyd7	1.4	8.5	1.6

Soil Classification	Percent of sample
Gravel	0.0
Sand	20.5
Coarse Sand	2.4
Medium Sand	5.8
Fine Sand	12.3
Silt	64.4
Clay	15.1


Particle Size of Soils by ASTM D422

Sample ID:	SMS0300N	**Percent Solids:**	37.0%	**Date Received:**	10/17/2020
Lab ID:	180-112434-A-5	**Specific Gravity:**	2.650	**Start Date:**	10/22/2020
				End Date:	10/28/2020

Shape (> #10): na

Non-soil material: plant

Hardness (> #10): na



Sieve size	Particle size, um	Percent finer	Incremental percent
3 inch	75000	100.0	0.0
2 inch	50000	100.0	0.0
1.5 inch	37500	100.0	0.0
1 inch	25000	100.0	0.0
3/4 inch	19000	100.0	0.0
3/8 inch	9500	100.0	0.0
#4	4750	100.0	0.0
#10	2000	97.8	2.2
#20	850	95.6	2.2
#40	425	91.5	4.1
#60	250	87.1	4.4
#80	180	83.4	3.7
#100	150	79.5	3.9
#200	75	66.9	12.6
Hyd1	32	39.4	27.5
Hyd2	21.2	29.9	9.5
Hyd3	12.5	25.1	4.8
Hyd4	9	20.4	4.7
Hyd5	6.3	15.6	4.8
Hyd6	3.3	10.9	4.7
Hyd7	1.4	7.3	3.6

Soil Classification	Percent of sample
Gravel	0.0
Sand	33.1
Coarse Sand	2.2
Medium Sand	6.3
Fine Sand	24.6
Silt	51.3
Clay	15.6

Sediment Grain Size - D422

Client	
Client Sample ID	SMS0100N
Lab Sample ID	180-112434-A-1

Date Received	10/17/2020
Start Date	10/22/2020 22:01
End Date	10/28/2020 12:27

Dry Weight Determination

Tin Weight	1.03	g
Wet Sample + Tin	27.88	g
Dry Sample + Tin	8.69	g
% Moisture	71.47	%

Non-soil material:	plant
Shape (> #10):	na
Hardness (> #10):	na

Date/Time in oven	10/22/2020 22:02
Date/Time out of oven	10/23/2020 15:44

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	47.85	223.65	175.8
Sample Weight (Oven Dried)			50.2

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			8.78
Sample <#10			41.4
% Passing #10			23.5

Hydrometer Data

Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500	447.21	449.54	2.33	g	95.4	Gravel	
#4	4750	487.98	491.90	3.92	g	87.6	Gravel	
#10	2000	462.59	465.12	2.53	g	82.6	Sand	Coarse
#20	850	378.33	380.20	1.87	g	78.9	Sand	Medium
#40	425	366.26	368.38	2.12	g	74.7	Sand	Medium
#60	250	347.91	349.92	2.01	g	70.7	Sand	Fine
#80	180	337.55	338.67	1.12	g	68.5	Sand	Fine
#100	150	327.89	328.86	0.97	g	66.6	Sand	Fine
#200	75	312.66	314.85	2.19	g	62.2	Sand	Fine
				0.00	g	62.2		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	50.2

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0095	20.5	35.6	21.1	Silt	
5	5	1.0085	20.5	22.7	17.9	Silt	
15	15	1.0075	20.5	13.3	14.7	Silt	
30	30	1.0070	20.5	9.4	13.1	Silt	
60	63	1.0060	20.5	6.6	9.86	Silt	
250	253	1.0050	20.5	3.3	6.67	Clay	
1440	1400	1.0040	20.5	1.4	3.47	Clay	

Sediment Grain Size - D422

Client	
Client Sample ID	SMS0200N
Lab Sample ID	180-112434-A-3

Date Received	10/17/2020
Start Date	10/22/2020 22:03
End Date	10/28/2020 12:30

Dry Weight Determination

Tin Weight	1.02	g
Wet Sample + Tin	36.59	g
Dry Sample + Tin	10.97	g
% Moisture	72.03	%

Non-soil material:	plant
Shape (> #10):	na
Hardness (> #10):	na

Date/Time in oven	10/22/2020 22:04
Date/Time out of oven	10/23/2020 15:45

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	47.85	222.28	174.43
Sample Weight (Oven Dried)			48.8

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			1.19
Sample <#10			47.6
% Passing #10			27.3

Hydrometer Data

Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500			0.00	g	100.0	Gravel	
#4	4750			0.00	g	100.0	Gravel	
#10	2000	462.59	463.78	1.19	g	97.6	Sand	Coarse
#20	850	373.62	374.90	1.28	g	95.0	Sand	Medium
#40	425	361.96	363.50	1.54	g	91.8	Sand	Medium
#60	250	351.98	353.57	1.59	g	88.5	Sand	Fine
#80	180	318.91	319.87	0.96	g	86.5	Sand	Fine
#100	150	328.17	329.26	1.09	g	84.3	Sand	Fine
#200	75	314.14	316.50	2.36	g	79.5	Sand	Fine
				0.00	g	79.5		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	48.8

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0155	20.5	33.5	41.4	Silt	
5	5	1.0130	20.5	21.8	33.2	Silt	
15	15	1.0105	20.5	12.9	25	Silt	
30	30	1.0090	20.5	9.2	20	Silt	
60	57	1.0075	20.5	6.8	15.1	Silt	
250	247	1.0060	20.5	3.3	10.1	Clay	
1440	1394	1.0055	20.5	1.4	8.5	Clay	

Sediment Grain Size - D422

Client	
Client Sample ID	SMS0300N
Lab Sample ID	180-112434-A-5

Date Received	10/17/2020
Start Date	10/22/2020 22:05
End Date	10/28/2020 12:38

Dry Weight Determination

Tin Weight	1.02	g
Wet Sample + Tin	28.79	g
Dry Sample + Tin	11.30	g
% Moisture	62.98	%

Non-soil material:	plant
Shape (> #10):	na
Hardness (> #10):	na

Date/Time in oven	10/22/2020 22:06
Date/Time out of oven	10/23/2020 15:45

Sample Weights	Tare (g)	Pan+Samp (g)	Samp (g)
Sample Weight (Wet)	47.86	230.43	182.57
Sample Weight (Oven Dried)			67.6

Sample Split (oven dried)	Tare (g)	Pan+Samp (g)	Samp (g)
Sample >=#10			1.51
Sample <#10			66.1
% Passing #10			36.2

Hydrometer Data

Serial Number	542321
Calib. Date (mm/dd/yyyy)	12/18/2019
Low Temp (C)	17.0
Reading at Low Temp	1.0035
High Temp (C)	23.0
Reading at High Temp	1.0025
Hydrometer Cal Slope	-0.000166667
Hydrometer Cal Intercept	1.006333333
Default Soil Gravity	2.6500

Gravel/Sand Fraction (Sieves)

Sample Fraction	Size (um)	Pan Tare (g)	Pan+Sample (g)	Sample		% Finer	Classification	Sub Class
3 inch	75000			0.00	g	100.0	Gravel	
2 inch	50000			0.00	g	100.0	Gravel	
1.5 inch	37500			0.00	g	100.0	Gravel	
1 inch	25000			0.00	g	100.0	Gravel	
3/4 inch	19000			0.00	g	100.0	Gravel	
3/8 inch	9500			0.00	g	100.0	Gravel	
#4	4750			0.00	g	100.0	Gravel	
#10	2000	462.59	464.10	1.51	g	97.8	Sand	Coarse
#20	850	378.33	379.83	1.50	g	95.6	Sand	Medium
#40	425	366.26	369.03	2.77	g	91.5	Sand	Medium
#60	250	347.91	350.89	2.98	g	87.1	Sand	Fine
#80	180	337.55	340.08	2.53	g	83.4	Sand	Fine
#100	150	327.89	330.54	2.65	g	79.5	Sand	Fine
#200	75	312.66	321.16	8.50	g	66.9	Sand	Fine
				0.00	g	66.9		

Adjusted Hydrometer Sample Mass

Hydrometer Sample Mass (g)	67.6

Silt/Clay Fraction (Hydrometer Test)

Hydrometer Test Time (min)	Actual	Spec. Gravity	Temp C	Particle Size (Micron)	% Finer	Classification	Sub Class
2	2	1.0195	20.5	32	39.4	Silt	
5	5	1.0155	20.5	21.2	29.9	Silt	
15	15	1.0135	20.5	12.5	25.1	Silt	
30	30	1.0115	20.5	9	20.4	Silt	
60	63	1.0095	20.5	6.3	15.6	Silt	
250	241	1.0075	20.5	3.3	10.9	Clay	
1440	1388	1.0060	20.5	1.4	7.33	Clay	

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: MB 180-334547/1-A
Matrix: Sediment
Analysis Batch: 334654

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334547

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		3.4	0.96	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Acenaphthylene	ND		3.4	0.73	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Anthracene	ND		3.4	0.87	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Benzo[a]anthracene	ND		3.4	1.5	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Benzo[b]fluoranthene	ND		3.4	0.82	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Benzo[k]fluoranthene	ND		3.4	1.0	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Benzo[g,h,i]perylene	ND		3.4	0.72	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Benzo[a]pyrene	ND		3.4	1.4	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Chrysene	ND		3.4	1.9	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Dibenz(a,h)anthracene	ND		3.4	2.1	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Fluoranthene	ND		3.4	0.88	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Fluorene	ND		3.4	0.66	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Indeno[1,2,3-cd]pyrene	ND		3.4	1.7	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Naphthalene	ND		3.4	0.65	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Phenanthrene	ND		3.4	0.90	ug/Kg		10/23/20 12:09	10/24/20 13:47	1
Pyrene	ND		3.4	0.79	ug/Kg		10/23/20 12:09	10/24/20 13:47	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*63*		*37 - 107*	*10/23/20 12:09*	*10/24/20 13:47*	*1*
Nitrobenzene-d5 (Surr)	*77*		*41 - 112*	*10/23/20 12:09*	*10/24/20 13:47*	*1*
Terphenyl-d14 (Surr)	*73*		*32 - 115*	*10/23/20 12:09*	*10/24/20 13:47*	*1*

Lab Sample ID: LCS 180-334547/2-A
Matrix: Sediment
Analysis Batch: 334654

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334547

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	333	182		ug/Kg		55	48 - 101
Acenaphthylene	333	177		ug/Kg		53	45 - 104
Anthracene	333	199		ug/Kg		60	50 - 111
Benzo[a]anthracene	333	210		ug/Kg		63	48 - 100
Benzo[b]fluoranthene	333	186		ug/Kg		56	46 - 100
Benzo[k]fluoranthene	333	182		ug/Kg		55	46 - 107
Benzo[g,h,i]perylene	333	219		ug/Kg		66	47 - 105
Benzo[a]pyrene	333	191		ug/Kg		57	48 - 106
Chrysene	333	204		ug/Kg		61	48 - 100
Dibenz(a,h)anthracene	333	221		ug/Kg		66	47 - 106
Fluoranthene	333	200		ug/Kg		60	52 - 100
Fluorene	333	179		ug/Kg		54	49 - 100
Indeno[1,2,3-cd]pyrene	333	213		ug/Kg		64	48 - 105
Naphthalene	333	195		ug/Kg		59	49 - 100
Phenanthrene	333	199		ug/Kg		60	48 - 106
Pyrene	333	202		ug/Kg		61	47 - 100

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*55*		*37 - 107*
Nitrobenzene-d5 (Surr)	*73*		*41 - 112*
Terphenyl-d14 (Surr)	*66*		*32 - 115*

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: 180-112434-2 MS
Matrix: Sediment
Analysis Batch: 334654

Client Sample ID: 0FS0300N
Prep Type: Total/NA
Prep Batch: 334547

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	ND		483	299		ug/Kg	☼	62	48 - 101
Acenaphthylene	ND		483	289		ug/Kg	☼	60	45 - 104
Anthracene	ND		483	342		ug/Kg	☼	71	50 - 111
Benzo[a]anthracene	63	J	483	403		ug/Kg	☼	71	48 - 100
Benzo[b]fluoranthene	77	J	483	380		ug/Kg	☼	63	46 - 100
Benzo[k]fluoranthene	70	J F1 F2	483	296		ug/Kg	☼	47	46 - 107
Benzo[g,h,i]perylene	ND		483	415		ug/Kg	☼	86	47 - 105
Benzo[a]pyrene	ND		483	322		ug/Kg	☼	67	48 - 106
Chrysene	95	J	483	372		ug/Kg	☼	57	48 - 100
Dibenz(a,h)anthracene	ND		483	351		ug/Kg	☼	73	47 - 106
Fluoranthene	98	J	483	427		ug/Kg	☼	68	52 - 100
Fluorene	ND		483	327		ug/Kg	☼	68	49 - 100
Indeno[1,2,3-cd]pyrene	ND		483	367		ug/Kg	☼	76	48 - 105
Naphthalene	ND		483	308		ug/Kg	☼	64	49 - 100
Phenanthrene	44	J	483	344		ug/Kg	☼	62	48 - 106
Pyrene	100	J	483	370		ug/Kg	☼	55	47 - 100

Surrogate	*MS %Recovery*	*MS Qualifier*	*Limits*
2-Fluorobiphenyl	*0*	*D X*	*37 - 107*
Nitrobenzene-d5 (Surr)	*0*	*D X*	*41 - 112*
Terphenyl-d14 (Surr)	*0*	*D X*	*32 - 115*

Lab Sample ID: 180-112434-2 MSD
Matrix: Sediment
Analysis Batch: 334654

Client Sample ID: 0FS0300N
Prep Type: Total/NA
Prep Batch: 334547

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Acenaphthene	ND		483	280		ug/Kg	☼	58	48 - 101	7	22
Acenaphthylene	ND		483	266		ug/Kg	☼	55	45 - 104	8	23
Anthracene	ND		483	297		ug/Kg	☼	62	50 - 111	14	26
Benzo[a]anthracene	63	J	483	385		ug/Kg	☼	67	48 - 100	5	24
Benzo[b]fluoranthene	77	J	483	304		ug/Kg	☼	47	46 - 100	22	26
Benzo[k]fluoranthene	70	J F1 F2	483	232	F1 F2	ug/Kg	☼	34	46 - 107	24	18
Benzo[g,h,i]perylene	ND		483	355		ug/Kg	☼	73	47 - 105	16	22
Benzo[a]pyrene	ND		483	333		ug/Kg	☼	69	48 - 106	3	21
Chrysene	95	J	483	379		ug/Kg	☼	59	48 - 100	2	26
Dibenz(a,h)anthracene	ND		483	321		ug/Kg	☼	66	47 - 106	9	24
Fluoranthene	98	J	483	377		ug/Kg	☼	58	52 - 100	12	26
Fluorene	ND		483	300		ug/Kg	☼	62	49 - 100	9	22
Indeno[1,2,3-cd]pyrene	ND		483	380		ug/Kg	☼	79	48 - 105	4	22
Naphthalene	ND		483	306		ug/Kg	☼	63	49 - 100	1	28
Phenanthrene	44	J	483	301		ug/Kg	☼	53	48 - 106	13	27
Pyrene	100	J	483	360		ug/Kg	☼	53	47 - 100	3	27

Surrogate	*MSD %Recovery*	*MSD Qualifier*	*Limits*
2-Fluorobiphenyl	*0*	*D X*	*37 - 107*
Nitrobenzene-d5 (Surr)	*0*	*D X*	*41 - 112*
Terphenyl-d14 (Surr)	*0*	*D X*	*32 - 115*

Method: 8015C - Nonhalogenated Organics using GC/FID -Modified (Diesel Range Organics)

Lab Sample ID: MB 240-457770/15-A
Matrix: Sediment
Analysis Batch: 457876

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 457770

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
DRO C10-C20	ND		17	7.6	mg/Kg		10/26/20 13:07	10/27/20 14:06	1
Oil Range Organics (C20-C36)	ND		17	7.6	mg/Kg		10/26/20 13:07	10/27/20 14:06	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl (Surr)	*89*		*39 - 120*	*10/26/20 13:07*	*10/27/20 14:06*	*1*

Lab Sample ID: LCS 240-457770/16-A
Matrix: Sediment
Analysis Batch: 457876

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 457770

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Diesel			83.3	66.9		mg/Kg		80	49 - 120		

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
o-Terphenyl (Surr)	*87*		*39 - 120*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Lab Sample ID: MB 140-43801/12-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43801

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	0.000209	J q	0.010	0.000073	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-2	ND		0.010	0.000081	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-3	0.000226	J q	0.010	0.000085	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-4	ND		0.020	0.0011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-5	ND		0.010	0.00092	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-6	ND		0.010	0.00081	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-7	ND		0.010	0.00083	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-8	ND		0.020	0.00075	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-9	ND		0.010	0.00085	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-10	ND		0.010	0.00091	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-11	0.00267	J q	0.020	0.00079	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-12	ND	C	0.020	0.00082	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-13	ND	C12	0.020	0.00082	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-14	ND		0.010	0.00070	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-15	ND		0.010	0.00086	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-16	ND		0.010	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-17	ND		0.010	0.00014	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-18	ND	C	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-19	ND		0.010	0.00017	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-20	0.000621	J q C	0.020	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-21	0.000230	J q C	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-22	ND		0.010	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-23	ND		0.010	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-24	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-25	ND		0.010	0.00014	ng/g		10/23/20 04:33	11/02/20 15:53	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43801/12-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43801

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-26	0.000298	J C	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-27	ND		0.010	0.000099	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-28	0.000621	J q C20	0.020	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-29	0.000298	J C26	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-30	ND	C18	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-31	0.000470	J q	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-32	0.000512	J	0.010	0.000095	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-33	0.000230	J q C21	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-34	ND		0.010	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-35	ND		0.010	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-36	ND		0.010	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-37	ND		0.010	0.00016	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-38	ND		0.010	0.00017	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-39	ND		0.010	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-40	ND	C	0.030	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-41	ND	C40	0.030	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-42	ND		0.010	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-43	ND	C	0.020	0.00038	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-44	0.00331	J q C	0.030	0.00036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-45	ND	C	0.020	0.00043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-46	ND		0.010	0.00052	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-47	0.00331	J q C44	0.030	0.00036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-48	ND		0.010	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-49	ND	C	0.020	0.00033	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-50	ND	C	0.020	0.00040	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-51	ND	C45	0.020	0.00043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-52	ND		0.010	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-53	ND	C50	0.020	0.00040	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-54	ND		0.010	0.000061	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-55	ND		0.010	0.00030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-56	ND		0.010	0.00030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-57	ND		0.010	0.00030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-58	ND		0.010	0.00031	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-59	ND	C	0.030	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-60	ND		0.010	0.00030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-61	ND	C	0.040	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-62	ND	C59	0.030	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-63	ND		0.010	0.00028	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-64	ND		0.010	0.00027	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-65	0.00331	J q C44	0.030	0.00036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-66	ND		0.010	0.00028	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-67	ND		0.010	0.00026	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-68	ND		0.010	0.00027	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-69	ND	C49	0.020	0.00033	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-70	ND	C61	0.040	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-71	ND	C40	0.030	0.00041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-72	ND		0.010	0.00030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-73	ND	C43	0.020	0.00038	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-74	ND	C61	0.040	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43801/12-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43801

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-75	ND	C59	0.030	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-76	ND	C61	0.040	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-77	ND		0.010	0.00028	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-78	ND		0.010	0.00031	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-79	ND		0.010	0.00027	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-80	ND		0.010	0.00026	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-81	ND		0.010	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-82	ND		0.010	0.000048	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-83	ND	C	0.020	0.000043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-84	ND		0.010	0.000048	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-85	0.000291	J q C	0.030	0.000035	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-86	ND	C	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-87	ND	C86	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-88	ND	C	0.020	0.000043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-89	ND		0.010	0.000047	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-90	0.000269	J q C	0.030	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-91	ND	C88	0.020	0.000043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-92	ND		0.010	0.000041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-93	ND	C	0.020	0.000041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-94	ND		0.010	0.000047	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-95	ND		0.010	0.000045	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-96	ND		0.010	0.000035	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-97	ND	C86	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-98	ND	C	0.020	0.000040	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-99	ND	C83	0.020	0.000043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-100	ND	C93	0.020	0.000041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-101	0.000269	J q C90	0.030	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-102	ND	C98	0.020	0.000040	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-103	ND		0.010	0.000041	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-104	ND		0.010	0.000031	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-105	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-106	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-107	ND		0.010	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-108	ND	C	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-109	ND	C86	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-110	0.0000741	J q C	0.020	0.000030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-111	ND		0.010	0.000029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-112	ND		0.010	0.000031	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-113	0.000269	J q C90	0.030	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-114	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-115	0.0000741	J q C110	0.020	0.000030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-116	0.000291	J q C85	0.030	0.000035	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-117	0.000291	J q C85	0.030	0.000035	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-118	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-119	ND	C86	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-120	ND		0.010	0.000029	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-121	ND		0.010	0.000030	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-122	ND		0.010	0.00014	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-123	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43801/12-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43801

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-124	ND	C108	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-125	ND	C86	0.060	0.000036	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-126	ND		0.010	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-127	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-128	ND	C	0.020	0.000095	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-129	0.000364	J q C	0.040	0.000098	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-130	ND		0.010	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-131	ND		0.010	0.00014	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-132	ND		0.010	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-133	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-134	ND	C	0.020	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-135	ND	C	0.020	0.000056	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-136	ND		0.010	0.000040	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-137	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-138	0.000364	J q C129	0.040	0.000098	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-139	ND	C	0.020	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-140	ND	C139	0.020	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-141	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-142	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-143	ND	C134	0.020	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-144	ND		0.010	0.000050	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-145	ND		0.010	0.000038	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-146	ND		0.010	0.00011	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-147	0.000330	J q C	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-148	ND		0.010	0.000054	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-149	0.000330	J q C147	0.020	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-150	ND		0.010	0.000037	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-151	ND	C135	0.020	0.000056	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-152	ND		0.010	0.000039	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-153	ND	C	0.020	0.000086	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-154	ND		0.010	0.000043	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-155	ND		0.010	0.000037	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-156	0.000328	J q C	0.020	0.00010	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-157	0.000328	J q C156	0.020	0.00010	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-158	ND		0.010	0.000077	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-159	ND		0.010	0.000082	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-160	0.000364	J q C129	0.040	0.000098	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-161	ND		0.010	0.000081	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-162	ND		0.010	0.000080	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-163	0.000364	J q C129	0.040	0.000098	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-164	ND		0.010	0.000086	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-165	ND		0.010	0.000092	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-166	ND	C128	0.020	0.000095	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-167	ND		0.010	0.000064	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-168	ND	C153	0.020	0.000086	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-169	ND		0.010	0.000062	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-170	ND		0.010	0.000085	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-171	ND	C	0.020	0.000084	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-172	ND		0.010	0.000083	ng/g		10/23/20 04:33	11/02/20 15:53	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43801/12-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43801

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-173	ND	C171	0.020	0.000084	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-174	ND		0.010	0.000078	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-175	ND		0.010	0.000075	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-176	ND		0.010	0.000057	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-177	ND		0.010	0.000080	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-178	ND		0.010	0.000082	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-179	ND		0.010	0.000060	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-180	ND	C	0.020	0.000063	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-181	ND		0.010	0.000075	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-182	ND		0.010	0.000072	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-183	ND	C	0.020	0.000074	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-184	ND		0.010	0.000062	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-185	ND	C183	0.020	0.000074	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-186	ND		0.010	0.000060	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-187	ND		0.010	0.000070	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-188	ND		0.010	0.000054	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-189	ND		0.010	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-190	ND		0.010	0.000054	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-191	ND		0.010	0.000057	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-192	ND		0.010	0.000063	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-193	ND	C180	0.020	0.000063	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-194	ND		0.010	0.00012	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-195	ND		0.010	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-196	ND		0.010	0.000077	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-197	ND		0.010	0.000059	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-198	ND	C	0.020	0.000079	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-199	ND	C198	0.020	0.000079	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-200	ND		0.010	0.000053	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-201	ND		0.010	0.000054	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-202	ND		0.010	0.000060	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-203	ND		0.010	0.000070	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-204	ND		0.010	0.000059	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-205	ND		0.010	0.00010	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-206	ND		0.010	0.00084	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-207	ND		0.010	0.00058	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-208	ND		0.010	0.00058	ng/g		10/23/20 04:33	11/02/20 15:53	1
PCB-209	ND		0.010	0.000060	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Monochlorobiphenyls	0.000435	J q	0.010	0.000079	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Dichlorobiphenyls	0.00267	J q	0.020	0.00085	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Trichlorobiphenyls	0.00213	J q	0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Tetrachlorobiphenyls	0.00331	J q	0.040	0.00032	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Pentachlorobiphenyls	0.000634	J q	0.060	0.000065	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Hexachlorobiphenyls	0.00102	J q	0.040	0.000085	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Heptachlorobiphenyls	ND		0.020	0.00015	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Octachlorobiphenyls	ND		0.020	0.00013	ng/g		10/23/20 04:33	11/02/20 15:53	1
Total Nonachlorobiphenyls	ND		0.010	0.00084	ng/g		10/23/20 04:33	11/02/20 15:53	1
Polychlorinated biphenyls, Total	0.0102	J q	0.060	0.00029	ng/g		10/23/20 04:33	11/02/20 15:53	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-1L	61		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-3L	61		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-4L	68		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-15L	68		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-19L	79		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-37L	69		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-54L	83		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-77L	73		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-81L	71		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-104L	72		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-105L	85		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-114L	82		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-118L	82		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-123L	80		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-126L	78		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-155L	79		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-156L	81	C	10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-157L	81	C156	10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-167L	81		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-169L	85		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-170L	81		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-188L	84		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-189L	78		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-202L	95		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-205L	71		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-206L	78		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-208L	82		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-209L	76		10 - 145	10/23/20 04:33	11/02/20 15:53	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	80		5 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-111L	85		10 - 145	10/23/20 04:33	11/02/20 15:53	1
PCB-178L	93		10 - 145	10/23/20 04:33	11/02/20 15:53	1

Lab Sample ID: LCS 140-43801/13-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43801

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1	0.500	0.425		ng/g		85	60 - 135
PCB-3	0.500	0.431		ng/g		86	60 - 135
PCB-4	0.500	0.485		ng/g		97	60 - 135
PCB-15	0.500	0.505		ng/g		101	60 - 135
PCB-19	0.500	0.521		ng/g		104	60 - 135
PCB-37	0.500	0.512		ng/g		102	60 - 135
PCB-54	0.500	0.482		ng/g		96	60 - 135
PCB-77	0.500	0.473		ng/g		95	60 - 135
PCB-81	0.500	0.469		ng/g		94	60 - 135
PCB-104	0.500	0.543		ng/g		109	60 - 135
PCB-105	0.500	0.516		ng/g		103	60 - 135
PCB-114	0.500	0.562		ng/g		112	60 - 135

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-43801/13-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43801

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
PCB-118			0.500	0.554		ng/g		111	60 - 135		
PCB-123			0.500	0.593		ng/g		119	60 - 135		
PCB-126			0.500	0.529		ng/g		106	60 - 135		
PCB-155			0.500	0.520		ng/g		104	60 - 135		
PCB-156			1.00	1.06	C	ng/g		106	60 - 135		
PCB-157			1.00	1.06	C156	ng/g		106	60 - 135		
PCB-167			0.500	0.546		ng/g		109	60 - 135		
PCB-169			0.500	0.482		ng/g		96	60 - 135		
PCB-188			0.500	0.521		ng/g		104	60 - 135		
PCB-189			0.500	0.541		ng/g		108	60 - 135		
PCB-202			0.500	0.476		ng/g		95	60 - 135		
PCB-205			0.500	0.581		ng/g		116	60 - 135		
PCB-206			0.500	0.492		ng/g		98	60 - 135		
PCB-208			0.500	0.521		ng/g		104	60 - 135		
PCB-209			0.500	0.559		ng/g		112	60 - 135		

Isotope Dilution	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-1L	*62*		*15 - 145*
PCB-3L	*61*		*15 - 145*
PCB-4L	*68*		*15 - 145*
PCB-15L	*67*		*15 - 145*
PCB-19L	*81*		*15 - 145*
PCB-37L	*70*		*15 - 145*
PCB-54L	*85*		*15 - 145*
PCB-77L	*75*		*40 - 145*
PCB-81L	*73*		*40 - 145*
PCB-104L	*71*		*40 - 145*
PCB-105L	*82*		*40 - 145*
PCB-114L	*80*		*40 - 145*
PCB-118L	*80*		*40 - 145*
PCB-123L	*80*		*40 - 145*
PCB-126L	*78*		*40 - 145*
PCB-155L	*79*		*40 - 145*
PCB-156L	*81*	*C*	*40 - 145*
PCB-157L	*81*	*C156*	*40 - 145*
PCB-167L	*81*		*40 - 145*
PCB-169L	*86*		*40 - 145*
PCB-170L	*81*		*40 - 145*
PCB-188L	*84*		*40 - 145*
PCB-189L	*78*		*40 - 145*
PCB-202L	*96*		*40 - 145*
PCB-205L	*71*		*40 - 145*
PCB-206L	*78*		*40 - 145*
PCB-208L	*82*		*40 - 145*
PCB-209L	*75*		*40 - 145*

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-28L	*81*		*15 - 145*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-43801/13-B
Matrix: Sediment
Analysis Batch: 44124

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43801

Surrogate	LCS %Recovery	LCS Qualifier	Limits
PCB-111L	86		40 - 145
PCB-178L	94		40 - 145

Method: 8290A - Dioxins and Furans (HRGC/HRMS)

Lab Sample ID: MB 140-43808/20-A
Matrix: Sediment
Analysis Batch: 44169

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43808

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
2,3,7,8-TCDD	ND		1.0	0.10	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total TCDD	ND		1.0	0.10	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,7,8-PeCDD	ND		5.0	0.069	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total PeCDD	ND		5.0	0.069	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,4,7,8-HxCDD	0.259	J	5.0	0.070	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,6,7,8-HxCDD	ND		5.0	0.064	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,7,8,9-HxCDD	ND		5.0	0.063	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total HxCDD	0.545	J I	5.0	0.065	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,4,6,7,8-HpCDD	ND		5.0	0.091	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total HpCDD	ND		5.0	0.091	pg/g		10/23/20 08:34	11/04/20 03:01	1
OCDD	0.920	J	10	0.066	pg/g		10/23/20 08:34	11/04/20 03:01	1
2,3,7,8-TCDF	ND		1.0	0.093	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total TCDF	ND		1.0	0.093	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,7,8-PeCDF	ND		5.0	0.068	pg/g		10/23/20 08:34	11/04/20 03:01	1
2,3,4,7,8-PeCDF	ND		5.0	0.062	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total PeCDF	ND		5.0	0.068	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,4,7,8-HxCDF	ND		5.0	0.060	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,6,7,8-HxCDF	ND		5.0	0.065	pg/g		10/23/20 08:34	11/04/20 03:01	1
2,3,4,6,7,8-HxCDF	ND		5.0	0.063	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,7,8,9-HxCDF	ND		5.0	0.074	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total HxCDF	ND		5.0	0.074	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,4,6,7,8-HpCDF	0.155	J I	5.0	0.032	pg/g		10/23/20 08:34	11/04/20 03:01	1
1,2,3,4,7,8,9-HpCDF	ND		5.0	0.040	pg/g		10/23/20 08:34	11/04/20 03:01	1
Total HpCDF	0.155	J I	5.0	0.036	pg/g		10/23/20 08:34	11/04/20 03:01	1
OCDF	0.460	J	10	0.032	pg/g		10/23/20 08:34	11/04/20 03:01	1

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
13C-2,3,7,8-TCDD	61		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,7,8-PeCDD	56		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,4,7,8-HxCDD	62		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,6,7,8-HxCDD	75		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,4,6,7,8-HpCDD	77		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-OCDD	78		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-2,3,7,8-TCDF	59		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,7,8-PeCDF	55		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-2,3,4,7,8-PeCDF	53		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,4,7,8-HxCDF	75		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,6,7,8-HxCDF	66		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-2,3,4,6,7,8-HxCDF	72		40 - 135	10/23/20 08:34	11/04/20 03:01	1

Method: 8290A - Dioxins and Furans (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-43808/20-A
Matrix: Sediment
Analysis Batch: 44169

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 43808

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
13C-1,2,3,7,8,9-HxCDF	73		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,4,6,7,8-HpCDF	74		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-1,2,3,4,7,8,9-HpCDF	77		40 - 135	10/23/20 08:34	11/04/20 03:01	1
13C-OCDF	70		40 - 135	10/23/20 08:34	11/04/20 03:01	1

Lab Sample ID: LCS 140-43808/19-A
Matrix: Sediment
Analysis Batch: 44169

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 43808

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
2,3,7,8-TCDD			20.0	19.1		pg/g		95	79 - 129		
1,2,3,7,8-PeCDD			100	97.3		pg/g		97	79 - 129		
1,2,3,4,7,8-HxCDD			100	110		pg/g		110	73 - 123		
1,2,3,6,7,8-HxCDD			100	102		pg/g		102	74 - 124		
1,2,3,7,8,9-HxCDD			100	110		pg/g		110	70 - 124		
1,2,3,4,6,7,8-HpCDD			100	107		pg/g		107	73 - 123		
OCDD			200	195		pg/g		98	75 - 125		
2,3,7,8-TCDF			20.0	20.4		pg/g		102	75 - 125		
1,2,3,7,8-PeCDF			100	100		pg/g		100	74 - 124		
2,3,4,7,8-PeCDF			100	100		pg/g		100	75 - 125		
1,2,3,4,7,8-HxCDF			100	92.9		pg/g		93	75 - 125		
1,2,3,6,7,8-HxCDF			100	104		pg/g		104	76 - 126		
2,3,4,6,7,8-HxCDF			100	106		pg/g		106	76 - 126		
1,2,3,7,8,9-HxCDF			100	105		pg/g		105	77 - 127		
1,2,3,4,6,7,8-HpCDF			100	96.6		pg/g		97	77 - 127		
1,2,3,4,7,8,9-HpCDF			100	101		pg/g		101	73 - 123		
OCDF			200	221		pg/g		111	49 - 128		

Isotope Dilution	LCS %Recovery	LCS Qualifier	Limits
13C-2,3,7,8-TCDD	62		40 - 135
13C-1,2,3,7,8-PeCDD	56		40 - 135
13C-1,2,3,4,7,8-HxCDD	66		40 - 135
13C-1,2,3,6,7,8-HxCDD	75		40 - 135
13C-1,2,3,4,6,7,8-HpCDD	74		40 - 135
13C-OCDD	74		40 - 135
13C-2,3,7,8-TCDF	58		40 - 135
13C-1,2,3,7,8-PeCDF	52		40 - 135
13C-2,3,4,7,8-PeCDF	53		40 - 135
13C-1,2,3,4,7,8-HxCDF	79		40 - 135
13C-1,2,3,6,7,8-HxCDF	72		40 - 135
13C-2,3,4,6,7,8-HxCDF	74		40 - 135
13C-1,2,3,7,8,9-HxCDF	73		40 - 135
13C-1,2,3,4,6,7,8-HpCDF	77		40 - 135
13C-1,2,3,4,7,8,9-HpCDF	77		40 - 135
13C-OCDF	67		40 - 135

Method: EPA 6020A - Metals (ICP/MS)

Lab Sample ID: MB 180-335170/1-A
Matrix: Sediment
Analysis Batch: 335640

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335170

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.050	0.016	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Barium	ND		0.50	0.064	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Antimony	ND		0.10	0.022	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Beryllium	ND		0.050	0.036	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Cadmium	ND		0.050	0.0085	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Calcium	6.54	J	25	3.8	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Chromium	ND		0.10	0.042	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Cobalt	ND		0.025	0.0065	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Copper	ND		0.15	0.10	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Magnesium	ND		25	7.9	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Iron	ND		2.5	2.4	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Lead	ND		0.050	0.050	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Potassium	ND		25	20	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Selenium	ND		0.25	0.061	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Silver	ND		0.050	0.014	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Thallium	ND		0.050	0.035	mg/Kg		10/29/20 08:20	11/02/20 18:55	1
Vanadium	ND		0.050	0.047	mg/Kg		10/29/20 08:20	11/02/20 18:55	1

Lab Sample ID: MB 180-335170/1-A
Matrix: Sediment
Analysis Batch: 335795

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335170

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	ND		0.25	0.22	mg/Kg		10/29/20 08:20	11/03/20 18:15	1
Nickel	0.107		0.050	0.047	mg/Kg		10/29/20 08:20	11/03/20 18:15	1
Zinc	ND		0.25	0.24	mg/Kg		10/29/20 08:20	11/03/20 18:15	1

Lab Sample ID: MB 180-335170/1-A
Matrix: Sediment
Analysis Batch: 335951

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335170

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sodium	ND		25	10	mg/Kg		10/29/20 08:20	11/04/20 18:52	1

Lab Sample ID: MB 180-335170/1-A
Matrix: Sediment
Analysis Batch: 336056

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335170

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	ND		3.0	2.9	mg/Kg		10/29/20 08:20	11/05/20 10:51	1

Lab Sample ID: LCS 180-335170/2-A
Matrix: Sediment
Analysis Batch: 335640

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335170

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	50.0	43.7		mg/Kg		87	80 - 120
Barium	50.0	45.7		mg/Kg		91	80 - 120
Antimony	12.5	11.5		mg/Kg		92	80 - 120

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 180-335170/2-A
Matrix: Sediment
Analysis Batch: 335640

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335170

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Beryllium	25.0	23.4		mg/Kg		94	80 - 120
Cadmium	25.0	23.7		mg/Kg		95	80 - 120
Calcium	1250	1190		mg/Kg		96	80 - 120
Chromium	25.0	23.8		mg/Kg		95	80 - 120
Cobalt	25.0	22.4		mg/Kg		89	80 - 120
Copper	25.0	22.2		mg/Kg		89	80 - 120
Magnesium	1250	1160		mg/Kg		93	80 - 120
Iron	250	236		mg/Kg		94	80 - 120
Lead	25.0	22.8		mg/Kg		91	80 - 120
Potassium	1250	1100		mg/Kg		88	80 - 120
Selenium	50.0	45.4		mg/Kg		91	80 - 120
Silver	12.5	11.2		mg/Kg		90	80 - 120
Thallium	50.0	45.1		mg/Kg		90	80 - 120
Vanadium	25.0	23.6		mg/Kg		94	80 - 120

Lab Sample ID: LCS 180-335170/2-A
Matrix: Sediment
Analysis Batch: 335795

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335170

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Manganese	25.0	23.1		mg/Kg		92	80 - 120
Nickel	25.0	22.2		mg/Kg		89	80 - 120
Zinc	12.5	12.0		mg/Kg		96	80 - 120

Lab Sample ID: LCS 180-335170/2-A
Matrix: Sediment
Analysis Batch: 336056

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335170

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Aluminum	250	242		mg/Kg		97	80 - 120
Sodium	1250	1350		mg/Kg		108	80 - 120

Method: EPA 7471B - Mercury (CVAA)

Lab Sample ID: MB 180-334165/1-A
Matrix: Sediment
Analysis Batch: 334475

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334165

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.0133	J	0.017	0.011	mg/Kg		10/21/20 08:22	10/22/20 13:32	1

Lab Sample ID: LCS 180-334165/2-A
Matrix: Sediment
Analysis Batch: 334475

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334165

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Mercury	0.208	0.209		mg/Kg		100	80 - 120

Method: 2540G - SM 2540G

Lab Sample ID: 180-112434-6 DU
Matrix: Sediment
Analysis Batch: 334684

Client Sample ID: 0FS0400N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Percent Moisture	28.8			30.8		%				7	10
Percent Solids	71.2			69.2		%				3	10

Method: EPA-Lloyd Kahn - Organic Carbon, Total (TOC)

Lab Sample ID: MB 180-334869/4
Matrix: Sediment
Analysis Batch: 334869

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Organic Carbon - Duplicates	ND		1000	750	mg/Kg			10/24/20 13:39	1

Lab Sample ID: LCS 180-334869/5
Matrix: Sediment
Analysis Batch: 334869

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Total Organic Carbon - Duplicates			37800	32400		mg/Kg		86	75 - 125		

Lab Sample ID: MB 180-335026/4
Matrix: Sediment
Analysis Batch: 335026

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Organic Carbon - Duplicates	ND		1000	750	mg/Kg			10/27/20 12:44	1

Lab Sample ID: LCS 180-335026/5
Matrix: Sediment
Analysis Batch: 335026

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Total Organic Carbon - Duplicates			37800	34800		mg/Kg		92	75 - 125		

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

GC/MS Semi VOA

Prep Batch: 334547

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	3541	
180-112434-4	0FS0100N	Total/NA	Sediment	3541	
180-112434-6	0FS0400N	Total/NA	Sediment	3541	
MB 180-334547/1-A	Method Blank	Total/NA	Sediment	3541	
LCS 180-334547/2-A	Lab Control Sample	Total/NA	Sediment	3541	
180-112434-2 MS	0FS0300N	Total/NA	Sediment	3541	
180-112434-2 MSD	0FS0300N	Total/NA	Sediment	3541	

Analysis Batch: 334654

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 8270D LL	334547
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 8270D LL	334547
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 8270D LL	334547
MB 180-334547/1-A	Method Blank	Total/NA	Sediment	EPA 8270D LL	334547
LCS 180-334547/2-A	Lab Control Sample	Total/NA	Sediment	EPA 8270D LL	334547
180-112434-2 MS	0FS0300N	Total/NA	Sediment	EPA 8270D LL	334547
180-112434-2 MSD	0FS0300N	Total/NA	Sediment	EPA 8270D LL	334547

GC Semi VOA

Prep Batch: 457770

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	3540C	
180-112434-4	0FS0100N	Total/NA	Sediment	3540C	
180-112434-6	0FS0400N	Total/NA	Sediment	3540C	
MB 240-457770/15-A	Method Blank	Total/NA	Sediment	3540C	
LCS 240-457770/16-A	Lab Control Sample	Total/NA	Sediment	3540C	

Analysis Batch: 457876

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	8015C	457770
180-112434-4	0FS0100N	Total/NA	Sediment	8015C	457770
MB 240-457770/15-A	Method Blank	Total/NA	Sediment	8015C	457770
LCS 240-457770/16-A	Lab Control Sample	Total/NA	Sediment	8015C	457770

Analysis Batch: 458086

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-6	0FS0400N	Total/NA	Sediment	8015C	457770

Specialty Organics

Prep Batch: 43801

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	HRMS-Sox	
180-112434-2	0FS0300N	Total/NA	Sediment	HRMS-Sox	
180-112434-3	SMS0200N	Total/NA	Sediment	HRMS-Sox	
180-112434-4	0FS0100N	Total/NA	Sediment	HRMS-Sox	
180-112434-5	SMS0300N	Total/NA	Sediment	HRMS-Sox	
180-112434-6	0FS0400N	Total/NA	Sediment	HRMS-Sox	
MB 140-43801/12-B	Method Blank	Total/NA	Sediment	HRMS-Sox	
LCS 140-43801/13-B	Lab Control Sample	Total/NA	Sediment	HRMS-Sox	

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-1

Specialty Organics

Prep Batch: 43808

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	8290	
180-112434-4	0FS0100N	Total/NA	Sediment	8290	
180-112434-6	0FS0400N	Total/NA	Sediment	8290	
MB 140-43808/20-A	Method Blank	Total/NA	Sediment	8290	
LCS 140-43808/19-A	Lab Control Sample	Total/NA	Sediment	8290	

Cleanup Batch: 43973

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	Split	43801
180-112434-2	0FS0300N	Total/NA	Sediment	Split	43801
180-112434-3	SMS0200N	Total/NA	Sediment	Split	43801
180-112434-4	0FS0100N	Total/NA	Sediment	Split	43801
180-112434-5	SMS0300N	Total/NA	Sediment	Split	43801
180-112434-6	0FS0400N	Total/NA	Sediment	Split	43801
MB 140-43801/12-B	Method Blank	Total/NA	Sediment	Split	43801
LCS 140-43801/13-B	Lab Control Sample	Total/NA	Sediment	Split	43801

Analysis Batch: 44124

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 140-43801/12-B	Method Blank	Total/NA	Sediment	1668C	43973
LCS 140-43801/13-B	Lab Control Sample	Total/NA	Sediment	1668C	43973

Analysis Batch: 44136

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	1668C	43973
180-112434-2	0FS0300N	Total/NA	Sediment	1668C	43973
180-112434-3	SMS0200N	Total/NA	Sediment	1668C	43973
180-112434-4	0FS0100N	Total/NA	Sediment	1668C	43973
180-112434-6	0FS0400N	Total/NA	Sediment	1668C	43973

Analysis Batch: 44166

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-5	SMS0300N	Total/NA	Sediment	1668C	43973

Analysis Batch: 44169

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 140-43808/20-A	Method Blank	Total/NA	Sediment	8290A	43808
LCS 140-43808/19-A	Lab Control Sample	Total/NA	Sediment	8290A	43808

Analysis Batch: 44180

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	8290A	43808
180-112434-4	0FS0100N	Total/NA	Sediment	8290A	43808
180-112434-6	0FS0400N	Total/NA	Sediment	8290A	43808

Analysis Batch: 44206

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	8290A	43808
180-112434-4	0FS0100N	Total/NA	Sediment	8290A	43808
180-112434-6	0FS0400N	Total/NA	Sediment	8290A	43808

Metals

Prep Batch: 334165

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	7471B	
180-112434-4	0FS0100N	Total/NA	Sediment	7471B	
180-112434-6	0FS0400N	Total/NA	Sediment	7471B	
MB 180-334165/1-A	Method Blank	Total/NA	Sediment	7471B	
LCS 180-334165/2-A	Lab Control Sample	Total/NA	Sediment	7471B	

Analysis Batch: 334475

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 7471B	334165
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 7471B	334165
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 7471B	334165
MB 180-334165/1-A	Method Blank	Total/NA	Sediment	EPA 7471B	334165
LCS 180-334165/2-A	Lab Control Sample	Total/NA	Sediment	EPA 7471B	334165

Prep Batch: 335170

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	3050B	
180-112434-4	0FS0100N	Total/NA	Sediment	3050B	
180-112434-6	0FS0400N	Total/NA	Sediment	3050B	
MB 180-335170/1-A	Method Blank	Total/NA	Sediment	3050B	
LCS 180-335170/2-A	Lab Control Sample	Total/NA	Sediment	3050B	

Analysis Batch: 335640

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 6020A	335170
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 6020A	335170
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 6020A	335170
MB 180-335170/1-A	Method Blank	Total/NA	Sediment	EPA 6020A	335170
LCS 180-335170/2-A	Lab Control Sample	Total/NA	Sediment	EPA 6020A	335170

Analysis Batch: 335795

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 6020A	335170
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 6020A	335170
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 6020A	335170
MB 180-335170/1-A	Method Blank	Total/NA	Sediment	EPA 6020A	335170
LCS 180-335170/2-A	Lab Control Sample	Total/NA	Sediment	EPA 6020A	335170

Analysis Batch: 335951

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 6020A	335170
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 6020A	335170
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 6020A	335170
MB 180-335170/1-A	Method Blank	Total/NA	Sediment	EPA 6020A	335170

Analysis Batch: 336056

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-2	0FS0300N	Total/NA	Sediment	EPA 6020A	335170
180-112434-4	0FS0100N	Total/NA	Sediment	EPA 6020A	335170
180-112434-6	0FS0400N	Total/NA	Sediment	EPA 6020A	335170
MB 180-335170/1-A	Method Blank	Total/NA	Sediment	EPA 6020A	335170

Metals (Continued)

Analysis Batch: 336056 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 180-335170/2-A	Lab Control Sample	Total/NA	Sediment	EPA 6020A	335170

General Chemistry

Analysis Batch: 334684

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	2540G	
180-112434-2	0FS0300N	Total/NA	Sediment	2540G	
180-112434-3	SMS0200N	Total/NA	Sediment	2540G	
180-112434-4	0FS0100N	Total/NA	Sediment	2540G	
180-112434-5	SMS0300N	Total/NA	Sediment	2540G	
180-112434-6	0FS0400N	Total/NA	Sediment	2540G	
180-112434-6 DU	0FS0400N	Total/NA	Sediment	2540G	

Analysis Batch: 334869

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	EPA-Lloyd Kahn	
MB 180-334869/4	Method Blank	Total/NA	Sediment	EPA-Lloyd Kahn	
LCS 180-334869/5	Lab Control Sample	Total/NA	Sediment	EPA-Lloyd Kahn	

Analysis Batch: 335026

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-3	SMS0200N	Total/NA	Sediment	EPA-Lloyd Kahn	
180-112434-5	SMS0300N	Total/NA	Sediment	EPA-Lloyd Kahn	
MB 180-335026/4	Method Blank	Total/NA	Sediment	EPA-Lloyd Kahn	
LCS 180-335026/5	Lab Control Sample	Total/NA	Sediment	EPA-Lloyd Kahn	

Geotechnical

Analysis Batch: 160516

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-1	SMS0100N	Total/NA	Sediment	D422	
180-112434-3	SMS0200N	Total/NA	Sediment	D422	
180-112434-5	SMS0300N	Total/NA	Sediment	D422	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: Sharon Drummond	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-63272-12755.2
Client Contact: Mr. Robert Kennedy	Phone: 410.533.7095	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 2 of 2
Company: AECOM		Analysis Requested		Job #:
Address: 250 Apollo Drive	Due Date Requested:			Preservation Codes: A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)
City: Chelmsford	TAT Requested (days): Standard			
State, Zip: MA, 01824				
Phone:	PO #: 126546			Other:
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Grain size (ASTM D 4464 Retention Extended)	TOC Lloyd Kahn	PCB (congeners) (EPA 1668C)	PAHs-primary pollutants (EPA 8270D)	PCDD/Fs (0378 C.E.T.) (EPA 8290A)	TPH - DRO/RO (EPA 8015D)	TAL metals (Total) (EPA 6020A/7471)	Wet Sediment Weight	Percent Solids	Rinsed sediment dry weight	Total Number of containers	Special Instructions/Note:
			Preservation Code:															
SMS0100N	10/15/20	1215	G	S			✓	✓	✓					✓	✓			
OFS0300N	10/15/20	1300	G	S			✓		✓	✓	✓	✓	✓		✓			Total wet sediment weight + % solids from 1-gal jars.
SMS0200N	10/15/20	1355	G	S			✓	✓	✓					✓	✓			
OFS0100N	10/15/20	1400	G	S			✓		✓	✓	✓	✓	✓					
SMS0300N	10/15/20	1500	G	S			✓	✓	✓					✓	✓			
OFS0400N	10/15/20	1515	G	S			✓		✓	✓	✓	✓	✓					OFS samples prioritize chemical analysis if not enough volume for grain size analysis.
SMS0100N-Mat	10/15/20	1215	G	S/Mat												✓		
SMS0200N-Mat	10/15/20	1355	G	S/Mat												✓		
SMS0300N-Mat	10/15/20	1500	G	S/Mat												✓		

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological
Sample Disposal: ☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months (A fee may be assessed if samples are retained longer than 1 month)
Deliverable Requested: I, II, III, IV, Other (specify)
Special Instructions/QC Requirements:

180-112434 Chain of Custody

Empty Kit Relinquished by:		Date:		Time:			
Relinquished by:	Date/Time: 10/15/20 1724	Company: AECOM	Received by:	Date/Time: 10/16/20 10:41	Company: ETA Bait		
Relinquished by:	Date/Time: 10/16/20 1700	Company: ETA Bait	Received by:	Date/Time: 10/17/20 930	Company: ETA Bait		
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company		
Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks:				

Ver: 01/16/2019



Do Not Lift Using This Tag

ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 16OCT20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

FedEx Express

2 of 3
MPS# 0263 7718 2377 6693
Mstr# 7718 2377 6248

SATURDAY 12:00P
PRIORITY OVERNIGHT

0201

15238
PA-US PIT

X0 AGCA

Uncorrected temp 17.8 °C
Thermometer ID 14
CF 0 Initials TB

PT-WI-SR-001 effective 7/26/13

Part # 156297-435 RRDW2 EXP 07/21



Using This Tag

ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US

SHIP DATE: 16OCT20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280

BILL RECIPIENT

TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058 REF: AECOM PEPCO
INV:
PO: DEPT:

FedEx Express

1 of 3
TRK# 0201 7718 2377 6248
MASTER

SATURDAY 12:00P
PRIORITY OVERNIGHT

15238
PA-US PIT

X0 AGCA

Uncorrected temp 15.1 °C
Thermometer ID 14
CF 0 Initials TB

PT

180-112434 Waybill

Part # 156297-435 RRDW2 EXP 07/21


Do Not Lift Using This Tag
539
5
12.00
A
6546
10.17
SHIP DATE: 16OCT20
ACTWGT 20.00 LB
CAD: 1030460/INET4280
BILL RECIPIENT
SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058
REF: AECOM PEPCO
DEPT:
FedEx Express
SATURDAY 12:00P
PRIORITY OVERNIGHT
3 of 3
MPS# 0263 7718 2377 6546
Mstr# 7718 2377 6248
0201
15238
PIT
PA-US
XO AGCA
Uncorrected temp 24 °C
Thermometer ID T4
CF 0 Initials B
PT-WI-SR-001 effective 7/26/13
Part # 156297-435 RRDW2 EXP 07/2

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-415718.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-112434-1
Address: 5815 Middlebrook Pike, ,	Due Date Requested: 11/2/2020			
City: Knoxville	TAT Requested (days):			
State, Zip: TN, 37921				
Phone: 865-291-3000(Tel) 865-584-4315(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:
A - HCL
B - NaOH
C - Zn Acetate
D - Nitric Acid
E - NaHSO4
M - Hexane
N - None
O - AsNaO2
P - Na2O4S
Q - Na2SO3
...2O3
4
...lodecahydrate
...ne
5
specify)

180-112434 Chain of Custody

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Screen_1668/Screen_PCB_P_S	1668C/1668_P_Sox Standard 209 List with Coolutions for Re	8290A/8290_P_Sox 17 Isomers + Totals	Total Number	Special Instructions/Note:
			Preservation Code:								
SMS0100N (180-112434-1)	10/15/20	12:15 Eastern		Sediment			X	X		1	
0FS0300N (180-112434-2)	10/15/20	13:00 Eastern		Sediment			X	X	X	1	
SMS0200N (180-112434-3)	10/15/20	13:55 Eastern		Sediment			X	X		1	
0FS0100N (180-112434-4)	10/15/20	14:00 Eastern		Sediment			X	X	X	1	
SMS0300N (180-112434-5)	10/15/20	15:00 Eastern		Sediment			X	X		1	
0FS0400N (180-112434-6)	10/15/20	15:15 Eastern		Sediment			X	X	X	1	
CUSTODY SEALS INTACT											
RECEIVED AT RT 0.4/CT 0.4°C BAD 10.20.20											
1 COOLER FEDEX # 168951036576 PD											

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	*Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		10/19/20 1700	EHA		10.20.20 09:45	EHA KNX
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Loc: 180
112434

EUROFINS/TESTAMERICA KNOXVILLE SAMPLE RECEIPT/CONDITION UPON RECEIPT ANOMALY CHECKLIST **Log In Number:**

Review Items	Yes	No	NA	If No, what was the problem?
1. Are the shipping containers intact?	✓			☐ **Containers, Broken**
2. Were ambient air containers received intact?			✓	☐ Checked in lab
3. The coolers/containers custody seal if present, is it intact?	✓			☐ Yes ☐ NA
4. Is the cooler temperature within limits? (> freezing temp. of water to 6 °C, VOST: 10°C) Thermometer ID : SC68 Correction factor: 0.0	✓ ✓			☐ **Cooler Out of Temp, Client Contacted, Proceed/Cancel** ☐ **Cooler Out of Temp, Same Day Receipt**
5. Were all of the sample containers received intact?	✓			☐ **Containers, Broken**
6. Were samples received in appropriate containers?	✓			☐ **Containers, Improper; Client Contacted; Proceed/Cancel**
7. Do sample container labels match COC? (IDs, Dates, Times)	✓			☐ **COC & Samples Do Not Match** ☐ **COC Incorrect/Incomplete** ☐ **COC Not Received**
8. Were all of the samples listed on the COC received?	✓			☐ **Sample Received, Not on COC** ☐ **Sample on COC, Not Received**
9. Is the date/time of sample collection noted?	✓			☐ **COC; No Date/Time; Client Contacted**
10. Was the sampler identified on the COC?			✓	☐ **Sampler Not Listed on COC**
11. Is the client and project name/# identified?	✓			☐ **COC Incorrect/Incomplete**
12. Are tests/parameters listed for each sample?	✓			☐ **COC No tests on COC**
13. Is the matrix of the samples noted?	✓			☐ **COC Incorrect/Incomplete**
14. Was COC relinquished? (Signed/Dated/Timed)	✓			☐ **COC Incorrect/Incomplete**
15. Were samples received within holding time?	✓			☐ **Holding Time - Receipt**
16. Were samples received with correct chemical preservative (excluding Encore)?			✓	☐ **pH Adjusted, pH Included (See box 16A)** ☐ **Incorrect Preservative**
17. Were VOA samples received without headspace?			✓	☐ **Headspace (VOA only)**
18. Did you check for residual chlorine, if necessary? (e.g. 1613B, 1668) Chlorine test strip lot number:			✓	☐ **Residual Chlorine**
19. For 1613B water samples is pH<9?			✓	☐ If no, notify lab to adjust
20. For rad samples was sample activity info. Provided?			✓	☐ Project missing info

Comments/Actions Taken

Labeling Verified by: **Date:**

pH test strip lot number:

	Box 16A: pH Preservation	Box 18A: Residual Chlorine
Preservative:		
Lot Number:		
Exp Date:		
Analyst:		
Date:		
Time:		

Project #: _____ PM Instructions: _____

Sample Receiving Associate: _____ Date: 10-20-20

QA026R32.doc, 062719

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

180-112434 Chain of Custody

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L		COC No: 180-415724.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-112434-1
Address: 30 Community Drive, Suite 11,	Due Date Requested: 10/29/2020			
City: South Burlington	TAT Requested (days):			
State, Zip: VT, 05403				
Phone: 802-660-1990(Tel) 802-660-1919(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	D422/ Grain Size (Sieve and Hydrometer)	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
SMS0100N (180-112434-1)	10/15/20	12:15 Eastern		Sediment			X		
SMS0200N (180-112434-3)	10/15/20	13:55 Eastern		Sediment			X		
SMS0300N (180-112434-5)	10/15/20	15:00 Eastern		Sediment			X		

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	***Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)***
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:


Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		10/16/20 1700		Taylor Whitehouse	10/20/20 1130	TAB
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.: NA	Cooler Temperature(s) °C and Other Remarks: 0-9

Ver: 01/16/2019

11/10/2020



ORIGIN ID:AGCA (412) 963-7058
PITTSBURGH SAMPLE RECEIVING
EUROFINS TESTAMERICA PITTSBURGH
301 ALPHA DRIVE

PITTSBURGH, PA 152381330
UNITED STATES US

SHIP DATE: 19OCT20
ACTWGT: 25.00 LB MAN
CAD: 7417337/CAFE3406

BILL SENDER

TO SHIPPING/RECEIVING
TESTAMERICA LABORATORIES, INC.
30 COMMUNITY DRIVE
SUITE 11
SOUTH BURLINGTON VT 05403
(802) 660-1990 REF: S180-64987
PO: YES DEPT: SAMPLE RECEIVING

FedEx Express

TRK# 0201 1689 5103 6624

TUE - 20 OCT 10:30A
PRIORITY OVERNIGHT

NL BTVA

05403
VT-US BTV

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-415739.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-112434-1
Address: 4101 Shuffel Street NW, ,	Due Date Requested: 10/30/2020			
City: North Canton	TAT Requested (days):			
State, Zip: OH, 44720				
Phone: 330-497-9396(Tel) 330-497-0772(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

C 327

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8015C_DRO/3540C (MOD) DRO/ORO (C10-C28, C28-C36)	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
0FS0300N (180-112434-2)	10/15/20	13:00 Eastern		Sediment			X	1	need to link ICVs
0FS0100N (180-112434-4)	10/15/20	14:00 Eastern		Sediment			X	1	need to link ICVs
0FS0400N (180-112434-6)	10/15/20	15:15 Eastern		Sediment			X	1	need to link ICVs

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
Unconfirmed	☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		10/14/2017			10-20-20 1000	
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Eurofins TestAmerica Canton Sample Receipt Form/Narrative **Login # :** _____

Canton Facility

Client EMA Pittsburgh Site Name _____ Cooler unpacked by: _____

Cooler Received on 10-20-20 Opened on 10-20-20

FedEx: 1st Grd Exp UPS FAS Clipper Client Drop Off TestAmerica Courier Other _____

Receipt After-hours: Drop-off Date/Time _____ Storage Location _____

TestAmerica Cooler # _____ Foam Box Client Cooler Box Other _____

Packing material used: Bubble Wrap Foam Plastic Bag None Other _____

COOLANT: Wet Ice Blue Ice Dry Ice Water None

1. Cooler temperature upon receipt ☐ See Multiple Cooler Form

IR GUN# IR-11 (CF +0.9 °C) Observed Cooler Temp._____°C Corrected Cooler Temp._____°C

IR GUN #IR-12 (CF +0.5°C) Observed Cooler Temp._____°C Corrected Cooler Temp._____°C

2. Were tamper/custody seals on the outside of the cooler(s)? If Yes Quantity 8	Yes	No
-Were the seals on the outside of the cooler(s) signed & dated?	Yes	No NA
-Were tamper/custody seals on the bottle(s) or bottle kits (LLHg/MeHg)?	Yes	No
-Were tamper/custody seals intact and uncompromised?	Yes	No NA
3. Shippers' packing slip attached to the cooler(s)?	Yes	No
4. Did custody papers accompany the sample(s)?	Yes	No
5. Were the custody papers relinquished & signed in the appropriate place?	Yes	No
6. Was/were the person(s) who collected the samples clearly identified on the COC?	Yes	No
7. Did all bottles arrive in good condition (Unbroken)?	Yes	No
8. Could all bottle labels (ID/Date/Time) be reconciled with the COC?	Yes	No
9. For each sample, does the COC specify preservatives (Y/N), # of containers (Y/N), and sample type of grab/comp (Y/N)?		
10. Were correct bottle(s) used for the test(s) indicated?	Yes	No
11. Sufficient quantity received to perform indicated analyses?	Yes	No
12. Are these work share samples and all listed on the COC?	Yes	No
If yes, Questions 13-17 have been checked at the originating laboratory.		
13. Were all preserved sample(s) at the correct pH upon receipt?	Yes	No NA pH Strip Lot# HC907861
14. Were VOAs on the COC?	Yes	No
15. Were air bubbles >6 mm in any VOA vials? ● ⬅ Larger than this.	Yes	No NA
16. Was a VOA trip blank present in the cooler(s)? Trip Blank Lot #_____	Yes	No
17. Was a LL Hg or Me Hg trip blank present? _____	Yes	No

Tests that are not checked for pH by Receiving:

VOAs
Oil and Grease
TOC

Contacted PM _____ Date _____ by _____ via Verbal Voice Mail Other

Concerning _____

18. CHAIN OF CUSTODY & SAMPLE DISCREPANCIES ☐ additional next page

Samples processed by:

19. SAMPLE CONDITION

Sample(s) _____ were received after the recommended holding time had expired.

Sample(s) _____ were received in a broken container.

Sample(s) _____ were received with bubble >6 mm in diameter. (Notify PM)

20. SAMPLE PRESERVATION

Sample(s) _____ were further preserved in the laboratory.

Time preserved: _____ Preservative(s) added/Lot number(s): _____

VOA Sample Preservation - Date/Time VOAs Frozen: _____

WI-NC-099

Login # : _____

Eurofins TestAmerica Canton Sample Receipt Multiple Cooler Form

Cooler Description (Circle)	IR Gun # (Circle)	Observed Temp °C	Corrected Temp °C	Coolant (Circle)
(TA) Client Box Other	IR-10 (IR-11)	2.0	2.9	(Wet Ice) Blue Ice Dry Ice Water None
(TA) Client Box Other	IR-10 (IR-11)	1.0	1.9	(Wet Ice) Blue Ice Dry Ice Water None
(TA) Client Box Other	IR-10 (IR-11)	13.4	14.3	Wet Ice Blue Ice Dry Ice Water (None)
(TA) Client Box Other	IR-10 (IR-11)	2.5	3.4	(Wet Ice) Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None
TA Client Box Other	IR-10 IR-11			Wet Ice Blue Ice Dry Ice Water None

☐ See Temperature Excursion Form

WI-NC-099 Cooler Receipt Form Page 2 – Multiple Coolers

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112434-1

Login Number: 112434
List Number: 1
Creator: Say, Thomas C

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112434-1

Login Number: 112434
List Number: 3
Creator: Jaffe, Nat S

List Source: Eurofins TestAmerica, Burlington
List Creation: 10/20/20 12:25 PM

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	Lab does not accept radioactive samples.
The cooler's custody seal, if present, is intact.	True	Seal present with no number.
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	0.9ºC
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	Received project as a subcontract.
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	N/A	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-112434-2
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
11/20/2020 1:54:47 PM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 4
Certification Summary 5
Sample Summary 6
Method Summary 7
Lab Chronicle 8
Client Sample Results 9
QC Sample Results 20
QC Association Summary 21
Chain of Custody 22
Receipt Checklists 26

Job ID: 180-112434-2

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-112434-2

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT

The samples were received on 10/17/2020 9:30 AM; the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 3 coolers at receipt time were 2.4º C, 15.1º C and 17.8º C.

PARTICLE SIZE DISTRIBUTION VIA LASER LIGHT SCATTERING

The relative percent difference between sample SMS0300N (180-112434-12) and the duplicate of this sample was outside of the control limits for Fine Sand (0.125 to 0.25 mm).

Definitions/Glossary

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Qualifiers

Geotechnical

Qualifier	Qualifier Description
F3	Duplicate RPD exceeds the control limit

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins Calscience LLC

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	Los Angeles County Sanitation Districts	10109	09-30-21
California	SCAQMD LAP	17LA0919	11-30-20
California	State	2944	09-30-21
Nevada	State	CA00111	07-31-21
Oregon	NELAP	CA300001	01-29-21
USDA	US Federal Programs	P330-20-00034	02-10-23
Washington	State	C916-18	10-11-21

Sample Summary

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-112434-10	SMS0100N	Solid	10/15/20 12:15	10/17/20 09:30	
180-112434-11	SMS0200N	Solid	10/15/20 13:55	10/17/20 09:30	
180-112434-12	SMS0300N	Solid	10/15/20 15:00	10/17/20 09:30	

Method Summary

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
D4464	Particle Size Distribution of Catalytic Material (Laser light scattering)	ASTM	ECL 1

Protocol References:

ASTM = ASTM International

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

Lab Chronicle

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0100N
Lab Sample ID: 180-112434-10
Date Collected: 10/15/20 12:15
Matrix: Solid
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			110893	11/18/20 16:45	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0200N
Lab Sample ID: 180-112434-11
Date Collected: 10/15/20 13:55
Matrix: Solid
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			110893	11/18/20 16:51	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0300N
Lab Sample ID: 180-112434-12
Date Collected: 10/15/20 15:00
Matrix: Solid
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	D4464		1			110893	11/18/20 16:56	C4LT	ECL 1
	Instrument ID: NOEQUIP									

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

Analyst References:

Lab: ECL 1

Batch Type: Analysis

C4LT = Jordan Stratford

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-2

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112434-10
Matrix: Solid

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**5.72**		0.01	0.01	%			11/18/20 16:45	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			11/18/20 16:45	1
Fine Sand (0.125 to 0.25mm)	**15.96**		0.01	0.01	%			11/18/20 16:45	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			11/18/20 16:45	1
Medium Sand (0.25 to 0.5 mm)	**3.03**		0.01	0.01	%			11/18/20 16:45	1
Silt (0.00391 to 0.0625mm)	**57.76**		0.01	0.01	%			11/18/20 16:45	1
Total Silt and Clay (0 to 0.0626mm)	**63.48**		0.01	0.01	%			11/18/20 16:45	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			11/18/20 16:45	1
Very Fine Sand (0.0625 to 0.125 mm)	**17.54**		0.01	0.01	%			11/18/20 16:45	1

Client Sample Results

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0200N
Lab Sample ID: 180-112434-11
Date Collected: 10/15/20 13:55
Matrix: Solid
Date Received: 10/17/20 09:30

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**5.27**		0.01	0.01	%			11/18/20 16:51	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			11/18/20 16:51	1
Fine Sand (0.125 to 0.25mm)	**10.65**		0.01	0.01	%			11/18/20 16:51	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			11/18/20 16:51	1
Medium Sand (0.25 to 0.5 mm)	**3.05**		0.01	0.01	%			11/18/20 16:51	1
Silt (0.00391 to 0.0625mm)	**67.45**		0.01	0.01	%			11/18/20 16:51	1
Total Silt and Clay (0 to 0.0626mm)	**72.72**		0.01	0.01	%			11/18/20 16:51	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			11/18/20 16:51	1
Very Fine Sand (0.0625 to 0.125 mm)	**13.59**		0.01	0.01	%			11/18/20 16:51	1

Client Sample Results

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0300N
Lab Sample ID: 180-112434-12
Date Collected: 10/15/20 15:00
Matrix: Solid
Date Received: 10/17/20 09:30

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Clay(less than 0.00391 mm)	**6.53**		0.01	0.01	%			11/18/20 16:56	1
Coarse Sand (0.5mm to 1mm)	ND		0.01	0.01	%			11/18/20 16:56	1
Fine Sand (0.125 to 0.25mm)	**9.34**		0.01	0.01	%			11/18/20 16:56	1
Gravel (greater than 2 mm)	ND		0.01	0.01	%			11/18/20 16:56	1
Medium Sand (0.25 to 0.5 mm)	**0.02**		0.01	0.01	%			11/18/20 16:56	1
Silt (0.00391 to 0.0625mm)	**70.76**		0.01	0.01	%			11/18/20 16:56	1
Total Silt and Clay (0 to 0.0626mm)	**77.29**		0.01	0.01	%			11/18/20 16:56	1
Very Coarse Sand (1 to 2mm)	ND		0.01	0.01	%			11/18/20 16:56	1
Very Fine Sand (0.0625 to 0.125 mm)	**13.35**		0.01	0.01	%			11/18/20 16:56	1

PARTICLE SIZE SUMMARY


(ASTM D422 / D4464M)

AECOM		Date Sampled:	10/15/20
		Date Received:	11/17/20
		Work Order No:	180-112434
		Date Analyzed:	11/18/20
		Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
SMS0100N		Very Fine Sand	0.068

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	3.03	15.96	17.54	57.76	5.72	63.48



V 3.0

PARTICLE SIZE SUMMARY


(ASTM D422 / D4464M)

AECOM		Date Sampled:	10/15/20
		Date Received:	11/17/20
		Work Order No:	180-112434
		Date Analyzed:	11/18/20
		Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
SMS0200N		Silt	0.058

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	3.05	10.65	13.59	67.45	5.27	72.72



V 3.0

PARTICLE SIZE SUMMARY


(ASTM D422 / D4464M)

AECOM		Date Sampled:	10/15/20
		Date Received:	11/17/20
		Work Order No:	180-112434
		Date Analyzed:	11/18/20
		Method:	ASTM D4464M

Project: Pepco Benning Road Facility

Sample ID	Depth ft	Description	Mean Grain Size mm
SMS0300N		Silt	0.041

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	0.00	7.08	13.91	72.30	6.71	79.01



V 3.0

PARTICLE SIZE SUMMARY

(ASTM D422 / D4464M)


AECOM

Date Sampled:	10/15/20
Date Received:	11/17/20
Work Order No:	180-112434
Date Analyzed:	11/18/20
Method:	ASTM D4464M

Project: Pepco Benning Road Facility


Sample ID	Depth ft	Description	Mean Grain Size mm
SMS0300N		Silt	0.045

Particle Size Distribution, wt by percent								
Total Gravel	Very Coarse Sand	Coarse Sand	Medium Sand	Fine Sand	Very Fine Sand	Silt	Clay	Total Silt & Clay
0.00	0.00	0.00	0.02	9.34	13.35	70.76	6.53	77.29



V 3.0

File name:	C:\LS13320\STD SAND_18 Nov 2020_17.04.49.$ls		
	STD SAND_18 Nov 2020_17.04.49.$ls		
File ID:	STD SAND		
Sample ID:	STD SAND		
Operator:	1106		
Run number:	5		
	Control Sample		
Comment 1:	ASTM D4464M , LPSA 1		
Comment 2:	1048387		
Optical model:	Fraunhofer.rf780d		
Residual:	0.96%		
LS 13 320	Aqueous Liquid Module		
Start time:	17:03 18 Nov 2020	Run length:	60 seconds
Pump speed:	49		
Obscuration:	10%		
Fluid:	Water		
Software:	6.01	Firmware:	4.00



Volume Statistics (Arithmetic) STD SAND_18 Nov 2020_17.04.49.$ls

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	217.3 µm	S.D.:	61.40 µm
Median:	210.5 µm	Variance:	3770 µm^2
Mean/Median ratio:	1.032	Skewness:	0.517 Right skewed
Mode:	203.5 µm	Kurtosis:	0.030 Leptokurtic

d_{10}: 143.6 µm d_{50}: 210.5 µm d_{90}: 302.6 µm

Folk and Ward Statistics (Phi)

Mean:	2.25	Median:	2.25	Deviation:	0.42
Skewness:	0.03	Kurtosis:	0.97		


<5%	<16%	<25%	<40%	<50%	<75%	<84%	<95%
128.9 µm	156.2 µm	171.9 µm	195.1 µm	210.5 µm	256.1 µm	279.9 µm	331.2 µm

Particle Diameter µm	STD SAND _18 Nov 2020_17.04 .49.$ls Volume %
0.04	0
0.4	0
1.95	0
3.91	0
62.5	3.99
125	68.0
250	28.0
500	0
1000	0
2000	

STD SAND_18 Nov 2020_17.04.49.$ls

Channel Diameter (Lower) µm	Diff. Volume %	Channel Diameter (Lower) µm	Diff. Volume %	Channel Diameter (Lower) µm	Diff. Volume %
0.375	0	24.95	0	1660	0
0.412	0	27.39	0	1822	0
0.452	0	30.07	0	2000	
0.496	0	33.01	0		
0.545	0	36.24	0		
0.598	0	39.78	0		
0.657	0	43.67	0		
0.721	0	47.94	0		
0.791	0	52.63	0		
0.869	0	57.77	0		
0.954	0	63.42	0.015		
1.047	0	69.62	0.13		
1.149	0	76.43	0.21		
1.261	0	83.90	0.19		
1.385	0	92.10	0.32		
1.520	0	101.1	0.72		
1.669	0	111.0	1.59		
1.832	0	121.8	3.05		
2.011	0	133.7	5.01		
2.208	0	146.8	7.29		
2.423	0	161.2	9.53		
2.660	0	176.9	11.3		
2.920	0	194.2	12.4		
3.206	0	213.2	12.4		
3.519	0	234.1	11.3		
3.863	0	256.9	9.37		
4.241	0	282.1	6.98		
4.656	0	309.6	4.54		
5.111	0	339.9	2.48		
5.611	0	373.1	1.00		
6.159	0	409.6	0.20		
6.761	0	449.7	0.0097		
7.422	0	493.6	0		
8.148	0	541.9	0		
8.944	0	594.9	0		
9.819	0	653.0	0		
10.78	0	716.9	0		
11.83	0	786.9	0		
12.99	0	863.9	0		
14.26	0	948.3	0		
15.65	0	1041	0		
17.18	0	1143	0		
18.86	0	1255	0		
20.71	0	1377	0		
22.73	0	1512	0		

File name:	C:\LS13320\STD SAND_18 Nov 2020_17.17.40.$ls		
	STD SAND_18 Nov 2020_17.17.40.$ls		
File ID:	STD SAND		
Sample ID:	STD SAND		
Operator:	1106		
Run number:	7		
	Control Sample		
Comment 1:	ASTM D4464M , LPSA 1		
Comment 2:	1048387		
Optical model:	Fraunhofer.rf780d		
Residual:	1.26%		
LS 13 320	Aqueous Liquid Module		
Start time:	17:16 18 Nov 2020	Run length:	60 seconds
Pump speed:	49		
Obscuration:	9%		
Fluid:	Water		
Software:	6.01	Firmware:	4.00



Volume Statistics (Arithmetic) STD SAND_18 Nov 2020_17.17.40.$ls

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	217.5 µm	S.D.:	61.13 µm
Median:	210.7 µm	Variance:	3736 µm^2
Mean/Median ratio:	1.033	Skewness:	0.521 Right skewed
Mode:	203.5 µm	Kurtosis:	0.040 Leptokurtic

d_{10}: 144.3 µm d_{50}: 210.7 µm d_{90}: 302.5 µm

Folk and Ward Statistics (Phi)

Mean:	2.25	Median:	2.25	Deviation:	0.41
Skewness:	0.03	Kurtosis:	0.97		

<5%	<16%	<25%	<40%	<50%	<75%	<84%	<95%
129.8 µm	156.8 µm	172.3 µm	195.4 µm	210.7 µm	256.1 µm	279.9 µm	331.0 µm

Particle Diameter µm	STD SAND _18 Nov 2020_17.17 .40.$ls Volume %
0.04	0
0.4	0
1.95	0
3.91	0
62.5	3.80
125	68.2
250	28.0
500	0
1000	0
2000	

STD SAND_18 Nov 2020_17.17.40.$ls

Channel Diameter (Lower) µm	Diff. Volume %	Channel Diameter (Lower) µm	Diff. Volume %	Channel Diameter (Lower) µm	Diff. Volume %
0.375	0	24.95	0	1660	0
0.412	0	27.39	0	1822	0
0.452	0	30.07	0	2000	
0.496	0	33.01	0		
0.545	0	36.24	0		
0.598	0	39.78	0		
0.657	0	43.67	0		
0.721	0	47.94	0		
0.791	0	52.63	0		
0.869	0	57.77	0		
0.954	0	63.42	0.015		
1.047	0	69.62	0.14		
1.149	0	76.43	0.21		
1.261	0	83.90	0.18		
1.385	0	92.10	0.28		
1.520	0	101.1	0.66		
1.669	0	111.0	1.52		
1.832	0	121.8	2.98		
2.011	0	133.7	4.97		
2.208	0	146.8	7.28		
2.423	0	161.2	9.57		
2.660	0	176.9	11.4		
2.920	0	194.2	12.4		
3.206	0	213.2	12.4		
3.519	0	234.1	11.3		
3.863	0	256.9	9.39		
4.241	0	282.1	6.97		
4.656	0	309.6	4.53		
5.111	0	339.9	2.47		
5.611	0	373.1	0.99		
6.159	0	409.6	0.20		
6.761	0	449.7	0.0090		
7.422	0	493.6	0		
8.148	0	541.9	0		
8.944	0	594.9	0		
9.819	0	653.0	0		
10.78	0	716.9	0		
11.83	0	786.9	0		
12.99	0	863.9	0		
14.26	0	948.3	0		
15.65	0	1041	0		
17.18	0	1143	0		
18.86	0	1255	0		
20.71	0	1377	0		
22.73	0	1512	0		

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112434-2

Method: D4464 - Particle Size Distribution of Catalytic Material (Laser light scattering)

Lab Sample ID: 180-112434-12 DU
Matrix: Solid
Analysis Batch: 110893

Client Sample ID: SMS0300N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Clay(less than 0.00391 mm)	6.53			6.71		%				3	20
Coarse Sand (0.5mm to 1mm)	ND			ND		%				NC	20
Fine Sand (0.125 to 0.25mm)	9.34			7.08	F3	%				28	20
Gravel (greater than 2 mm)	ND			ND		%				NC	20
Medium Sand (0.25 to 0.5 mm)	0.02			ND		%				NC	20
Silt (0.00391 to 0.0625mm)	70.76			72.30		%				2	20
Total Silt and Clay (0 to 0.0626mm)	77.29			79.01		%				2	20
Very Coarse Sand (1 to 2mm)	ND			ND		%				NC	20
Very Fine Sand (0.0625 to 0.125 mm)	13.35			13.91		%				4	20

Client: AECOM
Job ID: 180-112434-2
Project/Site: Pepco Benning Road Facility

Geotechnical

Analysis Batch: 110893

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112434-10	SMS0100N	Total/NA	Solid	D4464	
180-112434-11	SMS0200N	Total/NA	Solid	D4464	
180-112434-12	SMS0300N	Total/NA	Solid	D4464	
LCS 570-110893/5	Lab Control Sample	Total/NA	Solid	D4464	
LCSD 570-110893/7	Lab Control Sample Dup	Total/NA	Solid	D4464	
180-112434-12 DU	SMS0300N	Total/NA	Solid	D4464	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: Sharon Drummond	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-63272-12755.2
Client Contact: Mr. Robert Kennedy	Phone: 410.533.7095	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 2 of 2
Company: AECOM		Analysis Requested		Job #:
Address: 250 Apollo Drive	Due Date Requested:			Preservation Codes: A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)
City: Chelmsford	TAT Requested (days): Standard			
State, Zip: MA, 01824				
Phone:	PO #: 126546			Other:
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Grain size (ASTM D 4464 Rewelins Extended)	TOC Lloyd Kahn	PCB (congeners) (EPA 1668C)	PAHs-primary pollutants (EPA 8270D)	PCDD/Fs (0378 C.E.T.) (EPA 8290A)	TPH - DRO/RO (EPA 8015D)	TAL metals (Total) (EPA 6020/7471)	Wet Sediment Weight	Percent Solids	Rinsed sediment dry weight	Total Number of containers	Special Instructions/Note:
			Preservation Code:															
SMS0100N	10/15/20	1215	G	S			✓	✓	✓					✓	✓			
OFS0300N	10/15/20	1300	G	S			✓		✓	✓	✓	✓	✓					Total wet Sediment weight + % Solids From 1-gal jars.
SMS0200N	10/15/20	1355	G	S			✓	✓	✓					✓	✓			
OFS0100N	10/15/20	1400	G	S			✓		✓	✓	✓	✓	✓					
SMS0300N	10/15/20	1500	G	S			✓	✓	✓					✓	✓			
OFS0400N	10/15/20	1515	G	S			✓		✓	✓	✓	✓	✓					OFS samples prioritize chemical analysis if not enough volume for grain size analysis.
SMS0100N-Mat	10/15/20	1215	G	S/Mat												✓		
SMS0200N-Mat	10/15/20	1355	G	S/Mat												✓		
SMS0300N-Mat	10/15/20	1500	G	S/Mat												✓		

180-112434 Chain of Custody

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☒ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Special Instructions/QC Requirements:

Empty Kit Relinquished by: | Date: | Time:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
	10/15/20 1724	AECOM		10/16/20 10:41	ETA Balt
	10/16/20 1700	ETA Balt		10/17/20 930	ETA Balt

Custody Seals Intact: ☐ Yes ☐ No | Custody Seal No.:

Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Eurofins TestAmerica, Knoxville
5815 Middlebrook Pike
Knoxville, TN 37921
Phone: 865-291-3000 Fax: 865-584-4315

Chain of Custody Record

180-112434 Chain of Custody

Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):	Job #: 180-112434-1
Address: 301 Alpha Drive, RIDC Park,	Due Date Requested: 10/22/2020		
City: Pittsburgh	TAT Requested (days):		
State, Zip: PA, 15238			
Phone: 412-963-7058(Tel) 412-963-2468(Fax)	PO #:		
Email:	WO #:		
Project Name: Pepco Benning Road Facility	Project #: 18022565		
Site:	SSOW#:		

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Lloyd_Kahn_Mod/ (MOD) Organic Carbon, Total (TOC)	Moisture/ (MOD) Percent Moisture	Total Number of containers	Special Instructions/Note:
			Preservation Code:							
SMS0100N (180-112434-1)	10/15/20	12:15 Eastern		Sediment			X	X	1	
SMS0200N (180-112434-3)	10/15/20	13:55 Eastern		Sediment			X	X	1	
SMS0300N (180-112434-5)	10/15/20	15:00 Eastern		Sediment			X	X	1	

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
Unconfirmed	☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		11-13-20 15:30	FTA FNX		11-14-20	
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time: 10:30	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks

Ver: 01/16/2019

FedEx
eurofins
Environment Testing
TestAmerica
Part # 159465-434 RIT2 EXP 12/20
XO AGCA
PRIORITY OVERNIGHT
SATURDAY 12:00P
TRK# 9272 6084 4920
15238
PIT
PA-US
FedEx Express
PITTSBURGH PA 15238
RIDC PARK
301 ALPHA
TESTA
(412) 963-7058
(865) 291-3000
Uncorrected temp
Thermometer ID
Initials
CF
PT-WI-SR-001 effective 7/26/13

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-419078.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: Eurofins Calscience LLC		Accreditations Required (See note):		Job #: 180-112434-2
Address: 7440 Lincoln Way, ,	Due Date Requested: 10/23/2020			
City: Garden Grove	TAT Requested (days):			
State, Zip: CA, 92841				
Phone: 714-895-5494(Tel) 714-894-7501(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	D4464/ Full Analyte List	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
SMS0100N (180-112434-10)	10/15/20	12:15 Eastern		Solid			X	2	
SMS0200N (180-112434-11)	10/15/20	13:55 Eastern		Solid			X	2	
SMS0300N (180-112434-12)	10/15/20	15:00 Eastern		Solid			X	2	

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	*Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)*
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
1		11/16/20 1700			11/17/2020 1030	
2	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
3	Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.: N/A	Cooler Temperature(s) °C and Other Remarks: 3.0/2.2 RCG

Ver: 11/01/2020

11/20/2020

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112434-2

Login Number: 112434
List Number: 1
Creator: Say, Thomas C

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112434-2

Login Number: 112434
List Number: 5
Creator: Rivera, Isaac

List Source: Eurofins Calscience
List Creation: 11/17/20 01:54 PM

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	Seal present with no number.
Sample custody seals, if present, are intact.	N/A	Not Present
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	2.2
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	False	Received project as a subcontract.
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-112435-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
11/4/2020 5:10:32 PM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 4
Certification Summary 5
Sample Summary 6
Method Summary 7
Lab Chronicle 8
Client Sample Results 10
QC Sample Results 16
QC Association Summary 17
Chain of Custody 18
Receipt Checklists 19

Job ID: 180-112435-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-112435-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT

The samples were received on 10/17/2020 9:30 AM; the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 3 coolers at receipt time were 2.4º C, 15.1º C and 17.8º C.

PERCENT SOLIDS

For sample SMS0100N, 1 jar was received. The corrected wet weight of the sample was 2378.1 grams. The moisture content of the sample was 67 %. Therefore, the dry weight corrected result was 784.8 grams.

For sample SMS0200N, 3 jars were received. The corrected wet weight of the individual jars were 4597.9 grams, 4662.1 grams, and 4613.5 grams. The total wet weight was 13873.5 grams. The moisture content of each jar was 77.2%, 77%, and 73.4% respectively. Therefore, the dry weight of each jar was 1048.3 grams, 1072.3 grams, and 1227.2 grams. The total dry weight corrected result was 3347.8 grams.

For sample SMS0200N, 2 jars were received. The corrected wet weight of the individual jars were 4695.8 grams and 4792.0 grams. The total wet weight was 9487.8 grams. The moisture content of each jar was 70.8% and 72.4% respectively. Therefore, the dry weight of each jar was 1371.2 grams and 1322.6 grams. The total dry weight corrected result was 2693.8 grams.

Definitions/Glossary

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20 *
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	11-01-20
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-14-21
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-112435-1	SMS0100N	Sediment	10/15/20 12:15	10/17/20 09:30	
180-112435-2	SMS0200N JAR A	Sediment	10/15/20 13:55	10/17/20 09:30	
180-112435-3	SMS0300N JAR A	Sediment	10/15/20 15:00	10/17/20 09:30	
180-112435-4	SMS0200N JAR B	Sediment	10/15/20 13:55	10/17/20 09:30	
180-112435-5	SMS0200N JAR C	Sediment	10/15/20 13:55	10/17/20 09:30	
180-112435-6	SMS0300N JAR B	Sediment	10/15/20 15:00	10/17/20 09:30	

Method Summary

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
2540G	SM 2540G	SM22	TAL PIT

Protocol References:

SM22 = Standard Methods For The Examination Of Water And Wastewater, 22nd Edition

Laboratory References:

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0100N
Lab Sample ID: 180-112435-1
Date Collected: 10/15/20 12:15
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0200N JAR A
Lab Sample ID: 180-112435-2
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0300N JAR A
Lab Sample ID: 180-112435-3
Date Collected: 10/15/20 15:00
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0200N JAR B
Lab Sample ID: 180-112435-4
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0200N JAR C
Lab Sample ID: 180-112435-5
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SMS0300N JAR B
Lab Sample ID: 180-112435-6
Date Collected: 10/15/20 15:00
Matrix: Sediment
Date Received: 10/17/20 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	2540G		1			334153	10/21/20 07:20	MTW	TAL PIT
	Instrument ID: NOEQUIP									

Laboratory References:
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Analyst References:

Lab: TAL PIT

Batch Type: Analysis

MTW = Michael Wesoloski

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

Client Sample ID: SMS0100N
Date Collected: 10/15/20 12:15
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112435-1
Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	67.0		0.1	0.1	%			10/21/20 07:20	1

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0200N JAR A
Lab Sample ID: 180-112435-2
Date Collected: 10/15/20 13:55
Matrix: Sediment
Date Received: 10/17/20 09:30

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	77.2		0.1	0.1	%			10/21/20 07:20	1

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

Client Sample ID: SMS0300N JAR A

Date Collected: 10/15/20 15:00
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112435-3

Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	70.8		0.1	0.1	%			10/21/20 07:20	1

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

Client Sample ID: SMS0200N JAR B

Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112435-4

Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	77.0		0.1	0.1	%			10/21/20 07:20	1

Client Sample Results

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

Client Sample ID: SMS0200N JAR C

Date Collected: 10/15/20 13:55
Date Received: 10/17/20 09:30

Lab Sample ID: 180-112435-5

Matrix: Sediment

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	73.4		0.1	0.1	%			10/21/20 07:20	1

Client: AECOM
Job ID: 180-112435-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SMS0300N JAR B
Lab Sample ID: 180-112435-6
Date Collected: 10/15/20 15:00
Matrix: Sediment
Date Received: 10/17/20 09:30

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	72.4		0.1	0.1	%			10/21/20 07:20	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

Method: 2540G - SM 2540G

Lab Sample ID: 180-112435-1 DU
Matrix: Sediment
Analysis Batch: 334153

Client Sample ID: SMS0100N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Percent Moisture	67.0			68.2		%				2	10

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112435-1

General Chemistry

Analysis Batch: 334153

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112435-1	SMS0100N	Total/NA	Sediment	2540G	
180-112435-2	SMS0200N JAR A	Total/NA	Sediment	2540G	
180-112435-3	SMS0300N JAR A	Total/NA	Sediment	2540G	
180-112435-4	SMS0200N JAR B	Total/NA	Sediment	2540G	
180-112435-5	SMS0200N JAR C	Total/NA	Sediment	2540G	
180-112435-6	SMS0300N JAR B	Total/NA	Sediment	2540G	
180-112435-1 DU	SMS0100N	Total/NA	Sediment	2540G	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: Sharon Drummond	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-63272-12755.2
Client Contact: Mr. Robert Kennedy	Phone: 410.533.7095	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 2 of 2
Company: AECOM				Job #:
Address: 250 Apollo Drive	Due Date Requested:			
City: Chelmsford	TAT Requested (days): Standard			
State, Zip: MA, 01824				
Phone:	PO #: 126546			
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:
A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)
Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	Grain Size (ASTM D 4464 Eurofins Calscience)	TOC Lloyd Kahn	PCB Congeners (EPA 1668C)	PAHs-Drinking pollutant list (EPA 8270D LL)	PCDD/Fs (1378 LL) (EPA 8290A)	TPH - DRO/ORO (EPA 8015D)	TAL Metals (Total) (EPA 6020A/7471A)	Wet Sediment weight	Percent Solids	Rinsed sediment dry weight	Total Number of containers	Special Instructions/Note:
			Preservation Code:															
SMS0100N	10/15/20	1215	G	S			✓	✓	✓					✓	✓			
OFS0300N	10/15/20	1300	G	S			✓		✓	✓	✓	✓	✓					
SMS0200N	10/15/20	1355	G	S			✓	✓	✓					✓	✓			
OFS0100N	10/15/20	1400	G	S			✓		✓	✓	✓	✓	✓					
SMS0300N	10/15/20	1500	G	S			✓	✓	✓					✓	✓			
OFS0400N	10/15/20	1515	G	S			✓		✓	✓	✓	✓	✓					
SMS0100N-Mat	10/15/20	1215	G	S1 Mat												✓		
SMS0200N-Mat	10/15/20	1355	G	S1 Mat												✓		
SMS0300N-Mat	10/15/20	1500	G	S1 Mat												✓		

OFS samples: prioritize chemical analysis if not enough volume for grain size analysis.

180-112435 Chain of Custody

Possible Hazard Identification
☑ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☑ Unknown ☐ Radiological

Sample Di ☐ Retu — d longer than 1 month)
Special Ins — e For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)

Empty Kit Relinquished by: | Date: | Time:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
	10/15/20 1724	AECOM		10/16/20 10:41	ETA Surf
	10/16/20 1700	ETA-Balt		10/17/20 930	ETA Balt

Custody Seals Intact: Δ Yes Δ No | Custody Seal No.: | Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112435-1

Login Number: 112435
List Number: 1
Creator: Say, Thomas C

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-112989-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
12/3/2020 9:56:30 AM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS

Review your project results through TotalAccess

Have a Question? Ask The Expert

Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 5
Certification Summary 7
Sample Summary 10
Method Summary 11
Lab Chronicle 12
Client Sample Results 16
QC Sample Results 51
QC Association Summary 63
Chain of Custody 66
Receipt Checklists 73

Job ID: 180-112989-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-112989-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT

The samples were received on 10/30/2020 8:45 AM; the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 2 coolers at receipt time were 3.7º C and 3.9º C.

The container label for the following samples did not match the information listed on the Chain-of-Custody (COC): OFW0100N (180-112989-1) and OFW0200N (180-112989-2). The container labels list the opposite sample collection times as what is on the COC for these two samples. The times were logged in off of the COC.

SEMIVOLATILES

The continuing calibration verification (CCV) associated with batch 180-336474 recovered above the upper control limit for Pentachlorophenol. The samples associated with this CCV were non-detects for the affected analytes; therefore, the data have been reported.

DRO

Due to the concentration of DRO detected, sample OFW0300N (180-112989-3) was analyzed at a dilution. The reporting limits have been adjusted accordingly.

PCB CONGENERS

The following samples went through Gel-Permeation Cleanup procedure, based on EPA method 3640A: OFW0100N (180-112989-1), OFW0200N (180-112989-2), OFW0300N (180-112989-3), OFW0400N (180-112989-4) and OFW0500N (180-112989-5)

Due to the concentration of target compounds detected, sample OFW0100N (180-112989-1) and OFW0300N (180-112989-3) were analyzed at a dilution. The reporting limits have been adjusted accordingly.

Several analytes were detected in method blank MB 140-44772/7-A at levels that were above the method detection limit but below the reporting limit. The values should be considered estimates, and have been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged. .

METALS

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

GENERAL CHEMISTRY

Job ID: 180-112989-1 (Continued)

Laboratory: Eurofins TestAmerica, Pittsburgh (Continued)

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Qualifiers

GC/MS Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

GC Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Dioxin

Qualifier	Qualifier Description
B	Compound was found in the blank and sample.
C	The compound co-eluted with other compounds
C108	The compound co-eluted with PCB-108
C110	The compound co-eluted with PCB-110
C12	The compound co-eluted with PCB-12
C128	The compound co-eluted with PCB-128
C129	The compound co-eluted with PCB-129
C134	The compound co-eluted with PCB-134
C135	The compound co-eluted with PCB-135
C139	The compound co-eluted with PCB-139
C147	The compound co-eluted with PCB-147
C153	The compound co-eluted with PCB-153
C156	The compound co-eluted with PCB-156
C171	The compound co-eluted with PCB-171
C18	The compound co-eluted with PCB-18
C180	The compound co-eluted with PCB-180
C183	The compound co-eluted with PCB-183
C198	The compound co-eluted with PCB-198
C20	The compound co-eluted with PCB-20
C21	The compound co-eluted with PCB-21
C26	The compound co-eluted with PCB-26
C40	The compound co-eluted with PCB-40
C43	The compound co-eluted with PCB-43
C44	The compound co-eluted with PCB-44
C45	The compound co-eluted with PCB-45
C49	The compound co-eluted with PCB-49
C50	The compound co-eluted with PCB-50
C59	The compound co-eluted with PCB-59
C61	The compound co-eluted with PCB-61
C83	The compound co-eluted with PCB-83
C85	The compound co-eluted with PCB-85
C86	The compound co-eluted with PCB-86
C88	The compound co-eluted with PCB-88
C90	The compound co-eluted with PCB-90
C93	The compound co-eluted with PCB-93
C98	The compound co-eluted with PCB-98
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
q	The reported result is the estimated maximum possible concentration of this analyte, quantitated using the theoretical ion ratio. The measured ion ratio does not meet qualitative identification criteria and indicates a possible interference.

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20 *
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	12-31-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-14-21
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Canton

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
California	State	2927	02-23-21
Connecticut	State	PH-0590	12-31-21
Florida	NELAP	E87225	06-30-21
Georgia	State	4062	02-23-21
Illinois	NELAP	004498	07-31-21
Iowa	State	421	06-01-21
Kansas	NELAP	E-10336	04-30-21
Kentucky (UST)	State	112225	02-23-21
Kentucky (WW)	State	KY98016	12-31-20
Minnesota	NELAP	OH00048	12-31-20
Minnesota (Petrofund)	State	3506	08-01-21
New Jersey	NELAP	OH001	06-30-21
New York	NELAP	10975	03-31-21
Ohio VAP	State	CL0024	06-05-21
Oregon	NELAP	4062	02-24-21
Pennsylvania	NELAP	68-00340	08-31-21
Texas	NELAP	T104704517-18-10	08-31-21
USDA	US Federal Programs	P330-18-00281	09-17-21
Virginia	NELAP	010101	09-14-21
Washington	State	C971	01-12-21
West Virginia DEP	State	210	12-31-20

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Knoxville

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
	AFCEE	N/A	
ANAB	Dept. of Defense ELAP	L2311	02-13-22
ANAB	Dept. of Energy	L2311.01	02-13-22
ANAB	ISO/IEC 17025	L2311	02-13-22
ANAB	ISO/IEC 17025	L2311	02-14-22
Arkansas DEQ	State	88-0688	06-17-21
California	State	2423	06-30-21
Colorado	State	TN00009	02-28-21
Connecticut	State	PH-0223	09-30-21
Florida	NELAP	E87177	07-01-21
Georgia (DW)	State	906	12-11-22
Hawaii	State	NA	12-11-21
Kansas	NELAP	E-10349	11-01-20 *
Kentucky (DW)	State	90101	01-01-21
Louisiana	NELAP	LA110001	12-31-12 *
Louisiana	NELAP	83979	06-30-21
Louisiana (DW)	State	LA019	12-31-20
Maryland	State	277	03-31-21
Michigan	State	9933	12-11-22
Nevada	State	TN00009	07-31-21
New Hampshire	NELAP	299919	01-17-21
New Jersey	NELAP	TN001	07-01-21
New York	NELAP	10781	03-31-21
North Carolina (DW)	State	21705	07-31-21
North Carolina (WW/SW)	State	64	12-31-20
Ohio VAP	State	CL0059	06-02-23
Oklahoma	State	9415	08-31-21
Oregon	NELAP	TNI0189	01-02-21
Pennsylvania	NELAP	68-00576	12-31-20
Tennessee	State	02014	12-11-22
Texas	NELAP	T104704380-18-12	08-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	US Federal Programs	P330-19-00236	08-20-22
Utah	NELAP	TN00009	07-31-21
Virginia	NELAP	460176	09-14-21
Washington	State	C593	01-19-21
West Virginia (DW)	State	9955C	01-01-21
West Virginia DEP	State	345	05-01-21
Wisconsin	State	998044300	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-112989-1	OFW0100N	Water	10/29/20 11:45	10/30/20 08:45	
180-112989-2	OFW0200N	Water	10/29/20 11:50	10/30/20 08:45	
180-112989-3	OFW0300N	Water	10/29/20 11:35	10/30/20 08:45	
180-112989-4	OFW0400N	Water	10/29/20 11:20	10/30/20 08:45	
180-112989-5	OFW0500N	Water	10/29/20 11:05	10/30/20 08:45	

Method Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8270D LL	Semivolatile Organic Compounds by GC/MS - Low Level	SW846	TAL PIT
8015D	Diesel Range Organics (DRO) (GC)	SW846	TAL CAN
1668C	Chlorinated Biphenyl Congeners (HRGC/HRMS)	EPA	TAL KNX
EPA 6020A	Metals (ICP/MS)	SW846	TAL PIT
EPA 7470A	Mercury (CVAA)	SW846	TAL PIT
SM 2540D	Solids, Total Suspended (TSS)	SM	TAL PIT
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	TAL PIT
3510C LVI	Liquid-Liquid Extraction (Separatory Funnel) LVI	SW846	TAL CAN
3520C	Liquid-Liquid Extraction (Continuous)	SW846	TAL PIT
7470A	Preparation, Mercury	SW846	TAL PIT
HRMS-Sepf	Separatory Funnel (Liquid-Liquid) Extraction	EPA	TAL KNX

Protocol References:

EPA = US Environmental Protection Agency

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0100N
Lab Sample ID: 180-112989-1
Date Collected: 10/29/20 11:45
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			260 mL	250 uL	335567	11/02/20 11:02	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	336474	11/10/20 14:22	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			270 mL	5 mL	459194	11/04/20 07:54	BMB	TAL CAN
Total/NA	Analysis	8015D		1			459394	11/05/20 14:16	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1033.3 mL	20 uL	44772	11/24/20 12:36	SMA	TAL KNX
Total/NA	Analysis	1668C		10			44901	12/02/20 03:14	LKM	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336676	11/10/20 21:43	RSK	TAL PIT
	Instrument ID: A									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336907	11/12/20 09:37	RSK	TAL PIT
	Instrument ID: A									
Total/NA	Prep	7470A			50 mL	50 mL	335867	11/04/20 09:46	MM1	TAL PIT
Total/NA	Analysis	EPA 7470A		1			336250	11/06/20 14:09	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	SM 2540D		1	400 mL	1000 mL	335539	11/02/20 07:39	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0200N
Lab Sample ID: 180-112989-2
Date Collected: 10/29/20 11:50
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			260 mL	250 uL	335567	11/02/20 11:02	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	336474	11/10/20 14:47	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			260 mL	5 mL	459194	11/04/20 07:54	BMB	TAL CAN
Total/NA	Analysis	8015D		1			459394	11/05/20 14:44	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1047.4 mL	20 uL	44772	11/24/20 12:36	SMA	TAL KNX
Total/NA	Analysis	1668C		1			44901	12/02/20 04:16	LKM	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336676	11/10/20 21:46	RSK	TAL PIT
	Instrument ID: A									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336907	11/12/20 09:40	RSK	TAL PIT
	Instrument ID: A									
Total/NA	Prep	7470A			50 mL	50 mL	335867	11/04/20 09:46	MM1	TAL PIT
Total/NA	Analysis	EPA 7470A		1			336250	11/06/20 14:10	KEM	TAL PIT
	Instrument ID: HGY									

Lab Chronicle

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0200N
Lab Sample ID: 180-112989-2
Date Collected: 10/29/20 11:50
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	SM 2540D		1	500 mL	1000 mL	335539	11/02/20 07:39	AVS	TAL PIT

Client Sample ID: OFW0300N
Lab Sample ID: 180-112989-3
Date Collected: 10/29/20 11:35
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			250 mL	250 uL	335567	11/02/20 11:02	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	336474	11/10/20 15:12	VVP	TAL PIT
	Instrument ID: CH733									
Total/NA	Prep	3510C LVI			260 mL	5 mL	459194	11/04/20 07:54	BMB	TAL CAN
Total/NA	Analysis	8015D		5			459606	11/06/20 10:25	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1047.5 mL	20 uL	44772	11/24/20 12:36	SMA	TAL KNX
Total/NA	Analysis	1668C		10			44910	12/02/20 11:46	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336676	11/10/20 21:50	RSK	TAL PIT
	Instrument ID: A									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336907	11/12/20 09:44	RSK	TAL PIT
	Instrument ID: A									
Total/NA	Prep	7470A			50 mL	50 mL	335867	11/04/20 09:46	MM1	TAL PIT
Total/NA	Analysis	EPA 7470A		1			336250	11/06/20 14:11	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	SM 2540D		1	150 mL	1000 mL	335539	11/02/20 07:39	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0400N
Lab Sample ID: 180-112989-4
Date Collected: 10/29/20 11:20
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			260 mL	250 uL	336041	11/05/20 12:15	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	336496	11/10/20 14:57	VVP	TAL PIT
	Instrument ID: CH732									
Total/NA	Prep	3510C LVI			270 mL	5 mL	459194	11/04/20 07:54	BMB	TAL CAN
Total/NA	Analysis	8015D		1			459606	11/06/20 10:52	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1026.5 mL	20 uL	44772	11/24/20 12:36	SMA	TAL KNX
Total/NA	Analysis	1668C		1			44910	12/02/20 12:47	JMN	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336676	11/10/20 21:53	RSK	TAL PIT
	Instrument ID: A									

Lab Chronicle

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: OFW0400N
Lab Sample ID: 180-112989-4
Date Collected: 10/29/20 11:20
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336907	11/12/20 09:54	RSK	TAL PIT
	Instrument ID: A									
Total/NA	Prep	7470A			50 mL	50 mL	335867	11/04/20 09:46	MM1	TAL PIT
Total/NA	Analysis	EPA 7470A		1			336250	11/06/20 14:15	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	SM 2540D		1	1000 mL	1000 mL	335539	11/02/20 07:39	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: OFW0500N
Lab Sample ID: 180-112989-5
Date Collected: 10/29/20 11:05
Matrix: Water
Date Received: 10/30/20 08:45

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3520C			260 mL	250 uL	336041	11/05/20 12:15	BJT	TAL PIT
Total/NA	Analysis	EPA 8270D LL		1	1 mL	1 mL	336496	11/10/20 15:25	VVP	TAL PIT
	Instrument ID: CH732									
Total/NA	Prep	3510C LVI			260 mL	5 mL	459194	11/04/20 07:54	BMB	TAL CAN
Total/NA	Analysis	8015D		1			459394	11/05/20 16:05	LKG	TAL CAN
	Instrument ID: A2HP14R									
Total/NA	Prep	HRMS-Sepf			1036.3 mL	20 uL	44772	11/24/20 12:36	SMA	TAL KNX
Total/NA	Analysis	1668C		1			44901	12/02/20 07:21	LKM	TAL KNX
	Instrument ID: M1D									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336676	11/10/20 21:57	RSK	TAL PIT
	Instrument ID: A									
Total Recoverable	Prep	3005A			50 mL	50 mL	335675	11/03/20 08:21	KHM	TAL PIT
Total Recoverable	Analysis	EPA 6020A		1			336907	11/12/20 09:58	RSK	TAL PIT
	Instrument ID: A									
Total/NA	Prep	7470A			50 mL	50 mL	335867	11/04/20 09:46	MM1	TAL PIT
Total/NA	Analysis	EPA 7470A		1			336250	11/06/20 14:16	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	SM 2540D		1	200 mL	1000 mL	335539	11/02/20 07:39	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Laboratory References:

TAL CAN = Eurofins TestAmerica, Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396
TAL KNX = Eurofins TestAmerica, Knoxville, 5815 Middlebrook Pike, Knoxville, TN 37921, TEL (865)291-3000
TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

Analyst References:

Lab: TAL CAN
- Batch Type: Prep
  - BMB = Brittany Blythe
- Batch Type: Analysis
  - LKG = Lucas Grossman

Lab: TAL KNX
- Batch Type: Prep
  - SMA = Syed Ahmed
- Batch Type: Analysis
  - JMN = Jon Nordquist
  - LKM = Linda McWhirter

Lab: TAL PIT
- Batch Type: Prep
  - BJT = Bill Trout
  - KHM = Kyle Mucroski
  - MM1 = Mary Beth Miller
- Batch Type: Analysis
  - AVS = Abbey Smith
  - KEM = Kimberly Mahoney
  - RSK = Robert Kurtz
  - VVP = Vincent Piccolino

Client Sample ID: OFW0100N

Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.18	0.063	ug/L		11/02/20 11:02	11/10/20 14:22	1
Acenaphthylene	ND		0.18	0.063	ug/L		11/02/20 11:02	11/10/20 14:22	1
Anthracene	ND		0.18	0.047	ug/L		11/02/20 11:02	11/10/20 14:22	1
Benzo[a]anthracene	ND		0.18	0.072	ug/L		11/02/20 11:02	11/10/20 14:22	1
Benzo[b]fluoranthene	ND		0.18	0.093	ug/L		11/02/20 11:02	11/10/20 14:22	1
Benzo[k]fluoranthene	ND		0.18	0.085	ug/L		11/02/20 11:02	11/10/20 14:22	1
Benzo[g,h,i]perylene	ND		0.18	0.066	ug/L		11/02/20 11:02	11/10/20 14:22	1
Benzo[a]pyrene	ND		0.18	0.051	ug/L		11/02/20 11:02	11/10/20 14:22	1
Chrysene	ND		0.18	0.078	ug/L		11/02/20 11:02	11/10/20 14:22	1
Dibenz(a,h)anthracene	ND		0.18	0.069	ug/L		11/02/20 11:02	11/10/20 14:22	1
Fluoranthene	ND		0.18	0.058	ug/L		11/02/20 11:02	11/10/20 14:22	1
Fluorene	ND		0.18	0.066	ug/L		11/02/20 11:02	11/10/20 14:22	1
Indeno[1,2,3-cd]pyrene	ND		0.18	0.082	ug/L		11/02/20 11:02	11/10/20 14:22	1
Naphthalene	ND		0.18	0.057	ug/L		11/02/20 11:02	11/10/20 14:22	1
Phenanthrene	**0.066**	**J**	0.18	0.053	ug/L		11/02/20 11:02	11/10/20 14:22	1
Pyrene	ND		0.18	0.052	ug/L		11/02/20 11:02	11/10/20 14:22	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*50*		*23 - 105*	*11/02/20 11:02*	*11/10/20 14:22*	*1*
Nitrobenzene-d5 (Surr)	*53*		*28 - 111*	*11/02/20 11:02*	*11/10/20 14:22*	*1*
Terphenyl-d14 (Surr)	*53*		*20 - 126*	*11/02/20 11:02*	*11/10/20 14:22*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**2800**		460	210	ug/L		11/04/20 07:54	11/05/20 14:16	1
ORO C24-C40	**3900**		460	210	ug/L		11/04/20 07:54	11/05/20 14:16	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*77*		*52 - 121*	*11/04/20 07:54*	*11/05/20 14:16*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.62**		0.39	0.0025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-2	**0.035**	**J B q**	0.39	0.0029	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-3	**0.096**	**J B q**	0.39	0.0033	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-4	**0.12**	**J B**	0.58	0.035	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-5	ND		0.39	0.028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-6	ND		0.39	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-7	ND		0.39	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-8	**0.22**	**J B**	0.58	0.023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-9	ND		0.39	0.026	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-10	ND		0.39	0.028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-11	**1.1**	**B**	0.58	0.024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-12	ND	C	0.77	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-13	ND	C12	0.77	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-14	ND		0.39	0.021	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-15	**0.13**	**J B**	0.39	0.026	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-16	**0.12**	**J**	0.39	0.0078	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-17	**0.12**	**J B q**	0.39	0.0070	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-18	**0.31**	**J C B**	0.77	0.0062	ng/L		11/24/20 12:36	12/02/20 03:14	10

Client Sample ID: OFW0100N
Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.037	J	0.39	0.0086	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-20	0.60	J C B	0.77	0.0070	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-21	0.33	J C B	0.77	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-22	0.21	J B	0.39	0.0071	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-23	ND		0.39	0.0071	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-24	0.0083	J q	0.39	0.0059	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-25	0.035	J	0.39	0.0064	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-26	0.077	J C B	0.77	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-27	0.021	J q	0.39	0.0051	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-28	0.60	J B C20	0.77	0.0070	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-29	0.077	J C26 B	0.77	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-30	0.31	J C18 B	0.77	0.0062	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-31	0.50	B	0.39	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-32	0.10	J B	0.39	0.0049	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-33	0.33	J B C21	0.77	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-34	ND		0.39	0.0073	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-35	0.022	J	0.39	0.0071	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-36	ND		0.39	0.0069	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-37	0.20	J B q	0.39	0.0071	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-38	ND		0.39	0.0074	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-39	ND		0.39	0.0066	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-40	0.29	J C q	1.2	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-41	0.29	J q C40	1.2	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-42	0.11	J q	0.39	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-43	ND	C	0.77	0.017	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-44	0.59	J C B	1.2	0.016	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-45	0.071	J C q	0.77	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-46	ND		0.39	0.023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-47	0.59	J B C44	1.2	0.016	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-48	0.11	J	0.39	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-49	0.31	J C	0.77	0.015	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-50	0.055	J C	0.77	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-51	0.071	J C45 q	0.77	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-52	0.75	B	0.39	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-53	0.055	J C50	0.77	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-54	ND		0.39	0.0016	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-55	0.018	J q	0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-56	0.25	J B	0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-57	ND		0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-58	ND		0.39	0.014	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-59	0.052	J C	1.2	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-60	0.14	J	0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-61	1.1	J C B	1.5	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-62	0.052	J C59	1.2	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-63	0.020	J	0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-64	0.24	J B	0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-65	0.59	J B C44	1.2	0.016	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-66	0.45	B	0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-67	0.012	J q	0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10

Client Sample ID: OFW0100N
Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-69	0.31	J C49	0.77	0.015	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-70	1.1	J C61 B	1.5	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-71	0.29	J q C40	1.2	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-72	ND		0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-73	ND	C43	0.77	0.017	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-74	1.1	J C61 B	1.5	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-75	0.052	J C59	1.2	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-76	1.1	J C61 B	1.5	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-77	0.13	J B q	0.39	0.013	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-78	ND		0.39	0.014	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-79	0.017	J q	0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-80	ND		0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-81	ND		0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-82	0.23	J	0.39	0.0037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-83	0.82	C B	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-84	0.31	J	0.39	0.0038	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-85	0.25	J C B	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-86	1.1	J C B q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-87	1.1	J B C86 q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-88	0.17	J C	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-89	ND		0.39	0.0037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-90	1.8	C B	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-91	0.17	J C88	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-92	0.22	J	0.39	0.0032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-93	0.0087	J C q	0.77	0.0032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-94	ND		0.39	0.0037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-95	0.87	B q	0.39	0.0035	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-96	ND		0.39	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-97	1.1	J B C86 q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-98	0.020	J C q	0.77	0.0031	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-99	0.82	C83 B	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-100	0.0087	J C93 q	0.77	0.0032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-101	1.8	B C90	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-102	0.020	J C98 q	0.77	0.0031	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-103	ND		0.39	0.0032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-104	ND		0.39	0.0025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-105	1.2	B	0.39	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-106	ND		0.39	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-107	0.17	J	0.39	0.021	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-108	0.075	J C q	0.77	0.020	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-109	1.1	J B C86 q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-110	2.5	C B	0.77	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-111	ND		0.39	0.0023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-112	0.017	J	0.39	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-113	1.8	B C90	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-114	0.051	J q	0.39	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-115	2.5	B C110	0.77	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-116	0.25	J C85 B	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10

Client Sample ID: OFW0100N
Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.25	J C85 B	1.2	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-118	2.5	B	0.39	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-119	1.1	J B C86 q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-120	0.012	J q	0.39	0.0023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-121	ND		0.39	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-122	0.029	J q	0.39	0.022	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-123	0.022	J q	0.39	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-124	0.075	J q C108	0.77	0.020	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-125	1.1	J B C86 q	2.3	0.0028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-126	0.048	J q	0.39	0.022	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-127	ND		0.39	0.019	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-128	0.61	J C	0.77	0.036	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-129	3.7	C B	1.5	0.037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-130	0.17	J q	0.39	0.049	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-131	ND		0.39	0.051	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-132	0.91		0.39	0.047	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-133	ND		0.39	0.046	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-134	0.12	J C	0.77	0.048	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-135	0.62	J C	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-136	0.19	J	0.39	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-137	0.14	J q	0.39	0.041	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-138	3.7	B C129	1.5	0.037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-139	0.047	J C	0.77	0.041	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-140	0.047	J C139	0.77	0.041	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-141	0.59		0.39	0.043	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-142	ND		0.39	0.046	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-143	0.12	J C134	0.77	0.048	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-144	0.061	J q	0.39	0.0031	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-145	ND		0.39	0.0023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-146	0.35	J q	0.39	0.040	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-147	2.2	C	0.77	0.046	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-148	ND		0.39	0.0033	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-149	2.2	C147	0.77	0.046	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-150	ND		0.39	0.0022	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-151	0.62	J C135	0.77	0.0034	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-152	ND		0.39	0.0024	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-153	2.6	C B	0.77	0.032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-154	0.024	J	0.39	0.0026	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-155	ND		0.39	0.0022	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-156	0.45	J C	0.77	0.039	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-157	0.45	J C156	0.77	0.039	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-158	0.37	J	0.39	0.029	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-159	ND		0.39	0.031	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-160	3.7	B C129	1.5	0.037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-161	ND		0.39	0.030	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-162	ND		0.39	0.030	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-163	3.7	B C129	1.5	0.037	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-164	0.21	J	0.39	0.032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-165	ND		0.39	0.035	ng/L		11/24/20 12:36	12/02/20 03:14	10

Client Sample ID: OFW0100N

Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.61	J C128	0.77	0.036	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-167	0.14	J q	0.39	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-168	2.6	B C153	0.77	0.032	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-169	ND		0.39	0.022	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-170	0.92		0.39	0.0092	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-171	0.24	J C	0.77	0.0088	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-172	0.16	J	0.39	0.0087	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-173	0.24	J C171	0.77	0.0088	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-174	1.0		0.39	0.0082	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-175	0.027	J q	0.39	0.0079	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-176	0.076	J	0.39	0.0060	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-177	0.47		0.39	0.0084	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-178	0.21	J	0.39	0.0086	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-179	0.33	J q	0.39	0.0063	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-180	2.6	C B	0.77	0.0066	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-181	ND		0.39	0.0079	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-182	ND		0.39	0.0076	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-183	0.63	J C B	0.77	0.0078	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-184	ND		0.39	0.0065	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-185	0.63	J B C183	0.77	0.0078	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-186	ND		0.39	0.0063	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-187	1.4		0.39	0.0074	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-188	ND		0.39	0.0056	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-189	0.025	J	0.39	0.015	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-190	0.16	J	0.39	0.0057	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-191	0.043	J	0.39	0.0060	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-192	ND		0.39	0.0067	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-193	2.6	C180 B	0.77	0.0066	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-194	0.60		0.39	0.028	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-195	0.23	J	0.39	0.030	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-196	0.36	J	0.39	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-197	0.030	J	0.39	0.0094	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-198	0.90	C	0.77	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-199	0.90	C198	0.77	0.012	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-200	0.076	J	0.39	0.0084	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-201	0.086	J q	0.39	0.0086	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-202	0.11	J q	0.39	0.0096	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-203	0.46		0.39	0.011	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-204	ND		0.39	0.0094	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-205	ND		0.39	0.023	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-206	0.21	J q	0.39	0.033	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-207	ND		0.39	0.025	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-208	0.056	J	0.39	0.027	ng/L		11/24/20 12:36	12/02/20 03:14	10
PCB-209	0.053	J	0.39	0.024	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Monochlorobiphenyls	0.75	B q	0.39	0.0029	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Dichlorobiphenyls	1.6	B q	0.77	0.026	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Trichlorobiphenyls	2.7	B q	0.77	0.0068	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Tetrachlorobiphenyls	4.7	B q	1.5	0.014	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Pentachlorobiphenyls	12	B q	2.3	0.0084	ng/L		11/24/20 12:36	12/02/20 03:14	10

Client Sample ID: OFW0100N

Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	14	B q	1.5	0.028	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Heptachlorobiphenyls	8.3	B q	0.77	0.0077	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Octachlorobiphenyls	2.9	q	0.77	0.015	ng/L		11/24/20 12:36	12/02/20 03:14	10
Total Nonachlorobiphenyls	0.27	J q	0.39	0.028	ng/L		11/24/20 12:36	12/02/20 03:14	10
Polychlorinated biphenyls, Total	47	B q	2.3	0.018	ng/L		11/24/20 12:36	12/02/20 03:14	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*74*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-3L	*77*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-4L	*80*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-15L	*85*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-19L	*97*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-37L	*89*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-54L	*97*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-77L	*87*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-81L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-104L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-105L	*100*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-114L	*97*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-118L	*95*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-123L	*93*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-126L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-155L	*103*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-156L	*96*	*C*	*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-157L	*96*	*C156*	*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-167L	*93*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-169L	*103*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-170L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-188L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-189L	*83*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-202L	*105*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-205L	*75*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-206L	*87*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-208L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-209L	*88*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*100*		*5 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-111L	*101*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*
PCB-178L	*104*		*10 - 145*	*11/24/20 12:36*	*12/02/20 03:14*	*10*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	1100		30	13	ug/L		11/03/20 08:21	11/10/20 21:43	1
Arsenic	0.56	J	1.0	0.31	ug/L		11/03/20 08:21	11/10/20 21:43	1
Barium	22		10	1.6	ug/L		11/03/20 08:21	11/10/20 21:43	1
Beryllium	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:43	1
Cadmium	ND		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 21:43	1
Calcium	7000		500	130	ug/L		11/03/20 08:21	11/10/20 21:43	1
Chromium	3.2		2.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:43	1
Cobalt	0.70		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 21:43	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0100N
Date Collected: 10/29/20 11:45
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-1
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	12		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 21:43	1
Iron	2300		50	20	ug/L		11/03/20 08:21	11/12/20 09:37	1
Silver	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:43	1
Potassium	1200		500	160	ug/L		11/03/20 08:21	11/10/20 21:43	1
Magnesium	1300		500	83	ug/L		11/03/20 08:21	11/10/20 21:43	1
Manganese	37		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 21:43	1
Sodium	1500		500	350	ug/L		11/03/20 08:21	11/12/20 09:37	1
Nickel	2.4		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 21:43	1
Lead	18		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 21:43	1
Antimony	0.88	J	2.0	0.38	ug/L		11/03/20 08:21	11/10/20 21:43	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:43	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 21:43	1
Vanadium	3.8		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 21:43	1
Zinc	110		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 21:43	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 14:09	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	83		1.3	1.3	mg/L			11/02/20 07:39	1

Client Sample ID: OFW0200N

Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.18	0.063	ug/L		11/02/20 11:02	11/10/20 14:47	1
Acenaphthylene	ND		0.18	0.063	ug/L		11/02/20 11:02	11/10/20 14:47	1
Anthracene	ND		0.18	0.047	ug/L		11/02/20 11:02	11/10/20 14:47	1
Benzo[a]anthracene	ND		0.18	0.072	ug/L		11/02/20 11:02	11/10/20 14:47	1
Benzo[b]fluoranthene	**0.12**	**J**	0.18	0.093	ug/L		11/02/20 11:02	11/10/20 14:47	1
Benzo[k]fluoranthene	ND		0.18	0.085	ug/L		11/02/20 11:02	11/10/20 14:47	1
Benzo[g,h,i]perylene	ND		0.18	0.066	ug/L		11/02/20 11:02	11/10/20 14:47	1
Benzo[a]pyrene	ND		0.18	0.051	ug/L		11/02/20 11:02	11/10/20 14:47	1
Chrysene	**0.094**	**J**	0.18	0.078	ug/L		11/02/20 11:02	11/10/20 14:47	1
Dibenz(a,h)anthracene	ND		0.18	0.069	ug/L		11/02/20 11:02	11/10/20 14:47	1
Fluoranthene	**0.17**	**J**	0.18	0.058	ug/L		11/02/20 11:02	11/10/20 14:47	1
Fluorene	ND		0.18	0.066	ug/L		11/02/20 11:02	11/10/20 14:47	1
Indeno[1,2,3-cd]pyrene	ND		0.18	0.082	ug/L		11/02/20 11:02	11/10/20 14:47	1
Naphthalene	ND		0.18	0.057	ug/L		11/02/20 11:02	11/10/20 14:47	1
Phenanthrene	**0.11**	**J**	0.18	0.053	ug/L		11/02/20 11:02	11/10/20 14:47	1
Pyrene	**0.14**	**J**	0.18	0.052	ug/L		11/02/20 11:02	11/10/20 14:47	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*54*		*23 - 105*	*11/02/20 11:02*	*11/10/20 14:47*	*1*
Nitrobenzene-d5 (Surr)	*56*		*28 - 111*	*11/02/20 11:02*	*11/10/20 14:47*	*1*
Terphenyl-d14 (Surr)	*57*		*20 - 126*	*11/02/20 11:02*	*11/10/20 14:47*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**360**	**J**	480	220	ug/L		11/04/20 07:54	11/05/20 14:44	1
ORO C24-C40	**450**	**J**	480	220	ug/L		11/04/20 07:54	11/05/20 14:44	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*75*		*52 - 121*	*11/04/20 07:54*	*11/05/20 14:44*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.035**	**J**	0.038	0.00038	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-2	**0.0064**	**J B**	0.038	0.00042	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-3	**0.016**	**J B**	0.038	0.00044	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-4	**0.17**	**B**	0.057	0.0039	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-5	**0.0036**	**J q**	0.038	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-6	**0.049**		0.038	0.0025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-7	**0.0077**	**J q**	0.038	0.0025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-8	**0.19**	**B**	0.057	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-9	**0.011**	**J q**	0.038	0.0026	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-10	**0.012**	**J q**	0.038	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-11	**0.57**	**B**	0.057	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-12	**0.031**	**J C**	0.076	0.0025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-13	**0.031**	**J C12**	0.076	0.0025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-14	ND		0.038	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-15	**0.18**	**B**	0.038	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-16	**0.15**		0.038	0.00084	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-17	**0.18**	**B**	0.038	0.00076	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-18	**0.38**	**C B**	0.076	0.00067	ng/L		11/24/20 12:36	12/02/20 04:16	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0200N
Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.053		0.038	0.00093	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-20	0.72	C B	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-21	0.28	C B	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-22	0.22	B	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-23	ND		0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-24	0.0065	J q	0.038	0.00064	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-25	0.073		0.038	0.0010	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-26	0.14	C B	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-27	0.036	J	0.038	0.00055	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-28	0.72	B C20	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-29	0.14	C26 B	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-30	0.38	C18 B	0.076	0.00067	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-31	0.51	B	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-32	0.18	B	0.038	0.00053	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-33	0.28	B C21	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-34	0.0017	J q	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-35	0.030	J	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-36	0.0036	J	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-37	0.27	B	0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-38	ND		0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-39	0.0021	J	0.038	0.0010	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-40	0.40	C	0.11	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-41	0.40	C40	0.11	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-42	0.18		0.038	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-43	0.026	J C	0.076	0.0026	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-44	0.82	C B	0.11	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-45	0.18	C	0.076	0.0029	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-46	0.049		0.038	0.0035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-47	0.82	B C44	0.11	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-48	0.096		0.038	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-49	0.52	C	0.076	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-50	0.16	C	0.076	0.0027	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-51	0.18	C45	0.076	0.0029	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-52	1.0	B	0.038	0.0027	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-53	0.16	C50	0.076	0.0027	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-54	0.0059	J	0.038	0.00022	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-55	0.014	J	0.038	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-56	0.27	B	0.038	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-57	0.0057	J q	0.038	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-58	ND		0.038	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-59	0.064	J C	0.11	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-60	0.13		0.038	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-61	0.97	C B	0.15	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-62	0.064	J C59	0.11	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-63	0.021	J	0.038	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-64	0.26	B	0.038	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-65	0.82	B C44	0.11	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-66	0.58	B	0.038	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-67	0.014	J q	0.038	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1

Client Sample ID: OFW0200N
Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	0.0080	J	0.038	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-69	0.52	C49	0.076	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-70	0.97	C61 B	0.15	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-71	0.40	C40	0.11	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-72	0.010	J	0.038	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-73	0.026	J C43	0.076	0.0026	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-74	0.97	C61 B	0.15	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-75	0.064	J C59	0.11	0.0020	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-76	0.97	C61 B	0.15	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-77	0.087	B	0.038	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-78	ND		0.038	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-79	0.0086	J	0.038	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-80	ND		0.038	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-81	0.0033	J q	0.038	0.0019	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-82	0.16		0.038	0.00040	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-83	0.78	C B	0.076	0.00036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-84	0.37		0.038	0.00040	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-85	0.25	C B	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-86	0.94	C B	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-87	0.94	B C86	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-88	0.26	C	0.076	0.00036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-89	0.010	J q	0.038	0.00039	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-90	1.5	C B	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-91	0.26	C88	0.076	0.00036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-92	0.31		0.038	0.00034	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-93	0.047	J C	0.076	0.00035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-94	0.017	J	0.038	0.00039	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-95	1.3	B	0.038	0.00038	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-96	0.014	J	0.038	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-97	0.94	B C86	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-98	0.043	J C q	0.076	0.00034	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-99	0.78	C83 B	0.076	0.00036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-100	0.047	J C93	0.076	0.00035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-101	1.5	B C90	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-102	0.043	J C98 q	0.076	0.00034	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-103	0.020	J	0.038	0.00035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-104	0.0017	J	0.038	0.00026	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-105	0.46	B	0.038	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-106	ND		0.038	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-107	0.11		0.038	0.0025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-108	0.052	J C	0.076	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-109	0.94	B C86	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-110	1.8	C B	0.076	0.00025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-111	ND		0.038	0.00024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-112	0.0055	J q	0.038	0.00026	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-113	1.5	B C90	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-114	0.017	J q	0.038	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-115	1.8	B C110	0.076	0.00025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-116	0.25	C85 B	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1

Client Sample ID: OFW0200N
Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.25	C85 B	0.11	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-118	1.2	B	0.038	0.0022	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-119	0.94	B C86	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-120	0.0054	J q	0.038	0.00025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-121	0.0012	J q	0.038	0.00025	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-122	0.014	J q	0.038	0.0027	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-123	0.016	J q	0.038	0.0022	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-124	0.052	J C108	0.076	0.0024	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-125	0.94	B C86	0.23	0.00030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-126	0.0091	J	0.038	0.0027	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-127	ND		0.038	0.0023	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-128	0.36	C	0.076	0.0044	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-129	3.1	C B	0.15	0.0046	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-130	0.17		0.038	0.0060	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-131	0.027	J	0.038	0.0063	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-132	0.99		0.038	0.0059	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-133	0.034	J q	0.038	0.0057	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-134	0.16	C	0.076	0.0060	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-135	1.1	C	0.076	0.00053	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-136	0.36		0.038	0.00038	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-137	0.090		0.038	0.0051	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-138	3.1	B C129	0.15	0.0046	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-139	0.032	J C	0.076	0.0051	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-140	0.032	J C139	0.076	0.0051	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-141	0.70		0.038	0.0053	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-142	ND		0.038	0.0057	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-143	0.16	C134	0.076	0.0060	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-144	0.13		0.038	0.00048	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-145	0.0019	J	0.038	0.00036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-146	0.49		0.038	0.0050	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-147	3.2	C	0.076	0.0058	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-148	0.0035	J	0.038	0.00051	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-149	3.2	C147	0.076	0.0058	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-150	0.0059	J	0.038	0.00035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-151	1.1	C135	0.076	0.00053	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-152	0.0024	J	0.038	0.00037	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-153	2.7	C B	0.076	0.0040	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-154	0.028	J	0.038	0.00041	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-155	ND		0.038	0.00035	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-156	0.22	C	0.076	0.0048	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-157	0.22	C156	0.076	0.0048	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-158	0.28		0.038	0.0036	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-159	0.029	J	0.038	0.0038	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-160	3.1	B C129	0.15	0.0046	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-161	ND		0.038	0.0038	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-162	0.0084	J	0.038	0.0037	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-163	3.1	B C129	0.15	0.0046	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-164	0.22		0.038	0.0040	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-165	ND		0.038	0.0043	ng/L		11/24/20 12:36	12/02/20 04:16	1

Client Sample ID: OFW0200N
Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.36	C128	0.076	0.0044	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-167	0.10		0.038	0.0029	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-168	2.7	B C153	0.076	0.0040	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-169	0.0075	J q	0.038	0.0030	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-170	1.1		0.038	0.0012	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-171	0.31	C	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-172	0.19		0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-173	0.31	C171	0.076	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-174	1.2		0.038	0.0010	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-175	0.042		0.038	0.00099	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-176	0.14		0.038	0.00075	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-177	0.63		0.038	0.0010	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-178	0.23		0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-179	0.54		0.038	0.00079	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-180	2.4	C B	0.076	0.00083	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-181	0.0069	J	0.038	0.00098	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-182	0.0076	J q	0.038	0.00095	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-183	0.75	C B	0.076	0.00096	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-184	ND		0.038	0.00081	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-185	0.75	B C183	0.076	0.00096	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-186	ND		0.038	0.00078	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-187	1.4		0.038	0.00091	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-188	0.0039	J	0.038	0.00067	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-189	0.033	J	0.038	0.0022	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-190	0.18		0.038	0.00071	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-191	0.038		0.038	0.00074	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-192	ND		0.038	0.00083	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-193	2.4	C180 B	0.076	0.00083	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-194	0.62		0.038	0.0037	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-195	0.23		0.038	0.0041	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-196	0.29		0.038	0.0013	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-197	0.018	J	0.038	0.00097	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-198	0.71	C	0.076	0.0013	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-199	0.71	C198	0.076	0.0013	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-200	0.068		0.038	0.00086	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-201	0.079		0.038	0.00088	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-202	0.14		0.038	0.00098	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-203	0.46		0.038	0.0011	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-204	ND		0.038	0.00097	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-205	0.026	J	0.038	0.0031	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-206	0.67		0.038	0.0043	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-207	0.052		0.038	0.0031	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-208	0.18		0.038	0.0032	ng/L		11/24/20 12:36	12/02/20 04:16	1
PCB-209	0.13		0.038	0.0028	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Monochlorobiphenyls	0.057	B	0.038	0.00041	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Dichlorobiphenyls	1.2	B q	0.076	0.0026	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Trichlorobiphenyls	3.2	B q	0.076	0.00095	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Tetrachlorobiphenyls	5.9	B q	0.15	0.0022	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Pentachlorobiphenyls	9.7	B q	0.23	0.00099	ng/L		11/24/20 12:36	12/02/20 04:16	1

Client Sample ID: OFW0200N

Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	**15**	**B q**	0.15	0.0035	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Heptachlorobiphenyls	**9.2**	**B q**	0.076	0.00097	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Octachlorobiphenyls	**2.6**		0.076	0.0018	ng/L		11/24/20 12:36	12/02/20 04:16	1
Total Nonachlorobiphenyls	**0.90**		0.038	0.0036	ng/L		11/24/20 12:36	12/02/20 04:16	1
Polychlorinated biphenyls, Total	**48**	**B q**	0.23	0.0021	ng/L		11/24/20 12:36	12/02/20 04:16	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*62*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-3L	*65*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-4L	*68*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-15L	*83*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-19L	*83*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-37L	*86*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-54L	*100*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-77L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-81L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-104L	*86*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-105L	*102*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-114L	*104*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-118L	*102*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-123L	*102*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-126L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-155L	*96*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-156L	*91*	*C*	*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-157L	*91*	*C156*	*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-167L	*89*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-169L	*89*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-170L	*89*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-188L	*109*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-189L	*90*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-202L	*115*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-205L	*82*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-206L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-208L	*95*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-209L	*96*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*96*		*5 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-111L	*94*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*
PCB-178L	*112*		*10 - 145*	*11/24/20 12:36*	*12/02/20 04:16*	*1*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	**920**		30	13	ug/L		11/03/20 08:21	11/10/20 21:46	1
Arsenic	**1.4**		1.0	0.31	ug/L		11/03/20 08:21	11/10/20 21:46	1
Barium	**14**		10	1.6	ug/L		11/03/20 08:21	11/10/20 21:46	1
Beryllium	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:46	1
Cadmium	ND		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 21:46	1
Calcium	**5500**		500	130	ug/L		11/03/20 08:21	11/10/20 21:46	1
Chromium	**3.9**		2.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:46	1
Cobalt	**0.97**		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 21:46	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0200N
Date Collected: 10/29/20 11:50
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-2
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	14		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 21:46	1
Iron	2300		50	20	ug/L		11/03/20 08:21	11/12/20 09:40	1
Silver	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:46	1
Potassium	1100		500	160	ug/L		11/03/20 08:21	11/10/20 21:46	1
Magnesium	2100		500	83	ug/L		11/03/20 08:21	11/10/20 21:46	1
Manganese	58		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 21:46	1
Sodium	2000		500	350	ug/L		11/03/20 08:21	11/12/20 09:40	1
Nickel	8.7		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 21:46	1
Lead	21		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 21:46	1
Antimony	1.3	J	2.0	0.38	ug/L		11/03/20 08:21	11/10/20 21:46	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:46	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 21:46	1
Vanadium	18		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 21:46	1
Zinc	100		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 21:46	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 14:10	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	54		1.0	1.0	mg/L			11/02/20 07:39	1

Client Sample ID: OFW0300N
Lab Sample ID: 180-112989-3
Date Collected: 10/29/20 11:35
Matrix: Water
Date Received: 10/30/20 08:45

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.19	0.065	ug/L		11/02/20 11:02	11/10/20 15:12	1
Acenaphthylene	**0.096**	**J**	0.19	0.065	ug/L		11/02/20 11:02	11/10/20 15:12	1
Anthracene	ND		0.19	0.049	ug/L		11/02/20 11:02	11/10/20 15:12	1
Benzo[a]anthracene	**0.12**	**J**	0.19	0.075	ug/L		11/02/20 11:02	11/10/20 15:12	1
Benzo[b]fluoranthene	**0.16**	**J**	0.19	0.097	ug/L		11/02/20 11:02	11/10/20 15:12	1
Benzo[k]fluoranthene	ND		0.19	0.088	ug/L		11/02/20 11:02	11/10/20 15:12	1
Benzo[g,h,i]perylene	**0.12**	**J**	0.19	0.069	ug/L		11/02/20 11:02	11/10/20 15:12	1
Benzo[a]pyrene	ND		0.19	0.053	ug/L		11/02/20 11:02	11/10/20 15:12	1
Chrysene	**0.17**	**J**	0.19	0.081	ug/L		11/02/20 11:02	11/10/20 15:12	1
Dibenz(a,h)anthracene	ND		0.19	0.072	ug/L		11/02/20 11:02	11/10/20 15:12	1
Fluoranthene	**0.31**		0.19	0.060	ug/L		11/02/20 11:02	11/10/20 15:12	1
Fluorene	ND		0.19	0.069	ug/L		11/02/20 11:02	11/10/20 15:12	1
Indeno[1,2,3-cd]pyrene	ND		0.19	0.085	ug/L		11/02/20 11:02	11/10/20 15:12	1
Naphthalene	**0.059**	**J**	0.19	0.059	ug/L		11/02/20 11:02	11/10/20 15:12	1
Phenanthrene	**0.19**		0.19	0.055	ug/L		11/02/20 11:02	11/10/20 15:12	1
Pyrene	**0.31**		0.19	0.054	ug/L		11/02/20 11:02	11/10/20 15:12	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*60*		*23 - 105*	*11/02/20 11:02*	*11/10/20 15:12*	*1*
Nitrobenzene-d5 (Surr)	*62*		*28 - 111*	*11/02/20 11:02*	*11/10/20 15:12*	*1*
Terphenyl-d14 (Surr)	*80*		*20 - 126*	*11/02/20 11:02*	*11/10/20 15:12*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**12000**		2400	1100	ug/L		11/04/20 07:54	11/06/20 10:25	5
ORO C24-C40	**11000**		2400	1100	ug/L		11/04/20 07:54	11/06/20 10:25	5

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*72*		*52 - 121*	*11/04/20 07:54*	*11/06/20 10:25*	*5*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.19**	**J**	0.38	0.0026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-2	**0.028**	**J q B**	0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-3	**0.11**	**J B**	0.38	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-4	**0.44**	**J q B**	0.57	0.037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-5	ND		0.38	0.030	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-6	**0.22**	**J**	0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-7	**0.035**	**J q**	0.38	0.027	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-8	**1.2**	**B**	0.57	0.024	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-9	**0.081**	**J q**	0.38	0.027	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-10	ND		0.38	0.029	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-11	**11**	**B**	0.57	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-12	**0.19**	**J q C**	0.76	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-13	**0.19**	**J q C12**	0.76	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-14	ND		0.38	0.022	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-15	**0.65**	**B**	0.38	0.027	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-16	**0.69**		0.38	0.0076	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-17	**0.67**	**B**	0.38	0.0068	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-18	**1.5**	**C B**	0.76	0.0060	ng/L		11/24/20 12:36	12/02/20 11:46	10

Client Sample ID: OFW0300N
Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.12	J	0.38	0.0083	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-20	2.4	C B	0.76	0.0096	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-21	1.5	C B	0.76	0.0094	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-22	0.83	B	0.38	0.0098	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-23	ND		0.38	0.0097	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-24	0.023	J q	0.38	0.0057	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-25	0.13	J	0.38	0.0089	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-26	0.38	J C B	0.76	0.0094	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-27	0.098	J	0.38	0.0049	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-28	2.4	C20 B	0.76	0.0096	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-29	0.38	J C26 B	0.76	0.0094	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-30	1.5	C18 B	0.76	0.0060	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-31	2.1	B	0.38	0.0093	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-32	0.47	B	0.38	0.0047	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-33	1.5	C21 B	0.76	0.0094	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-34	ND		0.38	0.010	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-35	0.098	J	0.38	0.0098	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-36	ND		0.38	0.0095	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-37	0.72	B	0.38	0.0098	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-38	ND		0.38	0.010	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-39	ND		0.38	0.0091	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-40	1.7	C	1.1	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-41	1.7	C40	1.1	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-42	0.72		0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-43	0.077	J C	0.76	0.033	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-44	2.8	C B	1.1	0.031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-45	0.53	J C	0.76	0.037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-46	0.18	J	0.38	0.045	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-47	2.8	C44 B	1.1	0.031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-48	0.69		0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-49	1.5	C	0.76	0.029	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-50	0.33	J C	0.76	0.034	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-51	0.53	J C45	0.76	0.037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-52	3.9	B	0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-53	0.33	J C50	0.76	0.034	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-54	ND		0.38	0.0014	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-55	0.042	J q	0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-56	1.0	B	0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-57	ND		0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-58	ND		0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-59	0.23	J C	1.1	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-60	0.41		0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-61	4.1	C B	1.5	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-62	0.23	J C59	1.1	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-63	0.066	J q	0.38	0.024	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-64	1.3	B	0.38	0.024	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-65	2.8	C44 B	1.1	0.031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-66	2.0	B	0.38	0.024	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-67	0.052	J q	0.38	0.023	ng/L		11/24/20 12:36	12/02/20 11:46	10

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0300N
Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.38	0.023	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-69	1.5	C49	0.76	0.029	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-70	4.1	C61 B	1.5	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-71	1.7	C40	1.1	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-72	ND		0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-73	0.077	J C43	0.76	0.033	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-74	4.1	C61 B	1.5	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-75	0.23	J C59	1.1	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-76	4.1	C61 B	1.5	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-77	0.24	J B	0.38	0.028	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-78	ND		0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-79	ND		0.38	0.023	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-80	ND		0.38	0.022	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-81	ND		0.38	0.021	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-82	0.32	J	0.38	0.0048	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-83	1.2	C B	0.76	0.0044	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-84	0.73		0.38	0.0049	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-85	0.35	J C B	1.1	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-86	1.6	J q C B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-87	1.6	J q C86 B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-88	0.31	J C	0.76	0.0044	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-89	0.022	J q	0.38	0.0047	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-90	2.6	C B	1.1	0.0037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-91	0.31	J C88	0.76	0.0044	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-92	0.38	q	0.38	0.0041	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-93	0.026	J q C	0.76	0.0042	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-94	0.0093	J q	0.38	0.0047	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-95	2.5	B	0.38	0.0046	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-96	0.019	J q	0.38	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-97	1.6	J q C86 B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-98	0.061	J q C	0.76	0.0040	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-99	1.2	C83 B	0.76	0.0044	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-100	0.026	J q C93	0.76	0.0042	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-101	2.6	C90 B	1.1	0.0037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-102	0.061	J q C98	0.76	0.0040	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-103	0.015	J	0.38	0.0042	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-104	ND		0.38	0.0032	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-105	1.7	B	0.38	0.034	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-106	ND		0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-107	0.23	J q	0.38	0.038	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-108	0.11	J q C	0.76	0.036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-109	1.6	J q C86 B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-110	3.0	C B	0.76	0.0030	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-111	ND		0.38	0.0029	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-112	0.011	J	0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-113	2.6	C90 B	1.1	0.0037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-114	0.052	J q	0.38	0.032	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-115	3.0	C110 B	0.76	0.0030	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-116	0.35	J C85 B	1.1	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10

Client Sample ID: OFW0300N
Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.35	J C85 B	1.1	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-118	3.4	B	0.38	0.034	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-119	1.6	J q C86 B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-120	0.018	J q	0.38	0.0030	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-121	ND		0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-122	ND		0.38	0.041	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-123	0.042	J q	0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-124	0.11	J q C108	0.76	0.036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-125	1.6	J q C86 B	2.3	0.0036	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-126	ND		0.38	0.038	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-127	ND		0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-128	0.60	J C	0.76	0.064	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-129	5.2	C B	1.5	0.066	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-130	0.25	J q	0.38	0.087	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-131	ND		0.38	0.091	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-132	1.6		0.38	0.085	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-133	ND		0.38	0.083	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-134	0.19	J C	0.76	0.086	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-135	0.96	C	0.76	0.0047	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-136	0.41		0.38	0.0034	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-137	0.19	J	0.38	0.075	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-138	5.2	C129 B	1.5	0.066	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-139	ND	C	0.76	0.074	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-140	ND	C139	0.76	0.074	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-141	0.82		0.38	0.077	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-142	ND		0.38	0.082	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-143	0.19	J C134	0.76	0.086	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-144	0.11	J	0.38	0.0043	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-145	ND		0.38	0.0032	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-146	0.59		0.38	0.073	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-147	4.0	C	0.76	0.083	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-148	ND		0.38	0.0046	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-149	4.0	C147	0.76	0.083	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-150	ND		0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-151	0.96	C135	0.76	0.0047	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-152	ND		0.38	0.0033	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-153	3.6	C B	0.76	0.058	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-154	0.021	J	0.38	0.0037	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-155	ND		0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-156	0.50	J C	0.76	0.065	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-157	0.50	J C156	0.76	0.065	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-158	0.45		0.38	0.052	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-159	ND		0.38	0.055	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-160	5.2	C129 B	1.5	0.066	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-161	ND		0.38	0.055	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-162	ND		0.38	0.054	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-163	5.2	C129 B	1.5	0.066	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-164	0.28	J	0.38	0.058	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-165	ND		0.38	0.062	ng/L		11/24/20 12:36	12/02/20 11:46	10

Client Sample ID: OFW0300N
Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.60	J C128	0.76	0.064	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-167	0.15	J q	0.38	0.046	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-168	3.6	C153 B	0.76	0.058	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-169	ND		0.38	0.042	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-170	1.1		0.38	0.013	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-171	0.25	J C	0.76	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-172	0.14	J	0.38	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-173	0.25	J C171	0.76	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-174	0.96	q	0.38	0.010	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-175	0.032	J q	0.38	0.0098	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-176	0.099	J	0.38	0.0074	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-177	0.49		0.38	0.010	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-178	0.20	J	0.38	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-179	0.41		0.38	0.0078	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-180	2.3	C B	0.76	0.0082	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-181	ND		0.38	0.0097	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-182	ND		0.38	0.0094	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-183	0.67	J C B	0.76	0.0096	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-184	ND		0.38	0.0080	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-185	0.67	J C183 B	0.76	0.0096	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-186	ND		0.38	0.0078	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-187	1.1		0.38	0.0091	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-188	ND		0.38	0.0065	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-189	0.044	J	0.38	0.025	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-190	0.19	J	0.38	0.0071	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-191	0.028	J	0.38	0.0074	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-192	ND		0.38	0.0082	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-193	2.3	C180 B	0.76	0.0082	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-194	0.56		0.38	0.035	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-195	0.15	J q	0.38	0.038	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-196	0.25	J q	0.38	0.010	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-197	ND		0.38	0.0079	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-198	0.63	J C	0.76	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-199	0.63	J C198	0.76	0.011	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-200	0.068	J	0.38	0.0070	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-201	0.064	J	0.38	0.0072	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-202	0.12	J	0.38	0.0081	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-203	0.34	J q	0.38	0.0093	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-204	ND		0.38	0.0079	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-205	ND		0.38	0.029	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-206	0.37	J	0.38	0.033	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-207	ND		0.38	0.024	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-208	0.060	J q	0.38	0.026	ng/L		11/24/20 12:36	12/02/20 11:46	10
PCB-209	0.15	J	0.38	0.019	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Monochlorobiphenyls	0.33	J q B	0.38	0.0031	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Dichlorobiphenyls	14	q B	0.76	0.027	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Trichlorobiphenyls	12	q B	0.76	0.0084	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Tetrachlorobiphenyls	22	q B	1.5	0.027	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Pentachlorobiphenyls	19	q B	2.3	0.014	ng/L		11/24/20 12:36	12/02/20 11:46	10

Client Sample ID: OFW0300N

Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	20	q B	1.5	0.050	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Heptachlorobiphenyls	8.0	q B	0.76	0.0098	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Octachlorobiphenyls	2.2	q	0.76	0.015	ng/L		11/24/20 12:36	12/02/20 11:46	10
Total Nonachlorobiphenyls	0.43	q	0.38	0.028	ng/L		11/24/20 12:36	12/02/20 11:46	10
Polychlorinated biphenyls, Total	97	q B	2.3	0.022	ng/L		11/24/20 12:36	12/02/20 11:46	10

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*80*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-3L	*80*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-4L	*82*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-15L	*88*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-19L	*98*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-37L	*85*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-54L	*100*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-77L	*51*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-81L	*61*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-104L	*110*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-105L	*82*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-114L	*96*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-118L	*89*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-123L	*90*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-126L	*82*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-155L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-156L	*91*	*C*	*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-157L	*91*	*C156*	*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-167L	*88*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-169L	*96*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-170L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-188L	*100*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-189L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-202L	*99*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-205L	*75*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-206L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-208L	*73*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-209L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*99*		*5 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-111L	*69*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*
PCB-178L	*105*		*10 - 145*	*11/24/20 12:36*	*12/02/20 11:46*	*10*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	6200		30	13	ug/L		11/03/20 08:21	11/10/20 21:50	1
Arsenic	2.6		1.0	0.31	ug/L		11/03/20 08:21	11/10/20 21:50	1
Barium	150		10	1.6	ug/L		11/03/20 08:21	11/10/20 21:50	1
Beryllium	0.27	J	1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:50	1
Cadmium	1.0		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 21:50	1
Calcium	28000		500	130	ug/L		11/03/20 08:21	11/10/20 21:50	1
Chromium	17		2.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:50	1
Cobalt	4.4		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 21:50	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0300N
Date Collected: 10/29/20 11:35
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-3
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	86		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 21:50	1
Iron	13000		50	20	ug/L		11/03/20 08:21	11/12/20 09:44	1
Silver	1.0		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:50	1
Potassium	3100		500	160	ug/L		11/03/20 08:21	11/10/20 21:50	1
Magnesium	4900		500	83	ug/L		11/03/20 08:21	11/10/20 21:50	1
Manganese	190		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 21:50	1
Sodium	3500		500	350	ug/L		11/03/20 08:21	11/12/20 09:44	1
Nickel	13		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 21:50	1
Lead	100		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 21:50	1
Antimony	5.4		2.0	0.38	ug/L		11/03/20 08:21	11/10/20 21:50	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:50	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 21:50	1
Vanadium	16		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 21:50	1
Zinc	650		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 21:50	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 14:11	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	640		3.3	3.3	mg/L			11/02/20 07:39	1

Client Sample ID: OFW0400N

Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.18	0.063	ug/L		11/05/20 12:15	11/10/20 14:57	1
Acenaphthylene	ND		0.18	0.063	ug/L		11/05/20 12:15	11/10/20 14:57	1
Anthracene	ND		0.18	0.047	ug/L		11/05/20 12:15	11/10/20 14:57	1
Benzo[a]anthracene	ND		0.18	0.072	ug/L		11/05/20 12:15	11/10/20 14:57	1
Benzo[b]fluoranthene	ND		0.18	0.093	ug/L		11/05/20 12:15	11/10/20 14:57	1
Benzo[k]fluoranthene	ND		0.18	0.085	ug/L		11/05/20 12:15	11/10/20 14:57	1
Benzo[g,h,i]perylene	ND		0.18	0.066	ug/L		11/05/20 12:15	11/10/20 14:57	1
Benzo[a]pyrene	ND		0.18	0.051	ug/L		11/05/20 12:15	11/10/20 14:57	1
Chrysene	ND		0.18	0.078	ug/L		11/05/20 12:15	11/10/20 14:57	1
Dibenz(a,h)anthracene	ND		0.18	0.069	ug/L		11/05/20 12:15	11/10/20 14:57	1
Fluoranthene	ND		0.18	0.058	ug/L		11/05/20 12:15	11/10/20 14:57	1
Fluorene	ND		0.18	0.066	ug/L		11/05/20 12:15	11/10/20 14:57	1
Indeno[1,2,3-cd]pyrene	ND		0.18	0.082	ug/L		11/05/20 12:15	11/10/20 14:57	1
Naphthalene	ND		0.18	0.057	ug/L		11/05/20 12:15	11/10/20 14:57	1
Phenanthrene	ND		0.18	0.053	ug/L		11/05/20 12:15	11/10/20 14:57	1
Pyrene	ND		0.18	0.052	ug/L		11/05/20 12:15	11/10/20 14:57	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*72*		*23 - 105*	*11/05/20 12:15*	*11/10/20 14:57*	*1*
Nitrobenzene-d5 (Surr)	*72*		*28 - 111*	*11/05/20 12:15*	*11/10/20 14:57*	*1*
Terphenyl-d14 (Surr)	*60*		*20 - 126*	*11/05/20 12:15*	*11/10/20 14:57*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	ND		460	210	ug/L		11/04/20 07:54	11/06/20 10:52	1
ORO C24-C40	**250**	**J**	460	210	ug/L		11/04/20 07:54	11/06/20 10:52	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*79*		*52 - 121*	*11/04/20 07:54*	*11/06/20 10:52*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.0037**	**J q**	0.039	0.00028	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-2	**0.0021**	**J B q**	0.039	0.00032	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-3	**0.0033**	**J B**	0.039	0.00034	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-4	**0.013**	**J B q**	0.058	0.0029	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-5	ND		0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-6	**0.0040**	**J q**	0.039	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-7	ND		0.039	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-8	**0.021**	**J B q**	0.058	0.0018	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-9	ND		0.039	0.0021	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-10	ND		0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-11	**0.050**	**J B q**	0.058	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-12	ND	C	0.078	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-13	ND	C12	0.078	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-14	ND		0.039	0.0017	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-15	**0.015**	**J B**	0.039	0.0021	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-16	**0.0060**	**J q**	0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-17	**0.0075**	**J B q**	0.039	0.00063	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-18	**0.017**	**J C B**	0.078	0.00056	ng/L		11/24/20 12:36	12/02/20 12:47	1

Client Sample ID: OFW0400N
Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.0018	J q	0.039	0.00077	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-20	0.041	J C B	0.078	0.00072	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-21	0.014	J C B	0.078	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-22	0.012	J B	0.039	0.00074	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-23	ND		0.039	0.00073	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-24	0.00088	J	0.039	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-25	0.0017	J q	0.039	0.00066	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-26	0.0045	J C B q	0.078	0.00071	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-27	0.0012	J q	0.039	0.00046	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-28	0.041	J B C20	0.078	0.00072	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-29	0.0045	J C26 B q	0.078	0.00071	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-30	0.017	J C18 B	0.078	0.00056	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-31	0.026	J B q	0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-32	0.0077	J B	0.039	0.00044	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-33	0.014	J B C21	0.078	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-34	ND		0.039	0.00076	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-35	ND		0.039	0.00074	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-36	ND		0.039	0.00071	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-37	0.018	J B	0.039	0.00073	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-38	ND		0.039	0.00076	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-39	ND		0.039	0.00068	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-40	0.014	J C	0.12	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-41	0.014	J C40	0.12	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-42	0.0073	J	0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-43	ND	C	0.078	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-44	0.031	J C B	0.12	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-45	0.0049	J C	0.078	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-46	ND		0.039	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-47	0.031	J B C44	0.12	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-48	0.0041	J	0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-49	0.018	J C	0.078	0.0010	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-50	0.0040	J C	0.078	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-51	0.0049	J C45	0.078	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-52	0.053	B	0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-53	0.0040	J C50	0.078	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-54	ND		0.039	0.00019	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-55	ND		0.039	0.00089	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-56	0.017	J B	0.039	0.00089	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-57	ND		0.039	0.00090	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-58	ND		0.039	0.00092	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-59	0.0031	J C	0.12	0.00086	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-60	0.0091	J	0.039	0.00091	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-61	0.074	J C B	0.16	0.00085	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-62	0.0031	J C59	0.12	0.00086	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-63	ND		0.039	0.00083	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-64	0.021	J B	0.039	0.00082	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-65	0.031	J B C44	0.12	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-66	0.035	J B	0.039	0.00085	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-67	ND		0.039	0.00078	ng/L		11/24/20 12:36	12/02/20 12:47	1

Client Sample ID: OFW0400N

Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	ND		0.039	0.00080	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-69	**0.018**	**J C49**	0.078	0.0010	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-70	**0.074**	**J C61 B**	0.16	0.00085	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-71	**0.014**	**J C40**	0.12	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-72	ND		0.039	0.00089	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-73	ND	C43	0.078	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-74	**0.074**	**J C61 B**	0.16	0.00085	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-75	**0.0031**	**J C59**	0.12	0.00086	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-76	**0.074**	**J C61 B**	0.16	0.00085	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-77	**0.0081**	**J B**	0.039	0.00086	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-78	ND		0.039	0.00092	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-79	ND		0.039	0.00079	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-80	ND		0.039	0.00078	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-81	ND		0.039	0.00084	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-82	**0.018**	**J**	0.039	0.00071	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-83	**0.066**	**J C B q**	0.078	0.00065	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-84	**0.035**	**J**	0.039	0.00072	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-85	**0.026**	**J C B**	0.12	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-86	**0.098**	**J C B**	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-87	**0.098**	**J B C86**	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-88	**0.017**	**J C**	0.078	0.00064	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-89	ND		0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-90	**0.16**	**C B**	0.12	0.00054	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-91	**0.017**	**J C88**	0.078	0.00064	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-92	**0.025**	**J**	0.039	0.00061	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-93	**0.0022**	**J C q**	0.078	0.00062	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-94	ND		0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-95	**0.15**	**B**	0.039	0.00067	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-96	ND		0.039	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-97	**0.098**	**J B C86**	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-98	**0.0029**	**J C q**	0.078	0.00060	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-99	**0.066**	**J C83 B q**	0.078	0.00065	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-100	**0.0022**	**J C93 q**	0.078	0.00062	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-101	**0.16**	**B C90**	0.12	0.00054	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-102	**0.0029**	**J C98 q**	0.078	0.00060	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-103	ND		0.039	0.00062	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-104	ND		0.039	0.00047	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-105	**0.059**	**B**	0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-106	ND		0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-107	**0.010**	**J q**	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-108	**0.0063**	**J C q**	0.078	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-109	**0.098**	**J B C86**	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-110	**0.27**	**C B**	0.078	0.00045	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-111	ND		0.039	0.00043	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-112	**0.00097**	**J q**	0.039	0.00046	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-113	**0.16**	**B C90**	0.12	0.00054	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-114	**0.0017**	**J q**	0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-115	**0.27**	**B C110**	0.078	0.00045	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-116	**0.026**	**J C85 B**	0.12	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1

Client Sample ID: OFW0400N

Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.026	J C85 B	0.12	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-118	0.14	B	0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-119	0.098	J B C86	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-120	ND		0.039	0.00044	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-121	ND		0.039	0.00045	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-122	0.0027	J	0.039	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-123	0.0017	J q	0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-124	0.0063	J q C108	0.078	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-125	0.098	J B C86	0.23	0.00053	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-126	ND		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-127	ND		0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-128	0.049	J C	0.078	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-129	0.41	C B	0.16	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-130	0.023	J	0.039	0.0031	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-131	0.0046	J q	0.039	0.0032	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-132	0.11		0.039	0.0030	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-133	0.0037	J	0.039	0.0029	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-134	0.014	J C	0.078	0.0030	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-135	0.13	C	0.078	0.00083	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-136	0.040		0.039	0.00060	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-137	0.0096	J q	0.039	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-138	0.41	B C129	0.16	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-139	0.0040	J C q	0.078	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-140	0.0040	J C139 q	0.078	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-141	0.087		0.039	0.0027	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-142	ND		0.039	0.0029	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-143	0.014	J C134	0.078	0.0030	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-144	0.013	J	0.039	0.00075	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-145	ND		0.039	0.00057	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-146	0.048	q	0.039	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-147	0.35	C	0.078	0.0029	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-148	ND		0.039	0.00080	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-149	0.35	C147	0.078	0.0029	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-150	ND		0.039	0.00054	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-151	0.13	C135	0.078	0.00083	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-152	ND		0.039	0.00059	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-153	0.30	C B	0.078	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-154	0.0017	J q	0.039	0.00065	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-155	ND		0.039	0.00055	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-156	0.035	J C	0.078	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-157	0.035	J C156	0.078	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-158	0.035	J q	0.039	0.0018	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-159	0.0036	J q	0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-160	0.41	B C129	0.16	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-161	ND		0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-162	ND		0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-163	0.41	B C129	0.16	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-164	0.027	J	0.039	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-165	ND		0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 12:47	1

Client Sample ID: OFW0400N

Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.049	J C128	0.078	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-167	0.012	J	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-168	0.30	B C153	0.078	0.0020	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-169	ND		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-170	0.14		0.039	0.0017	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-171	0.036	J C	0.078	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-172	0.020	J	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-173	0.036	J C171	0.078	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-174	0.14		0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-175	0.0047	J	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-176	0.014	J	0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-177	0.072		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-178	0.023	J	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-179	0.053		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-180	0.30	C B	0.078	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-181	ND		0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-182	ND		0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-183	0.090	C B	0.078	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-184	ND		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-185	0.090	B C183	0.078	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-186	ND		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-187	0.16		0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-188	ND		0.039	0.00097	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-189	ND		0.039	0.0018	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-190	0.020	J q	0.039	0.0010	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-191	0.0060	J	0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-192	ND		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-193	0.30	C180 B	0.078	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-194	0.053		0.039	0.0044	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-195	0.026	J	0.039	0.0048	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-196	0.029	J	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-197	ND		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-198	0.061	J C	0.078	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-199	0.061	J C198	0.078	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-200	0.0057	J q	0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-201	0.0075	J	0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-202	0.0078	J q	0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-203	0.036	J	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-204	ND		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-205	ND		0.039	0.0037	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-206	0.020	J	0.039	0.0032	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-207	0.0047	J	0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-208	0.0043	J q	0.039	0.0023	ng/L		11/24/20 12:36	12/02/20 12:47	1
PCB-209	0.010	J q	0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Monochlorobiphenyls	0.0091	J B q	0.039	0.00031	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Dichlorobiphenyls	0.10	B q	0.078	0.0021	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Trichlorobiphenyls	0.16	B q	0.078	0.00067	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Tetrachlorobiphenyls	0.30	B	0.16	0.00095	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Pentachlorobiphenyls	1.1	B q	0.23	0.00083	ng/L		11/24/20 12:36	12/02/20 12:47	1

Client Sample ID: OFW0400N

Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4

Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	**1.7**	**B q**	0.16	0.0019	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Heptachlorobiphenyls	**1.1**	**B q**	0.078	0.0013	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Octachlorobiphenyls	**0.23**	**q**	0.078	0.0021	ng/L		11/24/20 12:36	12/02/20 12:47	1
Total Nonachlorobiphenyls	**0.029**	**J q**	0.039	0.0026	ng/L		11/24/20 12:36	12/02/20 12:47	1
Polychlorinated biphenyls, Total	**4.7**	**B q**	0.23	0.0016	ng/L		11/24/20 12:36	12/02/20 12:47	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*76*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-3L	*77*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-4L	*85*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-15L	*90*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-19L	*94*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-37L	*88*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-54L	*104*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-77L	*94*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-81L	*91*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-104L	*86*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-105L	*97*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-114L	*97*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-118L	*96*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-123L	*95*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-126L	*84*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-155L	*97*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-156L	*92*	*C*	*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-157L	*92*	*C156*	*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-167L	*93*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-169L	*94*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-170L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-188L	*101*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-189L	*112*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-202L	*116*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-205L	*89*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-206L	*109*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-208L	*118*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-209L	*109*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*94*		*5 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-111L	*101*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*
PCB-178L	*107*		*10 - 145*	*11/24/20 12:36*	*12/02/20 12:47*	*1*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	**380**		30	13	ug/L		11/03/20 08:21	11/10/20 21:53	1
Arsenic	**2.9**		1.0	0.31	ug/L		11/03/20 08:21	11/10/20 21:53	1
Barium	**10**		10	1.6	ug/L		11/03/20 08:21	11/10/20 21:53	1
Beryllium	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:53	1
Cadmium	ND		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 21:53	1
Calcium	**9300**		500	130	ug/L		11/03/20 08:21	11/10/20 21:53	1
Chromium	**1.8**	**J**	2.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:53	1
Cobalt	**0.58**		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 21:53	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0400N
Date Collected: 10/29/20 11:20
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-4
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	4.5		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 21:53	1
Iron	870		50	20	ug/L		11/03/20 08:21	11/12/20 09:54	1
Silver	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:53	1
Potassium	3100		500	160	ug/L		11/03/20 08:21	11/10/20 21:53	1
Magnesium	2300		500	83	ug/L		11/03/20 08:21	11/10/20 21:53	1
Manganese	16		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 21:53	1
Sodium	4700		500	350	ug/L		11/03/20 08:21	11/12/20 09:54	1
Nickel	5.4		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 21:53	1
Lead	3.6		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 21:53	1
Antimony	0.48	J	2.0	0.38	ug/L		11/03/20 08:21	11/10/20 21:53	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:53	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 21:53	1
Vanadium	26		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 21:53	1
Zinc	39		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 21:53	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 14:15	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	12		0.50	0.50	mg/L			11/02/20 07:39	1

Client Sample ID: OFW0500N

Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5

Matrix: Water

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.18	0.063	ug/L		11/05/20 12:15	11/10/20 15:25	1
Acenaphthylene	ND		0.18	0.063	ug/L		11/05/20 12:15	11/10/20 15:25	1
Anthracene	ND		0.18	0.047	ug/L		11/05/20 12:15	11/10/20 15:25	1
Benzo[a]anthracene	ND		0.18	0.072	ug/L		11/05/20 12:15	11/10/20 15:25	1
Benzo[b]fluoranthene	ND		0.18	0.093	ug/L		11/05/20 12:15	11/10/20 15:25	1
Benzo[k]fluoranthene	ND		0.18	0.085	ug/L		11/05/20 12:15	11/10/20 15:25	1
Benzo[g,h,i]perylene	ND		0.18	0.066	ug/L		11/05/20 12:15	11/10/20 15:25	1
Benzo[a]pyrene	ND		0.18	0.051	ug/L		11/05/20 12:15	11/10/20 15:25	1
Chrysene	ND		0.18	0.078	ug/L		11/05/20 12:15	11/10/20 15:25	1
Dibenz(a,h)anthracene	ND		0.18	0.069	ug/L		11/05/20 12:15	11/10/20 15:25	1
Fluoranthene	ND		0.18	0.058	ug/L		11/05/20 12:15	11/10/20 15:25	1
Fluorene	ND		0.18	0.066	ug/L		11/05/20 12:15	11/10/20 15:25	1
Indeno[1,2,3-cd]pyrene	ND		0.18	0.082	ug/L		11/05/20 12:15	11/10/20 15:25	1
Naphthalene	ND		0.18	0.057	ug/L		11/05/20 12:15	11/10/20 15:25	1
Phenanthrene	ND		0.18	0.053	ug/L		11/05/20 12:15	11/10/20 15:25	1
Pyrene	**0.053**	**J**	0.18	0.052	ug/L		11/05/20 12:15	11/10/20 15:25	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*57*		*23 - 105*	*11/05/20 12:15*	*11/10/20 15:25*	*1*
Nitrobenzene-d5 (Surr)	*55*		*28 - 111*	*11/05/20 12:15*	*11/10/20 15:25*	*1*
Terphenyl-d14 (Surr)	*55*		*20 - 126*	*11/05/20 12:15*	*11/10/20 15:25*	*1*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	**1200**		480	220	ug/L		11/04/20 07:54	11/05/20 16:05	1
ORO C24-C40	**2000**		480	220	ug/L		11/04/20 07:54	11/05/20 16:05	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*76*		*52 - 121*	*11/04/20 07:54*	*11/05/20 16:05*	*1*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	**0.023**	**J**	0.039	0.00051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-2	**0.0068**	**J q B**	0.039	0.00056	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-3	**0.015**	**J B**	0.039	0.00058	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-4	**0.091**	**B**	0.058	0.0029	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-5	**0.0057**	**J q**	0.039	0.0024	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-6	**0.044**	**q**	0.039	0.0021	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-7	**0.0062**	**J q**	0.039	0.0021	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-8	**0.21**	**B**	0.058	0.0019	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-9	**0.014**	**J q**	0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-10	ND		0.039	0.0023	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-11	**1.4**	**B**	0.058	0.0020	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-12	**0.031**	**J q C**	0.077	0.0021	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-13	**0.031**	**J q C12**	0.077	0.0021	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-14	ND		0.039	0.0018	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-15	**0.13**	**B**	0.039	0.0022	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-16	**0.18**		0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-17	**0.17**	**B**	0.039	0.00063	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-18	**0.40**	**C B**	0.077	0.00056	ng/L		11/24/20 12:36	12/02/20 07:21	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-19	0.036	J	0.039	0.00077	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-20	0.63	C B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-21	0.36	C B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-22	0.23	B	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-23	ND		0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-24	0.0060	J q	0.039	0.00053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-25	0.041		0.039	0.0013	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-26	0.10	C B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-27	0.026	J	0.039	0.00046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-28	0.63	C20 B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-29	0.10	C26 B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-30	0.40	C18 B	0.077	0.00056	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-31	0.56	B	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-32	0.12	B	0.039	0.00044	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-33	0.36	C21 B	0.077	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-34	ND		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-35	0.023	J	0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-36	0.0030	J	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-37	0.19	B	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-38	ND		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-39	0.0015	J q	0.039	0.0014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-40	0.46	C	0.12	0.0053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-41	0.46	C40	0.12	0.0053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-42	0.20		0.039	0.0053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-43	0.027	J C	0.077	0.0049	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-44	0.84	C B	0.12	0.0046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-45	0.16	C	0.077	0.0055	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-46	0.051		0.039	0.0067	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-47	0.84	C44 B	0.12	0.0046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-48	0.17		0.039	0.0052	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-49	0.46	C	0.077	0.0043	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-50	0.10	C	0.077	0.0051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-51	0.16	C45	0.077	0.0055	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-52	1.3	B	0.039	0.0052	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-53	0.10	C50	0.077	0.0051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-54	0.0010	J q	0.039	0.00022	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-55	0.013	J	0.039	0.0038	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-56	0.24	B	0.039	0.0038	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-57	ND		0.039	0.0039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-58	ND		0.039	0.0039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-59	0.074	J C	0.12	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-60	0.12		0.039	0.0039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-61	1.1	C B	0.15	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-62	0.074	J C59	0.12	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-63	0.013	J q	0.039	0.0036	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-64	0.37	B	0.039	0.0035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-65	0.84	C44 B	0.12	0.0046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-66	0.48	B	0.039	0.0036	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-67	0.013	J q	0.039	0.0034	ng/L		11/24/20 12:36	12/02/20 07:21	1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-68	0.0041	J q	0.039	0.0034	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-69	0.46	C49	0.077	0.0043	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-70	1.1	C61 B	0.15	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-71	0.46	C40	0.12	0.0053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-72	0.0041	J	0.039	0.0038	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-73	0.027	J C43	0.077	0.0049	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-74	1.1	C61 B	0.15	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-75	0.074	J C59	0.12	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-76	1.1	C61 B	0.15	0.0037	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-77	0.094	B	0.039	0.0041	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-78	ND		0.039	0.0039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-79	0.0092	J	0.039	0.0034	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-80	ND		0.039	0.0033	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-81	ND		0.039	0.0033	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-82	0.11		0.039	0.00047	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-83	0.47	C B	0.077	0.00043	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-84	0.27		0.039	0.00047	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-85	0.15	C B	0.12	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-86	0.61	C B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-87	0.61	C86 B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-88	0.14	C	0.077	0.00042	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-89	0.0067	J q	0.039	0.00046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-90	0.96	C B	0.12	0.00036	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-91	0.14	C88	0.077	0.00042	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-92	0.17		0.039	0.00040	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-93	0.0086	J C	0.077	0.00041	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-94	0.0033	J q	0.039	0.00046	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-95	1.0	B	0.039	0.00044	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-96	0.0060	J q	0.039	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-97	0.61	C86 B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-98	0.028	J C	0.077	0.00039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-99	0.47	C83 B	0.077	0.00043	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-100	0.0086	J C93	0.077	0.00041	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-101	0.96	C90 B	0.12	0.00036	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-102	0.028	J C98	0.077	0.00039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-103	0.0044	J q	0.039	0.00041	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-104	ND		0.039	0.00031	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-105	0.48	B	0.039	0.0063	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-106	ND		0.039	0.0058	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-107	0.079	q	0.039	0.0063	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-108	0.050	J C	0.077	0.0060	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-109	0.61	C86 B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-110	1.3	C B	0.077	0.00030	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-111	ND		0.039	0.00029	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-112	0.0017	J q	0.039	0.00030	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-113	0.96	C90 B	0.12	0.00036	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-114	0.018	J	0.039	0.0051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-115	1.3	C110 B	0.077	0.00030	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-116	0.15	C85 B	0.12	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-117	0.15	C85 B	0.12	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-118	1.1	B	0.039	0.0050	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-119	0.61	C86 B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-120	0.0021	J q	0.039	0.00029	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-121	ND		0.039	0.00030	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-122	0.017	J	0.039	0.0067	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-123	0.010	J q	0.039	0.0057	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-124	0.050	J C108	0.077	0.0060	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-125	0.61	C86 B	0.23	0.00035	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-126	0.022	J q	0.039	0.0069	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-127	ND		0.039	0.0058	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-128	0.37	C	0.077	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-129	2.8	C B	0.15	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-130	0.16		0.039	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-131	0.028	J	0.039	0.015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-132	0.94		0.039	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-133	0.028	J	0.039	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-134	0.14	C	0.077	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-135	0.58	C	0.077	0.00078	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-136	0.24		0.039	0.00056	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-137	0.11	q	0.039	0.012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-138	2.8	C129 B	0.15	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-139	0.037	J C	0.077	0.012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-140	0.037	J C139	0.077	0.012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-141	0.48		0.039	0.013	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-142	ND		0.039	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-143	0.14	C134	0.077	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-144	0.063		0.039	0.00070	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-145	0.0027	J	0.039	0.00053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-146	0.36		0.039	0.012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-147	2.5	C	0.077	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-148	ND		0.039	0.00075	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-149	2.5	C147	0.077	0.014	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-150	ND		0.039	0.00051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-151	0.58	C135	0.077	0.00078	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-152	0.0012	J q	0.039	0.00055	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-153	2.0	C B	0.077	0.0095	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-154	0.0078	J q	0.039	0.00061	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-155	ND		0.039	0.00051	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-156	0.23	C	0.077	0.010	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-157	0.23	C156	0.077	0.010	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-158	0.27		0.039	0.0086	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-159	ND		0.039	0.0091	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-160	2.8	C129 B	0.15	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-161	ND		0.039	0.0090	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-162	0.0096	J q	0.039	0.0089	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-163	2.8	C129 B	0.15	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-164	0.17		0.039	0.0096	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-165	ND		0.039	0.010	ng/L		11/24/20 12:36	12/02/20 07:21	1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-166	0.37	C128	0.077	0.011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-167	0.074		0.039	0.0073	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-168	2.0	C153 B	0.077	0.0095	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-169	ND		0.039	0.0080	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-170	0.58		0.039	0.0015	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-171	0.14	C	0.077	0.0013	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-172	0.081		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-173	0.14	C171	0.077	0.0013	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-174	0.53		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-175	0.017	J q	0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-176	0.058		0.039	0.00086	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-177	0.27		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-178	0.088		0.039	0.0012	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-179	0.24		0.039	0.00091	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-180	1.1	C B	0.077	0.00095	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-181	ND		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-182	ND		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-183	0.35	C B	0.077	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-184	ND		0.039	0.00093	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-185	0.35	C183 B	0.077	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-186	ND		0.039	0.00090	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-187	0.56		0.039	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-188	ND		0.039	0.00074	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-189	0.016	J	0.039	0.0052	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-190	0.079		0.039	0.00082	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-191	0.017	J	0.039	0.00085	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-192	ND		0.039	0.00095	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-193	1.1	C180 B	0.077	0.00095	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-194	0.26		0.039	0.0084	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-195	0.082	q	0.039	0.0092	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-196	0.12		0.039	0.0025	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-197	0.0062	J q	0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-198	0.26	C	0.077	0.0026	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-199	0.26	C198	0.077	0.0026	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-200	0.018	J q	0.039	0.0017	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-201	0.020	J q	0.039	0.0018	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-202	0.047		0.039	0.0020	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-203	0.14		0.039	0.0023	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-204	ND		0.039	0.0019	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-205	0.011	J	0.039	0.0071	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-206	0.11		0.039	0.0053	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-207	0.011	J	0.039	0.0039	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-208	0.023	J q	0.039	0.0041	ng/L		11/24/20 12:36	12/02/20 07:21	1
PCB-209	0.024	J q	0.039	0.0026	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Monochlorobiphenyls	0.045	q B	0.039	0.00055	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Dichlorobiphenyls	1.9	q B	0.077	0.0022	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Trichlorobiphenyls	3.1	q B	0.077	0.0011	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Tetrachlorobiphenyls	6.3	q B	0.15	0.0041	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Pentachlorobiphenyls	7.0	q B	0.23	0.0022	ng/L		11/24/20 12:36	12/02/20 07:21	1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Analyte	Result	Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Hexachlorobiphenyls	12	q B	0.15	0.0083	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Heptachlorobiphenyls	4.1	q B	0.077	0.0013	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Octachlorobiphenyls	0.96	q	0.077	0.0038	ng/L		11/24/20 12:36	12/02/20 07:21	1
Total Nonachlorobiphenyls	0.14	q	0.039	0.0045	ng/L		11/24/20 12:36	12/02/20 07:21	1
Polychlorinated biphenyls, Total	35	q B	0.23	0.0033	ng/L		11/24/20 12:36	12/02/20 07:21	1

Isotope Dilution	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-1L	*69*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-3L	*72*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-4L	*76*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-15L	*87*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-19L	*99*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-37L	*79*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-54L	*94*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-77L	*48*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-81L	*56*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-104L	*123*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-105L	*91*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-114L	*103*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-118L	*103*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-123L	*103*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-126L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-155L	*92*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-156L	*87*	*C*	*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-157L	*87*	*C156*	*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-167L	*88*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-169L	*87*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-170L	*91*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-188L	*116*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-189L	*86*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-202L	*114*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-205L	*78*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-206L	*85*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-208L	*82*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-209L	*97*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
PCB-28L	*99*		*5 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-111L	*76*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*
PCB-178L	*118*		*10 - 145*	*11/24/20 12:36*	*12/02/20 07:21*	*1*

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	2200		30	13	ug/L		11/03/20 08:21	11/10/20 21:57	1
Arsenic	2.4		1.0	0.31	ug/L		11/03/20 08:21	11/10/20 21:57	1
Barium	56		10	1.6	ug/L		11/03/20 08:21	11/10/20 21:57	1
Beryllium	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:57	1
Cadmium	ND		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 21:57	1
Calcium	18000		500	130	ug/L		11/03/20 08:21	11/10/20 21:57	1
Chromium	5.8		2.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:57	1
Cobalt	1.4		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 21:57	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Client Sample ID: OFW0500N
Date Collected: 10/29/20 11:05
Date Received: 10/30/20 08:45

Lab Sample ID: 180-112989-5
Matrix: Water

Method: EPA 6020A - Metals (ICP/MS) - Total Recoverable (Continued)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Copper	19		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 21:57	1
Iron	4200		50	20	ug/L		11/03/20 08:21	11/12/20 09:58	1
Silver	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 21:57	1
Potassium	1700		500	160	ug/L		11/03/20 08:21	11/10/20 21:57	1
Magnesium	3600		500	83	ug/L		11/03/20 08:21	11/10/20 21:57	1
Manganese	68		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 21:57	1
Sodium	2400		500	350	ug/L		11/03/20 08:21	11/12/20 09:58	1
Nickel	7.2		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 21:57	1
Lead	14		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 21:57	1
Antimony	2.0		2.0	0.38	ug/L		11/03/20 08:21	11/10/20 21:57	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 21:57	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 21:57	1
Vanadium	12		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 21:57	1
Zinc	100		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 21:57	1

Method: EPA 7470A - Mercury (CVAA)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 14:16	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	180		2.5	2.5	mg/L			11/02/20 07:39	1

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: MB 180-335567/1-A
Matrix: Water
Analysis Batch: 336474

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335567

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.19	0.065	ug/L		11/02/20 11:02	11/10/20 06:29	1
Acenaphthylene	ND		0.19	0.065	ug/L		11/02/20 11:02	11/10/20 06:29	1
Anthracene	ND		0.19	0.049	ug/L		11/02/20 11:02	11/10/20 06:29	1
Benzo[a]anthracene	ND		0.19	0.075	ug/L		11/02/20 11:02	11/10/20 06:29	1
Benzo[b]fluoranthene	ND		0.19	0.097	ug/L		11/02/20 11:02	11/10/20 06:29	1
Benzo[k]fluoranthene	ND		0.19	0.088	ug/L		11/02/20 11:02	11/10/20 06:29	1
Benzo[g,h,i]perylene	ND		0.19	0.069	ug/L		11/02/20 11:02	11/10/20 06:29	1
Benzo[a]pyrene	ND		0.19	0.053	ug/L		11/02/20 11:02	11/10/20 06:29	1
Chrysene	ND		0.19	0.081	ug/L		11/02/20 11:02	11/10/20 06:29	1
Dibenz(a,h)anthracene	ND		0.19	0.072	ug/L		11/02/20 11:02	11/10/20 06:29	1
Fluoranthene	ND		0.19	0.060	ug/L		11/02/20 11:02	11/10/20 06:29	1
Fluorene	ND		0.19	0.069	ug/L		11/02/20 11:02	11/10/20 06:29	1
Indeno[1,2,3-cd]pyrene	ND		0.19	0.085	ug/L		11/02/20 11:02	11/10/20 06:29	1
Naphthalene	ND		0.19	0.059	ug/L		11/02/20 11:02	11/10/20 06:29	1
Phenanthrene	ND		0.19	0.055	ug/L		11/02/20 11:02	11/10/20 06:29	1
Pyrene	ND		0.19	0.054	ug/L		11/02/20 11:02	11/10/20 06:29	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*63*		*23 - 105*	*11/02/20 11:02*	*11/10/20 06:29*	*1*
Nitrobenzene-d5 (Surr)	*66*		*28 - 111*	*11/02/20 11:02*	*11/10/20 06:29*	*1*
Terphenyl-d14 (Surr)	*63*		*20 - 126*	*11/02/20 11:02*	*11/10/20 06:29*	*1*

Lab Sample ID: LCS 180-335567/2-A
Matrix: Water
Analysis Batch: 336474

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335567

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	20.0	14.0		ug/L		70	50 - 100
Acenaphthylene	20.0	14.0		ug/L		70	51 - 100
Anthracene	20.0	14.5		ug/L		73	53 - 100
Benzo[a]anthracene	20.0	14.5		ug/L		73	51 - 100
Benzo[b]fluoranthene	20.0	13.3		ug/L		66	45 - 100
Benzo[k]fluoranthene	20.0	13.7		ug/L		69	49 - 100
Benzo[g,h,i]perylene	20.0	15.7		ug/L		78	51 - 100
Benzo[a]pyrene	20.0	14.4		ug/L		72	51 - 100
Chrysene	20.0	14.3		ug/L		72	51 - 100
Dibenz(a,h)anthracene	20.0	16.7		ug/L		84	50 - 100
Fluoranthene	20.0	15.7		ug/L		78	54 - 100
Fluorene	20.0	14.7		ug/L		73	53 - 100
Indeno[1,2,3-cd]pyrene	20.0	15.6		ug/L		78	50 - 100
Naphthalene	20.0	13.8		ug/L		69	55 - 100
Phenanthrene	20.0	14.1		ug/L		71	51 - 100
Pyrene	20.0	13.3		ug/L		66	47 - 100

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*65*		*23 - 105*
Nitrobenzene-d5 (Surr)	*71*		*28 - 111*
Terphenyl-d14 (Surr)	*65*		*20 - 126*

Method: EPA 8270D LL - Semivolatile Organic Compounds by GC/MS - Low Level

Lab Sample ID: MB 180-336041/1-A
Matrix: Water
Analysis Batch: 336496

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 336041

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.19	0.065	ug/L		11/05/20 12:15	11/10/20 08:05	1
Acenaphthylene	ND		0.19	0.065	ug/L		11/05/20 12:15	11/10/20 08:05	1
Anthracene	ND		0.19	0.049	ug/L		11/05/20 12:15	11/10/20 08:05	1
Benzo[a]anthracene	ND		0.19	0.075	ug/L		11/05/20 12:15	11/10/20 08:05	1
Benzo[b]fluoranthene	ND		0.19	0.097	ug/L		11/05/20 12:15	11/10/20 08:05	1
Benzo[k]fluoranthene	ND		0.19	0.088	ug/L		11/05/20 12:15	11/10/20 08:05	1
Benzo[g,h,i]perylene	ND		0.19	0.069	ug/L		11/05/20 12:15	11/10/20 08:05	1
Benzo[a]pyrene	ND		0.19	0.053	ug/L		11/05/20 12:15	11/10/20 08:05	1
Chrysene	ND		0.19	0.081	ug/L		11/05/20 12:15	11/10/20 08:05	1
Dibenz(a,h)anthracene	ND		0.19	0.072	ug/L		11/05/20 12:15	11/10/20 08:05	1
Fluoranthene	ND		0.19	0.060	ug/L		11/05/20 12:15	11/10/20 08:05	1
Fluorene	ND		0.19	0.069	ug/L		11/05/20 12:15	11/10/20 08:05	1
Indeno[1,2,3-cd]pyrene	ND		0.19	0.085	ug/L		11/05/20 12:15	11/10/20 08:05	1
Naphthalene	ND		0.19	0.059	ug/L		11/05/20 12:15	11/10/20 08:05	1
Phenanthrene	ND		0.19	0.055	ug/L		11/05/20 12:15	11/10/20 08:05	1
Pyrene	ND		0.19	0.054	ug/L		11/05/20 12:15	11/10/20 08:05	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*75*		*23 - 105*	*11/05/20 12:15*	*11/10/20 08:05*	*1*
Nitrobenzene-d5 (Surr)	*76*		*28 - 111*	*11/05/20 12:15*	*11/10/20 08:05*	*1*
Terphenyl-d14 (Surr)	*73*		*20 - 126*	*11/05/20 12:15*	*11/10/20 08:05*	*1*

Lab Sample ID: LCS 180-336041/2-A
Matrix: Water
Analysis Batch: 336496

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 336041

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthene	20.0	14.8		ug/L		74	50 - 100
Acenaphthylene	20.0	15.6		ug/L		78	51 - 100
Anthracene	20.0	15.8		ug/L		79	53 - 100
Benzo[a]anthracene	20.0	15.9		ug/L		79	51 - 100
Benzo[b]fluoranthene	20.0	15.4		ug/L		77	45 - 100
Benzo[k]fluoranthene	20.0	15.2		ug/L		76	49 - 100
Benzo[g,h,i]perylene	20.0	15.9		ug/L		79	51 - 100
Benzo[a]pyrene	20.0	16.3		ug/L		81	51 - 100
Chrysene	20.0	15.7		ug/L		78	51 - 100
Dibenz(a,h)anthracene	20.0	16.3		ug/L		82	50 - 100
Fluoranthene	20.0	15.8		ug/L		79	54 - 100
Fluorene	20.0	15.3		ug/L		76	53 - 100
Indeno[1,2,3-cd]pyrene	20.0	16.2		ug/L		81	50 - 100
Naphthalene	20.0	15.2		ug/L		76	55 - 100
Phenanthrene	20.0	15.2		ug/L		76	51 - 100
Pyrene	20.0	16.2		ug/L		81	47 - 100

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*77*		*23 - 105*
Nitrobenzene-d5 (Surr)	*76*		*28 - 111*
Terphenyl-d14 (Surr)	*77*		*20 - 126*

Method: 8015D - Diesel Range Organics (DRO) (GC)

Lab Sample ID: MB 240-459194/6-A
Matrix: Water
Analysis Batch: 459394

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 459194

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Diesel Range Organics [C10 - C28]	ND		500	230	ug/L		11/04/20 07:54	11/05/20 16:32	1
ORO C24-C40	ND		500	230	ug/L		11/04/20 07:54	11/05/20 16:32	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
o-Terphenyl	*76*		*52 - 121*	*11/04/20 07:54*	*11/05/20 16:32*	*1*

Lab Sample ID: LCS 240-459194/7-A
Matrix: Water
Analysis Batch: 459394

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 459194

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Diesel Range Organics [C10 - C28]			2000	1670		ug/L		84	56 - 120		

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
o-Terphenyl	*79*		*52 - 121*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS)

Lab Sample ID: MB 140-44772/7-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 44772

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1	ND		0.040	0.00022	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-2	0.00218	J	0.040	0.00025	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-3	0.00256	J	0.040	0.00027	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-4	0.00440	J q	0.060	0.0041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-5	ND		0.040	0.0033	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-6	ND		0.040	0.0029	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-7	ND		0.040	0.0030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-8	0.00548	J q	0.060	0.0027	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-9	ND		0.040	0.0030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-10	ND		0.040	0.0032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-11	0.0272	J q	0.060	0.0028	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-12	ND	C	0.080	0.0029	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-13	ND	C12	0.080	0.0029	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-14	ND		0.040	0.0025	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-15	0.00532	J q	0.040	0.0030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-16	ND		0.040	0.00054	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-17	0.00133	J q	0.040	0.00049	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-18	0.00242	J C q	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-19	ND		0.040	0.00059	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-20	0.00715	J C	0.080	0.00044	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-21	0.00331	J C	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-22	0.00181	J	0.040	0.00045	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-23	ND		0.040	0.00044	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-24	ND		0.040	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-44772/7-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 44772

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-25	ND		0.040	0.00040	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-26	0.000973	J C q	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-27	ND		0.040	0.00035	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-28	0.00715	J C20	0.080	0.00044	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-29	0.000973	J C26 q	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-30	0.00242	J C18 q	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-31	0.00529	J	0.040	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-32	0.00177	J	0.040	0.00034	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-33	0.00331	J C21	0.080	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-34	ND		0.040	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-35	ND		0.040	0.00045	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-36	ND		0.040	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-37	0.00281	J q	0.040	0.00044	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-38	ND		0.040	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-39	ND		0.040	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-40	ND	C	0.12	0.00076	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-41	ND	C40	0.12	0.00076	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-42	ND		0.040	0.00076	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-43	ND	C	0.080	0.00071	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-44	0.00462	J C q	0.12	0.00067	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-45	ND	C	0.080	0.00079	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-46	ND		0.040	0.00096	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-47	0.00462	J C44 q	0.12	0.00067	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-48	ND		0.040	0.00075	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-49	ND	C	0.080	0.00062	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-50	ND	C	0.080	0.00073	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-51	ND	C45	0.080	0.00079	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-52	0.00263	J q	0.040	0.00075	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-53	ND	C50	0.080	0.00073	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-54	ND		0.040	0.000090	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-55	ND		0.040	0.00055	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-56	0.00162	J q	0.040	0.00055	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-57	ND		0.040	0.00056	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-58	ND		0.040	0.00057	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-59	ND	C	0.12	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-60	ND		0.040	0.00056	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-61	0.00559	J C q	0.16	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-62	ND	C59	0.12	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-63	ND		0.040	0.00051	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-64	0.00111	J q	0.040	0.00050	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-65	0.00462	J C44 q	0.12	0.00067	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-66	0.00321	J	0.040	0.00052	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-67	ND		0.040	0.00048	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-68	ND		0.040	0.00049	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-69	ND	C49	0.080	0.00062	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-70	0.00559	J C61 q	0.16	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-71	ND	C40	0.12	0.00076	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-72	ND		0.040	0.00055	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-73	ND	C43	0.080	0.00071	ng/L		11/24/20 12:36	12/01/20 16:54	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-44772/7-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 44772

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-74	0.00559	J C61 q	0.16	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-75	ND	C59	0.12	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-76	0.00559	J C61 q	0.16	0.00053	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-77	0.00168	J	0.040	0.00054	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-78	ND		0.040	0.00057	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-79	ND		0.040	0.00049	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-80	ND		0.040	0.00048	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-81	ND		0.040	0.00051	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-82	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-83	0.00266	J C	0.080	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-84	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-85	0.000548	J C q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-86	0.00207	J C q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-87	0.00207	J C86 q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-88	ND	C	0.080	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-89	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-90	0.00298	J C q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-91	ND	C88	0.080	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-92	ND		0.040	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-93	ND	C	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-94	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-95	0.00304	J	0.040	0.00019	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-96	ND		0.040	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-97	0.00207	J C86 q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-98	ND	C	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-99	0.00266	J C83	0.080	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-100	ND	C93	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-101	0.00298	J C90 q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-102	ND	C98	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-103	ND		0.040	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-104	ND		0.040	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-105	0.00138	J q	0.040	0.00031	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-106	ND		0.040	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-107	ND		0.040	0.00034	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-108	ND	C	0.080	0.00033	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-109	0.00207	J C86 q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-110	0.00396	J C	0.080	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-111	ND		0.040	0.00012	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-112	ND		0.040	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-113	0.00298	J C90 q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-114	ND		0.040	0.00030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-115	0.00396	J C110	0.080	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-116	0.000548	J C85 q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-117	0.000548	J C85 q	0.12	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-118	0.00396	J q	0.040	0.00030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-119	0.00207	J C86 q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-120	ND		0.040	0.00012	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-121	ND		0.040	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-122	ND		0.040	0.00037	ng/L		11/24/20 12:36	12/01/20 16:54	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-44772/7-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 44772

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-123	ND		0.040	0.00033	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-124	ND	C108	0.080	0.00033	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-125	0.00207	J C86 q	0.24	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-126	ND		0.040	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-127	ND		0.040	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-128	ND	C	0.080	0.00036	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-129	0.00213	J C q	0.16	0.00037	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-130	ND		0.040	0.00048	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-131	ND		0.040	0.00051	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-132	ND		0.040	0.00047	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-133	ND		0.040	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-134	ND	C	0.080	0.00048	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-135	ND	C	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-136	ND		0.040	0.00012	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-137	ND		0.040	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-138	0.00213	J C129 q	0.16	0.00037	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-139	ND	C	0.080	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-140	ND	C139	0.080	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-141	ND		0.040	0.00043	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-142	ND		0.040	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-143	ND	C134	0.080	0.00048	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-144	ND		0.040	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-145	ND		0.040	0.00011	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-146	ND		0.040	0.00040	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-147	ND	C	0.080	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-148	ND		0.040	0.00016	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-149	ND	C147	0.080	0.00046	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-150	ND		0.040	0.00011	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-151	ND	C135	0.080	0.00017	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-152	ND		0.040	0.00012	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-153	0.00211	J C	0.080	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-154	ND		0.040	0.00013	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-155	ND		0.040	0.00011	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-156	ND	C	0.080	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-157	ND	C156	0.080	0.00041	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-158	ND		0.040	0.00029	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-159	ND		0.040	0.00031	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-160	0.00213	J C129 q	0.16	0.00037	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-161	ND		0.040	0.00030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-162	ND		0.040	0.00030	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-163	0.00213	J C129 q	0.16	0.00037	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-164	ND		0.040	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-165	ND		0.040	0.00034	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-166	ND	C128	0.080	0.00036	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-167	ND		0.040	0.00023	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-168	0.00211	J C153	0.080	0.00032	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-169	ND		0.040	0.00022	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-170	ND		0.040	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-171	ND	C	0.080	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: MB 140-44772/7-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 44772

Analyte	MB Result	MB Qualifier	RL	EDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-172	ND		0.040	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-173	ND	C171	0.080	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-174	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-175	ND		0.040	0.00019	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-176	ND		0.040	0.00014	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-177	ND		0.040	0.00020	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-178	ND		0.040	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-179	ND		0.040	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-180	0.00152	J C q	0.080	0.00016	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-181	ND		0.040	0.00019	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-182	ND		0.040	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-183	0.00197	J C q	0.080	0.00019	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-184	ND		0.040	0.00016	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-185	0.00197	J C183 q	0.080	0.00019	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-186	ND		0.040	0.00015	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-187	ND		0.040	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-188	ND		0.040	0.00014	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-189	ND		0.040	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-190	ND		0.040	0.00014	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-191	ND		0.040	0.00014	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-192	ND		0.040	0.00016	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-193	0.00152	J C180 q	0.080	0.00016	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-194	ND		0.040	0.00022	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-195	ND		0.040	0.00024	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-196	ND		0.040	0.000096	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-197	ND		0.040	0.000073	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-198	ND	C	0.080	0.000097	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-199	ND	C198	0.080	0.000097	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-200	ND		0.040	0.000065	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-201	ND		0.040	0.000067	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-202	ND		0.040	0.000075	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-203	ND		0.040	0.000087	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-204	ND		0.040	0.000074	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-205	ND		0.040	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-206	ND		0.040	0.0014	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-207	ND		0.040	0.00096	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-208	ND		0.040	0.00098	ng/L		11/24/20 12:36	12/01/20 16:54	1
PCB-209	ND		0.040	0.00012	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Monochlorobiphenyls	0.00474	J	0.040	0.00025	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Dichlorobiphenyls	0.0424	J q	0.080	0.0030	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Trichlorobiphenyls	0.0269	J q	0.080	0.00044	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Tetrachlorobiphenyls	0.0205	J q	0.16	0.00059	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Pentachlorobiphenyls	0.0206	J q	0.24	0.00021	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Hexachlorobiphenyls	0.00424	J q	0.16	0.00031	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Heptachlorobiphenyls	0.00349	J q	0.080	0.00018	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Octachlorobiphenyls	ND		0.080	0.00024	ng/L		11/24/20 12:36	12/01/20 16:54	1
Total Nonachlorobiphenyls	ND		0.040	0.0014	ng/L		11/24/20 12:36	12/01/20 16:54	1
Polychlorinated biphenyls, Total	0.123	J q	0.24	0.00072	ng/L		11/24/20 12:36	12/01/20 16:54	1

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Isotope Dilution	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-1L	64		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-3L	64		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-4L	76		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-15L	78		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-19L	83		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-37L	79		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-54L	92		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-77L	87		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-81L	85		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-104L	70		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-105L	92		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-114L	89		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-118L	89		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-123L	87		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-126L	86		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-155L	82		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-156L	92	C	10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-157L	92	C156	10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-167L	93		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-169L	99		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-170L	88		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-188L	83		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-189L	81		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-202L	104		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-205L	77		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-206L	90		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-208L	90		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-209L	92		10 - 145	11/24/20 12:36	12/01/20 16:54	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
PCB-28L	89		5 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-111L	96		10 - 145	11/24/20 12:36	12/01/20 16:54	1
PCB-178L	94		10 - 145	11/24/20 12:36	12/01/20 16:54	1

Lab Sample ID: LCS 140-44772/6-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 44772

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1	1.00	0.911		ng/L		91	60 - 135
PCB-3	1.00	0.925		ng/L		92	60 - 135
PCB-4	1.00	1.13		ng/L		113	60 - 135
PCB-15	1.00	1.17		ng/L		117	60 - 135
PCB-19	1.00	1.20		ng/L		120	60 - 135
PCB-37	1.00	1.09		ng/L		109	60 - 135
PCB-54	1.00	1.12		ng/L		112	60 - 135
PCB-77	1.00	1.04		ng/L		104	60 - 135
PCB-81	1.00	0.997		ng/L		100	60 - 135
PCB-104	1.00	1.29		ng/L		129	60 - 135
PCB-105	1.00	1.14		ng/L		114	60 - 135
PCB-114	1.00	1.24		ng/L		124	60 - 135

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-44772/6-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 44772

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
PCB-118			1.00	1.14		ng/L		114	60 - 135		
PCB-123			1.00	1.20		ng/L		120	60 - 135		
PCB-126			1.00	1.16		ng/L		116	60 - 135		
PCB-155			1.00	1.20		ng/L		120	60 - 135		
PCB-156			2.00	2.25	C	ng/L		112	60 - 135		
PCB-157			2.00	2.25	C156	ng/L		112	60 - 135		
PCB-167			1.00	1.13		ng/L		113	60 - 135		
PCB-169			1.00	1.02		ng/L		102	60 - 135		
PCB-188			1.00	1.10		ng/L		110	60 - 135		
PCB-189			1.00	1.10		ng/L		110	60 - 135		
PCB-202			1.00	0.865		ng/L		86	60 - 135		
PCB-205			1.00	1.08		ng/L		108	60 - 135		
PCB-206			1.00	0.762		ng/L		76	60 - 135		
PCB-208			1.00	0.768		ng/L		77	60 - 135		
PCB-209			1.00	0.682		ng/L		68	60 - 135		

Isotope Dilution	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-1L	*69*		*15 - 145*
PCB-3L	*70*		*15 - 145*
PCB-4L	*80*		*15 - 145*
PCB-15L	*82*		*15 - 145*
PCB-19L	*83*		*15 - 145*
PCB-37L	*82*		*15 - 145*
PCB-54L	*93*		*15 - 145*
PCB-77L	*91*		*40 - 145*
PCB-81L	*90*		*40 - 145*
PCB-104L	*74*		*40 - 145*
PCB-105L	*94*		*40 - 145*
PCB-114L	*90*		*40 - 145*
PCB-118L	*91*		*40 - 145*
PCB-123L	*88*		*40 - 145*
PCB-126L	*91*		*40 - 145*
PCB-155L	*86*		*40 - 145*
PCB-156L	*94*	*C*	*40 - 145*
PCB-157L	*94*	*C156*	*40 - 145*
PCB-167L	*95*		*40 - 145*
PCB-169L	*100*		*40 - 145*
PCB-170L	*90*		*40 - 145*
PCB-188L	*86*		*40 - 145*
PCB-189L	*85*		*40 - 145*
PCB-202L	*105*		*40 - 145*
PCB-205L	*79*		*40 - 145*
PCB-206L	*92*		*40 - 145*
PCB-208L	*92*		*40 - 145*
PCB-209L	*98*		*40 - 145*

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
PCB-28L	*93*		*15 - 145*

Method: 1668C - Chlorinated Biphenyl Congeners (HRGC/HRMS) (Continued)

Lab Sample ID: LCS 140-44772/6-A
Matrix: Water
Analysis Batch: 44889

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 44772

Surrogate	LCS %Recovery	LCS Qualifier	Limits
PCB-111L	99		40 - 145
PCB-178L	102		40 - 145

Method: EPA 6020A - Metals (ICP/MS)

Lab Sample ID: MB 180-335675/1-A
Matrix: Water
Analysis Batch: 336676

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 335675

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Aluminum	ND		30	13	ug/L		11/03/20 08:21	11/10/20 18:42	1
Arsenic	ND		1.0	0.31	ug/L		11/03/20 08:21	11/10/20 18:42	1
Barium	ND		10	1.6	ug/L		11/03/20 08:21	11/10/20 18:42	1
Beryllium	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 18:42	1
Cadmium	ND		1.0	0.22	ug/L		11/03/20 08:21	11/10/20 18:42	1
Calcium	ND		500	130	ug/L		11/03/20 08:21	11/10/20 18:42	1
Chromium	ND		2.0	1.5	ug/L		11/03/20 08:21	11/10/20 18:42	1
Cobalt	ND		0.50	0.13	ug/L		11/03/20 08:21	11/10/20 18:42	1
Copper	ND		2.0	0.63	ug/L		11/03/20 08:21	11/10/20 18:42	1
Silver	ND		1.0	0.18	ug/L		11/03/20 08:21	11/10/20 18:42	1
Potassium	ND		500	160	ug/L		11/03/20 08:21	11/10/20 18:42	1
Magnesium	ND		500	83	ug/L		11/03/20 08:21	11/10/20 18:42	1
Manganese	ND		5.0	0.87	ug/L		11/03/20 08:21	11/10/20 18:42	1
Nickel	ND		1.0	0.34	ug/L		11/03/20 08:21	11/10/20 18:42	1
Lead	ND		1.0	0.13	ug/L		11/03/20 08:21	11/10/20 18:42	1
Antimony	ND		2.0	0.38	ug/L		11/03/20 08:21	11/10/20 18:42	1
Selenium	ND		5.0	1.5	ug/L		11/03/20 08:21	11/10/20 18:42	1
Thallium	ND		1.0	0.15	ug/L		11/03/20 08:21	11/10/20 18:42	1
Vanadium	ND		1.0	0.99	ug/L		11/03/20 08:21	11/10/20 18:42	1
Zinc	ND		5.0	3.2	ug/L		11/03/20 08:21	11/10/20 18:42	1

Lab Sample ID: MB 180-335675/1-A
Matrix: Water
Analysis Batch: 336907

Client Sample ID: Method Blank
Prep Type: Total Recoverable
Prep Batch: 335675

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Iron	ND		50	20	ug/L		11/03/20 08:21	11/12/20 07:50	1
Sodium	ND		500	350	ug/L		11/03/20 08:21	11/12/20 07:50	1

Lab Sample ID: LCS 180-335675/2-A
Matrix: Water
Analysis Batch: 336676

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 335675

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Aluminum	5000	5090		ug/L		102	80 - 120
Arsenic	1000	998		ug/L		100	80 - 120
Barium	1000	968		ug/L		97	80 - 120
Beryllium	500	494		ug/L		99	80 - 120
Cadmium	500	477		ug/L		95	80 - 120

Method: EPA 6020A - Metals (ICP/MS) (Continued)

Lab Sample ID: LCS 180-335675/2-A
Matrix: Water
Analysis Batch: 336676

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 335675

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Calcium	25000	28600		ug/L		114	80 - 120
Chromium	500	476		ug/L		95	80 - 120
Cobalt	500	486		ug/L		97	80 - 120
Copper	500	476		ug/L		95	80 - 120
Silver	250	249		ug/L		100	80 - 120
Potassium	25000	25000		ug/L		100	80 - 120
Magnesium	25000	25600		ug/L		102	80 - 120
Manganese	500	475		ug/L		95	80 - 120
Nickel	500	473		ug/L		95	80 - 120
Lead	500	494		ug/L		99	80 - 120
Antimony	250	238		ug/L		95	80 - 120
Selenium	1000	978		ug/L		98	80 - 120
Thallium	1000	1040		ug/L		104	80 - 120
Vanadium	500	471		ug/L		94	80 - 120
Zinc	250	252		ug/L		101	80 - 120

Lab Sample ID: LCS 180-335675/2-A
Matrix: Water
Analysis Batch: 336907

Client Sample ID: Lab Control Sample
Prep Type: Total Recoverable
Prep Batch: 335675

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Iron	5000	5300		ug/L		106	80 - 120
Sodium	25000	26100		ug/L		104	80 - 120

Method: EPA 7470A - Mercury (CVAA)

Lab Sample ID: MB 180-335867/1-A
Matrix: Water
Analysis Batch: 336250

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 335867

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.20	0.13	ug/L		11/04/20 09:46	11/06/20 13:53	1

Lab Sample ID: LCS 180-335867/2-A
Matrix: Water
Analysis Batch: 336250

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 335867

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Mercury	2.50	2.42		ug/L		97	80 - 120

Method: SM 2540D - Solids, Total Suspended (TSS)

Lab Sample ID: MB 180-335539/2
Matrix: Water
Analysis Batch: 335539

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Suspended Solids	ND		0.50	0.50	mg/L			11/02/20 07:39	1

Method: SM 2540D - Solids, Total Suspended (TSS) (Continued)

Lab Sample ID: LCS 180-335539/1
Matrix: Water
Analysis Batch: 335539

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Total Suspended Solids			31.6	28.0		mg/L		89	80 - 120		

Lab Sample ID: 180-112989-2 DU
Matrix: Water
Analysis Batch: 335539

Client Sample ID: OFW0200N
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Total Suspended Solids	54			50.0		mg/L				8	10

QC Association Summary

Client: AECOM
Job ID: 180-112989-1
Project/Site: Pepco Benning Road Facility

GC/MS Semi VOA

Prep Batch: 335567

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	3520C	
180-112989-2	OFW0200N	Total/NA	Water	3520C	
180-112989-3	OFW0300N	Total/NA	Water	3520C	
MB 180-335567/1-A	Method Blank	Total/NA	Water	3520C	
LCS 180-335567/2-A	Lab Control Sample	Total/NA	Water	3520C	

Prep Batch: 336041

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-4	OFW0400N	Total/NA	Water	3520C	
180-112989-5	OFW0500N	Total/NA	Water	3520C	
MB 180-336041/1-A	Method Blank	Total/NA	Water	3520C	
LCS 180-336041/2-A	Lab Control Sample	Total/NA	Water	3520C	

Analysis Batch: 336474

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	EPA 8270D LL	335567
180-112989-2	OFW0200N	Total/NA	Water	EPA 8270D LL	335567
180-112989-3	OFW0300N	Total/NA	Water	EPA 8270D LL	335567
MB 180-335567/1-A	Method Blank	Total/NA	Water	EPA 8270D LL	335567
LCS 180-335567/2-A	Lab Control Sample	Total/NA	Water	EPA 8270D LL	335567

Analysis Batch: 336496

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-4	OFW0400N	Total/NA	Water	EPA 8270D LL	336041
180-112989-5	OFW0500N	Total/NA	Water	EPA 8270D LL	336041
MB 180-336041/1-A	Method Blank	Total/NA	Water	EPA 8270D LL	336041
LCS 180-336041/2-A	Lab Control Sample	Total/NA	Water	EPA 8270D LL	336041

GC Semi VOA

Prep Batch: 459194

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	3510C LVI	
180-112989-2	OFW0200N	Total/NA	Water	3510C LVI	
180-112989-3	OFW0300N	Total/NA	Water	3510C LVI	
180-112989-4	OFW0400N	Total/NA	Water	3510C LVI	
180-112989-5	OFW0500N	Total/NA	Water	3510C LVI	
MB 240-459194/6-A	Method Blank	Total/NA	Water	3510C LVI	
LCS 240-459194/7-A	Lab Control Sample	Total/NA	Water	3510C LVI	

Analysis Batch: 459394

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	8015D	459194
180-112989-2	OFW0200N	Total/NA	Water	8015D	459194
180-112989-5	OFW0500N	Total/NA	Water	8015D	459194
MB 240-459194/6-A	Method Blank	Total/NA	Water	8015D	459194
LCS 240-459194/7-A	Lab Control Sample	Total/NA	Water	8015D	459194

Analysis Batch: 459606

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-3	OFW0300N	Total/NA	Water	8015D	459194

GC Semi VOA (Continued)

Analysis Batch: 459606 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-4	OFW0400N	Total/NA	Water	8015D	459194

Specialty Organics

Prep Batch: 44772

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	HRMS-Sepf	
180-112989-2	OFW0200N	Total/NA	Water	HRMS-Sepf	
180-112989-3	OFW0300N	Total/NA	Water	HRMS-Sepf	
180-112989-4	OFW0400N	Total/NA	Water	HRMS-Sepf	
180-112989-5	OFW0500N	Total/NA	Water	HRMS-Sepf	
MB 140-44772/7-A	Method Blank	Total/NA	Water	HRMS-Sepf	
LCS 140-44772/6-A	Lab Control Sample	Total/NA	Water	HRMS-Sepf	

Analysis Batch: 44889

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 140-44772/7-A	Method Blank	Total/NA	Water	1668C	44772
LCS 140-44772/6-A	Lab Control Sample	Total/NA	Water	1668C	44772

Analysis Batch: 44901

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	1668C	44772
180-112989-2	OFW0200N	Total/NA	Water	1668C	44772
180-112989-5	OFW0500N	Total/NA	Water	1668C	44772

Analysis Batch: 44910

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-3	OFW0300N	Total/NA	Water	1668C	44772
180-112989-4	OFW0400N	Total/NA	Water	1668C	44772

Metals

Prep Batch: 335675

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total Recoverable	Water	3005A	
180-112989-2	OFW0200N	Total Recoverable	Water	3005A	
180-112989-3	OFW0300N	Total Recoverable	Water	3005A	
180-112989-4	OFW0400N	Total Recoverable	Water	3005A	
180-112989-5	OFW0500N	Total Recoverable	Water	3005A	
MB 180-335675/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 180-335675/2-A	Lab Control Sample	Total Recoverable	Water	3005A	

Prep Batch: 335867

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	7470A	
180-112989-2	OFW0200N	Total/NA	Water	7470A	
180-112989-3	OFW0300N	Total/NA	Water	7470A	
180-112989-4	OFW0400N	Total/NA	Water	7470A	
180-112989-5	OFW0500N	Total/NA	Water	7470A	
MB 180-335867/1-A	Method Blank	Total/NA	Water	7470A	
LCS 180-335867/2-A	Lab Control Sample	Total/NA	Water	7470A	

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112989-1

Metals

Analysis Batch: 336250

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	EPA 7470A	335867
180-112989-2	OFW0200N	Total/NA	Water	EPA 7470A	335867
180-112989-3	OFW0300N	Total/NA	Water	EPA 7470A	335867
180-112989-4	OFW0400N	Total/NA	Water	EPA 7470A	335867
180-112989-5	OFW0500N	Total/NA	Water	EPA 7470A	335867
MB 180-335867/1-A	Method Blank	Total/NA	Water	EPA 7470A	335867
LCS 180-335867/2-A	Lab Control Sample	Total/NA	Water	EPA 7470A	335867

Analysis Batch: 336676

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total Recoverable	Water	EPA 6020A	335675
180-112989-2	OFW0200N	Total Recoverable	Water	EPA 6020A	335675
180-112989-3	OFW0300N	Total Recoverable	Water	EPA 6020A	335675
180-112989-4	OFW0400N	Total Recoverable	Water	EPA 6020A	335675
180-112989-5	OFW0500N	Total Recoverable	Water	EPA 6020A	335675
MB 180-335675/1-A	Method Blank	Total Recoverable	Water	EPA 6020A	335675
LCS 180-335675/2-A	Lab Control Sample	Total Recoverable	Water	EPA 6020A	335675

Analysis Batch: 336907

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total Recoverable	Water	EPA 6020A	335675
180-112989-2	OFW0200N	Total Recoverable	Water	EPA 6020A	335675
180-112989-3	OFW0300N	Total Recoverable	Water	EPA 6020A	335675
180-112989-4	OFW0400N	Total Recoverable	Water	EPA 6020A	335675
180-112989-5	OFW0500N	Total Recoverable	Water	EPA 6020A	335675
MB 180-335675/1-A	Method Blank	Total Recoverable	Water	EPA 6020A	335675
LCS 180-335675/2-A	Lab Control Sample	Total Recoverable	Water	EPA 6020A	335675

General Chemistry

Analysis Batch: 335539

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112989-1	OFW0100N	Total/NA	Water	SM 2540D	
180-112989-2	OFW0200N	Total/NA	Water	SM 2540D	
180-112989-3	OFW0300N	Total/NA	Water	SM 2540D	
180-112989-4	OFW0400N	Total/NA	Water	SM 2540D	
180-112989-5	OFW0500N	Total/NA	Water	SM 2540D	
MB 180-335539/2	Method Blank	Total/NA	Water	SM 2540D	
LCS 180-335539/1	Lab Control Sample	Total/NA	Water	SM 2540D	
180-112989-2 DU	OFW0200N	Total/NA	Water	SM 2540D	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

Baltimore #201

eurofins | Environment Testing America

Client Information	Sampler: QIANG HUANG	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-63831-12848.1
Client Contact: Mr. Robert Kennedy	Phone: 240-374-8920	E-Mail: Jill.Colussy@Eurofinset.com		Page: Page 1 of 1
Company: AECOM				Job #:
Address: 250 Apollo Drive	Due Date Requested:			
City: Chelmsford	TAT Requested (days):			
State, Zip: MA, 01824				
Phone:	PO #: 126546			
Email: robert.kennedy@aecom.com	WO #: 60631088.3			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL	M - Hexane
B - NaOH	N - None
C - Zn Acetate	O - AsNaO2
D - Nitric Acid	P - Na2O4S
E - NaHSO4	Q - Na2SO3
F - MeOH	R - Na2S2O3
G - Amchlor	S - H2SO4
H - Ascorbic Acid	T - TSP Dodecahydrate
I - Ice	U - Acetone
J - DI Water	V - MCAA
K - EDTA	W - pH 4-5
L - EDA	Z - other (specify)

Other:

Sample Identification	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C - PCB Congeners	8270D-LL-PAH by GC/MS	6020A - TAL Metals (ICP/MS)	6020A-Lead	2540D - Local Method	8015D-DRO - DRO (OA)	Total Number of containers	Special Instructions/Note:
			Preservation Code:											
OFW0100N	10/29/20	1145	G	W			X	X	X	X	X			
OFW0200N	10/29/20	1150	G	W			X	X	X	X	X			
OFW0300N	10/29/20	1135	G	W			X	X	X	X	X			
OFW0400N	10/29/20	1120	G	W			X	X	X	X	X			
OFW0500N	10/29/20	1105	G	W			X	X	X	X	X			

180-112989 Chain of Custody

Possible Hazard Identification
☐ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown ☐ Radiological

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)
☐ Return To Client ☐ Disposal By Lab ☐ Archive For _____ Months

Deliverable Requested: I, II, III, IV, Other (specify)


Special Instructions/QC Requirements:


Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

	Relinquished by	Date/Time	Company	Received by	Date/Time	Company
1	QIANG HUANG	10/29/2020 1345			10/29/20 1750	EA Salt
2		10/29/20 17:00	EA Salt		10/30/20 845	
3		Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019


Do Not Lift Using This Tag
ORIGIN ID:KEUA (410) 869-0085
SETH CAPLAN
EUROFINS TESTAMERICA
7526 CONNELLEY DR
SUITE F
BALTIMORE, MD 21228
UNITED STATES US
SHIP DATE: 29OCT20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280
BILL RECIPIENT
TO SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058
REF: AECOM PEPCO
INV:
PO:
DEPT:
FedEx Express
FRI - 30 OCT 10:30A
PRIORITY OVERNIGHT
1 of 2
TRK# 0201 7719 4166 5320
MASTER
15238
EA AGCA
PA-US PIT
Uncorrected temp 3.9 °C
Thermometer ID 14
CF 0 Initials JJ
PT-WI-SR-001 effective 7/26/13
Part # 156297-435 RRDW2 EXP 07/21
180-112989 Waybill


Do Not Ent Using This Tag
IN ID:KEUA (410) 869-0035
CAPLAN
FINS TESTAMERICA
CONNELLEY DR
E F
MORE, MD 21228
ED STATES US
SHIP DATE: 29OCT20
ACTWGT: 20.00 LB
CAD: 1030460/INET4280
BILL RECIPIENT
SAMPLE RECEIVING
TEST AMERICA PITTSBURGH
301 ALPHA DR
RIDC PARK
PITTSBURGH PA 15238
REF: AECOM PEPCO
112) 963-7058
INV:
PO:
DEPT:
568J2/A27E/B766
FedEx Express
FRI - 30 OCT 10:30A
PRIORITY OVERNIGHT
2 of 2
MPS# 0263 7719 4166 5423
Mstr# 7719 4166 5320
0201
15238
EA AGCA
PA-US PIT
Part # 156297-435 RRDW2 EXP 07/21
Uncorrected temp 3.7 °C
Thermometer ID 14
CF 0 Initials TJ
PT-WI-SR-001 effective 7/26/13

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

Chain of Custody Record

180-112989 Chain of Custody

Eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L		/153.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-112989-1
Address: 5815 Middlebrook Pike, ,	Due Date Requested: 11/13/2020			
City: Knoxville	TAT Requested (days):			
State, Zip: TN, 37921				
Phone: 865-291-3000(Tel) 865-584-4315(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)

Other:

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	1668C/1668_P_Sep PCB Congeners	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
OFW0100N (180-112989-1)	10/29/20	11:45 Eastern		Water			X	2	RT: 1.5°C CT: 1.6°C
OFW0200N (180-112989-2)	10/29/20	11:50 Eastern		Water			X	2	1 Cooler, Fedex Po
OFW0300N (180-112989-3)	10/29/20	11:35 Eastern		Water			X	2	Custody seal intact
OFW0400N (180-112989-4)	10/29/20	11:20 Eastern		Water			X	2	[illegible] 5103 9520
OFW0500N (180-112989-5)	10/29/20	11:05 Eastern		Water			X	2	RC-ND
									KW 10/31/20

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said complicance to Eurofins TestAmerica.

Possible Hazard Identification	***Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)***
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
[signature]	10/30/20 845	Eurofins	[signature]	10/31/20 0940	ETA
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: ∆ Yes ∆ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Loc: 180
112989

EUROFINS/TESTAMERICA KNOXVILLE SAMPLE RECEIPT/CONDITION UPON RECEIPT ANOMALY CHECKLIST **Log In Number:**

Review Items	Yes	No	NA	If No, what was the problem?
1. Are the shipping containers intact?	/			☐ **Containers, Broken**
2. Were ambient air containers received intact?			/	☐ Checked in lab
3. The coolers/containers custody seal if present, is it intact?	/			☐ Yes ☐ NA
4. Is the cooler temperature within limits? (> freezing temp. of water to 6 °C, VOST: 10°C) Thermometer ID : SC 68 Correction factor: + 0.1	/			☐ **Cooler Out of Temp, Client Contacted, Proceed/Cancel** ☐ **Cooler Out of Temp, Same Day Receipt**
5. Were all of the sample containers received intact?	/			☐ **Containers, Broken**
6. Were samples received in appropriate containers?	/			☐ **Containers, Improper; Client Contacted; Proceed/Cancel**
7. Do sample container labels match COC? (IDs, Dates, Times)	/			☐ **COC & Samples Do Not Match** ☐ **COC Incorrect/Incomplete** ☐ **COC Not Received**
8. Were all of the samples listed on the COC received?	/			☐ **Sample Received, Not on COC** ☐ **Sample on COC, Not Received**
9. Is the date/time of sample collection noted?	/			☐ **COC; No Date/Time; Client Contacted**
10. Was the sampler identified on the COC?			/	☐ **Sampler Not Listed on COC**
11. Is the client and project name/# identified?	/			☐ **COC Incorrect/Incomplete**
12. Are tests/parameters listed for each sample?	/			☐ **COC No tests on COC**
13. Is the matrix of the samples noted?	/			☐ **COC Incorrect/Incomplete**
14. Was COC relinquished? (Signed/Dated/Timed)	/			☐ **COC Incorrect/Incomplete**
15. Were samples received within holding time?	/			☐ **Holding Time - Receipt**
16. Were samples received with correct chemical preservative (excluding Encore)?			/	☐ **pH Adjusted, pH Included (See box 16A)** ☐ **Incorrect Preservative**
17. Were VOA samples received without headspace?			/	☐ **Headspace (VOA only)**
18. Did you check for residual chlorine, if necessary? (e.g. 1613B, 1668) Chlorine test strip lot number: 8178 2021/01	/			☐ **Residual Chlorine**
19. For 1613B water samples is pH<9?			/	☐ If no, notify lab to adjust
20. For rad samples was sample activity info. Provided?			/	☐ Project missing info

Comments/Actions Taken

Labeling Verified by: **Date:**

pH test strip lot number:

	Box 16A: pH Preservation	Box 18A: Residual Chlorine
Preservative:		
Lot Number:		
Exp Date:		
Analyst:		
Date:		
Time:		

Project #: _____ PM Instructions: _____

Sample Receiving Associate: _____ Date: 10/31/20

QA026R32.doc, 062719

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive RIDC Park
Pittsburgh, PA 15238
Phone: 412-963-7058 Fax: 412-963-2468

D 9130

Chain of Custody Record

eurofins | Environment Testing America

Client Information (Sub Contract Lab)	Sampler:	Lab PM: Colussy, Jill L	Carrier Tracking No(s):	COC No: 180-417154.1
Client Contact: Shipping/Receiving	Phone:	E-Mail: Jill.Colussy@Eurofinset.com	State of Origin: Maryland	Page: Page 1 of 1
Company: TestAmerica Laboratories, Inc.		Accreditations Required (See note):		Job #: 180-112989-1
Address: 4101 Shuffel Street NW, ,	Due Date Requested: 11/13/2020			
City: North Canton	TAT Requested (days):			
State, Zip: OH, 44720				
Phone: 330-497-9396(Tel) 330-497-0772(Fax)	PO #:			
Email:	WO #:			
Project Name: Pepco Benning Road Facility	Project #: 18022565			
Site:	SSOW#:			

Analysis Requested

Preservation Codes:

A - HCL, B - NaOH, C - Zn Acetate, D - Nitric Acid, E - NaHSO4, F - MeOH, G - Amchlor, H - Ascorbic Acid, I - Ice, J - DI Water, K - EDTA, L - EDA, M - Hexane, N - None, O - AsNaO2, P - Na2O4S, Q - Na2SO3, R - Na2S2O3, S - H2SO4, T - TSP Dodecahydrate, U - Acetone, V - MCAA, W - pH 4-5, Z - other (specify)

Other:

C263

Sample Identification - Client ID (Lab ID)	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8015D_DRO/3510C_LVI DRO/ORO	Total Number of containers	Special Instructions/Note:
			Preservation Code:						
OFW0100N (180-112989-1)	10/29/20	11:45 Eastern		Water			X	2	need to link ICVs
OFW0200N (180-112989-2)	10/29/20	11:50 Eastern		Water			X	2	need to link ICVs
OFW0300N (180-112989-3)	10/29/20	11:35 Eastern		Water			X	2	need to link ICVs
OFW0400N (180-112989-4)	10/29/20	11:20 Eastern		Water			X	2	need to link ICVs
OFW0500N (180-112989-5)	10/29/20	11:05 Eastern		Water			X	2	need to link ICVs

Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins TestAmerica.

Possible Hazard Identification	***Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)***
Unconfirmed	☐ *Return To Client* ☐ *Disposal By Lab* ☐ *Archive For* _____ *Months*
Deliverable Requested: I, II, III, IV, Other (specify) Primary Deliverable Rank: 4	Special Instructions/QC Requirements:

Empty Kit Relinquished by:	Date:	Time:	Method of Shipment:

Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
	10/30/20 845	CTN ATV		10-31-20 930	TestAmerica
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company
Relinquished by:	Date/Time:	Company	Received by:	Date/Time:	Company

Custody Seals Intact: Δ Yes Δ No	Custody Seal No.:	Cooler Temperature(s) °C and Other Remarks:

Ver: 01/16/2019

Eurofins TestAmerica Canton Sample Receipt Form/Narrative **Login # :** _____
Canton Facility

Client EA Pittsburgh Site Name _____ Cooler unpacked by:

Cooler Received on 10-3-20 Opened on 11-2-20

FedEx: 1st Grd Exp UPS FAS Clipper Client Drop Off TestAmerica Courier Other _____

Receipt After-hours: Drop-off Date/Time _____ Storage Location _____

TestAmerica Cooler # 1 Foam Box Client Cooler Box Other _____

Packing material used: Bubble Wrap Foam Plastic Bag None Other _____

COOLANT: Wet Ice Blue Ice Dry Ice Water None

1. Cooler temperature upon receipt ☐ See Multiple Cooler Form
   IR GUN# IR-11 (CF +0.9 °C) Observed Cooler Temp. 2.9 °C Corrected Cooler Temp. 3.8 °C
   IR GUN #IR-12 (CF +0.5°C) Observed Cooler Temp. _____ °C Corrected Cooler Temp. _____ °C
2. Were tamper/custody seals on the outside of the cooler(s)? If Yes Quantity 1 Yes No
   -Were the seals on the outside of the cooler(s) signed & dated? Yes No NA
   -Were tamper/custody seals on the bottle(s) or bottle kits (LLHg/MeHg)? Yes No
   -Were tamper/custody seals intact and uncompromised? Yes No NA
3. Shippers' packing slip attached to the cooler(s)? Yes No
4. Did custody papers accompany the sample(s)? Yes No
5. Were the custody papers relinquished & signed in the appropriate place? Yes No
6. Was/were the person(s) who collected the samples clearly identified on the COC? Yes No
7. Did all bottles arrive in good condition (Unbroken)? Yes No
8. Could all bottle labels (ID/Date/Time) be reconciled with the COC? Yes No
9. For each sample, does the COC specify preservatives (Y/N), # of containers (Y/N), and sample type of grab/comp (Y/N)?
10. Were correct bottle(s) used for the test(s) indicated? Yes No
11. Sufficient quantity received to perform indicated analyses? Yes No
12. Are these work share samples and all listed on the COC? Yes No
    If yes, Questions 13-17 have been checked at the originating laboratory.
13. Were all preserved sample(s) at the correct pH upon receipt? Yes No NA pH Strip Lot# HC907861
14. Were VOAs on the COC? Yes No
15. Were air bubbles >6 mm in any VOA vials? ● ⬅ Larger than this. Yes No NA
16. Was a VOA trip blank present in the cooler(s)? Trip Blank Lot #_____ Yes No
17. Was a LL Hg or Me Hg trip blank present? _____ Yes No

Tests that are not checked for pH by Receiving:
VOAs
Oil and Grease
TOC

Contacted PM _____ Date _____ by _____ via Verbal Voice Mail Other

Concerning _____

18. CHAIN OF CUSTODY & SAMPLE DISCREPANCIES ☐ additional next page

Samples processed by:

19. SAMPLE CONDITION

Sample(s) _____ were received after the recommended holding time had expired.
Sample(s) _____ were received in a broken container.
Sample(s) _____ were received with bubble >6 mm in diameter. (Notify PM)

20. SAMPLE PRESERVATION

Sample(s) _____ were further preserved in the laboratory.
Time preserved: _____ Preservative(s) added/Lot number(s): _____

VOA Sample Preservation - Date/Time VOAs Frozen: _____

WI-NC-099

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112989-1

Login Number: 112989
List Number: 1
Creator: Say, Thomas C

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-107648-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
7/14/2020 11:41:44 AM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 4
Certification Summary 5
Sample Summary 6
Method Summary 7
Lab Chronicle 8
Client Sample Results 10
QC Sample Results 12
QC Association Summary 14
Chain of Custody 15
Receipt Checklists 17

Job ID: 180-107648-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-107648-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 06/27/2020; the samples arrived in good condition, properly preserved and on ice. The temperature of the coolers at receipt was 2.7 C.

PCBS
Due to the concentration of PCBs detected, the samples were analyzed at a dilution. The reporting limits have been adjusted accordingly.

The samples and the matrix spike duplicate had surrogate Decachlorobiphenyl recover above the control limits. The recoveries of Tetrachloro-m-xylene were within the control limits.

The matrix spike and matrix spike duplicate of sample SED7C-DEW (0-18") (180-107648-1) recovered above the control limits for PCB-1016.

The presence of the '4' qualifier indicates analytes where the concentration in the unspiked sample exceeded four times the spiking amount.

Continuing calibration standard 180-321360/26 recovered below criteria for Tetrachloro-m-xylene on the back column. All PCB results were reported from the front column.

PERCENT SOLIDS
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Definitions/Glossary

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Qualifiers

GC Semi VOA

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.
F1	MS and/or MSD recovery exceeds control limits.
X	Surrogate recovery exceeds control limits

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-20
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	08-01-20
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	01-01-21
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	05-23-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-20
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-15-20
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-20

Sample Summary

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-107648-1	SED7C-DEW (0-18")	Sediment	06/26/20 09:00	06/27/20 09:00	
180-107648-2	SED7.5E-DEW (0-18")	Sediment	06/26/20 09:05	06/27/20 09:00	

Method Summary

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8082A	Polychlorinated Biphenyls (PCBs) (GC)	SW846	TAL PIT
PCB	Total PCB Calculation	TAL SOP	TAL PIT
2540G	SM 2540G	SM22	TAL PIT
3541	Automated Soxhlet Extraction (Low Level)	SW846	TAL PIT
3660B	Sulfur Cleanup	SW846	TAL PIT
3665A	Sulfuric Acid/Permanganate Cleanup	SW846	TAL PIT

Protocol References:

SM22 = Standard Methods For The Examination Of Water And Wastewater, 22nd Edition

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

TAL SOP = TestAmerica Laboratories, Standard Operating Procedure

Laboratory References:

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: SED7C-DEW (0-18")
Lab Sample ID: 180-107648-1
Date Collected: 06/26/20 09:00
Matrix: Sediment
Date Received: 06/27/20 09:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	PCB		1			321464	07/13/20 12:52	DFE	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	2540G		1			320310	07/02/20 07:35	MM1	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SED7C-DEW (0-18")
Lab Sample ID: 180-107648-1
Date Collected: 06/26/20 09:00
Matrix: Sediment
Date Received: 06/27/20 09:00
Percent Solids: 55.8

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.18 g	1.0 mL	321038	07/09/20 10:06	CSC	TAL PIT
Total/NA	Cleanup	3665A			2 mL	2 mL	321357	07/13/20 04:30	JMO	TAL PIT
Total/NA	Cleanup	3660B			2 mL	2 mL	321358	07/13/20 04:31	JMO	TAL PIT
Total/NA	Analysis	EPA 8082A		10			321360	07/13/20 10:50	JMO	TAL PIT
	Instrument ID: CHGC8									

Client Sample ID: SED7.5E-DEW (0-18")
Lab Sample ID: 180-107648-2
Date Collected: 06/26/20 09:05
Matrix: Sediment
Date Received: 06/27/20 09:00

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	PCB		1			321464	07/13/20 12:52	DFE	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	2540G		1			320310	07/02/20 07:35	MM1	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: SED7.5E-DEW (0-18")
Lab Sample ID: 180-107648-2
Date Collected: 06/26/20 09:05
Matrix: Sediment
Date Received: 06/27/20 09:00
Percent Solids: 42.5

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.14 g	1.0 mL	321038	07/09/20 10:06	CSC	TAL PIT
Total/NA	Cleanup	3665A			2 mL	2 mL	321357	07/13/20 04:30	JMO	TAL PIT
Total/NA	Cleanup	3660B			2 mL	2 mL	321358	07/13/20 04:31	JMO	TAL PIT
Total/NA	Analysis	EPA 8082A		10			321360	07/13/20 11:47	JMO	TAL PIT
	Instrument ID: CHGC8									

Laboratory References:

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-107648-1
Project/Site: Pepco Benning Road Facility

Analyst References:

Lab: TAL PIT

- Batch Type: Cleanup
  - JMO = John Oravec
- Batch Type: Prep
  - CSC = Chayce Cockroft
- Batch Type: Analysis
  - DFE = David Eppinger
  - JMO = John Oravec
  - MM1 = Mary Beth Miller

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-107648-1

Client Sample ID: SED7C-DEW (0-18")

Date Collected: 06/26/20 09:00
Date Received: 06/27/20 09:00

Lab Sample ID: 180-107648-1

Matrix: Sediment
Percent Solids: 55.8

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	ND	F1	7.4	2.4	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1221	ND		7.4	2.6	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1232	ND		7.4	1.8	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1242	ND		7.4	1.1	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1248	**210**		7.4	1.8	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1254	ND		7.4	2.2	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1260	**360**		7.4	2.1	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1262	ND		7.4	2.6	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10
PCB-1268	ND		7.4	1.0	ug/Kg	☼	07/09/20 10:06	07/13/20 10:50	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*137*		*20 - 150*	*07/09/20 10:06*	*07/13/20 10:50*	*10*
DCB Decachlorobiphenyl (Surr)	*193*	*X*	*20 - 150*	*07/09/20 10:06*	*07/13/20 10:50*	*10*
Tetrachloro-m-xylene	*88*		*20 - 138*	*07/09/20 10:06*	*07/13/20 10:50*	*10*
Tetrachloro-m-xylene	*87*		*20 - 138*	*07/09/20 10:06*	*07/13/20 10:50*	*10*

Method: PCB - Total PCB Calculation

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Polychlorinated biphenyls, Total	**570**		7.4	2.6	ug/Kg			07/13/20 12:52	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	**44.2**		0.1	0.1	%			07/02/20 07:35	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-107648-1

Client Sample ID: SED7.5E-DEW (0-18")

Date Collected: 06/26/20 09:05
Date Received: 06/27/20 09:00

Lab Sample ID: 180-107648-2

Matrix: Sediment
Percent Solids: 42.5

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	ND		9.8	3.2	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1221	ND		9.8	3.5	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1232	ND		9.8	2.4	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1242	ND		9.8	1.4	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1248	**630**		9.8	2.4	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1254	ND		9.8	2.9	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1260	**1500**		9.8	2.8	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1262	ND		9.8	3.4	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10
PCB-1268	ND		9.8	1.3	ug/Kg	☼	07/09/20 10:06	07/13/20 11:47	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*155*	*X*	*20 - 150*	*07/09/20 10:06*	*07/13/20 11:47*	*10*
DCB Decachlorobiphenyl (Surr)	*160*	*X*	*20 - 150*	*07/09/20 10:06*	*07/13/20 11:47*	*10*
Tetrachloro-m-xylene	*81*		*20 - 138*	*07/09/20 10:06*	*07/13/20 11:47*	*10*
Tetrachloro-m-xylene	*83*		*20 - 138*	*07/09/20 10:06*	*07/13/20 11:47*	*10*

Method: PCB - Total PCB Calculation

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Polychlorinated biphenyls, Total	**2100**		9.8	3.5	ug/Kg			07/13/20 12:52	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	**57.5**		0.1	0.1	%			07/02/20 07:35	1

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC)

Lab Sample ID: MB 180-321038/1-C
Matrix: Sediment
Analysis Batch: 321360

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 321038

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	ND		0.42	0.14	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1221	ND		0.42	0.15	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1232	ND		0.42	0.10	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1242	ND		0.42	0.061	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1248	ND		0.42	0.10	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1254	ND		0.42	0.13	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1260	ND		0.42	0.12	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1262	ND		0.42	0.15	ug/Kg		07/09/20 10:06	07/13/20 10:32	1
PCB-1268	ND		0.42	0.056	ug/Kg		07/09/20 10:06	07/13/20 10:32	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*96*		*20 - 150*	*07/09/20 10:06*	*07/13/20 10:32*	*1*
DCB Decachlorobiphenyl (Surr)	*103*		*20 - 150*	*07/09/20 10:06*	*07/13/20 10:32*	*1*
Tetrachloro-m-xylene	*90*		*20 - 138*	*07/09/20 10:06*	*07/13/20 10:32*	*1*
Tetrachloro-m-xylene	*87*		*20 - 138*	*07/09/20 10:06*	*07/13/20 10:32*	*1*

Lab Sample ID: LCS 180-321038/2-C
Matrix: Sediment
Analysis Batch: 321360

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 321038

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1016	33.3	31.2		ug/Kg		94	27 - 117
PCB-1260	33.3	30.2		ug/Kg		91	29 - 107

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
DCB Decachlorobiphenyl (Surr)	*90*		*20 - 150*
DCB Decachlorobiphenyl (Surr)	*98*		*20 - 150*
Tetrachloro-m-xylene	*89*		*20 - 138*
Tetrachloro-m-xylene	*85*		*20 - 138*

Lab Sample ID: 180-107648-1 MS
Matrix: Sediment
Analysis Batch: 321360

Client Sample ID: SED7C-DEW (0-18")
Prep Type: Total/NA
Prep Batch: 321038

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
PCB-1016	ND	F1	59.6	196	F1	ug/Kg	☼	329	27 - 117
PCB-1260	360		59.6	304	4	ug/Kg	☼	-88	29 - 107

Surrogate	*MS %Recovery*	*MS Qualifier*	*Limits*
DCB Decachlorobiphenyl (Surr)	*116*		*20 - 150*
DCB Decachlorobiphenyl (Surr)	*147*		*20 - 150*
Tetrachloro-m-xylene	*80*		*20 - 138*
Tetrachloro-m-xylene	*82*		*20 - 138*

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC) (Continued)

Lab Sample ID: 180-107648-1 MSD
Client Sample ID: SED7C-DEW (0-18")
Matrix: Sediment
Prep Type: Total/NA
Analysis Batch: 321360
Prep Batch: 321038

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
PCB-1016	ND	F1	59.6	241	F1	ug/Kg	☼	404	27 - 117	20	40
PCB-1260	360		59.6	384	4	ug/Kg	☼	46	29 - 107	23	40

Surrogate	*MSD %Recovery*	*MSD Qualifier*	*Limits*
DCB Decachlorobiphenyl (Surr)	*141*		*20 - 150*
DCB Decachlorobiphenyl (Surr)	*159*	*X*	*20 - 150*
Tetrachloro-m-xylene	*92*		*20 - 138*
Tetrachloro-m-xylene	*97*		*20 - 138*

Method: 2540G - SM 2540G

Lab Sample ID: 180-107648-2 DU
Client Sample ID: SED7.5E-DEW (0-18")
Matrix: Sediment
Prep Type: Total/NA
Analysis Batch: 320310

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Percent Moisture	57.5		53.7		%		7	10

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-107648-1

GC Semi VOA

Prep Batch: 321038

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	3541	
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	3541	
MB 180-321038/1-C	Method Blank	Total/NA	Sediment	3541	
LCS 180-321038/2-C	Lab Control Sample	Total/NA	Sediment	3541	
180-107648-1 MS	SED7C-DEW (0-18")	Total/NA	Sediment	3541	
180-107648-1 MSD	SED7C-DEW (0-18")	Total/NA	Sediment	3541	

Cleanup Batch: 321357

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	3665A	321038
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	3665A	321038
MB 180-321038/1-C	Method Blank	Total/NA	Sediment	3665A	321038
LCS 180-321038/2-C	Lab Control Sample	Total/NA	Sediment	3665A	321038
180-107648-1 MS	SED7C-DEW (0-18")	Total/NA	Sediment	3665A	321038
180-107648-1 MSD	SED7C-DEW (0-18")	Total/NA	Sediment	3665A	321038

Cleanup Batch: 321358

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	3660B	321357
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	3660B	321357
MB 180-321038/1-C	Method Blank	Total/NA	Sediment	3660B	321357
LCS 180-321038/2-C	Lab Control Sample	Total/NA	Sediment	3660B	321357
180-107648-1 MS	SED7C-DEW (0-18")	Total/NA	Sediment	3660B	321357
180-107648-1 MSD	SED7C-DEW (0-18")	Total/NA	Sediment	3660B	321357

Analysis Batch: 321360

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	EPA 8082A	321358
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	EPA 8082A	321358
MB 180-321038/1-C	Method Blank	Total/NA	Sediment	EPA 8082A	321358
LCS 180-321038/2-C	Lab Control Sample	Total/NA	Sediment	EPA 8082A	321358
180-107648-1 MS	SED7C-DEW (0-18")	Total/NA	Sediment	EPA 8082A	321358
180-107648-1 MSD	SED7C-DEW (0-18")	Total/NA	Sediment	EPA 8082A	321358

Analysis Batch: 321464

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	PCB	
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	PCB	

General Chemistry

Analysis Batch: 320310

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-107648-1	SED7C-DEW (0-18")	Total/NA	Sediment	2540G	
180-107648-2	SED7.5E-DEW (0-18")	Total/NA	Sediment	2540G	
180-107648-2 DU	SED7.5E-DEW (0-18")	Total/NA	Sediment	2540G	

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238-2907
phone 412.963.7058 fax 412.963.2468

Chain of Custody Record

eurofins | Environment Testing TestAmerica

Regulatory Program: ☐ DW ☐ NPDES ☐ RCRA ☐ Other:

TestAmerica Laboratories, Inc. d/b/a Eurofins TestAmerica

	Project Manager: Kris Carbonneau		COC No:
Client Contact	**Email: kris.carbonneau@aecom.com**	**Site Contact:**	**Date: 6-26-20**	___1___ of __1___ COCs
AECOM	**Tel/Fax:**	**Lab Contact: Jill Colussy**	**Carrier:**	TALS Project #:
Address	**Analysis Turnaround Time**			Sampler:
City/State/Zip	☐ CALENDAR DAYS ☑ WORKING DAYS			**For Lab Use Only:**
(xxx) xxx-xxxx Phone	TAT if different from Below _____			Walk-in Client:
(xxx) xxx-xxxx FAX	☑ 2 weeks			Lab Sampling:
Project Name: Pepco Benning Road TS	☐ 1 week			
PO# 60631088	☐ 2 days			Job / SDG No.:
Quote# 18022551	☐ 1 day			

Sample Identification	Sample Date	Sample Time	Sample Type (C=Comp, G=Grab)	Matrix	# of Cont.	Filtered Sample (Y / N)	Perform MS / MSD (Y / N)	PCBs as Aroclors 8082	PCBs as Congeners 1668C	Sample Specific Notes:
SED7C-DEW (0-18")	6/26/20	900	G	S	2			X	X	
SED7.5E-DEW (0-18")	6/26/20	905	G	S	2			X	X	

180-107648 Chain of Custody

Preservation Used: 1= Ice, 2= HCl; 3= H2SO4; 4=HNO3; 5=NaOH; 6= Other _____

Possible Hazard Identification:
Are any samples from a listed EPA Hazardous Waste? Please List any EPA Waste Codes for the sample in the Comments Section if the lab is to dispose of the sample.

☑ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return to Client ☑ Disposal by Lab ☐ Archive for _____ Months

Special Instructions/QC Requirements & Comments:

Custody Seals Intact: ☐ Yes ☐ No | Custody Seal No.: | Cooler Temp. (°C): Obs'd:_____ Corr'd:_____ | Therm ID No.:_____

Relinquished by:	Company: KEMRON	Date/Time: 6/26/20 1100	Received by:	Company: ETA	Date/Time: ETA 11:00
Relinquished by:	Company:	Date/Time: 6/26/20	Received by:	Company: ETA PHT	Date/Time: 06/27/2020 0900
Relinquished by:	Company:	Date/Time:	Received in Laboratory by:	Company:	Date/Time:

Form No. CA-C-WI-002, Rev. 4.33, dated 5/4/2020



180-107648 Waybill

eurofins | Environment Testing TestAmerica

Part # 158469-434 RIT2 EXP 09/20

ORIGIN ID:LIYA (678) 966-9991
GEORGE TAYLOR
EUROFINS TESTAMERICA
6500 MCDONOUGH DRIVE
SUITE C-10
NORCROSS, GA 30093
UNITED STATES US

SHIP DATE: 26JUN20
ACTWGT: 15.95 LB
CAD: 859116/CAFE3313

BILL RECIPIENT

TO SAMPLE RECIEVING
EUROFINS TESTAMERICA PITTSBURGH
301 ALPHA DR.
RIDC PARK
PITTSBURGH PA 15238
(412) 963-7058
REF: KEMRON

FedEx Express

TRK# 0201 1516 9324 1014

SATURDAY 12:00P
PRIORITY OVERNIGHT

XO AGCA

15238
PA-US PIT

Uncorrected temp 2.7/2.7C
Thermometer ID
CF 0 Initials
PT-WI-SR-001 effective 7/26/13

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-107648-1

Login Number: 107648
List Number: 1
Creator: DiNardo, Nicholas J

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

eurofins | Environment Testing America



ANALYTICAL REPORT

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238
Tel: (412)963-7058

Laboratory Job ID: 180-112242-1
Client Project/Site: Pepco Benning Road Facility

For:
AECOM
250 Apollo Drive
Chelmsford, Massachusetts 01824

Attn: Mr. Robert Kennedy

Authorized for release by:
11/5/2020 3:31:14 PM

Jill Colussy, Project Manager I
(412)963-2444
Jill.Colussy@Eurofinset.com

LINKS
Review your project results through TotalAccess
Have a Question? Ask The Expert
Visit us at: www.eurofinsus.com/Env

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

PA Lab ID: 02-00416

Table of Contents

Cover Page 1
Table of Contents 2
Case Narrative 3
Definitions/Glossary 5
Certification Summary 6
Sample Summary 7
Method Summary 8
Lab Chronicle 9
Client Sample Results 12
QC Sample Results 18
QC Association Summary 26
Chain of Custody 30
Receipt Checklists 31

Job ID: 180-112242-1

Laboratory: Eurofins TestAmerica, Pittsburgh

Narrative

CASE NARRATIVE

Client: AECOM

Project: Pepco Benning Road Facility

Report Number: 180-112242-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

RECEIPT
The samples were received on 10/14/2020; the samples arrived in good condition, properly preserved and on ice. The temperature of the coolers at receipt was 2.6 C.

VOLATILES
The continuing calibration verification (CCV) analyzed in batch 180-334149 was outside the method criteria for the following analyte(s): 2-Butanone and Methyl Tert Butyl Ether. A CCV standard at or below the reporting limit (RL) was analyzed with the affected samples and found to be acceptable. As indicated in the reference method, sample analysis may proceed; however, any detection for the affected analyte(s) is considered estimated.

SEMIVOLATILES
No analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

PESTICIDES
Toxaphene recovered below criteria for continuing calibration standard CCVIS 180-334876/43. This is a pattern recognition compound and was not detected in samples.

PCBS
Due to the concentration of PCBs detected, sample 0746-009 (180-112242-1) and 0746-10 (180-112242-2) were analyzed at a dilution. The reporting limits have been adjusted accordingly.

HERBICIDES
The continuing calibration verification (CCV) associated with batch 180-335001 recovered above the upper control limit for all analytes of interest. The samples associated with this CCV were non-detects for the affected analytes; therefore, the data have been reported.

METALS
Mercury was detected in method blank MB 180-334370/1-A at a level that was above the method detection limit but below the reporting limit. The value should be considered an estimate, and has been flagged. If the associated sample reported a result above the MDL and/or RL, the result has been flagged.

GENERAL CHEMISTRY
The following samples were assumed to contain Sulfide due to nature of sample matrix: 0746-009 (180-112242-1) and 0746-010

Job ID: 180-112242-1 (Continued)

Laboratory: Eurofins TestAmerica, Pittsburgh (Continued)

(180-112242-2). The sulfide was treated and removed prior to distillation with 200 uL of bismuth nitrate solution.

Samples 0746-009 (180-112242-1), 0746-010 (180-112242-2), (180-112242-A-1 MS) and (180-112242-A-1 MSD) required anti foam for the sulfide distillation.

The matrix spike and matrix spike duplicate of sample 0746-009 (180-112242-1) recovered outside of the control limits for sulfide.

Definitions/Glossary

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Qualifiers

GC/MS Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

GC Semi VOA

Qualifier	Qualifier Description
p	The %RPD between the primary and confirmation column/detector is >40%. The lower value has been reported.

Metals

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

General Chemistry

Qualifier	Qualifier Description
F1	MS and/or MSD recovery exceeds control limits.
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Accreditation/Certification Summary

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Laboratory: Eurofins TestAmerica, Pittsburgh

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arkansas DEQ	State	19-033-0	06-27-21
California	State	2891	04-30-21
Connecticut	State	PH-0688	09-30-20 *
Florida	NELAP	E871008	06-30-21
Georgia	State	PA 02-00416	04-30-21
Illinois	NELAP	004375	06-30-21
Kansas	NELAP	E-10350	01-31-21
Kentucky (UST)	State	162013	04-30-21
Kentucky (WW)	State	KY98043	12-31-20
Louisiana	NELAP	04041	06-30-21
Maine	State	PA00164	03-06-22
Minnesota	NELAP	042-999-482	12-31-20
Nevada	State	PA00164	07-31-21
New Hampshire	NELAP	2030	04-05-21
New Jersey	NELAP	PA005	06-30-21
New York	NELAP	11182	04-01-21
North Carolina (WW/SW)	State	434	11-01-20
North Dakota	State	R-227	04-30-21
Oregon	NELAP	PA-2151	02-06-21
Pennsylvania	NELAP	02-00416	04-30-21
Rhode Island	State	LAO00362	12-31-20
South Carolina	State	89014	04-30-21
Texas	NELAP	T104704528	03-31-21
US Fish & Wildlife	US Federal Programs	058448	07-31-21
USDA	Federal	P-Soil-01	06-26-22
USDA	US Federal Programs	P330-16-00211	06-26-22
Utah	NELAP	PA001462019-8	05-31-21
Virginia	NELAP	10043	09-14-21
West Virginia DEP	State	142	02-01-21
Wisconsin	State	998027800	08-31-21

* Accreditation/Certification renewal pending - accreditation/certification considered valid.

Sample Summary

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
180-112242-1	0746-009	Sediment	10/13/20 10:00	10/14/20 09:30	
180-112242-2	0746-010	Sediment	10/13/20 10:05	10/14/20 09:30	

Method Summary

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Method	Method Description	Protocol	Laboratory
EPA 8260C	Volatile Organic Compounds by GC/MS	SW846	TAL PIT
EPA 8270D	Semivolatile Organic Compounds (GC/MS)	SW846	TAL PIT
EPA 8081B	Organochlorine Pesticides (GC)	SW846	TAL PIT
EPA 8082A	Polychlorinated Biphenyls (PCBs) (GC)	SW846	TAL PIT
EPA 8151A	Herbicides (GC)	SW846	TAL PIT
PCB	Total PCB Calculation	TAL SOP	TAL PIT
EPA 6010B	Metals (ICP)	SW846	TAL PIT
EPA 7470A	Mercury (CVAA)	SW846	TAL PIT
2540G	SM 2540G	SM22	TAL PIT
EPA 1020B	Ignitability, Small Scale Closed-Cup Method	SW846	TAL PIT
EPA 9014	Cyanide	SW846	TAL PIT
EPA 9034	Sulfide, Acid soluble and Insoluble (Titrimetric)	SW846	TAL PIT
3010A	Preparation, Total Metals	SW846	TAL PIT
3510C	Liquid-Liquid Extraction (Separatory Funnel)	SW846	TAL PIT
3541	Automated Soxhlet Extraction (Low Level)	SW846	TAL PIT
3660B	Sulfur Cleanup	SW846	TAL PIT
3665A	Sulfuric Acid/Permanganate Cleanup	SW846	TAL PIT
5030C	Purge and Trap	SW846	TAL PIT
7470A	Preparation, Mercury	SW846	TAL PIT
8151A	Extraction (Herbicides)	SW846	TAL PIT
9010C	Cyanide, Distillation	SW846	TAL PIT
9030B	Sulfide, Distillation (Acid Soluble and Insoluble)	SW846	TAL PIT
EPA 1311	TCLP Extraction	SW846	TAL PIT

Protocol References:

SM22 = Standard Methods For The Examination Of Water And Wastewater, 22nd Edition

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

TAL SOP = TestAmerica Laboratories, Standard Operating Procedure

Laboratory References:

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Lab Chronicle

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0746-009
Date Collected: 10/13/20 10:00
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-1
Matrix: Sediment

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
TCLP	Leach	EPA 1311			25.11 g	500 mL	334016	10/20/20 12:00	GRN	TAL PIT
TCLP	Analysis	EPA 8260C		1	0.125 mL	5 mL	334149	10/21/20 12:48	KLG	TAL PIT
	Instrument ID: CHHP9									
TCLP	Leach	EPA 1311			100.17 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3510C			200 mL	10.0 mL	334211	10/21/20 09:35	CBY	TAL PIT
TCLP	Analysis	EPA 8270D		1	1 mL	1 mL	334310	10/22/20 20:29	VVP	TAL PIT
	Instrument ID: CH732									
TCLP	Leach	EPA 1311			100.17 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3510C			100 mL	40.0 mL	334210	10/21/20 09:20	CBY	TAL PIT
TCLP	Analysis	EPA 8081B		1			334876	10/27/20 22:49	DFE	TAL PIT
	Instrument ID: CHGC17									
TCLP	Leach	EPA 1311			100.17 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	8151A			100 mL	10.0 mL	334218	10/21/20 13:00	CBY	TAL PIT
TCLP	Analysis	EPA 8151A		20			335001	10/28/20 09:05	JMO	TAL PIT
	Instrument ID: CGC1									
Total/NA	Analysis	PCB		1			335216	10/22/20 08:20	SAB	TAL PIT
	Instrument ID: NOEQUIP									
TCLP	Leach	EPA 1311			100.17 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3010A			5 mL	50 mL	334406	10/22/20 15:35	TJO	TAL PIT
TCLP	Analysis	EPA 6010B		1			334692	10/23/20 16:35	RJG	TAL PIT
	Instrument ID: C									
TCLP	Leach	EPA 1311			100.17 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	7470A			50 mL	50 mL	334370	10/22/20 13:22	MM1	TAL PIT
TCLP	Analysis	EPA 7470A		1			335034	10/27/20 18:25	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	EPA 1020B		1			334348	10/22/20 11:46	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: 0746-009
Date Collected: 10/13/20 10:00
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-1
Matrix: Sediment
Percent Solids: 59.4

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.4 g	1.0 mL	334300	10/22/20 08:20	B1B	TAL PIT
Total/NA	Cleanup	3665A			2 mL	2 mL	334523	10/23/20 10:31	KSM	TAL PIT
Total/NA	Cleanup	3660B			2 mL	2 mL	334525	10/23/20 10:36	KSM	TAL PIT
Total/NA	Analysis	EPA 8082A		10			334490	10/24/20 03:50	JMO	TAL PIT
	Instrument ID: CHGC10									
Total/NA	Prep	9010C			0.55 g	10 mL	334633	10/24/20 12:15	CMR	TAL PIT
Total/NA	Analysis	EPA 9014		1			334930	10/26/20 17:26	CMR	TAL PIT
	Instrument ID: SEAL2									
Total/NA	Prep	9030B			4.99 g	50 mL	334074	10/20/20 15:00	CMR	TAL PIT
Total/NA	Analysis	EPA 9034		1			334204	10/20/20 17:32	CMR	TAL PIT
	Instrument ID: NOEQUIP									

Lab Chronicle

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0746-010
Date Collected: 10/13/20 10:05
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-2
Matrix: Sediment

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
TCLP	Leach	EPA 1311			25.25 g	500 mL	334016	10/20/20 12:00	GRN	TAL PIT
TCLP	Analysis	EPA 8260C		1	0.125 mL	5 mL	334149	10/21/20 13:10	KLG	TAL PIT
	Instrument ID: CHHP9									
TCLP	Leach	EPA 1311			100.06 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3510C			200 mL	10.0 mL	334211	10/21/20 09:35	CBY	TAL PIT
TCLP	Analysis	EPA 8270D		1	1 mL	1 mL	334310	10/22/20 20:52	VVP	TAL PIT
	Instrument ID: CH732									
TCLP	Leach	EPA 1311			100.06 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3510C			100 mL	40.0 mL	334210	10/21/20 09:20	CBY	TAL PIT
TCLP	Analysis	EPA 8081B		1			334876	10/27/20 23:05	DFE	TAL PIT
	Instrument ID: CHGC17									
TCLP	Leach	EPA 1311			100.06 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	8151A			100 mL	10.0 mL	334218	10/21/20 13:00	CBY	TAL PIT
TCLP	Analysis	EPA 8151A		20			335001	10/28/20 10:48	JMO	TAL PIT
	Instrument ID: CGC1									
Total/NA	Analysis	PCB		1			335216	10/22/20 08:20	SAB	TAL PIT
	Instrument ID: NOEQUIP									
TCLP	Leach	EPA 1311			100.06 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	3010A			5 mL	50 mL	334406	10/22/20 15:35	TJO	TAL PIT
TCLP	Analysis	EPA 6010B		1			334692	10/23/20 16:40	RJG	TAL PIT
	Instrument ID: C									
TCLP	Leach	EPA 1311			100.06 g	2000 mL	334011	10/20/20 12:00	GRN	TAL PIT
TCLP	Prep	7470A			50 mL	50 mL	334370	10/22/20 13:22	MM1	TAL PIT
TCLP	Analysis	EPA 7470A		1			335034	10/27/20 18:26	KEM	TAL PIT
	Instrument ID: HGY									
Total/NA	Analysis	2540G		1			334684	10/25/20 15:07	KPO	TAL PIT
	Instrument ID: NOEQUIP									
Total/NA	Analysis	EPA 1020B		1			334348	10/22/20 11:46	AVS	TAL PIT
	Instrument ID: NOEQUIP									

Client Sample ID: 0746-010
Date Collected: 10/13/20 10:05
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-2
Matrix: Sediment
Percent Solids: 50.6

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3541			30.4 g	1.0 mL	334300	10/22/20 08:20	B1B	TAL PIT
Total/NA	Cleanup	3665A			2 mL	2 mL	334523	10/23/20 10:31	KSM	TAL PIT
Total/NA	Cleanup	3660B			2 mL	2 mL	334525	10/23/20 10:36	KSM	TAL PIT
Total/NA	Analysis	EPA 8082A		10			334490	10/24/20 04:10	JMO	TAL PIT
	Instrument ID: CHGC10									
Total/NA	Prep	9010C			0.49 g	10 mL	334633	10/24/20 12:15	CMR	TAL PIT
Total/NA	Analysis	EPA 9014		1			334930	10/26/20 17:28	CMR	TAL PIT
	Instrument ID: SEAL2									
Total/NA	Prep	9030B			5.01 g	50 mL	334074	10/20/20 15:00	CMR	TAL PIT
Total/NA	Analysis	EPA 9034		1			334204	10/20/20 17:37	CMR	TAL PIT
	Instrument ID: NOEQUIP									

Lab Chronicle

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Laboratory References:

TAL PIT = Eurofins TestAmerica, Pittsburgh, 301 Alpha Drive, RIDC Park, Pittsburgh, PA 15238, TEL (412)963-7058

Analyst References:

Lab: TAL PIT

- Batch Type: Leach
  - GRN = Gavin Nicholls
  - KSM = Kiley Miller
- Batch Type: Prep
  - B1B = Bella Ballin
  - CBY = Charles Yushinski
  - CMR = Carl Reagle
  - MM1 = Mary Beth Miller
  - TJO = Tyler Oliver
- Batch Type: Analysis
  - AVS = Abbey Smith
  - CMR = Carl Reagle
  - DFE = David Eppinger
  - JMO = John Oravec
  - KEM = Kimberly Mahoney
  - KLG = Kathy Gordon
  - KPO = Kiera O'Neil
  - RJG = Rob Good
  - SAB = Sharon Bacha
  - VVP = Vincent Piccolino

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0746-009
Lab Sample ID: 180-112242-1
Date Collected: 10/13/20 10:00
Matrix: Sediment
Date Received: 10/14/20 09:30

Method: EPA 8260C - Volatile Organic Compounds by GC/MS - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane	ND		0.20	0.058	mg/L			10/21/20 12:48	1
2-Butanone (MEK)	ND		0.20	0.12	mg/L			10/21/20 12:48	1
Benzene	ND		0.20	0.079	mg/L			10/21/20 12:48	1
Carbon tetrachloride	ND		0.20	0.13	mg/L			10/21/20 12:48	1
Chlorobenzene	ND		0.20	0.063	mg/L			10/21/20 12:48	1
Chloroform	ND		0.20	0.085	mg/L			10/21/20 12:48	1
Tetrachloroethene	ND		0.20	0.080	mg/L			10/21/20 12:48	1
Trichloroethene	ND		0.20	0.060	mg/L			10/21/20 12:48	1
Vinyl chloride	ND		0.20	0.15	mg/L			10/21/20 12:48	1
1,1-Dichloroethene	ND		0.20	0.11	mg/L			10/21/20 12:48	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
1,2-Dichloroethane-d4 (Surr)	*97*		*53 - 150*		*10/21/20 12:48*	*1*
4-Bromofluorobenzene (Surr)	*70*		*54 - 125*		*10/21/20 12:48*	*1*
Dibromofluoromethane (Surr)	*91*		*55 - 150*		*10/21/20 12:48*	*1*
Toluene-d8 (Surr)	*117*		*63 - 127*		*10/21/20 12:48*	*1*

Method: EPA 8270D - Semivolatile Organic Compounds (GC/MS) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,4-Dichlorobenzene	ND		0.050	0.0045	mg/L		10/21/20 09:35	10/22/20 20:29	1
2,4,5-Trichlorophenol	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:29	1
2,4,6-Trichlorophenol	ND		0.050	0.0095	mg/L		10/21/20 09:35	10/22/20 20:29	1
2,4-Dinitrotoluene	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:29	1
2-Methylphenol	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 20:29	1
Methylphenol, 3 & 4	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:29	1
Hexachlorobenzene	ND		0.050	0.0055	mg/L		10/21/20 09:35	10/22/20 20:29	1
Hexachlorobutadiene	ND		0.050	0.0084	mg/L		10/21/20 09:35	10/22/20 20:29	1
Hexachloroethane	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 20:29	1
Nitrobenzene	ND		0.050	0.012	mg/L		10/21/20 09:35	10/22/20 20:29	1
Pentachlorophenol	ND		0.25	0.0075	mg/L		10/21/20 09:35	10/22/20 20:29	1
Pyridine	ND		0.10	0.0082	mg/L		10/21/20 09:35	10/22/20 20:29	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*63*		*55 - 107*	*10/21/20 09:35*	*10/22/20 20:29*	*1*
2-Fluorophenol (Surr)	*66*		*60 - 108*	*10/21/20 09:35*	*10/22/20 20:29*	*1*
2,4,6-Tribromophenol (Surr)	*74*		*24 - 113*	*10/21/20 09:35*	*10/22/20 20:29*	*1*
Nitrobenzene-d5 (Surr)	*66*		*62 - 115*	*10/21/20 09:35*	*10/22/20 20:29*	*1*
Phenol-d5 (Surr)	*67*		*52 - 107*	*10/21/20 09:35*	*10/22/20 20:29*	*1*
Terphenyl-d14 (Surr)	*64*		*44 - 116*	*10/21/20 09:35*	*10/22/20 20:29*	*1*

Method: EPA 8081B - Organochlorine Pesticides (GC) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chlordane (technical)	ND		0.0050	0.0029	mg/L		10/21/20 09:20	10/27/20 22:49	1
Endrin	ND		0.00050	0.000091	mg/L		10/21/20 09:20	10/27/20 22:49	1
gamma-BHC (Lindane)	ND		0.00050	0.00012	mg/L		10/21/20 09:20	10/27/20 22:49	1
Heptachlor	ND		0.00050	0.00018	mg/L		10/21/20 09:20	10/27/20 22:49	1
Heptachlor epoxide	ND		0.00050	0.00014	mg/L		10/21/20 09:20	10/27/20 22:49	1
Methoxychlor	ND		0.00050	0.00031	mg/L		10/21/20 09:20	10/27/20 22:49	1
Toxaphene	ND		0.040	0.020	mg/L		10/21/20 09:20	10/27/20 22:49	1

Client Sample ID: 0746-009
Date Collected: 10/13/20 10:00
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-1
Matrix: Sediment

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*91*		*58 - 115*	*10/21/20 09:20*	*10/27/20 22:49*	*1*
DCB Decachlorobiphenyl (Surr)	*96*		*58 - 115*	*10/21/20 09:20*	*10/27/20 22:49*	*1*
Tetrachloro-m-xylene	*89*		*43 - 118*	*10/21/20 09:20*	*10/27/20 22:49*	*1*
Tetrachloro-m-xylene	*89*		*43 - 118*	*10/21/20 09:20*	*10/27/20 22:49*	*1*

Method: EPA 8151A - Herbicides (GC) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
2,4-D	ND		0.040	0.020	mg/L		10/21/20 13:00	10/28/20 09:05	20
Silvex (2,4,5-TP)	ND		0.010	0.0030	mg/L		10/21/20 13:00	10/28/20 09:05	20

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2,4-Dichlorophenylacetic acid	*71*		*23 - 122*	*10/21/20 13:00*	*10/28/20 09:05*	*20*
2,4-Dichlorophenylacetic acid	*66*		*23 - 122*	*10/21/20 13:00*	*10/28/20 09:05*	*20*

Method: PCB - Total PCB Calculation

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Polychlorinated biphenyls, Total	**440**		6.9	2.5	ug/Kg			10/22/20 08:20	1

Method: EPA 6010B - Metals (ICP) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.50	0.041	mg/L		10/22/20 15:35	10/23/20 16:35	1
Barium	**0.30**	**J**	2.0	0.026	mg/L		10/22/20 15:35	10/23/20 16:35	1
Cadmium	ND		0.50	0.0028	mg/L		10/22/20 15:35	10/23/20 16:35	1
Chromium	**0.019**	**J**	0.50	0.0078	mg/L		10/22/20 15:35	10/23/20 16:35	1
Lead	ND		0.50	0.029	mg/L		10/22/20 15:35	10/23/20 16:35	1
Selenium	**0.036**	**J**	0.50	0.036	mg/L		10/22/20 15:35	10/23/20 16:35	1
Silver	ND		0.50	0.0085	mg/L		10/22/20 15:35	10/23/20 16:35	1

Method: EPA 7470A - Mercury (CVAA) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.00020	0.00013	mg/L		10/22/20 13:22	10/27/20 18:25	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	**40.5**		0.1	0.1	%			10/25/20 15:07	1
Ignitability	**>140**				Degrees F			10/22/20 11:46	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112242-1

Client Sample ID: 0746-009
Date Collected: 10/13/20 10:00
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-1
Matrix: Sediment
Percent Solids: 59.4

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	ND		6.9	2.2	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1221	ND		6.9	2.5	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1232	ND		6.9	1.7	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1242	ND		6.9	1.0	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1248	**160**		6.9	1.7	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1254	ND		6.9	2.1	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1260	**280**		6.9	2.0	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1262	ND		6.9	2.4	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10
PCB-1268	ND		6.9	0.93	ug/Kg	☼	10/22/20 08:20	10/24/20 03:50	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*84*	*p*	*20 - 150*	*10/22/20 08:20*	*10/24/20 03:50*	*10*
DCB Decachlorobiphenyl (Surr)	*135*		*20 - 150*	*10/22/20 08:20*	*10/24/20 03:50*	*10*
Tetrachloro-m-xylene	*114*		*20 - 138*	*10/22/20 08:20*	*10/24/20 03:50*	*10*
Tetrachloro-m-xylene	*102*		*20 - 138*	*10/22/20 08:20*	*10/24/20 03:50*	*10*

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Cyanide, Total	**0.62**		0.31	0.094	mg/Kg	☼	10/24/20 12:15	10/26/20 17:26	1
Sulfide	**59**	**F1**	51	17	mg/Kg	☼	10/20/20 15:00	10/20/20 17:32	1

Client: AECOM
Job ID: 180-112242-1
Project/Site: Pepco Benning Road Facility

Client Sample ID: 0746-010
Date Collected: 10/13/20 10:05
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-2
Matrix: Sediment

Method: EPA 8260C - Volatile Organic Compounds by GC/MS - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane	ND		0.20	0.058	mg/L			10/21/20 13:10	1
2-Butanone (MEK)	ND		0.20	0.12	mg/L			10/21/20 13:10	1
Benzene	ND		0.20	0.079	mg/L			10/21/20 13:10	1
Carbon tetrachloride	ND		0.20	0.13	mg/L			10/21/20 13:10	1
Chlorobenzene	ND		0.20	0.063	mg/L			10/21/20 13:10	1
Chloroform	ND		0.20	0.085	mg/L			10/21/20 13:10	1
Tetrachloroethene	ND		0.20	0.080	mg/L			10/21/20 13:10	1
Trichloroethene	ND		0.20	0.060	mg/L			10/21/20 13:10	1
Vinyl chloride	ND		0.20	0.15	mg/L			10/21/20 13:10	1
1,1-Dichloroethene	ND		0.20	0.11	mg/L			10/21/20 13:10	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
1,2-Dichloroethane-d4 (Surr)	*100*		*53 - 150*		*10/21/20 13:10*	*1*
4-Bromofluorobenzene (Surr)	*72*		*54 - 125*		*10/21/20 13:10*	*1*
Dibromofluoromethane (Surr)	*95*		*55 - 150*		*10/21/20 13:10*	*1*
Toluene-d8 (Surr)	*90*		*63 - 127*		*10/21/20 13:10*	*1*

Method: EPA 8270D - Semivolatile Organic Compounds (GC/MS) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,4-Dichlorobenzene	ND		0.050	0.0045	mg/L		10/21/20 09:35	10/22/20 20:52	1
2,4,5-Trichlorophenol	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:52	1
2,4,6-Trichlorophenol	ND		0.050	0.0095	mg/L		10/21/20 09:35	10/22/20 20:52	1
2,4-Dinitrotoluene	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:52	1
2-Methylphenol	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 20:52	1
Methylphenol, 3 & 4	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 20:52	1
Hexachlorobenzene	ND		0.050	0.0055	mg/L		10/21/20 09:35	10/22/20 20:52	1
Hexachlorobutadiene	ND		0.050	0.0084	mg/L		10/21/20 09:35	10/22/20 20:52	1
Hexachloroethane	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 20:52	1
Nitrobenzene	ND		0.050	0.012	mg/L		10/21/20 09:35	10/22/20 20:52	1
Pentachlorophenol	ND		0.25	0.0075	mg/L		10/21/20 09:35	10/22/20 20:52	1
Pyridine	ND		0.10	0.0082	mg/L		10/21/20 09:35	10/22/20 20:52	1

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*67*		*55 - 107*	*10/21/20 09:35*	*10/22/20 20:52*	*1*
2-Fluorophenol (Surr)	*71*		*60 - 108*	*10/21/20 09:35*	*10/22/20 20:52*	*1*
2,4,6-Tribromophenol (Surr)	*78*		*24 - 113*	*10/21/20 09:35*	*10/22/20 20:52*	*1*
Nitrobenzene-d5 (Surr)	*69*		*62 - 115*	*10/21/20 09:35*	*10/22/20 20:52*	*1*
Phenol-d5 (Surr)	*71*		*52 - 107*	*10/21/20 09:35*	*10/22/20 20:52*	*1*
Terphenyl-d14 (Surr)	*68*		*44 - 116*	*10/21/20 09:35*	*10/22/20 20:52*	*1*

Method: EPA 8081B - Organochlorine Pesticides (GC) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chlordane (technical)	ND		0.0050	0.0029	mg/L		10/21/20 09:20	10/27/20 23:05	1
Endrin	ND		0.00050	0.000091	mg/L		10/21/20 09:20	10/27/20 23:05	1
gamma-BHC (Lindane)	ND		0.00050	0.00012	mg/L		10/21/20 09:20	10/27/20 23:05	1
Heptachlor	ND		0.00050	0.00018	mg/L		10/21/20 09:20	10/27/20 23:05	1
Heptachlor epoxide	ND		0.00050	0.00014	mg/L		10/21/20 09:20	10/27/20 23:05	1
Methoxychlor	ND		0.00050	0.00031	mg/L		10/21/20 09:20	10/27/20 23:05	1
Toxaphene	ND		0.040	0.020	mg/L		10/21/20 09:20	10/27/20 23:05	1

Client Sample ID: 0746-010
Date Collected: 10/13/20 10:05
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-2
Matrix: Sediment

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*92*		*58 - 115*	*10/21/20 09:20*	*10/27/20 23:05*	*1*
DCB Decachlorobiphenyl (Surr)	*103*		*58 - 115*	*10/21/20 09:20*	*10/27/20 23:05*	*1*
Tetrachloro-m-xylene	*93*		*43 - 118*	*10/21/20 09:20*	*10/27/20 23:05*	*1*
Tetrachloro-m-xylene	*93*		*43 - 118*	*10/21/20 09:20*	*10/27/20 23:05*	*1*

Method: EPA 8151A - Herbicides (GC) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
2,4-D	ND		0.040	0.020	mg/L		10/21/20 13:00	10/28/20 10:48	20
Silvex (2,4,5-TP)	ND		0.010	0.0030	mg/L		10/21/20 13:00	10/28/20 10:48	20

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2,4-Dichlorophenylacetic acid	*79*		*23 - 122*	*10/21/20 13:00*	*10/28/20 10:48*	*20*
2,4-Dichlorophenylacetic acid	*80*		*23 - 122*	*10/21/20 13:00*	*10/28/20 10:48*	*20*

Method: PCB - Total PCB Calculation

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Polychlorinated biphenyls, Total	**1600**		8.1	2.9	ug/Kg			10/22/20 08:20	1

Method: EPA 6010B - Metals (ICP) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	**0.057**	**J**	0.50	0.041	mg/L		10/22/20 15:35	10/23/20 16:40	1
Barium	**0.37**	**J**	2.0	0.026	mg/L		10/22/20 15:35	10/23/20 16:40	1
Cadmium	ND		0.50	0.0028	mg/L		10/22/20 15:35	10/23/20 16:40	1
Chromium	ND		0.50	0.0078	mg/L		10/22/20 15:35	10/23/20 16:40	1
Lead	ND		0.50	0.029	mg/L		10/22/20 15:35	10/23/20 16:40	1
Selenium	ND		0.50	0.036	mg/L		10/22/20 15:35	10/23/20 16:40	1
Silver	ND		0.50	0.0085	mg/L		10/22/20 15:35	10/23/20 16:40	1

Method: EPA 7470A - Mercury (CVAA) - TCLP

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.00020	0.00013	mg/L		10/22/20 13:22	10/27/20 18:26	1

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Moisture	**49.4**		0.1	0.1	%			10/25/20 15:07	1
Ignitability	**>140**				Degrees F			10/22/20 11:46	1

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112242-1

Client Sample ID: 0746-010
Date Collected: 10/13/20 10:05
Date Received: 10/14/20 09:30

Lab Sample ID: 180-112242-2
Matrix: Sediment
Percent Solids: 50.6

Method: EPA 8082A - Polychlorinated Biphenyls (PCBs) (GC)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
PCB-1016	ND		8.1	2.6	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1221	ND		8.1	2.9	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1232	ND		8.1	2.0	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1242	ND		8.1	1.2	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1248	**440**		8.1	2.0	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1254	ND		8.1	2.4	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1260	**1200**		8.1	2.3	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1262	ND		8.1	2.9	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10
PCB-1268	ND		8.1	1.1	ug/Kg	☼	10/22/20 08:20	10/24/20 04:10	10

Surrogate	*%Recovery*	*Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*110*		*20 - 150*	*10/22/20 08:20*	*10/24/20 04:10*	*10*
DCB Decachlorobiphenyl (Surr)	*148*		*20 - 150*	*10/22/20 08:20*	*10/24/20 04:10*	*10*
Tetrachloro-m-xylene	*128*		*20 - 138*	*10/22/20 08:20*	*10/24/20 04:10*	*10*
Tetrachloro-m-xylene	*118*		*20 - 138*	*10/22/20 08:20*	*10/24/20 04:10*	*10*

General Chemistry

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Cyanide, Total	**0.47**		0.40	0.12	mg/Kg	☼	10/24/20 12:15	10/26/20 17:28	1
Sulfide	**41**	**J**	59	20	mg/Kg	☼	10/20/20 15:00	10/20/20 17:37	1

Method: EPA 8260C - Volatile Organic Compounds by GC/MS

Lab Sample ID: LCS 180-334149/3
Matrix: Sediment
Analysis Batch: 334149

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
1,2-Dichloroethane	0.0100	0.00855		mg/L		86	62 - 129
2-Butanone (MEK)	0.0100	0.00680		mg/L		68	33 - 133
Benzene	0.0100	0.00875		mg/L		88	72 - 118
Carbon tetrachloride	0.0100	0.00912		mg/L		91	69 - 137
Chlorobenzene	0.0100	0.00936		mg/L		94	77 - 122
Chloroform	0.0100	0.00880		mg/L		88	78 - 119
Tetrachloroethene	0.0100	0.00977		mg/L		98	75 - 125
Trichloroethene	0.0100	0.00912		mg/L		91	76 - 120
Vinyl chloride	0.0100	0.00764		mg/L		76	52 - 130
1,1-Dichloroethene	0.0100	0.00847		mg/L		85	60 - 131

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
1,2-Dichloroethane-d4 (Surr)	*86*		*53 - 150*
4-Bromofluorobenzene (Surr)	*84*		*54 - 125*
Dibromofluoromethane (Surr)	*86*		*55 - 150*
Toluene-d8 (Surr)	*93*		*63 - 127*

Lab Sample ID: LB 180-334016/1-A
Matrix: Sediment
Analysis Batch: 334149

Client Sample ID: Method Blank
Prep Type: TCLP

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane	ND		0.050	0.015	mg/L			10/21/20 11:44	1
2-Butanone (MEK)	ND		0.050	0.029	mg/L			10/21/20 11:44	1
Benzene	ND		0.050	0.020	mg/L			10/21/20 11:44	1
Carbon tetrachloride	ND		0.050	0.033	mg/L			10/21/20 11:44	1
Chlorobenzene	ND		0.050	0.016	mg/L			10/21/20 11:44	1
Chloroform	ND		0.050	0.021	mg/L			10/21/20 11:44	1
Tetrachloroethene	ND		0.050	0.020	mg/L			10/21/20 11:44	1
Trichloroethene	ND		0.050	0.015	mg/L			10/21/20 11:44	1
Vinyl chloride	ND		0.050	0.037	mg/L			10/21/20 11:44	1
1,1-Dichloroethene	ND		0.050	0.029	mg/L			10/21/20 11:44	1

Surrogate	*LB %Recovery*	*LB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
1,2-Dichloroethane-d4 (Surr)	*101*		*53 - 150*		*10/21/20 11:44*	*1*
4-Bromofluorobenzene (Surr)	*86*		*54 - 125*		*10/21/20 11:44*	*1*
Dibromofluoromethane (Surr)	*95*		*55 - 150*		*10/21/20 11:44*	*1*
Toluene-d8 (Surr)	*116*		*63 - 127*		*10/21/20 11:44*	*1*

Method: EPA 8270D - Semivolatile Organic Compounds (GC/MS)

Lab Sample ID: MB 180-334211/1-A
Matrix: Sediment
Analysis Batch: 334310

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334211

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,4-Dichlorobenzene	ND		0.050	0.0045	mg/L		10/21/20 09:35	10/22/20 10:04	1
2,4,5-Trichlorophenol	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 10:04	1

Method: EPA 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: MB 180-334211/1-A
Matrix: Sediment
Analysis Batch: 334310

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334211

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
2,4,6-Trichlorophenol	ND		0.050	0.0095	mg/L		10/21/20 09:35	10/22/20 10:04	1
2,4-Dinitrotoluene	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 10:04	1
2-Methylphenol	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 10:04	1
Methylphenol, 3 & 4	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 10:04	1
Hexachlorobenzene	ND		0.050	0.0055	mg/L		10/21/20 09:35	10/22/20 10:04	1
Hexachlorobutadiene	ND		0.050	0.0084	mg/L		10/21/20 09:35	10/22/20 10:04	1
Hexachloroethane	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 10:04	1
Nitrobenzene	ND		0.050	0.012	mg/L		10/21/20 09:35	10/22/20 10:04	1
Pentachlorophenol	ND		0.25	0.0075	mg/L		10/21/20 09:35	10/22/20 10:04	1
Pyridine	ND		0.10	0.0082	mg/L		10/21/20 09:35	10/22/20 10:04	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*65*		*55 - 107*	*10/21/20 09:35*	*10/22/20 10:04*	*1*
2-Fluorophenol (Surr)	*69*		*60 - 108*	*10/21/20 09:35*	*10/22/20 10:04*	*1*
2,4,6-Tribromophenol (Surr)	*71*		*24 - 113*	*10/21/20 09:35*	*10/22/20 10:04*	*1*
Nitrobenzene-d5 (Surr)	*67*		*62 - 115*	*10/21/20 09:35*	*10/22/20 10:04*	*1*
Phenol-d5 (Surr)	*70*		*52 - 107*	*10/21/20 09:35*	*10/22/20 10:04*	*1*
Terphenyl-d14 (Surr)	*66*		*44 - 116*	*10/21/20 09:35*	*10/22/20 10:04*	*1*

Lab Sample ID: LCS 180-334211/2-A
Matrix: Sediment
Analysis Batch: 334310

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334211

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
1,4-Dichlorobenzene	0.250	0.184		mg/L		74	60 - 100
2,4,5-Trichlorophenol	0.250	0.175		mg/L		70	54 - 100
2,4,6-Trichlorophenol	0.250	0.182		mg/L		73	56 - 100
2,4-Dinitrotoluene	0.250	0.151		mg/L		61	42 - 100
2-Methylphenol	0.250	0.191		mg/L		76	60 - 101
Methylphenol, 3 & 4	0.500	0.395		mg/L		79	62 - 106
Hexachlorobenzene	0.250	0.135		mg/L		54	37 - 100
Hexachlorobutadiene	0.250	0.182		mg/L		73	50 - 103
Hexachloroethane	0.250	0.178		mg/L		71	59 - 104
Nitrobenzene	0.250	0.172		mg/L		69	58 - 113
Pentachlorophenol	0.250	0.153	J	mg/L		61	18 - 100
Pyridine	0.250	0.193		mg/L		77	54 - 119

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2-Fluorobiphenyl	*70*		*55 - 107*
2-Fluorophenol (Surr)	*75*		*60 - 108*
2,4,6-Tribromophenol (Surr)	*82*		*24 - 113*
Nitrobenzene-d5 (Surr)	*69*		*62 - 115*
Phenol-d5 (Surr)	*75*		*52 - 107*
Terphenyl-d14 (Surr)	*74*		*44 - 116*

Method: EPA 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCSD 180-334211/3-A
Matrix: Sediment
Analysis Batch: 334310

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 334211

Analyte			Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
1,4-Dichlorobenzene			0.250	0.188		mg/L		75	60 - 100	2	15
2,4,5-Trichlorophenol			0.250	0.185		mg/L		74	54 - 100	6	16
2,4,6-Trichlorophenol			0.250	0.179		mg/L		71	56 - 100	2	15
2,4-Dinitrotoluene			0.250	0.152		mg/L		61	42 - 100	0	17
2-Methylphenol			0.250	0.188		mg/L		75	60 - 101	1	15
Methylphenol, 3 & 4			0.500	0.399		mg/L		80	62 - 106	1	15
Hexachlorobenzene			0.250	0.136		mg/L		55	37 - 100	1	15
Hexachlorobutadiene			0.250	0.182		mg/L		73	50 - 103	0	15
Hexachloroethane			0.250	0.181		mg/L		73	59 - 104	2	16
Nitrobenzene			0.250	0.171		mg/L		68	58 - 113	0	15
Pentachlorophenol			0.250	0.156	J	mg/L		63	18 - 100	2	16
Pyridine			0.250	0.200		mg/L		80	54 - 119	4	16

Surrogate	*LCSD %Recovery*	*LCSD Qualifier*	*Limits*
2-Fluorobiphenyl	*69*		*55 - 107*
2-Fluorophenol (Surr)	*74*		*60 - 108*
2,4,6-Tribromophenol (Surr)	*84*		*24 - 113*
Nitrobenzene-d5 (Surr)	*69*		*62 - 115*
Phenol-d5 (Surr)	*76*		*52 - 107*
Terphenyl-d14 (Surr)	*74*		*44 - 116*

Lab Sample ID: LB 180-334011/1-C
Matrix: Sediment
Analysis Batch: 334310

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334211

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
1,4-Dichlorobenzene	ND		0.050	0.0045	mg/L		10/21/20 09:35	10/22/20 11:38	1
2,4,5-Trichlorophenol	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 11:38	1
2,4,6-Trichlorophenol	ND		0.050	0.0095	mg/L		10/21/20 09:35	10/22/20 11:38	1
2,4-Dinitrotoluene	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 11:38	1
2-Methylphenol	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 11:38	1
Methylphenol, 3 & 4	ND		0.050	0.0079	mg/L		10/21/20 09:35	10/22/20 11:38	1
Hexachlorobenzene	ND		0.050	0.0055	mg/L		10/21/20 09:35	10/22/20 11:38	1
Hexachlorobutadiene	ND		0.050	0.0084	mg/L		10/21/20 09:35	10/22/20 11:38	1
Hexachloroethane	ND		0.050	0.0040	mg/L		10/21/20 09:35	10/22/20 11:38	1
Nitrobenzene	ND		0.050	0.012	mg/L		10/21/20 09:35	10/22/20 11:38	1
Pentachlorophenol	ND		0.25	0.0075	mg/L		10/21/20 09:35	10/22/20 11:38	1
Pyridine	ND		0.10	0.0082	mg/L		10/21/20 09:35	10/22/20 11:38	1

Surrogate	*LB %Recovery*	*LB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2-Fluorobiphenyl	*67*		*55 - 107*	*10/21/20 09:35*	*10/22/20 11:38*	*1*
2-Fluorophenol (Surr)	*68*		*60 - 108*	*10/21/20 09:35*	*10/22/20 11:38*	*1*
2,4,6-Tribromophenol (Surr)	*73*		*24 - 113*	*10/21/20 09:35*	*10/22/20 11:38*	*1*
Nitrobenzene-d5 (Surr)	*68*		*62 - 115*	*10/21/20 09:35*	*10/22/20 11:38*	*1*
Phenol-d5 (Surr)	*68*		*52 - 107*	*10/21/20 09:35*	*10/22/20 11:38*	*1*
Terphenyl-d14 (Surr)	*69*		*44 - 116*	*10/21/20 09:35*	*10/22/20 11:38*	*1*

Method: EPA 8081B - Organochlorine Pesticides (GC)

Lab Sample ID: MB 180-334210/1-A
Matrix: Sediment
Analysis Batch: 334876

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334210

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chlordane (technical)	ND		0.0050	0.0029	mg/L		10/21/20 09:20	10/27/20 21:46	1
Endrin	ND		0.00050	0.000091	mg/L		10/21/20 09:20	10/27/20 21:46	1
gamma-BHC (Lindane)	ND		0.00050	0.00012	mg/L		10/21/20 09:20	10/27/20 21:46	1
Heptachlor	ND		0.00050	0.00018	mg/L		10/21/20 09:20	10/27/20 21:46	1
Heptachlor epoxide	ND		0.00050	0.00014	mg/L		10/21/20 09:20	10/27/20 21:46	1
Methoxychlor	ND		0.00050	0.00031	mg/L		10/21/20 09:20	10/27/20 21:46	1
Toxaphene	ND		0.040	0.020	mg/L		10/21/20 09:20	10/27/20 21:46	1

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*83*		*58 - 115*	*10/21/20 09:20*	*10/27/20 21:46*	*1*
DCB Decachlorobiphenyl (Surr)	*90*		*58 - 115*	*10/21/20 09:20*	*10/27/20 21:46*	*1*
Tetrachloro-m-xylene	*79*		*43 - 118*	*10/21/20 09:20*	*10/27/20 21:46*	*1*
Tetrachloro-m-xylene	*77*		*43 - 118*	*10/21/20 09:20*	*10/27/20 21:46*	*1*

Lab Sample ID: LCS 180-334210/2-A
Matrix: Sediment
Analysis Batch: 334876

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334210

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Endrin			0.0100	0.00840		mg/L		84	37 - 150		
gamma-BHC (Lindane)			0.0100	0.00786		mg/L		79	50 - 137		
Heptachlor			0.0100	0.00798		mg/L		80	49 - 135		
Heptachlor epoxide			0.0100	0.00765		mg/L		76	49 - 133		
Methoxychlor			0.0100	0.00768		mg/L		77	45 - 150		

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
DCB Decachlorobiphenyl (Surr)	*89*		*58 - 115*
DCB Decachlorobiphenyl (Surr)	*97*		*58 - 115*
Tetrachloro-m-xylene	*90*		*43 - 118*
Tetrachloro-m-xylene	*85*		*43 - 118*

Lab Sample ID: LCSD 180-334210/3-A
Matrix: Sediment
Analysis Batch: 334876

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 334210

Analyte			Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Endrin			0.0100	0.00862		mg/L		86	37 - 150	3	15
gamma-BHC (Lindane)			0.0100	0.00789		mg/L		79	50 - 137	0	18
Heptachlor			0.0100	0.00808		mg/L		81	49 - 135	1	22
Heptachlor epoxide			0.0100	0.00765		mg/L		77	49 - 133	0	15
Methoxychlor			0.0100	0.00802		mg/L		80	45 - 150	4	17

Surrogate	*LCSD %Recovery*	*LCSD Qualifier*	*Limits*
DCB Decachlorobiphenyl (Surr)	*95*		*58 - 115*
DCB Decachlorobiphenyl (Surr)	*96*		*58 - 115*
Tetrachloro-m-xylene	*88*		*43 - 118*
Tetrachloro-m-xylene	*91*		*43 - 118*

Method: EPA 8081B - Organochlorine Pesticides (GC) (Continued)

Lab Sample ID: LB 180-334011/1-B
Matrix: Sediment
Analysis Batch: 334876

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334210

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chlordane (technical)	ND		0.0050	0.0029	mg/L		10/21/20 09:20	10/27/20 22:33	1
Endrin	ND		0.00050	0.000091	mg/L		10/21/20 09:20	10/27/20 22:33	1
gamma-BHC (Lindane)	ND		0.00050	0.00012	mg/L		10/21/20 09:20	10/27/20 22:33	1
Heptachlor	ND		0.00050	0.00018	mg/L		10/21/20 09:20	10/27/20 22:33	1
Heptachlor epoxide	ND		0.00050	0.00014	mg/L		10/21/20 09:20	10/27/20 22:33	1
Methoxychlor	ND		0.00050	0.00031	mg/L		10/21/20 09:20	10/27/20 22:33	1
Toxaphene	ND		0.040	0.020	mg/L		10/21/20 09:20	10/27/20 22:33	1

Surrogate	*LB %Recovery*	*LB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
DCB Decachlorobiphenyl (Surr)	*103*		*58 - 115*	*10/21/20 09:20*	*10/27/20 22:33*	*1*
DCB Decachlorobiphenyl (Surr)	*101*		*58 - 115*	*10/21/20 09:20*	*10/27/20 22:33*	*1*
Tetrachloro-m-xylene	*96*		*43 - 118*	*10/21/20 09:20*	*10/27/20 22:33*	*1*
Tetrachloro-m-xylene	*98*		*43 - 118*	*10/21/20 09:20*	*10/27/20 22:33*	*1*

Method: EPA 8151A - Herbicides (GC)

Lab Sample ID: MB 180-334218/1-A
Matrix: Sediment
Analysis Batch: 335001

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334218

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
2,4-D	ND		0.040	0.020	mg/L		10/21/20 13:00	10/28/20 08:39	20
Silvex (2,4,5-TP)	ND		0.010	0.0030	mg/L		10/21/20 13:00	10/28/20 08:39	20

Surrogate	*MB %Recovery*	*MB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2,4-Dichlorophenylacetic acid	*79*		*23 - 122*	*10/21/20 13:00*	*10/28/20 08:39*	*20*
2,4-Dichlorophenylacetic acid	*69*		*23 - 122*	*10/21/20 13:00*	*10/28/20 08:39*	*20*

Lab Sample ID: LCS 180-334218/2-A
Matrix: Sediment
Analysis Batch: 335001

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334218

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
2,4-D			0.200	0.132		mg/L		66	19 - 127		
Silvex (2,4,5-TP)			0.0500	0.0431		mg/L		86	24 - 128		

Surrogate	*LCS %Recovery*	*LCS Qualifier*	*Limits*
2,4-Dichlorophenylacetic acid	*89*		*23 - 122*
2,4-Dichlorophenylacetic acid	*81*		*23 - 122*

Lab Sample ID: LCSD 180-334218/3-A
Matrix: Sediment
Analysis Batch: 335001

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 334218

Analyte			Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
2,4-D			0.200	0.125		mg/L		63	19 - 127	5	35
Silvex (2,4,5-TP)			0.0500	0.0400		mg/L		80	24 - 128	7	35

Method: EPA 8151A - Herbicides (GC) (Continued)

Lab Sample ID: LCSD 180-334218/3-A
Matrix: Sediment
Analysis Batch: 335001

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 334218

Surrogate	*LCSD %Recovery*	*LCSD Qualifier*	*Limits*
2,4-Dichlorophenylacetic acid	*81*		*23 - 122*
2,4-Dichlorophenylacetic acid	*73*		*23 - 122*

Lab Sample ID: LB 180-334011/1-D
Matrix: Sediment
Analysis Batch: 335001

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334218

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
2,4-D	ND		0.040	0.020	mg/L		10/21/20 13:00	10/28/20 11:40	20
Silvex (2,4,5-TP)	ND		0.010	0.0030	mg/L		10/21/20 13:00	10/28/20 11:40	20

Surrogate	*LB %Recovery*	*LB Qualifier*	*Limits*	*Prepared*	*Analyzed*	*Dil Fac*
2,4-Dichlorophenylacetic acid	*93*		*23 - 122*	*10/21/20 13:00*	*10/28/20 11:40*	*20*
2,4-Dichlorophenylacetic acid	*92*		*23 - 122*	*10/21/20 13:00*	*10/28/20 11:40*	*20*

Method: EPA 6010B - Metals (ICP)

Lab Sample ID: MB 180-334406/1-A
Matrix: Sediment
Analysis Batch: 334692

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334406

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.50	0.041	mg/L		10/22/20 15:35	10/23/20 14:34	1
Barium	ND		2.0	0.026	mg/L		10/22/20 15:35	10/23/20 14:34	1
Cadmium	ND		0.50	0.0028	mg/L		10/22/20 15:35	10/23/20 14:34	1
Chromium	ND		0.50	0.0078	mg/L		10/22/20 15:35	10/23/20 14:34	1
Lead	ND		0.50	0.029	mg/L		10/22/20 15:35	10/23/20 14:34	1
Selenium	ND		0.50	0.036	mg/L		10/22/20 15:35	10/23/20 14:34	1
Silver	ND		0.50	0.0085	mg/L		10/22/20 15:35	10/23/20 14:34	1

Lab Sample ID: LCS 180-334406/2-A
Matrix: Sediment
Analysis Batch: 334692

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334406

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	10.0	10.7		mg/L		107	80 - 120
Barium	10.0	10.0		mg/L		100	80 - 120
Cadmium	5.00	5.22		mg/L		104	80 - 120
Chromium	5.00	4.98		mg/L		100	80 - 120
Lead	5.00	5.01		mg/L		100	80 - 120
Selenium	10.0	10.7		mg/L		107	80 - 120
Silver	2.50	2.59		mg/L		104	80 - 120

Lab Sample ID: LB 180-334011/1-F
Matrix: Sediment
Analysis Batch: 334692

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334406

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	ND		0.50	0.041	mg/L		10/22/20 15:35	10/23/20 16:26	1

Method: EPA 6010B - Metals (ICP) (Continued)

Lab Sample ID: LB 180-334011/1-F
Matrix: Sediment
Analysis Batch: 334692

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334406

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Barium	ND		2.0	0.026	mg/L		10/22/20 15:35	10/23/20 16:26	1
Cadmium	ND		0.50	0.0028	mg/L		10/22/20 15:35	10/23/20 16:26	1
Chromium	ND		0.50	0.0078	mg/L		10/22/20 15:35	10/23/20 16:26	1
Lead	ND		0.50	0.029	mg/L		10/22/20 15:35	10/23/20 16:26	1
Selenium	ND		0.50	0.036	mg/L		10/22/20 15:35	10/23/20 16:26	1
Silver	ND		0.50	0.0085	mg/L		10/22/20 15:35	10/23/20 16:26	1

Method: EPA 7470A - Mercury (CVAA)

Lab Sample ID: MB 180-334370/1-A
Matrix: Sediment
Analysis Batch: 335034

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334370

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.000188	J	0.00020	0.00013	mg/L		10/22/20 13:22	10/27/20 18:21	1

Lab Sample ID: LCS 180-334370/2-A
Matrix: Sediment
Analysis Batch: 335034

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334370

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Mercury	0.00250	0.00274		mg/L		109	80 - 120

Lab Sample ID: LB 180-334011/1-E
Matrix: Sediment
Analysis Batch: 335034

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 334370

Analyte	LB Result	LB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Mercury	ND		0.00020	0.00013	mg/L		10/22/20 13:22	10/27/20 18:23	1

Method: EPA 9014 - Cyanide

Lab Sample ID: MB 180-334633/4-A
Matrix: Sediment
Analysis Batch: 334930

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334633

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Cyanide, Total	ND		0.50	0.15	mg/Kg		10/24/20 12:15	10/26/20 17:21	1

Lab Sample ID: HLCS 180-334633/2-A
Matrix: Sediment
Analysis Batch: 334930

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334633

Analyte	Spike Added	HLCS Result	HLCS Qualifier	Unit	D	%Rec	%Rec. Limits
Cyanide, Total	0.250	0.254		mg/Kg		101	90 - 110

Method: EPA 9014 - Cyanide (Continued)

Lab Sample ID: LCS 180-334633/3-A
Matrix: Sediment
Analysis Batch: 334930

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334633

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Cyanide, Total	23.1	22.9		mg/Kg		99	25 - 150

Lab Sample ID: LLCS 180-334633/1-A
Matrix: Sediment
Analysis Batch: 334930

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334633

Analyte	Spike Added	LLCS Result	LLCS Qualifier	Unit	D	%Rec	%Rec. Limits
Cyanide, Total	0.0500	0.0511		mg/Kg		102	90 - 110

Method: EPA 9034 - Sulfide, Acid soluble and Insoluble (Titrimetric)

Lab Sample ID: MB 180-334074/1-A
Matrix: Sediment
Analysis Batch: 334204

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 334074

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sulfide	ND		30	10	mg/Kg		10/20/20 15:00	10/20/20 17:28	1

Lab Sample ID: LCS 180-334074/2-A
Matrix: Sediment
Analysis Batch: 334204

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 334074

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Sulfide	121	105		mg/Kg		86	85 - 115

Lab Sample ID: 180-112242-1 MS
Matrix: Sediment
Analysis Batch: 334204

Client Sample ID: 0746-009
Prep Type: Total/NA
Prep Batch: 334074

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Sulfide	59	F1	204	147	F1	mg/Kg	☼	43	75 - 125

Lab Sample ID: 180-112242-1 MSD
Matrix: Sediment
Analysis Batch: 334204

Client Sample ID: 0746-009
Prep Type: Total/NA
Prep Batch: 334074

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Sulfide	59	F1	203	156	F1	mg/Kg	☼	47	75 - 125	6	20

GC/MS VOA

Leach Batch: 334016

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 1311	
180-112242-2	0746-010	TCLP	Sediment	EPA 1311	
LB 180-334016/1-A	Method Blank	TCLP	Sediment	EPA 1311	

Analysis Batch: 334149

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 8260C	334016
180-112242-2	0746-010	TCLP	Sediment	EPA 8260C	334016
LB 180-334016/1-A	Method Blank	TCLP	Sediment	EPA 8260C	334016
LCS 180-334149/3	Lab Control Sample	Total/NA	Sediment	EPA 8260C	

GC/MS Semi VOA

Leach Batch: 334011

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 1311	
180-112242-2	0746-010	TCLP	Sediment	EPA 1311	
LB 180-334011/1-C	Method Blank	TCLP	Sediment	EPA 1311	

Prep Batch: 334211

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	3510C	334011
180-112242-2	0746-010	TCLP	Sediment	3510C	334011
LB 180-334011/1-C	Method Blank	TCLP	Sediment	3510C	334011
MB 180-334211/1-A	Method Blank	Total/NA	Sediment	3510C	
LCS 180-334211/2-A	Lab Control Sample	Total/NA	Sediment	3510C	
LCSD 180-334211/3-A	Lab Control Sample Dup	Total/NA	Sediment	3510C	

Analysis Batch: 334310

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 8270D	334211
180-112242-2	0746-010	TCLP	Sediment	EPA 8270D	334211
LB 180-334011/1-C	Method Blank	TCLP	Sediment	EPA 8270D	334211
MB 180-334211/1-A	Method Blank	Total/NA	Sediment	EPA 8270D	334211
LCS 180-334211/2-A	Lab Control Sample	Total/NA	Sediment	EPA 8270D	334211
LCSD 180-334211/3-A	Lab Control Sample Dup	Total/NA	Sediment	EPA 8270D	334211

GC Semi VOA

Leach Batch: 334011

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 1311	
180-112242-2	0746-010	TCLP	Sediment	EPA 1311	
LB 180-334011/1-B	Method Blank	TCLP	Sediment	EPA 1311	
LB 180-334011/1-D	Method Blank	TCLP	Sediment	EPA 1311	

Prep Batch: 334210

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	3510C	334011
180-112242-2	0746-010	TCLP	Sediment	3510C	334011
LB 180-334011/1-B	Method Blank	TCLP	Sediment	3510C	334011
MB 180-334210/1-A	Method Blank	Total/NA	Sediment	3510C	

GC Semi VOA (Continued)

Prep Batch: 334210 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 180-334210/2-A	Lab Control Sample	Total/NA	Sediment	3510C	
LCSD 180-334210/3-A	Lab Control Sample Dup	Total/NA	Sediment	3510C	

Prep Batch: 334218

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	8151A	334011
180-112242-2	0746-010	TCLP	Sediment	8151A	334011
LB 180-334011/1-D	Method Blank	TCLP	Sediment	8151A	334011
MB 180-334218/1-A	Method Blank	Total/NA	Sediment	8151A	
LCS 180-334218/2-A	Lab Control Sample	Total/NA	Sediment	8151A	
LCSD 180-334218/3-A	Lab Control Sample Dup	Total/NA	Sediment	8151A	

Prep Batch: 334300

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	3541	
180-112242-2	0746-010	Total/NA	Sediment	3541	

Analysis Batch: 334490

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	EPA 8082A	334525
180-112242-2	0746-010	Total/NA	Sediment	EPA 8082A	334525

Cleanup Batch: 334523

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	3665A	334300
180-112242-2	0746-010	Total/NA	Sediment	3665A	334300

Cleanup Batch: 334525

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	3660B	334523
180-112242-2	0746-010	Total/NA	Sediment	3660B	334523

Analysis Batch: 334876

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 8081B	334210
180-112242-2	0746-010	TCLP	Sediment	EPA 8081B	334210
LB 180-334011/1-B	Method Blank	TCLP	Sediment	EPA 8081B	334210
MB 180-334210/1-A	Method Blank	Total/NA	Sediment	EPA 8081B	334210
LCS 180-334210/2-A	Lab Control Sample	Total/NA	Sediment	EPA 8081B	334210
LCSD 180-334210/3-A	Lab Control Sample Dup	Total/NA	Sediment	EPA 8081B	334210

Analysis Batch: 335001

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 8151A	334218
180-112242-2	0746-010	TCLP	Sediment	EPA 8151A	334218
LB 180-334011/1-D	Method Blank	TCLP	Sediment	EPA 8151A	334218
MB 180-334218/1-A	Method Blank	Total/NA	Sediment	EPA 8151A	334218
LCS 180-334218/2-A	Lab Control Sample	Total/NA	Sediment	EPA 8151A	334218
LCSD 180-334218/3-A	Lab Control Sample Dup	Total/NA	Sediment	EPA 8151A	334218

QC Association Summary

Client: AECOM
Project/Site: Pepco Benning Road Facility

Job ID: 180-112242-1

GC Semi VOA

Analysis Batch: 335216

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	PCB	
180-112242-2	0746-010	Total/NA	Sediment	PCB	

Metals

Leach Batch: 334011

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 1311	
180-112242-2	0746-010	TCLP	Sediment	EPA 1311	
LB 180-334011/1-E	Method Blank	TCLP	Sediment	EPA 1311	
LB 180-334011/1-F	Method Blank	TCLP	Sediment	EPA 1311	

Prep Batch: 334370

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	7470A	334011
180-112242-2	0746-010	TCLP	Sediment	7470A	334011
LB 180-334011/1-E	Method Blank	TCLP	Sediment	7470A	334011
MB 180-334370/1-A	Method Blank	Total/NA	Sediment	7470A	
LCS 180-334370/2-A	Lab Control Sample	Total/NA	Sediment	7470A	

Prep Batch: 334406

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	3010A	334011
180-112242-2	0746-010	TCLP	Sediment	3010A	334011
LB 180-334011/1-F	Method Blank	TCLP	Sediment	3010A	334011
MB 180-334406/1-A	Method Blank	Total/NA	Sediment	3010A	
LCS 180-334406/2-A	Lab Control Sample	Total/NA	Sediment	3010A	

Analysis Batch: 334692

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 6010B	334406
180-112242-2	0746-010	TCLP	Sediment	EPA 6010B	334406
LB 180-334011/1-F	Method Blank	TCLP	Sediment	EPA 6010B	334406
MB 180-334406/1-A	Method Blank	Total/NA	Sediment	EPA 6010B	334406
LCS 180-334406/2-A	Lab Control Sample	Total/NA	Sediment	EPA 6010B	334406

Analysis Batch: 335034

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	TCLP	Sediment	EPA 7470A	334370
180-112242-2	0746-010	TCLP	Sediment	EPA 7470A	334370
LB 180-334011/1-E	Method Blank	TCLP	Sediment	EPA 7470A	334370
MB 180-334370/1-A	Method Blank	Total/NA	Sediment	EPA 7470A	334370
LCS 180-334370/2-A	Lab Control Sample	Total/NA	Sediment	EPA 7470A	334370

General Chemistry

Prep Batch: 334074

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	9030B	
180-112242-2	0746-010	Total/NA	Sediment	9030B	
MB 180-334074/1-A	Method Blank	Total/NA	Sediment	9030B	
LCS 180-334074/2-A	Lab Control Sample	Total/NA	Sediment	9030B	

General Chemistry (Continued)

Prep Batch: 334074 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1 MS	0746-009	Total/NA	Sediment	9030B	
180-112242-1 MSD	0746-009	Total/NA	Sediment	9030B	

Analysis Batch: 334204

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	EPA 9034	334074
180-112242-2	0746-010	Total/NA	Sediment	EPA 9034	334074
MB 180-334074/1-A	Method Blank	Total/NA	Sediment	EPA 9034	334074
LCS 180-334074/2-A	Lab Control Sample	Total/NA	Sediment	EPA 9034	334074
180-112242-1 MS	0746-009	Total/NA	Sediment	EPA 9034	334074
180-112242-1 MSD	0746-009	Total/NA	Sediment	EPA 9034	334074

Analysis Batch: 334348

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	EPA 1020B	
180-112242-2	0746-010	Total/NA	Sediment	EPA 1020B	

Prep Batch: 334633

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	9010C	
180-112242-2	0746-010	Total/NA	Sediment	9010C	
MB 180-334633/4-A	Method Blank	Total/NA	Sediment	9010C	
HLCS 180-334633/2-A	Lab Control Sample	Total/NA	Sediment	9010C	
LCS 180-334633/3-A	Lab Control Sample	Total/NA	Sediment	9010C	
LLCS 180-334633/1-A	Lab Control Sample	Total/NA	Sediment	9010C	

Analysis Batch: 334684

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	2540G	
180-112242-2	0746-010	Total/NA	Sediment	2540G	

Analysis Batch: 334930

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
180-112242-1	0746-009	Total/NA	Sediment	EPA 9014	334633
180-112242-2	0746-010	Total/NA	Sediment	EPA 9014	334633
MB 180-334633/4-A	Method Blank	Total/NA	Sediment	EPA 9014	334633
HLCS 180-334633/2-A	Lab Control Sample	Total/NA	Sediment	EPA 9014	334633
LCS 180-334633/3-A	Lab Control Sample	Total/NA	Sediment	EPA 9014	334633
LLCS 180-334633/1-A	Lab Control Sample	Total/NA	Sediment	EPA 9014	334633

Eurofins TestAmerica, Pittsburgh
301 Alpha Drive
RIDC Park
Pittsburgh, PA 15238-2907
phone 412.963.7058 fax 412.963.2468

Chain of Custody Record

eurofins Environment Testing TestAmerica

244- ATLANTA

Regulatory Program: ☐ DW ☐ NPDES ☐ RCRA ☐ Other:

TestAmerica Laboratories, Inc. d/b/a Eurofins TestAmerica

	Project Manager: Kris Carbonneau		COC No:
Client Contact	**Email: kris.carbonneau@aecom.com**	**Site Contact:**	**Date: 10-13-20**	___1___ of __1___ COCs
AECOM	**Tel/Fax:**	**Lab Contact: Jill Colussy**	**Carrier:**	TALS Project #:
Address	**Analysis Turnaround Time**			Sampler:
City/State/Zip	☐ CALENDAR DAYS ☑ WORKING DAYS			**For Lab Use Only:**
(xxx) xxx-xxxx Phone	TAT if different from Below _____			Walk-in Client:
(xxx) xxx-xxxx FAX	☑ 2 weeks			Lab Sampling:
Project Name: Pepco Benning Road TS	☐ 1 week			
PO# 60631088	☐ 2 days			Job / SDG No.:
Quote# 18022551	☐ 1 day			

Sample Identification	Sample Date	Sample Time	Sample Type (C=Comp, G=Grab)	Matrix	# of Cont.	Filtered Sample (Y / N)	Perform MS / MSD (Y / N)	TCLP PCBs as Aroclors 8082	Totals PCBs as Aroclors 8082	Sample Specific Notes:
0746-009	10/13/20	1000	G	S	4			X	X	
0746-010	10/13/20	1005	G	S	4			X	X	

180-112242 Chain of Custody

Preservation Used: 1= Ice, 2= HCl; 3= H2SO4; 4=HNO3; 5=NaOH; 6= Other _____

Possible Hazard Identification:
Are any samples from a listed EPA Hazardous Waste? Please List any EPA Waste Codes for the sample in the Comments Section if the lab is to dispose of the sample.

☑ Non-Hazard ☐ Flammable ☐ Skin Irritant ☐ Poison B ☐ Unknown

Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)

☐ Return to Client ☑ Disposal by Lab ☐ Archive for_____ Months

Special Instructions/QC Requirements & Comments:

Custody Seals Intact: ☐ Yes ☐ No | Custody Seal No.: | Cooler Temp. (°C): Obs'd:_____ Corr'd:_____ | Therm ID No.:_____

Relinquished by: Stan Antw	Company: KEMRON	Date/Time: 10/13/20 1100	Received by:	Company: ETA	Date/Time: 10/13/20 11:00
Relinquished by:	Company: ETA	Date/Time: 10/13/20 16:00	Received by:	Company: ETA	Date/Time: 10-14-20
Relinquished by:	Company:	Date/Time:	Received in Laboratory by:	Company:	Date/Time: 9:30

Form No. CA-C-WI-002, Rev. 4.33, dated 5/4/2020

Login Sample Receipt Checklist

Client: AECOM

Job Number: 180-112242-1

Login Number: 112242
List Number: 1
Creator: Watson, Debbie

List Source: Eurofins TestAmerica, Pittsburgh

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	False	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

An Exelon Company

Appendix C

DPW Outfall Monitoring Results

Table C-1
NPDES MSGP Discharge Monitoring and PCB Sampling Results for Outfall 001
Benning Road Facility RI/FS Project
3200 Benning Road, NE
Washington, DC 20019

		LOCATION ID	DPW Outfall 001	DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001		DPW Outfall 001			
		SAMPLE ID	BENCHMARK	17I0391-01	17I0391-02	18H0647-01	18H0647-02	18L0946-01	18L0946-02	19B1120-01	19B1120-02	19F1450-01	19F1450-02	19K0640-01	19K0640-02	20A0476-01	20A0476-02	20G0965-01	20G0965-02	20H0585-01	20H0585-02	20L0296-01	20L0296-02	POD-001	
		SAMPLE_DATE	NA	10/9/2017	10/9/2017	9/17/2018	9/17/2018	2/21/2019	2/21/2019	6/24/2019	6/24/2019	10/30/2019	10/30/2019	12/29/2019	12/29/2019	1/12/2020	1/12/2020	7/30/2020	7/30/2020	9/9/2020	9/9/2020	12/4/2020	12/4/2020	11/30/2020	
ANALYTIC_METHOD	CHEMICAL_NAME	UNITS																							
335.4	Cyanide, Total	mg/l	0.022	<0.0050		<0.0050		<0.0050		<0.0050		<0.0050		0.012		0.031			<0.0050		<0.0050	<0.0026			
410.4	Chemical Oxygen Demand, Total	mg/l	120	<50	89	<50	<50	52	57	<50	<50	740	360	250	<50	160	250	860	5300	560	850	140	240		
SM 4500-NH3 B+C-1	Ammonia as N	mg/L	2.14	<1.0		1.1		<1.0		6.2		2.2		<1.0		<1.0			4.8		2.8	<1.0			
245.1	Mercury	mg/l	0.0014	<0.00020		<0.00020		<0.00020		<0.00020		<0.00020		<0.00020		<0.00020			<0.00020		<0.00057	<0.00057			
200.2/200.7	Antimony	mg/l	NA	0.046		0.13		<0.040		<0.040		<0.040		<0.040		<0.040									
200.2/200.7	Arsenic	mg/l	0.15	0.040		0.022		<0.020		<0.020		<0.020		<0.020		<0.020			0.0033*		<0.0050*	0.0044*			
200.2/200.7	Cadmium	mg/l	0.0005	<0.010		<0.010		<0.010		<0.010		<0.010		<0.010		<0.010			0.000618*		<0.00125*	0.00198*			
200.2/200.7	Calcium	mg/l	NA	2.8	2.7	1.6	1.6	17	15	67	67	58	58	61	61	38	43	61.8	61.0	56.2	56.9				
200.2/200.7	Lead	mg/l	0.014	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	0.044	0.046	0.0182*	0.0253*	0.0177*	0.0174*	0.0682*	0.0806*		
200.2/200.7	Magnesium	mg/l	0.064	0.25	0.22	0.32	0.32	2.9	2.4	12	12	5.0	5.1	13	14	6.9	6.9	6.22	6.18	5.73	5.73	6.15**			
200.2/200.8	Magnesium	mg/l	0.064																		5.36				
200.2/200.7	Selenium	mg/l	0.005	<0.040	<0.040	<0.040		<0.040		<0.040		<0.040		<0.040		<0.040			<0.0050*		<0.025*	0.0014*			
200.2/200.7	Silver	mg/l	0.0007	<0.0040		<0.0040		<0.0040		<0.0040		<0.0040		<0.0040		<0.0040			<0.0010*		<0.0050*	<0.0010*			
200.2/200.7	Aluminum	mg/l	0.75		<0.10		<0.10		0.74		<0.10		0.64		0.25		2.3	0.773*		1.19			1.43*		
200.2/200.7	Copper	mg/l	0.0038		<0.020		<0.020		<0.020		<0.020		0.079		<0.020		0.054	0.0745*		0.0588*			0.0522*		
200.2/200.7	Iron	mg/l	1.0		0.2		0.033		1.5		4.4		2.7		6.8		4.7	3.43	3.34	3.54			9.0		
200.2/200.7	Zinc	mg/l	0.04		0.039		0.026		0.072		0.024		0.23		0.061		0.39	0.456*		0.367*			0.333*		
SM 2340 B-11	Hardness (as CaCO3) for Sector K	mg/l	8.1	8.1		5.3		55		220		170		210		120		180		164					
SM 2340 B-11	Hardness (as CaCO3) for Sector N	mg/l	7.7		7.7		5.2		48		220		170		210		140		178		166				
SM 2540 D-11	Total Suspended Solids (TSS)	mg/l	100		26		2.6		12		13		30		<20		96	70		88			2600		
EPA Method 1668C	Total PCB	pg/l	NA																					18600***	

Notes:
mg/L =milligram per liter
J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte.
U = The analyte was not detected above the indicated reporting detection limit.
NA = No benchmark value provided for this analyte.
*Analytical method differs. Method 200.2/200.8 was applied.
**Analytical method differs. Method 200.2/6020B was applied.
*** Stormwater sampling conducted by Tetra Tech on November 30, 2020.
Blank cells highlighted in gray indicats sample not analyzed for the parameter/analysis.
Cells highlighted in yellow indicates results exceeding benchmark values.

Table C-2
NPDES MSGP Discharge Monitoring and PCB Sampling Results for Outfall 002
Benning Road Facility RI/FS Project
3200 Benning Road, NE
Washington, DC 20019

		LOCATION ID	DPW Outfall 002	DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		DPW Outfall 002		
		SAMPLE ID	BENCHMARK	17I0391-03	17I0391-04	18H0647-03	18H0647-04	18L0946-03	18L0946-04	19B1120-03	19B1120-04	19F1450-03	19F1450-04	19K0640-03	19K0640-04	20A0476-03	20A0476-04	20G0965-03	20G0965-04	20H0585-03	20H0585-04	20L0296-03	20L0296-04	POD-002
		SAMPLE_DATE	NA	10/9/2017	10/9/2017	9/17/2018	9/17/2018	2/21/2019	2/21/2019	6/24/2019	6/24/2019	10/30/2019	10/30/2019	12/29/2019	12/29/2019	1/12/2020	1/12/2020	7/30/2020	7/30/2020	9/9/2020	9/9/2020	12/4/2020	12/4/2020	11/30/2020
ANALYTIC_METHOD	CHEMICAL_NAME	UNITS																						
335.4	Cyanide, Total	mg/l	0.022	0.060		0.046		0.011		<0.0050		<0.0050		0.0057		<0.0050			<0.0050		<0.0050	<0.0026		
410.4	Chemical Oxygen Demand, Total	mg/l	120	37000	37000	12000	16000	530	770	<50	<50	410	730	3100	3100	280	280	500	2600	890	1000	130	96	
SM 4500-NH3 B+C-11	Ammonia as N	mg/L	2.14	28		<1.0		<1.0		2.5		1.7		9.0		<1.0			19		4.8	<1.0		
245.1	Mercury	mg/l	0.0014	0.00046		0.00045		0.00030		<0.00020		<0.00020		<0.00020		<0.00020			<0.00057		<0.00057	<0.00057		
200.2/200.7	Antimony	mg/l	NA	<0.20		<0.20		<0.20		<0.040		<0.040		<0.050		<0.040								
200.2/200.7	Arsenic	mg/l	0.15	<0.10		<0.10		<0.10		<0.020		<0.020		<0.025		<0.020			0.0139*		0.0058*	0.0031*		
200.2/200.7	Cadmium	mg/l	0.0053	<0.050		<0.050		<0.050		<0.010		<0.010		<0.012		<0.010			0.000956*		<0.00125*	<0.000250*		
200.2/200.7	Calcium	mg/l	NA	1400	1500	900	880	31	28	69	69	97	87	120	120	16	15	146	139	160	152			
200.2/200.7	Lead	mg/l	0.262	1.4	1.5	0.28	0.29	<0.10	<0.10	<0.020	<0.020	<0.020	<0.020	<0.025	<0.025	<0.020	<0.020	0.0399*	0.0384*	0.0140*	0.0177*	0.0042*	0.0069*	
200.2/200.7	Magnesium	mg/l	0.064	140	160	50	49	4.4	3.7	15	14	18	16	3.7	9.6	1.4	1.4	13.2	12.5	19.4	17.8	9.36**		
200.2/200.8	Magnesium	mg/l	0.064																		17.0			
200.2/200.7	Selenium	mg/l	0.005	<0.20	<1.0	<0.20		<0.20		<0.040		<0.040		<0.050		<0.040			<0.0050*		<0.0250*	<0.0014*		
200.2/200.7	Silver	mg/l	0.0183	<0.020		<0.020		<0.020		<0.0040		<0.0040		<0.0040		<0.0040			<0.0010*		<0.0050*	<0.0010*		
200.2/200.7	Aluminum	mg/l	0.75		11		9.1		3.5		<0.10		0.44		0.87		0.90	0.581*		0.637			0.338*	
200.2/200.7	Copper	mg/l	0.0332		2.3		0.43		0.16		<0.020		<0.020		0.23		0.027	0.278*		0.0605*			0.0145*	
200.2/200.7	Iron	mg/l	1.0		180		48		6.1		5.6		5.4		4.1		1.8	4.09	4.41	4.78			7.4	
200.2/200.7	Zinc	mg/l	0.26		16		7.8		0.33		<0.020		0.11		0.52		0.13	0.834*		0.286*			0.0555*	
SM 2340 B-11	Hardness (as CaCO3) for Sector K	mg/l	4000	4000		2500		96		230		310		300		45		420		480				
SM 2340 B-11	Hardness (as CaCO3) for Sector N	mg/l	4300		4300		2400		85		230		280		340		44		398		452			
SM 2540 D-11	Total Suspended Solids (TSS)	mg/l	100		1200		5000		170		9		46		100		76	120		62			35	
EPA Method 1668C	Total PCB	pg/l	NA																					7840***

Notes:
mg/L =milligram per liter
J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte.
U = The analyte was not detected above the indicated reporting detection limit.
NA = No benchmark value provided for this analyte.
*Analytical method differs. Method 200.2/200.8 was applied.
**Analytical method differs. Method 200.2/6020B was applied.
*** Stormwater sampling conducted by Tetra Tech on November 30, 2020.
Blank cells highlighted in gray indicats sample not analyzed for the parameter/analysis.
Cells highlighted in yellow indicates results exceeding benchmark values.

The Quarterly Sampling Event for July-September 2017 was conducted for the following site(s):

Table 3 – Quarterly Sampling Location				
Site #	**SWP3 Appendix ID**	**Address**	**Outfall Number**	**Flow Conditions**
8	H	3200 BENNING ROAD, NE	001/002	Good

SWP3 – Stormwater Pollution Prevention Plan

Relevant site maps can be found in **Section 6.0**.

Laboratory Results

TABLE 6 - LAB ANALYSES: SITE #8 -3200 BENNING RD NE OUTFALL 001
REPORT NO.: 1710391

Sector K Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	ND	0.022 mg/L
Chemical Oxygen Demand, Total	ND	120 mg/L
Ammonia as N	ND	2.14 mg/L
Mercury	ND	0.0014 mg/L
Silver	ND	0.0007 mg/L
Arsenic	0.040 mg/L	0.15 mg/L
Cadmium	ND	0.0005 mg/L
Magnesium	**0.25 mg/L**	**0.064 mg/L**
Lead	ND	0.014 mg/L
Selenium	ND	0.005 mg/L
Hardness ($CaCO_3$)	8.1 mg/L	
Sector N Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentrations**
Chemical Oxygen Demand, Total	89 mg/L	120 mg/L
Total Suspended Solids	26 mg/L	100 mg/L
Aluminum	ND	0.75 mg/L
Copper	ND	0.0038 mg/L
Iron	0.20 mg/L	1.0 mg/L
Lead	ND	0.014 mg/L
Zinc	0.039 mg/L	0.04 mg/L
Hardness ($CaCO_3$)	7.7 mg/L	


ND – Non Detect

TABLE 7 - LAB ANALYSES: SITE #8 -3200 BENNING RD NE OUTFALL 002
REPORT NO.: 17I0391

Sector K Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentrations**
Cyanide, Total	**0.060 mg/L**	**0.022 mg/L**
Chemical Oxygen Demand, Total	**37,000 mg/L**	**120 mg/L**
Ammonia as N	**28 mg/L**	**2.14 mg/L**
Mercury	0.00046 mg/L	0.0014 mg/L
Silver	ND	0.0183 mg/L
Arsenic	ND	0.15 mg/L
Cadmium	ND	0.0053 mg/L
Magnesium	**140 mg/L**	**0.064 mg/L**
Lead	**1.4 mg/L**	**0.262 mg/L**
Selenium	ND	0.005 mg/L
Hardness ($CaCO_3$)	4,000 mg/L	
Sector N Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentrations**
Chemical Oxygen Demand, Total	**37,000 mg/L**	**120 mg/L**
Total Suspended Solids	**1,200 mg/L**	**100 mg/L**
Aluminum	**11 mg/L**	**0.75 mg/L**
Copper	**2.3 mg/L**	**0.0332 mg/L**
Iron	**180 mg/L**	**1.0 mg/L**
Lead	**1.5 mg/L**	**0.262 mg/L**
Zinc	**16 mg/L**	**0.26 mg/L**
Hardness ($CaCO_3$)	4,300 mg/L	

ND – Non Detect

Parameters that are above the Benchmark Monitoring Concentration are bolded within their respective tables. Benchmark Monitoring Concentrations are found in the representative subsector of Part 8 "Sector-Specific Requirements for Industrial Activity," of the National Pollutant Discharge Elimination System (NPDES) Multi-Sector General Permit for Stormwater Discharges Associated with Industrial Activity (MSGP). As per Part 6.2.1 "Benchmark Monitoring," after collection of 4 quarterly samples, if the average of the 4 monitoring values for any parameter exceeds the benchmark, in accordance with Part 3.2, review the selection, design, installation, and implementation of control measures to determine if modifications are necessary to meet the effluent limits in the permit.



APEX
8854 RIXLEW LANE
MANASSAS, VA 20109
TELEPHONE: (703) 396-6730
FAX: (703) 396-6743

Appendix H
3200 Benning Road NE,
Washington, DC 21002
Benning Road
SWMA Waste/Recycling Facility

0 25 50 100 150 200 Feet

Coordinate System: Lambert Conformal Conic
Central Meridian: 77°0'0"W
1st Std Parallel: 38°18'0"N
2nd Std Parallel: 39°27'0"N
Latitude of Origin: 37°40'0"N

N

Department of Public Works
Washington, DC SWP3 2010
Appendix Update: 7/1/2014
2010 USGS Orthoimage
.16 Meter Resolution

MICROBAC®

Microbac Laboratories, Inc.

Baltimore Division

2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

COVER LETTER

Andrea Owen Heller
Apex Companies, LLC
8854 Rixlew Lane
Manassas, VA 20109

RE: DC DPW - Site #8

October 18, 2017
Report No.: 17I0391

The report of analyses contains test results for samples received at Microbac Laboratories, Inc., Baltimore Division on 10/09/2017 08:37.

The enclosed results were obtained from and applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report has been reviewed and meet the applicable project and certification specific requirements, unless otherwise noted.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories, Inc.

We appreciate the opportunity to service your analytical needs. If you have any questions, please feel free to contact us.

This Data Package contains the following:

- This Cover Page
- Sample Summary
- Test Results
- Certifications/Notes and Definitions
- Cooler Receipt Log
- Chain of Custody

Final report reviewed by: Michael M. Gallion/Project Manager — 10/18/2017 Report issue date

All samples received in proper condition and results conform to ISO 17025 and TNI NELAC standards unless otherwise noted.

If we have not met or exceeded your expectations, please contact Michael M. Gallion/Project Manager at 410-633-1800. You may also contact Trevor Boyce, President at trevor.boyce@microbac.com. Any complaint about the quality of reported results may be referred to the accrediting authority if such complaints cannot be resolved directly with the customer.

MICROBAC

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

SAMPLE SUMMARY

Sample ID	Laboratory ID	Matrix	Type	Date Sampled	Date Received
Site # 8 Sector K (001)	17I0391-01	Stormwater	Grab	10/09/2017 05:30	10/09/2017 08:37
Site #8 Sector N (001)	17I0391-02	Stormwater	Grab	10/09/2017 05:30	10/09/2017 08:37
Site #8 Sector K (002)	17I0391-03	Stormwater	Grab	10/09/2017 05:00	10/09/2017 08:37
Site #8 Sector N (002)	17I0391-04	Stormwater	Grab	10/09/2017 05:00	10/09/2017 08:37

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC®

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 1710391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Site # 8 Sector K (001)

1710391-01 (Stormwater) Sampled: 10/09/2017 05:30; Type: Grab

Analyte	Result	Reporting Limit	Units	Limits	Prepared	Analyzed	Analyst	Method	Notes
Microbac Laboratories, Inc. - Baltimore									
Wet Chemistry									
Ammonia as N	ND	1.0	mg/L		101117 1445	101117 1630	ANC	SM 4500-NH3 B+C-11	
COD, Total	ND	50	mg/L		101217 0900	101217 1342	LCR	EPA 410.4	
Cyanide, Total	ND	0.0050	mg/L		101117 1025	101117 1442	SRZ	EPA 335.4	
Metals, Total by EPA 200 Series Methods									
Antimony	**0.046**	0.040	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Arsenic	**0.040**	0.020	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Cadmium	ND	0.010	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Calcium	**2.8**	0.20	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Hardness (as CaCO3)	**8.1**	1.3	mg/L		101117 1516	101217 1656	APS	SM 2340 B-11	
Lead	ND	0.020	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Magnesium	**0.25**	0.20	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Selenium	ND	0.040	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Silver	ND	0.0040	mg/L		101117 1516	101217 1656	APS	EPA 200.7	
Microbac Laboratories, Inc. - Chicagoland									
Metals									
Mercury	ND	0.00020	mg/L		101217 1103	101217 1349	BTM	EPA 245.1 Rev 3.0	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 1710391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Site #8 Sector N (001)

17I0391-02 (Stormwater) Sampled: 10/09/2017 05:30; Type: Grab

Analyte	Result	Reporting Limit	Units	Limits	Prepared	Analyzed	Analyst	Method	Notes
Microbac Laboratories, Inc. - Baltimore									
Wet Chemistry									
COD, Total	**89**	50	mg/L		101217 0900	101217 1342	LCR	EPA 410.4	
Total Suspended Solids	**26**	1.3	mg/L		101117 1300	101217 1415	LCR	SM 2540 D-11	
Metals, Total by EPA 200 Series Methods									
Aluminum	ND	0.10	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Calcium	**2.7**	0.20	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Copper	ND	0.020	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Hardness (as CaCO3)	**7.7**	1.3	mg/L		101117 1516	101217 1707	APS	SM 2340 B-11	
Iron	**0.20**	0.020	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Lead	ND	0.020	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Magnesium	**0.22**	0.20	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Selenium	ND	0.040	mg/L		101117 1516	101217 1707	APS	EPA 200.7	
Zinc	**0.039**	0.020	mg/L		101117 1516	101217 1707	APS	EPA 200.7	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC®

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Site #8 Sector K (002)

17I0391-03 (Stormwater) Sampled: 10/09/2017 05:00; Type: Grab

Analyte	Result	Reporting Limit	Units	Limits	Prepared	Analyzed	Analyst	Method	Notes
Microbac Laboratories, Inc. - Baltimore									
Wet Chemistry									
Ammonia as N	**28**	2.0	mg/L		101117 1445	101117 1630	ANC	SM 4500-NH3 B+C-11	
COD, Total	**37000**	2500	mg/L		101217 0900	101217 1342	LCR	EPA 410.4	
Cyanide, Total	**0.060**	0.0050	mg/L		101117 1025	101117 1444	SRZ	EPA 335.4	
Metals, Total by EPA 200 Series Methods									
Antimony	ND	0.20	mg/L		101117 1516	101217 1718	APS	EPA 200.7	
Arsenic	ND	0.10	mg/L		101117 1516	101217 1718	APS	EPA 200.7	
Cadmium	ND	0.050	mg/L		101117 1516	101217 1718	APS	EPA 200.7	
Calcium	**1400**	5.0	mg/L		101117 1516	101217 1729	APS	EPA 200.7	
Hardness (as CaCO3)	**4000**	33	mg/L		101117 1516	101217 1729	APS	SM 2340 B-11	
Lead	**1.4**	0.50	mg/L		101117 1516	101217 1729	APS	EPA 200.7	
Magnesium	**140**	5.0	mg/L		101117 1516	101217 1729	APS	EPA 200.7	
Selenium	ND	0.20	mg/L		101117 1516	101217 1718	APS	EPA 200.7	
Silver	ND	0.020	mg/L		101117 1516	101217 1718	APS	EPA 200.7	
Microbac Laboratories, Inc. - Chicagoland									
Metals									
Mercury	**0.00046**	0.00020	mg/L		101217 1103	101217 1351	BTM	EPA 245.1 Rev 3.0	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC®

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Site #8 Sector N (002)

17I0391-04 (Stormwater) Sampled: 10/09/2017 05:00; Type: Grab

Analyte	Result	Reporting Limit	Units	Limits	Prepared	Analyzed	Analyst	Method	Notes
Microbac Laboratories, Inc. - Baltimore									
Wet Chemistry									
COD, Total	**37000**	2500	mg/L		101217 0900	101217 1342	LCR	EPA 410.4	
Total Suspended Solids	**1200**	67	mg/L		101117 1300	101217 1415	LCR	SM 2540 D-11	
Metals, Total by EPA 200 Series Methods									
Aluminum	**11**	2.5	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Calcium	**1500**	5.0	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Copper	**2.3**	0.50	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Hardness (as CaCO3)	**4300**	33	mg/L		101117 1516	101217 1732	APS	SM 2340 B-11	
Iron	**180**	0.50	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Lead	**1.5**	0.50	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Magnesium	**160**	5.0	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Selenium	ND	1.0	mg/L		101117 1516	101217 1732	APS	EPA 200.7	
Zinc	**16**	0.50	mg/L		101117 1516	101217 1732	APS	EPA 200.7	

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC®

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Project Requested Certification(s):

Florida - NELAC

Analyte Certification Exception Summary

No certification exceptions

All analysis performed were analyzed under the required certification unless otherwise noted in the above summary.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Certification List

Below is a list of certifications maintained by Microbac Laboratories, Inc. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. A complete list of individual analytes pursuant to each certification below is available upon request.

Code	Description	Certification Number	Expires
Microbac Laboratories, Inc. - Baltimore			
A2LA1	A2LA (Biology)	410.02	04/30/2019
A2LA2	A2LA (Environmental)	410.01	04/30/2019
VA-B	Commonwealth of Virginia (NELAC) - Baltimore	460285	03/14/2018
CPSC	CPSC Testing of Childrens Products and Jewelry	410.01	04/30/2019
Pb	Environmental Lead (ELLAP)	410.01	04/30/2019
FL	Florida - NELAC	E871126	06/30/2018
MD	State of Maryland (Drinking Water)	109	06/30/2018
WV	West Virginia	054	08/31/2018
Microbac Laboratories, Inc. - Chicagoland			
A2LA-B	A2LA (Biology)	3045.01	09/30/2018
A2LA-C	A2LA (Chemistry)	3045.02	09/30/2018
A2LA_	A2LA ISO/IEC 17025 Biological Testing (a)	3045.01	09/30/2018
A2LA	A2LA ISO/IEC 17025 Env. DoD Testing (b)	3045.02	09/30/2018
CDC-ELITE	Center of Disease Control Legionella ELITE Membership (c)		12/01/2017
ILDPH	Illinois DOPH Micro analysis of drinking water (e)	1755266	12/31/2019
ILEPA	Illinois EPA drinking water, wastewater and solid waste analy	200064	05/31/2018
INSDH	Indiana SDH chemical analysis of drinking water (g)	C-45-03	12/31/2019
INDH	Indiana SDH Micro analysis of drinking water (f)	M-45-8	12/31/2019
ISBOAH	Indiana State Board of Animal Health for microbiological anal	18137	03/31/2019
KSDOH	Kansas Dept Health & Env. NELAP (i)	E-10397	01/31/2018
KYEPP	Kentucky EPPC analysis Underground Storage Tanks (k)	75	01/31/2018
KYDEP	Kentucky Wastewater Laboratory Certification Program (j)	90147	12/31/2017
NYDOH	New York State Department of Health Wadsworth (m)	12006	04/01/2018
NCDEN	North Carolina DENR NPDES effluent, surface water (l)	597	12/31/2017
PADEP	Pennsylvania Department of Environmental Protect (n)	68-04863	07/31/2018
USDAS	USDA Permit To Receive Soil (-)	P330-13-00270	10/17/2019
CGL-VA	VA NELAP	460280	06/14/2018
VELAP	Virginia Department of General Services Division of Consolid	7990	06/15/2018

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Microbac Laboratories, Inc. - Richmond

VA-R	Commonwealth of Virginia (NELAC) - Richmond	460022	06/14/2018

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

Michael M. Gallion, Project Manager

Original Report

MICROBAC®

Microbac Laboratories, Inc.
Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

CERTIFICATE OF ANALYSIS

Apex Companies, LLC	Project: DC DPW - Site #8	Report: 17I0391
8854 Rixlew Lane	Project Number: Stormwater	Reported: 10/18/2017 16:05
Manassas, VA 20109	Project Manager: Andrea Owen Heller	

Qualifiers/Notes and Definitions

General Definitions:

DET	Analyte DETECTED
ND	Analyte NOT DETECTED at or above the reporting limit
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference

Sample/Sample Receipt Qualifiers and Notes:

Microbac Laboratories, Inc. - Baltimore

17I0391-04	Sample preserved with Sulfuric Acid to pH <2 upon receipt.
17I0391-04	Aliquot of sample preserved with Nitric Acid to pH <2 upon receipt.
17I0391-03	Sample preserved with Sulfuric Acid to pH <2 upon receipt.
17I0391-03	Aliquot of sample preserved with Nitric Acid to pH <2 upon receipt.

MICROBAC®

Microbac Laboratories, Inc.

Baltimore Division

2101 Van Deman Street • Baltimore, MD 21224

Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

Cooler Receipt Log

Cooler ID: Default Cooler **Cooler Temp:** 6.90°C **Work Order:** 17I0391

Custody Seals Intact:	Yes	COC/Containers Agree:	Yes
Containers Intact:	Yes	Correct Preservation:	Yes
Received On Ice:	Yes	Correct Number of Containers Received:	Yes
Radiation Scan Acceptable:	Yes	Sufficient Sample Volume for Testing:	Yes
COC Present:	Yes	Samples Received in Proper Condition:	Yes

Comments:

MICROBAC
Microbac Laboratories, Inc., Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224
Phone: 410-633-1800
Fax: 410-633-655
www.microbac.com

17I0391

Tentatively Scheduled Date 9/7/2017

Client: **Apex Companies, LLC**
Project: **DC DPW - Site #8**
Project Number: **Stormwater**

Report To:
Andrea Owen Heller
8854 Rixlew Lane
Manassas, VA 20109
Phone: (703) 396-6730

Invoice To:
Andrea Owen Heller
8854 Rixlew Lane
Manassas, VA 20109
Phone :(703) 396-6730

TAT 7 days

Sample ID: Site # 8 Sector K (001)

Lab Sample ID: 17I0391-01
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 0530

Analysis			Hold
Hg_Total	EPA 245.1		28
M_Ag_ICP	EPA 200.7		180
M_As_ICP	EPA 200.7		180
M_Cd_ICP	EPA 200.7		180
M_Mg_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Sb_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
NH3_Titration	SM 4500-NH3 B+C-11		28
		B-1000ml Plastic H2SO4 to pH <2	
TP_Total_Seal	EPA 335.4		14
		P- 250ml Plastic Absorbic then NaOH to pH >12	
		Total Containers: 3	

Sample ID: Site #8 Sector N (001)

Lab Sample ID: 17I0391-02
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 0530

Analysis			Hold
M_Al_ICP	EPA 200.7		180
M_Cu_ICP	EPA 200.7		180
M_Fe_ICP	EPA 200.7		180
M_Mn_ICP	EPA 200.7		180
M_Zn_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
		B-1000ml Plastic H2SO4 to pH <2	
TSS	SM 2540 D-11		7
		B-1000ml Plastic Neat	
		Total Containers: 3	

Sample ID: Site #8 Sector K (002)

Lab Sample ID: 17I0391-03
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 05:00

Analysis	Hold

MICROBAC
Microbac Laboratories, Inc., Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224
Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

17I0391

Client: **Apex Companies, LLC**
Project: **DC DPW - Site #8**
Project Number: **Stormwater**

Tentatively Scheduled Date 9/7/2017

Hg_Total	EPA 245.1		28
M_Ag_ICP	EPA 200.7		180
M_As_ICP	EPA 200.7		180
M_Cd_ICP	EPA 200.7		180
M_Mg_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Sb_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
NH3_Titration	SM 4500-NH3 B+C-11		28
		B-1000ml Plastic H2SO4 to pH <2	
CN_Total_Seal	EPA 335.4		14
		P- 250ml Plastic Absorbic then NaOH to pH >12	
		Total Containers:	3

Sample ID: Site #8 Sector N (002)

Lab Sample ID: **17I0391-04**
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 0500

Analysis			Hold
M_Al_ICP	EPA 200.7		180
M_Cu_ICP	EPA 200.7		180
M_Fe_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Zn_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
		B-1000ml Plastic H2SO4 to pH <2	
TSS	SM 2540 D-11		7
		B-1000ml Plastic Neat	
		Total Containers:	3

Sampled by: WTWinn	Date/Time: 10/9 2:37	Received by:
Printed Name: Tyler Warren		Printed Name
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:

As Received at Laboratory: On Ice: (Yes) No Cooler Temp 10.9°C Total Bottles 12

Notes:

please analyze for hardness and total selenium

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: 1
Client: Apex
Form Completed By: [illegible]
Shipper: [illegible]

Receipt Date / Time: 10/09/17 0832
Work Order # 17I0391

☐ Microbac ☒ Client ☐ UPS ☐ FedEx
Custody Tape Intact: (YES) / NO / NA
Containers Intact: (YES) / NO
Sample Received on Ice or refrigerated: (YES) / NO / NA
Infrared (IR) Temperature: 6.9 °C

Chain of Custody Present with shipment: (YES) / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / NA
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity:

A - ___	Unpreserved ___	H_2SO_4 4	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid:	If preserved pH <2 ~~NA~~, pH >10 ___
B - 2	Unpreserved 4	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ~~NA~~, pH >10 ___
C - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
D - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
E - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
H - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
K - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
L - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
M - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
P - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH 2	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ~~NA~~ adj
W - ___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
V - ___	Unpreserved ___	HCl ___	HCl / Ascorbic Acid ___	HCl / NaTHIO **(Checked at time of Analysis)**			
F - ___	Unpreserved ___	NaTHIO **(Checked at time of Analysis)**					
S - ___	Unpreserved ___	NaTHIO **(Checked at time of Analysis)**					
SN - ___	Unpreserved ___	NaTHIO ___	NaTHIO/EDTA **(Checked at time of Analysis)**				
___	Unpreserved ___	H_2SO_4 ___	HNO_2 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___
___	Unpreserved ___	H_2SO_4 ___	HNO_3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___

Describe preservation requirements not met:

All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*

Sample ID: 17I0391 - 03/04[A] H_2SO_4 HNO_3 NaOH 5 mls added to adjust pH, pH must < 2 for each sample
Sample ID: ___ H_2SO_4 HNO_3 NaOH ___ mls added
Sample ID: 17I0391 - 02[B]/04[B] H_2SO_4 HNO_3 NaOH 5 mls added to each bottle to adjust pH, pH must < 2.
Sample ID: ___ H_2SO_4 HNO_3 NaOH ___ mls added

H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

CH Na 10/09/17 0900

Describe Anomalies:
Metals bottles for samples - 01 & -03 split for Hg subout. 10/09/17

Contact information / Summary of Actions:
Date / Time: ___ Contact: ___ Contact By: ___
Comments: ___

Microbac Laboratories, Inc. - Baltimore

MICROBAC

17J0554 Dave Bryant
Microbac - BLT
17I0391
10/10/2017

SUBCONTRACT ORDER
17I0391

SENDING LABORATORY:

Microbac Laboratories, Inc. - Baltimore
2101 Van Deman Street
Baltimore, MD 21224
Phone: 410.633.1800
Project Manager: Michael M. Gallion

RECEIVING LABORATORY:

Microbac - CGL
250 West 84th Drive
Merrillville, IN 46410
Phone: (219) 769-8378

17J0554

Project Info:

Project Name: DC DPW - Site #8
Project No: Stormwater

Client: Apex Companies, LLC
Project Type: ENV-WasteWater
Project Location: Maryland (South)

Report TAT: 7
Due: ~~09/18/2017 17:00~~ 10/04/17 10:00

Sample ID: 17I0391-01 **Matrix: Stormwater** **Sampled: 09/07/2017 00:00**

-01

Analysis	Method	Analysis Due	Expires
Hg_Total Mercury	**EPA 245.1** 0.0002 mg/L	**09/18/2017 16:00**	**10/05/2017 00:00**

Sample ID: 17I0391-03 **Matrix: Stormwater** **Sampled: 09/07/2017 00:00**

-02

Analysis	Method	Analysis Due	Expires
Hg_Total Mercury	**EPA 245.1** 0.0002 mg/L	**09/18/2017 16:00**	**10/05/2017 00:00**

300
300

1.5
01 0.5
1.0 °C

Released By	Date	Received By	Date
[signature]	10/09/17	[signature]	
[signature]		[signature]	10-10-17/0900

Fedex

MICROBAC
Microbac Laboratories, Inc., Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224
Phone: 410-633-1800
Fax: 410-633-6554
www.microbac.com

17I0391

Tentatively Scheduled Date: 9/7/2017

Client: **Apex Companies, LLC**
Project: **DC DPW - Site #8**
Project Number: **Stormwater**

Report To:
Andrea Owen Heller
8854 Rixlew Lane
Manassas, VA 20109
Phone: (703) 396-6730

Invoice To:
Andrea Owen Heller
8854 Rixlew Lane
Manassas, VA 20109
Phone :(703) 396-6730

TAT 7 days

Sample ID: Site # 8 Sector K (001)

Lab Sample ID: 17I0391-01
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 0530

Analysis			Hold
Hg_Total	EPA 245.1		28
M_Ag_ICP	EPA 200.7		180
M_As_ICP	EPA 200.7		180
M_Cd_ICP	EPA 200.7		180
M_Mg_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Sb_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
NH3_Titration	SM 4500-NH3 B+C-11		28
		B-1000ml Plastic H2SO4 to pH <2	
TP_Total_Seal	EPA 335.4		14
		P- 250ml Plastic Absorbic then NaOH to pH >12	
		Total Containers: 3	

Sample ID: Site #8 Sector N (001)

Lab Sample ID: 17I0391-02
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 0530

Analysis			Hold
M_Al_ICP	EPA 200.7		180
M_Cu_ICP	EPA 200.7		180
M_Fe_ICP	EPA 200.7		180
M_Mn_ICP	EPA 200.7		180
M_Zn_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
		B-1000ml Plastic H2SO4 to pH <2	
TSS	SM 2540 D-11		7
		B-1000ml Plastic Neat	
		Total Containers: 3	

Sample ID: Site #8 Sector K (002)

Lab Sample ID: 17I0391-03
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/4 05:00

Analysis	Hold

MICROBAC
Microbac Laboratories, Inc., Baltimore Division
2101 Van Deman Street • Baltimore, MD 21224
Phone: 410-633-1800
Fax: 410-633-6553
www.microbac.com

17I0391

Client: **Apex Companies, LLC**
Project: **DC DPW - Site #8**
Project Number: **Stormwater**

Tentatively Scheduled Date 9/7/2017

Hg_Total	EPA 245.1		28
M_Ag_ICP	EPA 200.7		180
M_As_ICP	EPA 200.7		180
M_Cd_ICP	EPA 200.7		180
M_Mg_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Sb_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
NH3_Titration	SM 4500-NH3 B-C-11		28
		B-1000ml Plastic H2SO4 to pH <2	
CR_Total_Seal	EPA 335.4		14
		P- 250ml Plastic Absorbic then NaOH to pH >12	
		Total Containers: 3	

Sample ID: Site #8 Sector N (002)

Lab Sample ID: **17I0391-04**
Matrix: Stormwater
Type: Grab
Sampled Date & Time: 10/9 0500

Analysis	TAT		Hold
M_Al_ICP	EPA 200.7		180
M_Cu_ICP	EPA 200.7		180
M_Fe_ICP	EPA 200.7		180
M_Pb_ICP	EPA 200.7		180
M_Zn_ICP	EPA 200.7		180
		A- 500ml Plastic HNO3 to pH <2	
COD_Total_HL	EPA 410.4		28
		B-1000ml Plastic H2SO4 to pH <2	
TSS	SM 2540 D-11		7
		B-1000ml Plastic Neat	
		Total Containers: 3	

Sampled by: W Winn	Date/Time: 10/9 2137	Received by:
Printed Name: Tyler Warren		Printed Name:
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:

As Received at Laboratory: On Ice: (Yes) No Cooler Temp 6.9°C Total Bottles 12

Notes:

please analyze for hardness and total selenium

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: 1
Client: Apex
Form Completed By: [illegible]
Shipper: [illegible]

Receipt Date / Time: 10/04/17 0837
Work Order # 17I0391

☐ Microbac ☒ Client ☐ UPS ☐ FedEx
Custody Tape Intact: (YES) / NO / NA
Containers Intact: (YES) / NO
Sample Received on Ice or refrigerated: (YES) / NO / NA
Infrared (IR) Temperature: 6.9 °C

Chain of Custody Present with shipment: (YES) / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / NA
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity:

A - ___ Unpreserved ___ H2SO4 4 HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid: If preserved pH <2 ok, pH >10___
B - 2 Unpreserved 4 H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2 ok, pH >10___
C - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
D - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
E - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
H - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
K - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
L - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
M- ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
P - ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH 2 NaOH/Ascorbic Acid If preserved pH <2___, pH >10 ok
W- ___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN- ___ Unpreserved ___ NaTHIO ___ NaTHIO/EDTA **(Checked at time of Analysis)**

___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
___ Unpreserved ___ H2SO4 ___ HNO3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___

Describe preservation requirements not met:

All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*

Sample ID: 17I0391-03/04[B] (H2SO4) HNO3 NaOH 5 mls added to adjust pH, pH now < 2 after each sample
Sample ID: ___ H2SO4 HNO3 NaOH ___ mls added
Sample ID: 17I0391-03[C]/04[B] H2SO4 (HNO3) NaOH 5 mls added to each bottle to adjust pH, pH now < 2
Sample ID: ___ H2SO4 HNO3 NaOH ___ mls added

H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

10/04/17 0900

Describe Anomalies:
Metals bottles for samples -01 & -03 split for Hg subcont. 10/04/17

Contact information / Summary of Actions:
Date / Time: ___ Contact: ___ Contact By: ___
Comments: ___

Microbac Laboratories, Inc. - Baltimore

MICROBAC

17J0554 Dave Bryant
Microbac - BLT
17I0391
10/10/2017

SUBCONTRACT ORDER
17I0391

SENDING LABORATORY:

Microbac Laboratories, Inc. - Baltimore
2101 Van Deman Street
Baltimore, MD 21224
Phone: 410.633.1800
Project Manager: Michael M. Gallion

RECEIVING LABORATORY:

Microbac - CGL
250 West 84th Drive
Merrillville, IN 46410
Phone: (219) 769-8378

17J0554

Project Info:

Project Name: DC DPW - Site #8
Project No: Stormwater

Client: Apex Companies, LLC
Project Type: ENV-WasteWater
Project Location: Maryland (South)

Report TAT: 7
Due: 09/18/2017 17:00
10 Emw 10/04/17

Sample ID: 17I0391-01 **Matrix: Stormwater** **Sampled: 09/07/2017 00:00**

-01

Analysis	Method	Analysis Due	Expires
Hg_Total	**EPA 245.1**	**09/18/2017 16:00**	**10/05/2017 00:00**
Mercury	0.0002 mg/L		

Sample ID: 17I0391-03 **Matrix: Stormwater** **Sampled: 09/07/2017 00:00**

-02

Analysis	Method	Analysis Due	Expires
Hg_Total	**EPA 245.1**	**09/18/2017 16:00**	**10/05/2017 00:00**
Mercury	0.0002 mg/L		

300
300

1.5
01 0.5
1.0 e

Released By	Date	Received By	Date
[signature]	10/09/17	[signature]	
Released By	Date	Received By	Date
		[signature]	10-1017/0900

Fedex

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
Appendix H - 3200 Benning Rd, NE

NPDES Tracking No.
DC0000221

Outfall Name/Number
001

"Substantially Identical Outfall"?
No

Substitute Sample?
Yes

Person(s)/Title(s) Collecting Sample
Tyler Warren

Amount (inches)
0.56

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)
792 Hours

Current Rainfall Event

Start Time of Discharge:
04:55 AM

Substitute Sample?
Yes

Time Sample Collected (must be within one-hour of start of discharge, or explain)
05:30 AM

Time Sample Examined (must be within 30 minutes after sample collected, or explain)
05:40 AM

Comments
Water was clear, no signs of solids.

Nature of Discharge
Rainfall

Previous Storm Ended >72 hours Before Start of Storm?
Yes

Parameter

Color
None

Odor
None

Clarity
Clear

Floating Solids
No

Settled Solids
No

Suspended Solids
No

Foam (gently shake sample)
No

Oil Sheen
None

Other Obvious Indicators of Stormwater Pollution
No

Detail any concerns, additional comments, and any corrective actions taken below
Water at outfall was clear and free of odor or any signs of pollution.


NPDES Quarterly Visual Assessment Form

Photos

Photo Number	Photo Description	Photo
1	Water flowing out of outfall 001	

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:

Name	Signature	Date Signed
Tyler Warren		10/09/2017

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
Title		

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
Appendix H - 3200 Benning Rd, NE

NPDES Tracking No.
DC0000221

Outfall Name/Number
002

"Substantially Identical Outfall"?
No

Substitute Sample?
Yes

Person(s)/Title(s) Collecting Sample
Tyler Warren

Amount (inches)
0.56

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)
792 Hours

Current Rainfall Event

Start Time of Discharge:
04:55 AM

Substitute Sample?
Yes

Time Sample Collected (must be within one-hour of start of discharge, or explain)
05:00 AM

Time Sample Examined (must be within 30 minutes after sample collected, or explain)
05:14 AM

Comments
Water was a dark color. Not transparent.

Nature of Discharge
Rainfall

Previous Storm Ended >72 hours Before Start of Storm?
Yes

Parameter

Color
Other

If Other, describe:
Dark grey color.

Odor
Musty

Clarity
Cloudy

Floating Solids
No

Settled Solids
No

Suspended Solids
No

Foam (gently shake sample)
No

Oil Sheen
None

Other Obvious Indicators of Stormwater Pollution
No

Detail any concerns, additional comments, and any corrective actions taken below


NPDES Quarterly Visual Assessment Form

Photos

Photo Number	Photo Description	Photo
1	Flow at outfall 002 where sample was collected	

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:

Name	Signature	Date Signed
Tyler Warren		10/09/2017

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
Title		

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
Appendix H
NPDES Tracking No.
DC0000221
Outfall Name/Number
002B
"Substantially Identical Outfall"?
No
Substitute Sample?
No
Person(s)/Title(s) Collecting Sample
Andrew Hughey
Amount (inches)
0.15

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)
>72 hrs
Current Rainfall Event
Start Time of Discharge:
01:30 PM
Current Rainfall Amount (inches)
0.15
Substitute Sample?
No
Time Sample Collected (must be within one-hour of start of discharge, or explain)
04:50 PM
Time Sample Examined (must be within 30 minutes after sample collected, or explain)
04:56 PM

Comments
First discharge occurred during quick downpour while I was sampling other sites. Flow had stopped by the time I arrived, so I had to wait for more rain.
Nature of Discharge
Rainfall
If Rainfall, amount (inches)
.15
Previous Storm Ended >72 hours Before Start of Storm?
Yes


Parameter

Color
Other
If Other, describe:
Black
Odor
Sour
Other
Clarity
Opaque
Floating Solids
No
Settled Solids
No

Suspended Solids
No
Foam (gently shake sample)
No
Oil Sheen
None
Other Obvious Indicators of Stormwater Pollution
No
Detail any concerns, additional comments, and any corrective actions taken below
Pollution is due to nearby trash source. Inside outfall drop inlet, a significant amount of sludge from trash runoff has collected.

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:


Name	Signature	Date Signed
Andrew Hughey		09/17/2018

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
	09/17/2018	

Title



APEX
8854 RIXLEW LANE
MANASSAS, VA 20109
TELEPHONE: (703) 396-6730
FAX: (703) 396-6743

Appendix H
3200 Benning Road NE,
Washington, DC 21002
Benning Road
SWMA Waste/Recycling Facility

0 25 50 100 150 200 Feet

Coordinate System: Lambert Conformal Conic
Central Meridian: 77°0'0"W
1st Std Parallel: 38°18'0"N
2nd Std Parallel: 39°27'0"N
Latitude of Origin: 37°40'0"N

N

Department of Public Works
Washington, DC SWP3 2010
Appendix Update: 7/1/2014
2010 USGS Orthoimage
.16 Meter Resolution

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18H0647

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DC DPW - Site #8

Project / PO Number: N/A
Received: 09/19/2018
Reported: 09/28/2018

Analytical Testing Parameters

Client Sample ID:	Site # 8 Sector K (001)		
Sample Matrix:	Stormwater	**Collected By:**	Customer
Lab Sample ID:	18H0647-01	**Collection Date:**	09/17/2018 17:00

Wet Chemistry	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4								
Cyanide, Total	<0.0050		0.0050	mg/L		09/24/18 1107	09/24/18 1300	SRZ
Method: EPA 410.4								
COD, Total	<50		50	mg/L		09/27/18 0830	09/27/18 1145	LCR
Method: SM 4500-NH3 B+C-11								
Ammonia as N	1.1		1.0	mg/L		09/24/18 1613	09/24/18 1630	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1								
Mercury	<0.00020		0.00020	mg/L		09/27/18 1000	09/27/18 1416	APS

Metals, Total by EPA 200 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7								
Antimony	0.13		0.040	mg/L		09/20/18 1128	09/24/18 1644	APS
Arsenic	0.022		0.020	mg/L		09/20/18 1128	09/24/18 1644	APS
Cadmium	<0.010		0.010	mg/L		09/20/18 1128	09/24/18 1644	APS
Calcium	1.6		0.20	mg/L		09/20/18 1128	09/24/18 1644	APS
Lead	<0.020		0.020	mg/L		09/20/18 1128	09/24/18 1644	APS
Magnesium	0.32		0.20	mg/L		09/20/18 1128	09/24/18 1644	APS
Selenium	<0.040		0.040	mg/L		09/20/18 1128	09/24/18 1644	APS
Silver	<0.0040		0.0040	mg/L		09/20/18 1128	09/24/18 1644	APS
Method: SM 2340 B-11								
Hardness (as CaCO3)	5.3		1.3	mg/L		09/20/18 1128	09/24/18 1644	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18H0647

Client Sample ID:	Site #8 Sector N (001)		
Sample Matrix:	Stormwater	**Collected By:**	Customer
Lab Sample ID:	18H0647-02	**Collection Date:**	09/17/2018 17:00

Wet Chemistry	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4								
COD, Total	<50		50	mg/L		09/27/18 0830	09/27/18 1145	LCR
Method: SM 2540 D-11								
Total Suspended Solids	2.6		2.0	mg/L		09/20/18 0730	09/21/18 1500	LCR

Metals, Total by EPA 200 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7								
Aluminum	<0.10		0.10	mg/L		09/20/18 1128	09/24/18 1654	APS
Calcium	1.6		0.20	mg/L		09/20/18 1128	09/24/18 1654	APS
Copper	<0.020		0.020	mg/L		09/20/18 1128	09/24/18 1654	APS
Iron	0.033		0.020	mg/L		09/20/18 1128	09/24/18 1654	APS
Lead	<0.020		0.020	mg/L		09/20/18 1128	09/24/18 1654	APS
Magnesium	0.32		0.20	mg/L		09/20/18 1128	09/24/18 1654	APS
Zinc	0.026		0.020	mg/L		09/20/18 1128	09/24/18 1654	APS
Method: SM 2340 B-11								
Hardness (as CaCO3)	5.2		1.3	mg/L		09/20/18 1128	09/24/18 1654	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18H0647

Client Sample ID:	Site #8 Sector K (002)		
Sample Matrix:	Stormwater	**Collected By:**	Customer
Lab Sample ID:	18H0647-03	**Collection Date:**	09/17/2018 16:50

Wet Chemistry	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4								
Cyanide, Total	0.046		0.0050	mg/L		09/25/18 0836	09/25/18 1152	SRZ
Method: EPA 410.4								
COD, Total	12000		500	mg/L		09/27/18 0830	09/27/18 1145	LCR
Method: SM 4500-NH3 B+C-11								
Ammonia as N	<1.0		1.0	mg/L		09/24/18 1613	09/24/18 1630	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1								
Mercury	0.00045		0.00020	mg/L		09/27/18 1000	09/27/18 1418	APS

Metals, Total by EPA 200 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7								
Antimony	<0.20		0.20	mg/L		09/20/18 1128	09/24/18 1705	APS
Arsenic	<0.10		0.10	mg/L		09/20/18 1128	09/24/18 1705	APS
Cadmium	<0.050		0.050	mg/L		09/20/18 1128	09/24/18 1705	APS
Calcium	900		5.0	mg/L		09/20/18 1128	09/24/18 1748	APS
Lead	0.28		0.10	mg/L		09/20/18 1128	09/24/18 1705	APS
Magnesium	50		5.0	mg/L		09/20/18 1128	09/24/18 1748	APS
Selenium	<0.20		0.20	mg/L		09/20/18 1128	09/24/18 1705	APS
Silver	<0.020		0.020	mg/L		09/20/18 1128	09/24/18 1705	APS
Method: SM 2340 B-11								
Hardness (as CaCO3)	2500		33	mg/L		09/20/18 1128	09/24/18 1748	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18H0647

Client Sample ID:	Site #8 Sector N (002)		
Sample Matrix:	Stormwater	**Collected By:**	Customer
Lab Sample ID:	18H0647-04	**Collection Date:**	09/17/2018 16:50

Wet Chemistry	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4								
COD, Total	16000		1200	mg/L		09/27/18 0830	09/27/18 1145	LCR
Method: SM 2540 D-11								
Total Suspended Solids	5000		200	mg/L		09/20/18 0730	09/21/18 1500	LCR

Metals, Total by EPA 200 Series Methods	Result	Limit(s)	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7								
Aluminum	9.1		0.50	mg/L		09/20/18 1128	09/24/18 1709	APS
Calcium	880		5.0	mg/L		09/20/18 1128	09/24/18 1752	APS
Copper	0.43		0.10	mg/L		09/20/18 1128	09/24/18 1709	APS
Iron	48		0.50	mg/L		09/20/18 1128	09/24/18 1752	APS
Lead	0.29		0.10	mg/L		09/20/18 1128	09/24/18 1709	APS
Magnesium	49		5.0	mg/L		09/20/18 1128	09/24/18 1752	APS
Zinc	7.8		0.10	mg/L		09/20/18 1128	09/24/18 1709	APS
Method: SM 2340 B-11								
Hardness (as CaCO3)	2400		33	mg/L		09/20/18 1128	09/24/18 1752	APS

*Results in **bold** have exceeded a limit defined for this project. Limits are provided for reference but as regulatory limits change frequently, Microbac Laboratories, Inc. advises the recipient of this report to confirm such limits and units of concentration with the appropriate Federal, state or local authorities before acting on the data.*

Definitions

RL: Reporting Limit

Project Requested Certification(s)

Microbac Laboratories, Inc. - Baltimore
E871126 Florida - NELAC

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Isang Isang
Client Relations
Reported: 09/28/2018 10:30

MICROBAC®

www.microbac.com

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

18H0647

TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Reviewed By: II
Date: 9/20/18

Project Name: DC DPW - Site #8

Project / PO Number: N/A
Tenatively Scheduled: 8/8/2018
Field Route ID: Customer Prelogs - Baltimore

Client Sample ID: Site # 8 Sector K (001)
Lab Sample ID: 18H0647-01
Matrix: Stormwater
Type: Grab

Sampled Date & Time: 9/17/18 1700

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
P- 250ml Plastic Absorbic then NaOH to pH >12	A
B-1000ml Plastic H2SO4 to pH <2	B
A- 500ml Plastic HNO3 to pH <2	C

Client Sample ID: Site #8 Sector N (001)
Lab Sample ID: 18H0647-02
Matrix: Stormwater
Type: Grab

Sampled Date & Time: 9/17/18 1700

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days
TSS	SM 2540 D-11		7.00 days

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

18H0647

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DC DPW - Site #8

Project / PO Number: N/A
Tenatively Scheduled: 8/8/2018
Field Route ID: Customer Prelogs - Baltimore

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
B-1000ml Plastic Neat	C

Client Sample ID: Site #8 Sector K (002)
Lab Sample ID: 18H0647-03
Matrix: Stormwater
Type: Grab

Sampled Date & Time: 9/17/18 1650

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
P- 250ml Plastic Absorbic then NaOH to pH >12	A
B-1000ml Plastic H2SO4 to pH <2	B
A- 500ml Plastic HNO3 to pH <2	C

Client Sample ID: Site #8 Sector N (002)
Lab Sample ID: 18H0647-04
Matrix: Stormwater
Type: Grab

Sampled Date & Time: 9/17/18 1650

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days

MICROBAC®

www.microbac.com

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

18H0647

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DC DPW - Site #8

Project / PO Number: N/A
Tenatively Scheduled: 8/8/2018
Field Route ID: Customer Prelogs - Baltimore

TSS	SM 2540 D-11	7.00 days

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
B-1000ml Plastic Neat	C

Sampled/Relinquished by:		Date/Time: 9/18/18 1651	Received by:
Printed Name:			Printed Name:
Relinquished by:		Date/Time: 9/19/18 11:23	Received by:
Printed Name:			Printed Name:
Relinquished by:		Date/Time: 9/19/18 14:25	Received by:
Printed Name:			Printed Name:

As Received at Laboratory: On Ice: (Yes) / No Temp 2.3 °C Total Bottles: 12

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

Cooler Receipt Form / Sample Acceptance & Noncompliance Form	Microbac Laboratories, Inc., Baltimore Division Control # 606-03 Effective Date: 11/30/2016 Page 1 of 1

Number of Coolers Received: 1
Client: Apex
Form Completed By: Tiffany Bock

Receipt Date / Time: 9/19/18 / 14:25
Work Order #

Shipper: ☐ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact: YES / NO / NA
Containers Intact: YES / NO
Sample Received on Ice or refrigerated: YES / NO / NA
Infrared (IR) Temperature: 2.3 °C

Chain of Custody Present with shipment: YES / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / NA
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity: 9 11 TRB 9/19/18

A - ___	Unpreserved	___ H2SO4	9 HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid:	If preserved pH <2 ___, pH >10 ___	
B - 7	Unpreserved	8 H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
C - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
D - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
E - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
H - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
K - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
L - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
M - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
P - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	4 NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
W - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
V - ___	Unpreserved	___ HCl	___ HCl / Ascorbic Acid	___ HCl / NaTHIO **(Checked at time of Analysis)**				
F - ___	Unpreserved	___ NaTHIO **(Checked at time of Analysis)**						
S - ___	Unpreserved	___ NaTHIO **(Checked at time of Analysis)**						
SN - ___	Unpreserved	___ NaTHIO	___ NaTHIO/EDTA **(Checked at time of Analysis)**					
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 ___, pH >10 ___	

Describe preservation requirements not met:

All Acid preserved <2 pH	*NaOH preserved >12 pH*	*All others >2 and <10 (usually 4-8)*
Sample ID: _____	H_2SO_4 HNO_3 NaOH	_____ mls added
Sample ID: _____	H_2SO_4 HNO_3 NaOH	_____ mls added
Sample ID: _____	H_2SO_4 HNO_3 NaOH	_____ mls added
Sample ID: _____	H_2SO_4 HNO_3 NaOH	_____ mls added

H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:
18H0647-04B, 18H0647-03C, 18H0647-04A, 18H0647-03B
pH was low than 2. Added 3 ml HNO3 to A bottles & 5 mL AS soln to B bottles
Now pH is correct. TRB 9/19/18

Contact information / Summary of Actions:

Date / Time: _____ Contact: _____ Contact By: _____
Comments: _____

APEX

TABLE 6 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 001
REPORT NO.: 18H0647

Sector K Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	<0.0050 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	<50 mg/L	120 mg/L
Ammonia as N	1.1 mg/L	2.14 mg/L
Mercury	<0.00020 mg/L	0.0014 mg/L
Silver	**<0.0040 mg/L**	**0.0007 mg/L**
Arsenic	0.022 mg/L	0.15 mg/L
Cadmium	**<0.010 mg/L**	**0.0005 mg/L**
Magnesium	0.32 mg/L	0.064 mg/L
Lead	**<0.020 mg/L**	**0.014 mg/L**
Selenium	**<0.040 mg/L**	**0.005 mg/L**
Hardness ($CaCO_3$)	5.3 mg/L	
Sector N Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Chemical Oxygen Demand, Total	<50 mg/L	120 mg/L
Total Suspended Solids	2.6 mg/L	100 mg/L
Aluminum	<0.10 mg/L	0.75 mg/L
Copper	**<0.020 mg/L**	**0.0038 mg/L**
Iron	0.033 mg/L	1.0 mg/L
Lead	**<0.020 mg/L**	**0.014 mg/L**
Zinc	0.026 mg/L	0.04 mg/L
Hardness ($CaCO_3$)	5.2 mg/L	

ND – Non Detect

* – Result is less than the detection limit

TABLE 7 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 002
REPORT NO.: 18H0647

Sector K Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	0.046 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	**12,000 mg/L**	**120 mg/L**
Ammonia as N	<1.0 mg/L	2.14 mg/L
Mercury	0.00045 mg/L	0.0014 mg/L
Silver	<0.020 mg/L*	0.0183 mg/L
Arsenic	<0.10 mg/L	0.15 mg/L

APEX

TABLE 6 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 001
REPORT NO.: 18H0647

Sector K Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	<0.0050 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	<50 mg/L	120 mg/L
Ammonia as N	1.1 mg/L	2.14 mg/L
Mercury	<0.00020 mg/L	0.0014 mg/L
Silver	**<0.0040 mg/L**	**0.0007 mg/L**
Arsenic	0.022 mg/L	0.15 mg/L
Cadmium	**<0.010 mg/L**	**0.0005 mg/L**
Magnesium	0.32 mg/L	0.064 mg/L
Lead	**<0.020 mg/L**	**0.014 mg/L**
Selenium	**<0.040 mg/L**	**0.005 mg/L**
Hardness ($CaCO_3$)	5.3 mg/L	
Sector N Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Chemical Oxygen Demand, Total	<50 mg/L	120 mg/L
Total Suspended Solids	2.6 mg/L	100 mg/L
Aluminum	<0.10 mg/L	0.75 mg/L
Copper	**<0.020 mg/L**	**0.0038 mg/L**
Iron	0.033 mg/L	1.0 mg/L
Lead	**<0.020 mg/L**	**0.014 mg/L**
Zinc	0.026 mg/L	0.04 mg/L
Hardness ($CaCO_3$)	5.2 mg/L	

ND – Non Detect

* – Result is less than the detection limit

TABLE 7 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 002
REPORT NO.: 18H0647

Sector K Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	0.046 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	**12,000 mg/L**	**120 mg/L**
Ammonia as N	<1.0 mg/L	2.14 mg/L
Mercury	0.00045 mg/L	0.0014 mg/L
Silver	<0.020 mg/L*	0.0183 mg/L
Arsenic	<0.10 mg/L	0.15 mg/L

Cadmium	**<0.050 mg/L**	**0.0053 mg/L**
Magnesium	**50 mg/L**	**0.064 mg/L**
Lead	**0.28 mg/L**	**0.262 mg/L**
Selenium	**<0.20 mg/L**	**0.005 mg/L**
Hardness ($CaCO_3$)	2,500 mg/L	
Sector N Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Chemical Oxygen Demand, Total	**16,000 mg/L**	**120 mg/L**
Total Suspended Solids	**5,000 mg/L**	**100 mg/L**
Aluminum	**9.1 mg/L**	**0.75 mg/L**
Copper	**0.43 mg/L**	**0.0332 mg/L**
Iron	**48 mg/L**	**1.0 mg/L**
Lead	**0.29 mg/L**	**0.262 mg/L**
Zinc	**7.8 mg/L**	**0.26 mg/L**
Hardness ($CaCO_3$)	2,400 mg/L	

ND – Non Detect
* – Result is less than the detection limit

TABLE 8 - LAB ANALYSES: SITE #9 – 2400 EAST CAPITOL ST SE OUTALL 001
REPORT NO.: 18H0648-01

Sector L Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentrations**
Total Suspended Solids	**190 mg/L**	**100 mg/L**
Iron	**4.0 mg/L**	**1.0 mg/L**

ND – Non Detect
* – Result is less than the detection limit

TABLE 9 - LAB ANALYSES: SITE #10 - 3865 FORT RENO DR NW OUTFALL 001
REPORT NO.: 18H0644-01

Sector L Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentrations**
Total Suspended Solids	87 mg/L	100 mg/L
Iron	**1.7 mg/L**	**1.0 mg/L**

ND – Non Detect
* – Result is less than the detection limit

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
Appendix H
NPDES Tracking No.
DC0000221
Outfall Name/Number
001
"Substantially Identical Outfall"?
No
Substitute Sample?
No
Person(s)/Title(s) Collecting Sample
Andrew Hughey
Amount (inches)
.15

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)
>72hrs
Current Rainfall Event
Start Time of Discharge:
01:30 PM
Current Rainfall Amount (inches)
0.15
Substitute Sample?
No
Time Sample Collected (must be within one-hour of start of discharge, or explain)
05:00 PM
Time Sample Examined (must be within 30 minutes after sample collected, or explain)
05:06 PM

Comments
First discharge occurred during a quick downpour, and flow had ceased by the time I arrived. I had to wait for more rain.
Nature of Discharge
Rainfall
If Rainfall, amount (inches)
0.15
Previous Storm Ended >72 hours Before Start of Storm?
Yes


Parameter

Color
None
Odor
Petroleum/Gas
Clarity
Slightly Cloudy
Floating Solids
No
Settled Solids
No

Suspended Solids
Yes
If Yes, describe
Organic material
Foam (gently shake sample)
No
Oil Sheen
None
Other Obvious Indicators of Stormwater Pollution
No
Detail any concerns, additional comments, and any corrective actions taken below

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:


Name	Signature	Date Signed
Andrew Hughey		09/17/2018

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
	09/17/2018	

Title



APEX
8854 RIXLEW LANE
MANASSAS, VA 20109
TELEPHONE: (703) 396-6730
FAX: (703) 396-6743

Appendix H
3200 Benning Road NE,
Washington, DC 21002
Benning Road
SWMA Waste/Recycling Facility

0 25 50 100 150 200 Feet

Coordinate System: Lambert Conformal Conic
Central Meridian: 77°0'0"W
1st Std Parallel: 38°18'0"N
2nd Std Parallel: 39°27'0"N
Latitude of Origin: 37°40'0"N

N

Department of Public Works
Washington, DC SWP3 2010
Appendix Update: 7/1/2014
2010 USGS Orthoimage
.16 Meter Resolution

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18L0946

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 02/22/2019
Reported: 03/08/2019

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector K
Sample Matrix: Aqueous
Lab Sample ID: 18L0946-01
Collected By: Customer
Collection Date: 02/21/2019 8:45

Wet Chemistry	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4							
Cyanide, Total	<0.0050	0.0050	mg/L		02/25/19 1406	02/25/19 1601	SRZ
Method: EPA 410.4							
COD, Total	**52**	50	mg/L		03/01/19 0927	03/04/19 0913	ENK
Method: SM 4500-NH3 B+C-11							
Ammonia as N	<1.0	1.0	mg/L		03/05/19 1214	03/05/19 1257	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1							
Mercury	<0.00020	0.00020	mg/L		02/28/19 1310	02/28/19 1642	APS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7							
Antimony	<0.040	0.040	mg/L		02/25/19 0715	02/25/19 1811	APS
Arsenic	<0.020	0.020	mg/L		02/25/19 0715	02/25/19 1811	APS
Cadmium	<0.010	0.010	mg/L		02/25/19 0715	02/25/19 1811	APS
Calcium	**17**	0.20	mg/L		02/25/19 0715	02/25/19 1811	APS
Lead	<0.020	0.020	mg/L		02/25/19 0715	02/25/19 1811	APS
Magnesium	**2.9**	0.20	mg/L		02/25/19 0715	02/25/19 1811	APS
Selenium	<0.040	0.040	mg/L		02/25/19 0715	02/25/19 1811	APS
Silver	<0.0040	0.0040	mg/L		02/25/19 0715	02/25/19 1811	APS
Method: SM 2340 B-11							
Hardness (as CaCO3)	**55**	1.3	mg/L		02/25/19 0715	02/25/19 1811	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18L0946

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	18L0946-02	**Collection Date:**	02/21/2019 8:45

Wet Chemistry	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4							
COD, Total	**57**	50	mg/L		03/01/19 0927	03/04/19 0913	ENK
Method: SM 2540 D-11							
Total Suspended Solids	**12**	5.0	mg/L		02/26/19 0904	02/27/19 1147	VAS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7							
Aluminum	**0.74**	0.10	mg/L		02/25/19 0715	02/25/19 1815	APS
Calcium	**15**	0.20	mg/L		02/25/19 0715	02/25/19 1815	APS
Copper	<0.020	0.020	mg/L		02/25/19 0715	02/25/19 1815	APS
Iron	**1.5**	0.020	mg/L		02/25/19 0715	02/25/19 1815	APS
Lead	<0.020	0.020	mg/L		02/25/19 0715	02/25/19 1815	APS
Magnesium	**2.4**	0.20	mg/L		02/25/19 0715	02/25/19 1815	APS
Zinc	**0.072**	0.020	mg/L		02/25/19 0715	02/25/19 1815	APS
Method: SM 2340 B-11							
Hardness (as CaCO3)	**48**	1.3	mg/L		02/25/19 0715	02/25/19 1815	APS

CERTIFICATE OF ANALYSIS

18L0946

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	18L0946-03	**Collection Date:**	02/21/2019 9:15

Wet Chemistry	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4							
Cyanide, Total	**0.011**	0.0050	mg/L		03/04/19 1105	03/04/19 1414	SRZ
Method: EPA 410.4							
COD, Total	**530**	50	mg/L		03/05/19 0822	03/06/19 1125	ENK
Method: SM 4500-NH3 B+C-11							
Ammonia as N	<1.0	1.0	mg/L		03/05/19 1214	03/05/19 1257	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1							
Mercury	**0.00030**	0.00020	mg/L		02/28/19 1310	02/28/19 1649	APS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7							
Antimony	<0.20	0.20	mg/L		02/25/19 0715	02/25/19 1818	APS
Arsenic	<0.10	0.10	mg/L		02/25/19 0715	02/25/19 1818	APS
Cadmium	<0.050	0.050	mg/L		02/25/19 0715	02/25/19 1818	APS
Calcium	**31**	1.0	mg/L		02/25/19 0715	02/25/19 1818	APS
Lead	<0.10	0.10	mg/L		02/25/19 0715	02/25/19 1818	APS
Magnesium	**4.4**	1.0	mg/L		02/25/19 0715	02/25/19 1818	APS
Selenium	<0.20	0.20	mg/L		02/25/19 0715	02/25/19 1818	APS
Silver	<0.020	0.020	mg/L		02/25/19 0715	02/25/19 1818	APS
Method: SM 2340 B-11							
Hardness (as CaCO3)	**96**	6.6	mg/L		02/25/19 0715	02/25/19 1818	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

18L0946

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	18L0946-04	**Collection Date:**	02/21/2019 9:15

Wet Chemistry	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4							
COD, Total	**770**	50	mg/L		03/05/19 0822	03/06/19 1125	ENK
Method: SM 2540 D-11							
Total Suspended Solids	**170**	40	mg/L		02/26/19 0904	02/27/19 1147	VAS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7							
Aluminum	**3.5**	0.50	mg/L		02/25/19 0715	02/25/19 1822	APS
Calcium	**28**	1.0	mg/L		02/25/19 0715	02/25/19 1822	APS
Copper	**0.16**	0.10	mg/L		02/25/19 0715	02/25/19 1822	APS
Iron	**6.1**	0.10	mg/L		02/25/19 0715	02/25/19 1822	APS
Lead	<0.10	0.10	mg/L		02/25/19 0715	02/25/19 1822	APS
Magnesium	**3.7**	1.0	mg/L		02/25/19 0715	02/25/19 1822	APS
Zinc	**0.33**	0.10	mg/L		02/25/19 0715	02/25/19 1822	APS
Method: SM 2340 B-11							
Hardness (as CaCO3)	**85**	6.6	mg/L		02/25/19 0715	02/25/19 1822	APS

Definitions

RL: Reporting Limit

Report Comments

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Jake Mason
Client Relations
Reported: 03/08/2019 12:19

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19B1120

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 06/27/2019
Reported: 07/11/2019

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector K
Sample Matrix: Aqueous
Lab Sample ID: 19B1120-01
Collected By: Customer
Collection Date: 06/24/2019 18:15

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	<0.0050	0.0050	mg/L	1		07/01/19 0809	07/01/19 1521	SRZ
EPA 410.4								
COD, Total	<50	50	mg/L	1		06/28/19 1111	06/28/19 1311	DPG
SM 4500-NH3 B+C-11								
Ammonia as N	**6.2**	1.0	mg/L	1		07/03/19 1453	07/03/19 1532	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		07/10/19 1056	07/10/19 1556	APS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Arsenic	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Cadmium	<0.010	0.010	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Calcium	**67**	0.20	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Lead	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Magnesium	**12**	0.20	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Selenium	<0.040	0.040	mg/L	1		07/02/19 0927	07/09/19 1351	APS
Silver	<0.0040	0.0040	mg/L	1		07/02/19 0927	07/09/19 1351	APS
SM 2340 B-11								
Hardness (as CaCO3)	**220**	1.3	mg/L	1		07/02/19 0927	07/09/19 1351	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19B1120

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19B1120-02	**Collection Date:**	06/24/2019 18:15

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	<50	50	mg/L	1		06/28/19 1111	06/28/19 1311	DPG
SM 2540 D-11								
Total Suspended Solids	**13**	5.0	mg/L	5		06/28/19 1207	07/02/19 0828	EIP

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	<0.10	0.10	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Calcium	**67**	0.20	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Copper	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Iron	**4.4**	0.020	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Lead	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Magnesium	**12**	0.20	mg/L	1		07/02/19 0927	07/09/19 1355	APS
Zinc	**0.024**	0.020	mg/L	1		07/02/19 0927	07/09/19 1355	APS
SM 2340 B-11								
Hardness (as CaCO3)	**220**	1.3	mg/L	1		07/02/19 0927	07/09/19 1355	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19B1120

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19B1120-03	**Collection Date:**	06/24/2019 19:00

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	<0.0050	0.0050	mg/L	1		07/03/19 1028	07/03/19 1143	SRZ
EPA 410.4								
COD, Total	<50	50	mg/L	1		06/28/19 1111	06/28/19 1311	DPG
SM 4500-NH3 B+C-11								
Ammonia as N	**2.5**	1.0	mg/L	1		07/03/19 1453	07/03/19 1532	OCT

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		07/10/19 1056	07/10/19 1609	APS

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Arsenic	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Cadmium	<0.010	0.010	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Calcium	**69**	0.20	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Lead	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Magnesium	**15**	0.20	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Selenium	<0.040	0.040	mg/L	1		07/02/19 0927	07/09/19 1358	APS
Silver	<0.0040	0.0040	mg/L	1		07/02/19 0927	07/09/19 1358	APS
SM 2340 B-11								
Hardness (as CaCO3)	**230**	1.3	mg/L	1		07/02/19 0927	07/09/19 1358	APS

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19B1120

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19B1120-04	**Collection Date:**	06/24/2019 19:00

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	<50	50	mg/L	1		06/28/19 1111	06/28/19 1311	DPG
SM 2540 D-11								
Total Suspended Solids	**9.0**	5.0	mg/L	5		06/28/19 1207	07/02/19 0828	EIP

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	<0.10	0.10	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Calcium	**69**	0.20	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Copper	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Iron	**5.6**	0.020	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Lead	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Magnesium	**14**	0.20	mg/L	1		07/02/19 0927	07/09/19 1402	APS
Zinc	<0.020	0.020	mg/L	1		07/02/19 0927	07/09/19 1402	APS
SM 2340 B-11								
Hardness (as CaCO3)	**230**	1.3	mg/L	1		07/02/19 0927	07/09/19 1402	APS

Definitions

RL: Reporting Limit

Report Comments

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Evelyn Shinas
Customer Relationship Coordinator
Reported: 07/11/2019 11:55

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19F1450

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 10/30/2019
Reported: 11/12/2019

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector K
Sample Matrix: Aqueous
Lab Sample ID: 19F1450-01
Collected By: Customer
Collection Date: 10/30/2019 19:20

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	<0.0050	0.0050	mg/L	1		11/11/19 0953	11/11/19 1103	SRZ
EPA 410.4								
COD, Total	**740**	250	mg/L	1		11/05/19 1054	11/06/19 1213	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	**2.2**	1.0	mg/L	1		11/07/19 1130	11/07/19 1308	SRZ

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		11/04/19 0917	11/04/19 1356	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Arsenic	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Cadmium	<0.010	0.010	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Calcium	**58**	0.20	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Lead	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Magnesium	**5.0**	0.20	mg/L	1	**B14**	11/04/19 1453	11/06/19 1456	TCB
Selenium	<0.040	0.040	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
Silver	<0.0040	0.0040	mg/L	1		11/04/19 1453	11/06/19 1456	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**170**	1.3	mg/L	1		11/04/19 1453	11/06/19 1456	TCB

CERTIFICATE OF ANALYSIS

19F1450

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19F1450-02	**Collection Date:**	10/30/2019 19:20

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	**360**	50	mg/L	1		11/05/19 1054	11/06/19 1213	EIP
SM 2540 D-11								
Total Suspended Solids	**30**	20	mg/L	20		11/05/19 1636	11/06/19 1113	EIP

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**0.64**	0.10	mg/L	1		11/04/19 1453	11/06/19 1459	TCB
Calcium	**58**	0.20	mg/L	1		11/04/19 1453	11/06/19 1459	TCB
Copper	**0.079**	0.020	mg/L	1		11/04/19 1453	11/06/19 1459	TCB
Iron	**2.7**	0.020	mg/L	1		11/04/19 1453	11/06/19 1459	TCB
Lead	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1459	TCB
Magnesium	**5.1**	0.20	mg/L	1	**B14**	11/04/19 1453	11/06/19 1459	TCB
Zinc	**0.23**	0.020	mg/L	1	**B14**	11/04/19 1453	11/06/19 1459	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**170**	1.3	mg/L	1		11/04/19 1453	11/06/19 1459	TCB

CERTIFICATE OF ANALYSIS

19F1450

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19F1450-03	**Collection Date:**	10/30/2019 19:25

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	<0.0050	0.0050	mg/L	1		11/11/19 0953	11/11/19 1101	SRZ
EPA 410.4								
COD, Total	**410**	50	mg/L	1		11/05/19 1054	11/06/19 1213	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	**1.7**	1.0	mg/L	1		11/07/19 1130	11/07/19 1308	SRZ

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		11/04/19 0917	11/04/19 1358	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Arsenic	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Cadmium	<0.010	0.010	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Calcium	**97**	0.20	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Lead	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Magnesium	**18**	0.20	mg/L	1	**B14**	11/04/19 1453	11/06/19 1503	TCB
Selenium	<0.040	0.040	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
Silver	<0.0040	0.0040	mg/L	1		11/04/19 1453	11/06/19 1503	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**310**	1.3	mg/L	1		11/04/19 1453	11/06/19 1503	TCB

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19F1450

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19F1450-04	**Collection Date:**	10/30/2019 19:25

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	**730**	50	mg/L	1		11/05/19 1054	11/06/19 1213	EIP
SM 2540 D-11								
Total Suspended Solids	**46**	12	mg/L	13		11/05/19 1636	11/06/19 1113	EIP

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**0.44**	0.10	mg/L	1		11/04/19 1453	11/06/19 1506	TCB
Calcium	**87**	0.20	mg/L	1		11/04/19 1453	11/06/19 1506	TCB
Copper	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1506	TCB
Iron	**5.4**	0.020	mg/L	1		11/04/19 1453	11/06/19 1506	TCB
Lead	<0.020	0.020	mg/L	1		11/04/19 1453	11/06/19 1506	TCB
Magnesium	**16**	0.20	mg/L	1	**B14**	11/04/19 1453	11/06/19 1506	TCB
Zinc	**0.11**	0.020	mg/L	1	**B14**	11/04/19 1453	11/06/19 1506	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**280**	1.3	mg/L	1		11/04/19 1453	11/06/19 1506	TCB

Definitions

B14: Target analyte detected in method blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

RL: Reporting Limit

Report Comments

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Evelyn Shinas
Customer Relationship Coordinator
Reported: 11/12/2019 13:04

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19F1450

TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 6/28/2019
Field Route ID:

Client Sample ID: Site # 8 Outfall 001 Sector K
Lab Sample ID: 19F1450-01
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 10/30 1920

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
P- 250ml Plastic Absorbic then NaOH to pH >12	A
B-1000ml Plastic H2SO4 to pH <2	B
A- 500ml Plastic HNO3 to pH <2	C

Client Sample ID: Site # 8 Outfall 001 Sector N
Lab Sample ID: 19F1450-02
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 10/30 1920

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days
TSS	SM 2540 D-11		7.00 days

MICROBAC

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19F1450

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 6/28/2019
Field Route ID:

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
H-½ Gallon Plastic Neat	C

Client Sample ID: Site # 8 Outfall 002 Sector K
Lab Sample ID: 19F1450-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 10/30 1925

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
A- 500ml Plastic HNO3 to pH <2	A
B-1000ml Plastic H2SO4 to pH <2	B
P- 250ml Plastic Absorbic then NaOH to pH >12	C

Client Sample ID: Site # 8 Outfall 002 Sector N
Lab Sample ID: 19F1450-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 10/30 1925

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19F1450

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 6/28/2019
Field Route ID:

TSS	SM 2540 D-11		7.00 days

Container(s)
B-1000ml Plastic H2SO4 to pH <2
A- 500ml Plastic HNO3 to pH <2
H-½ Gallon Plastic Neat

Designator
A
B
C

Sampled/Relinquished by:	Date/Time: 10/30 2130	Received by: Margaret Mayatt
Printed Name: Customer Tyler Warren		Printed Name: Margaret King
Relinquished by: Mayatt	Date/Time: 10/31/19 1150	Received by:
Printed Name: Margaret King		Printed Name: MLF
Relinquished by:	Date/Time: 10/31/19 1525	Received by: 10/31/19
Printed Name:		Printed Name: 1525

As Received at Laboratory: On Ice: Yes / No Temp 3.4 °C Total Containers: 12

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

Microbac Laboratories, Inc.
2101 Van Deman Street | Baltimore, MD 21224 | 410.633.1800 p | www.microbac.com

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: 1
Client: Apex
Form Completed By: HNO. 11:89

Receipt Date / Time: 10/31/19 1525
Work Order # 19F1445 / 1450 / 1951054

Shipper: ☒ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact: (YES) / NO / NA
Containers Intact: (YES) / NO
Sample Received on Ice or refrigerated: (YES) / NO / NA
Infrared (IR) Temperature: 3.4 °C

Chain of Custody Present with shipment: (YES) / NO
Sample Bottle IDs agree with COC: (YES) / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: (YES) / NO (If No, contact client immediately)
Headspace in container: YES / NO / (NA)
Type of Sample: (Water) Soil Wipes Oil Filter Solid Sludge Food Swab Other

***Container Type / Quantity*:**

A - ___	Unpreserved	___ H2SO4	6 HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid:	If preserved pH <2___, pH >10___
B - ___	Unpreserved	4 H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
C - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
D - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
E - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
H - 4	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
K - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
L - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
M - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
P - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	2 NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
W - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN - ___ Unpreserved ___ NaTHIO ___ NaTHIO/EDTA **(Checked at time of Analysis)**

___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

Describe preservation requirements not met:
All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:
Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19K0640

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 12/31/2019
Reported: 01/07/2020

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector K
Sample Matrix: Aqueous
Lab Sample ID: 19K0640-01
Collected By: Customer
Collection Date: 12/29/2019 11:35

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	**0.012**	0.0050	mg/L	1		01/02/20 0931	01/02/20 1334	SRZ
EPA 410.4								
COD, Total	**250**	50	mg/L	1		01/02/20 1045	01/02/20 1259	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	<1.0	1.0	mg/L	1		01/06/20 0940	01/06/20 1145	VAS

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		01/02/20 0915	01/02/20 1403	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		01/02/20 1416	01/06/20 1221	TCB
Arsenic	<0.020	0.020	mg/L	1		01/02/20 1416	01/06/20 1221	TCB
Cadmium	<0.010	0.010	mg/L	1		01/02/20 1416	01/06/20 1221	TCB
Calcium	**61**	0.20	mg/L	1		01/02/20 1416	01/06/20 1221	TCB
Lead	<0.020	0.020	mg/L	1	**B15**	01/02/20 1416	01/06/20 1221	TCB
Magnesium	**13**	0.20	mg/L	1	**B10, B12, B14**	01/02/20 1416	01/06/20 1221	TCB
Selenium	<0.040	0.040	mg/L	1		01/02/20 1416	01/06/20 1221	TCB
Silver	<0.0040	0.0040	mg/L	1		01/02/20 1416	01/06/20 1611	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**210**	1.3	mg/L	1		01/02/20 1416	01/06/20 1221	TCB

CERTIFICATE OF ANALYSIS

19K0640

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19K0640-02	**Collection Date:**	12/29/2019 11:35

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	<50	50	mg/L	1		01/02/20 1045	01/02/20 1259	EIP
SM 2540 D-11								
Total Suspended Solids	<20	20	mg/L	20		01/02/20 0954	01/03/20 1126	DPG

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**0.25**	0.10	mg/L	1		01/02/20 1416	01/06/20 1232	TCB
Calcium	**61**	0.20	mg/L	1		01/02/20 1416	01/06/20 1232	TCB
Copper	<0.020	0.020	mg/L	1		01/02/20 1416	01/06/20 1232	TCB
Iron	**6.8**	0.020	mg/L	1	**B10, B14**	01/02/20 1416	01/06/20 1232	TCB
Lead	<0.020	0.020	mg/L	1	**B15**	01/02/20 1416	01/06/20 1232	TCB
Magnesium	**14**	0.20	mg/L	1	**B10, B12, B14**	01/02/20 1416	01/06/20 1232	TCB
Zinc	**0.061**	0.020	mg/L	1	**B14**	01/02/20 1416	01/06/20 1232	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**210**	1.3	mg/L	1		01/02/20 1416	01/06/20 1232	TCB

CERTIFICATE OF ANALYSIS

19K0640

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19K0640-03	**Collection Date:**	12/29/2019 11:40

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	**0.0057**	0.0050	mg/L	1		01/02/20 0931	01/02/20 1332	SRZ
EPA 410.4								
COD, Total	**3100**	250	mg/L	1		01/02/20 1045	01/02/20 1259	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	**9.0**	1.0	mg/L	1		01/06/20 0940	01/06/20 1145	VAS

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		01/02/20 0915	01/02/20 1405	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.050	0.050	mg/L	1		01/02/20 1416	01/06/20 1342	TCB
Arsenic	<0.025	0.025	mg/L	1		01/02/20 1416	01/06/20 1342	TCB
Cadmium	<0.012	0.012	mg/L	1		01/02/20 1416	01/06/20 1342	TCB
Calcium	**120**	0.25	mg/L	1		01/02/20 1416	01/06/20 1342	TCB
Lead	<0.025	0.025	mg/L	1	**B15**	01/02/20 1416	01/06/20 1342	TCB
Magnesium	**3.7**	0.25	mg/L	1	**B10, B12, B14**	01/02/20 1416	01/06/20 1342	TCB
Selenium	<0.050	0.050	mg/L	1		01/02/20 1416	01/06/20 1342	TCB
Silver	<0.0040	0.0040	mg/L	1		01/02/20 1416	01/06/20 1621	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**300**	1.7	mg/L	1		01/02/20 1416	01/06/20 1342	TCB

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

19K0640

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	19K0640-04	**Collection Date:**	12/29/2019 11:40

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	**3100**	250	mg/L	1		01/02/20 1045	01/02/20 1259	EIP
SM 2540 D-11								
Total Suspended Solids	**100**	25	mg/L	25		01/02/20 0954	01/03/20 1126	DPG

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**0.87**	0.12	mg/L	1		01/02/20 1416	01/06/20 1355	TCB
Calcium	**120**	0.25	mg/L	1		01/02/20 1416	01/06/20 1355	TCB
Copper	**0.23**	0.025	mg/L	1		01/02/20 1416	01/06/20 1355	TCB
Iron	**4.1**	0.025	mg/L	1	**B10, B14**	01/02/20 1416	01/06/20 1355	TCB
Lead	<0.025	0.025	mg/L	1		01/02/20 1416	01/06/20 1355	TCB
Magnesium	**9.6**	0.25	mg/L	1	**B10, B12, B14**	01/02/20 1416	01/06/20 1355	TCB
Zinc	**0.52**	0.025	mg/L	1	**B14**	01/02/20 1416	01/06/20 1355	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**340**	1.7	mg/L	1		01/02/20 1416	01/06/20 1355	TCB

Definitions

B10: Target analyte detected in continuing calibration blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

B12: Target analyte detected in initial calibration blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

B14: Target analyte detected in method blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

B15: Target analyte detected in method blank >2.2 times the MDL but less than the reporting limit. Sample result was less than the reporting limit. No impact on data.

mg/L: Milligrams per Liter

RL: Reporting Limit

Project Requested Certification(s)

Microbac Laboratories, Inc. - Baltimore

460285

E871126

Commonwealth of Virginia (NELAC) - Baltimore

Florida - NELAC

CERTIFICATE OF ANALYSIS

19K0640

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Marissa Mamone

Client Relations

Reported: 01/07/2020 16:57

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19K0640

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 11/13/2019
Field Route ID:

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
H-½ Gallon Plastic Neat	C

Client Sample ID: Site # 8 Outfall 002 Sector K
Lab Sample ID: 19K0640-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/29/19/1140

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
A- 500ml Plastic HNO3 to pH <2	A
B-1000ml Plastic H2SO4 to pH <2	B
P- 250ml Plastic Absorbic then NaOH to pH >12	C

Client Sample ID: Site # 8 Outfall 002 Sector N
Lab Sample ID: 19K0640-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/29/19/1140

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days

MICROBAC®

www.microbac.com

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19K0640

TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 11/13/2019
Field Route ID:

Client Sample ID: Site # 8 Outfall 001 Sector K
Lab Sample ID: 19K0640-01
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/29/19 / 11:35

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
P-250ml Plastic Absorbic then NaOH to pH >12	A
B-1000ml Plastic H2SO4 to pH <2	B
A- 500ml Plastic HNO3 to pH <2	C

Client Sample ID: Site # 8 Outfall 001 Sector N
Lab Sample ID: 19K0640-02
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/29/19 / 11:35

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days
TSS	SM 2540 D-11		7.00 days

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

19K0640

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project / PO Number: N/A
Tenatively Scheduled: 11/13/2019
Field Route ID:

TSS	SM 2540 D-11	7.00 days

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
H-½ Gallon Plastic Neat	C

Sampled/Relinquished by: 12-31-19	Date/Time:	Received by: 12-31-19
Printed Name: Customer 0900		Printed Name: Rick Price 0900
Relinquished by:	Date/Time: 12-31-19 @1059	Received by: 12-31-19
Printed Name: Ricky Price		Printed Name: Hailey Woodward 1059
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:

As Received at Laboratory: On Ice: (Yes / No) Temp 2.9 °C Total Containers: 12

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: 1
Client: Apex
Form Completed By: Haley

Receipt Date / Time: 12/3/19
Work Order # 19120646

Shipper: ☒ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact: YES / NO / NA
Containers Intact: YES / NO
Sample Received on Ice or refrigerated: YES / NO / NA
Infrared (IR) Temperature: 2.9 °C

Chain of Custody Present with shipment: YES / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / NA
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity:

A - ___	Unpreserved ___	H2SO4 ___	HNO3 4	HCl ___	NaOH ___	NaOH/Ascorbic Acid:	If preserved pH <2___, pH >10___
B - ___	Unpreserved 4	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
C - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
D - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
E - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
H - 2	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
K - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
L - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
M- ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
P - ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl 2	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
W- ___	Unpreserved ___	H2SO4 ___	HNO3 ___	HCl ___	NaOH ___	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN- ___ Unpreserved ___ NaTHIO ___ NaTHIO/EDTA **(Checked at time of Analysis)**

___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

Describe preservation requirements not met:
All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:
Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20A0476

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 01/14/2020
Reported: 01/24/2020

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector K
Sample Matrix: Aqueous
Lab Sample ID: 20A0476-01
Collected By: Customer
Collection Date: 01/12/2020 1:15

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	**0.031**	0.0050	mg/L	1		01/15/20 0936	01/15/20 1358	SRZ
EPA 410.4								
COD, Total	**160**	50	mg/L	1		01/16/20 0849	01/16/20 1401	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	<1.0	1.0	mg/L	1		01/16/20 1110	01/16/20 1227	VAS

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		01/16/20 0917	01/16/20 1457	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Arsenic	<0.020	0.020	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Cadmium	<0.010	0.010	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Calcium	**38**	0.20	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Lead	**0.044**	0.020	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Magnesium	**6.9**	0.20	mg/L	1	**B10, B14**	01/17/20 0801	01/21/20 1441	TCB
Selenium	<0.040	0.040	mg/L	1		01/17/20 0801	01/21/20 1441	TCB
Silver	<0.0040	0.0040	mg/L	1		01/17/20 0801	01/22/20 1509	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**120**	1.3	mg/L	1		01/17/20 0801	01/21/20 1441	TCB

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20A0476

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20A0476-02	**Collection Date:**	01/12/2020 1:15

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	**250**	50	mg/L	1		01/16/20 0849	01/16/20 1401	EIP
SM 2540 D-11								
Total Suspended Solids	**96**	10	mg/L	10		01/15/20 1625	01/16/20 1045	DPG

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**2.3**	0.10	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
Calcium	**43**	0.20	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
Copper	**0.054**	0.020	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
Iron	**4.7**	0.020	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
Lead	**0.046**	0.020	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
Magnesium	**6.9**	0.20	mg/L	1	**B10, B14**	01/17/20 0801	01/21/20 1445	TCB
Zinc	**0.39**	0.020	mg/L	1		01/17/20 0801	01/21/20 1445	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**140**	1.3	mg/L	1		01/17/20 0801	01/21/20 1445	TCB

CERTIFICATE OF ANALYSIS

20A0476

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20A0476-03	**Collection Date:**	01/12/2020 1:25

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4								
Cyanide, Total	<0.0050	0.0050	mg/L	1		01/15/20 0936	01/15/20 1412	SRZ
EPA 410.4								
COD, Total	**280**	50	mg/L	1		01/16/20 0849	01/16/20 1401	EIP
SM 4500-NH3 B+C-11								
Ammonia as N	<1.0	1.0	mg/L	1		01/16/20 1110	01/16/20 1227	VAS

Mercury, Total by EPA 200/7000 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1								
Mercury	<0.00020	0.00020	mg/L	1		01/16/20 0917	01/16/20 1459	LNR

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Antimony	<0.040	0.040	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Arsenic	<0.020	0.020	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Cadmium	<0.010	0.010	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Calcium	**16**	0.20	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Lead	<0.020	0.020	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Magnesium	**1.4**	0.20	mg/L	1	**B10, B14**	01/17/20 0801	01/21/20 1519	TCB
Selenium	<0.040	0.040	mg/L	1		01/17/20 0801	01/21/20 1519	TCB
Silver	<0.0040	0.0040	mg/L	1		01/17/20 0801	01/22/20 1513	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**45**	1.3	mg/L	1		01/17/20 0801	01/21/20 1519	TCB

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20A0476

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20A0476-04	**Collection Date:**	01/12/2020 1:25

Wet Chemistry	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4								
COD, Total	**280**	50	mg/L	1		01/16/20 0849	01/16/20 1401	EIP
SM 2540 D-11								
Total Suspended Solids	**76**	10	mg/L	10		01/15/20 1625	01/16/20 1045	DPG

Metals, Total by EPA 200 Series Methods	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.7								
Aluminum	**0.90**	0.10	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
Calcium	**15**	0.20	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
Copper	**0.027**	0.020	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
Iron	**1.8**	0.020	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
Lead	<0.020	0.020	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
Magnesium	**1.4**	0.20	mg/L	1	**B10, B14**	01/17/20 0801	01/21/20 1537	TCB
Zinc	**0.13**	0.020	mg/L	1		01/17/20 0801	01/21/20 1537	TCB
SM 2340 B-11								
Hardness (as CaCO3)	**44**	1.3	mg/L	1		01/17/20 0801	01/21/20 1537	TCB

Definitions

B10: Target analyte detected in continuing calibration blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

B14: Target analyte detected in method blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.

mg/L: Milligrams per Liter

RL: Reporting Limit

Project Requested Certification(s)

Microbac Laboratories, Inc. - Baltimore

460285 — Commonwealth of Virginia (NELAC) - Baltimore

E871126 — Florida - NELAC

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included.

Reviewed and Approved By:



Marissa Mamone

Client Relations

Reported: 01/24/2020 12:31

MICROBAC

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

20A0476

Reviewed By: AL

Date: 1/15/20 TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 1/6/2020
Field Route:

Client Sample ID: Site # 8 Outfall 001 Sector K
Lab Sample ID: 20A0476-01
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1/12/19 / 01:15

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
P- 250ml Plastic Absorbic then NaOH to pH >12	A
B-1000ml Plastic H2SO4 to pH <2	B
A- 500ml Plastic HNO3 to pH <2	C

Client Sample ID: Site # 8 Outfall 001 Sector N
Lab Sample ID: 20A0476-02
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1/12/19 / 1:15

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days
TSS	SM 2540 D-11		7.00 days

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

20A0476

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 1/6/2020
Field Route:

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
H-½ Gallon Plastic Neat	C

Client Sample ID: Site # 8 Outfall 002 Sector K
Lab Sample ID: 20A0476-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1/12/19 / 1:25

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
Hg_Total	EPA 245.1		28.00 days
M_Ag_ICP	EPA 200.7		180.00 days
M_As_ICP	EPA 200.7		180.00 days
M_Cd_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Sb_ICP	EPA 200.7		180.00 days
M_Se_ICP	EPA 200.7		180.00 days
CN_Total_Seal	EPA 335.4		14.00 days
COD_Total_HL	EPA 410.4		28.00 days
NH3_Titration	SM 4500-NH3 B+C-11		28.00 days

Container(s)	Designator
A- 500ml Plastic HNO3 to pH <2	A
B-1000ml Plastic H2SO4 to pH <2	B
P- 250ml Plastic Absorbic then NaOH to pH >12	C

Client Sample ID: Site # 8 Outfall 002 Sector N
Lab Sample ID: 20A0476-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1/12/19 / 1:25

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	varies		180.00 days
M_Al_ICP	EPA 200.7		180.00 days
M_Cu_ICP	EPA 200.7		180.00 days
M_Fe_ICP	EPA 200.7		180.00 days
M_Pb_ICP	EPA 200.7		180.00 days
M_Zn_ICP	EPA 200.7		180.00 days
COD_Total_HL	EPA 410.4		28.00 days

MICROBAC

Microbac Laboratories, Inc. - Baltimore

Chain of Custody

20A0476

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 1/6/2020
Field Route:

		7.00 days
TSS	SM 2540 D-11	

Container(s)	Designator
B-1000ml Plastic H2SO4 to pH <2	A
A- 500ml Plastic HNO3 to pH <2	B
H-½ Gallon Plastic Neat	C

Sampled/Relinquished by: [signature]	Date/Time: 1/14/20 1132hrs	Received by: Roberta Hanna
Printed Name: Customer Rick McBride		Printed Name: Roberta Hanna
Relinquished by: Roberta Hanna	Date/Time: 1/14/20 1338	Received by: [signature] 01/14/20
Printed Name: Roberta Hanna		Printed Name: [signature] 1338
Relinquished by:	Date/Time:	Received by:
Printed Name:		Printed Name:

As Received at Laboratory: On Ice: (Yes) / No Temp 1.7 °C Total Containers: 12

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: ~~2~~ 2 AS 01/14/20
Client: APEX -
Form Completed By:

Receipt Date / Time: 01/14/20 1338 AS 01/14/20 1334
Work Order # 20A0475/0476

Shipper:	☒ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact:	YES / NO / NA
Containers Intact:	YES / NO
Sample Received on Ice or refrigerated:	YES / NO / NA 0475
	Infrared (IR) Temperature: 0.9 °C 1.7 0476
Chain of Custody Present with shipment:	YES / NO
Sample Bottle IDs agree with COC:	YES / NO
Preservation requirements met:	YES / NO / Not Checked
Correct Number of Containers / Sample Volume:	YES / NO (If No, contact client immediately)
Headspace in container:	YES / NO (NA)
Type of Sample:	(Water) Soil Wipes Oil Filter Solid Sludge Food Swab Other

***Container Type / Quantity*:**

A -	___ Unpreserved	___ H2SO4	8 HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid:	If preserved pH <2 Yes, pH >10 All	
B -	___ Unpreserved	8 H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 Yes, pH >10___	
C -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2 All, pH >10___	
D -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
E -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
H -	4 Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
K -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
L -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
M-	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
P -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH 4	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
W-	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	

V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN- ___ Unpreserved ___ NaTHIO ___ NaTHIO/EDTA **(Checked at time of Analysis)**

___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___	

Describe preservation requirements not met:
All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*

Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added

H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:

Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____





District Department of Public Works
NPDES Stormwater Monitoring
Visual Assessment and Sampling Report

Site 8 – 3200 Benning Road, NE
July 30, 2020 – Rain Event

Prepared for

District Department of Public Works
1725 15th Street NE, Suite 211
Washington, DC 20002



Prepared by

Apex Companies, LLC
9700 Capitol Court, Suite 100
Manassas, VA 20110

August 26, 2020



Table of Contents

1.0 Narrative Report
2.0 Meteorological Reporting Data
3.0 Quarterly Visual Assessment Forms
4.0 Analytical Data Report
5.0 Relevant Site Maps

1.0 NARRATIVE REPORT

1.0 NARRATIVE REPORT

The National Oceanic and Atmospheric Administration (NOAA) rain gauge located at Reagan National Airport was used to track and document the meteorological conditions for DC area. Descriptions and detailed meteorological data along with numerical data tables for this particular storm water event are provided in **Section 2.0** of this report.

July 30, 2020 – Rain Event:
The weather conditions for this event consisted of light rain and temperatures at approximately seventy-eight degrees Fahrenheit. The average wind speed was approximately 8 miles per hour for the duration of this water sampling event.

Sampling began during the evening of July 30, 2020. The meteorological data for this event is summarized in Table 1.

Table 1 – Stormwater Sampling Characteristics

Date	Precipitation (inches)	Duration (hours)	Hours to Previous Rain Event	Gauge Location
July 30, 2020	0.15	~6	~216	National Airport

The Quarterly Visual Assessment for July-September 2020 was conducted for the following site:

Table 2 – Quarterly Visual Assessment Locations

Site #	SWP3 Appendix ID	Address	Outfall Number	Flow Conditions
8	H	3200 BENNING ROAD, NE	001/002	Good

SWP3 – Stormwater Pollution Prevention Plan

The Quarterly Sampling Event for July-September 2020 was conducted for the following site:

Table 3 – Quarterly Sampling Locations

Site #	SWP3 Appendix ID	Address	Outfall Number	Flow Conditions
8	H	3200 BENNING ROAD, NE	001/002	Good

SWP3 – Stormwater Pollution Prevention Plan

Completed Quarterly Visual Assessment Forms can be found in **Section 3.0**.

Relevant site maps can be found in **Section 6.0**.

Laboratory Results

TABLE 4 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 001
REPORT NO.: 20G0965

Sector K Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	<0.0050 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	**5300 mg/L**	**120 mg/L**
Ammonia as N	**4.8 mg/L**	**2.14 mg/L**
Mercury	<0.00020 mg/L	0.0014 mg/L
Silver	<0.0010 mg/L	0.0065 mg/L
Arsenic	0.0033 mg/L	0.15 mg/L
Cadmium	.000618 mg/L	0.0029 mg/L
Magnesium	**6.18 mg/L**	**0.064 mg/L**
Lead	0.0253 mg/L	0.122 mg/L
Selenium	<0.0050 mg/L	0.005 mg/L
Receiving Waterbody Hardness($CaCO_3$)*	135 mg/L	
Sector N Results for Outfall 001		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Chemical Oxygen Demand, Total	**860 mg/L**	**120 mg/L**
Total Suspended Solids	70 mg/L	100 mg/L
Aluminum	**0.773 mg/L**	**0.75 mg/L**
Copper	**0.0745 mg/L**	**0.0189 mg/L**
Iron	**3.43 mg/L**	**1.0 mg/L**
Lead	0.0182 mg/L	0.122 mg/L
Zinc	**0.456 mg/L**	**0.16 mg/L**
Receiving Waterbody Hardness($CaCO_3$)*	135 mg/L	

* – Provided by EPA

ND – Non Detect

TABLE 5 - LAB ANALYSES: SITE #8 – 3200 BENNING ROAD, NE OUTFALL 002
REPORT NO.: 20G0965

Sector K Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Cyanide, Total	<0.0050 mg/L	0.022 mg/L
Chemical Oxygen Demand, Total	**2600 mg/L**	**120 mg/L**
Ammonia as N	**19 mg/L**	**2.14 mg/L**
Mercury	<0.00057 mg/L	0.0014 mg/L
Silver	<0.0010 mg/L	0.0065 mg/L
Arsenic	0.0139 mg/L	0.15 mg/L
Cadmium	0.000956 mg/L	0.0029 mg/L
Magnesium	**12.5 mg/L**	**0.064 mg/L**
Lead	0.0384 mg/L	0.122 mg/L
Selenium	<0.0050 mg/L	0.005 mg/L
Receiving Waterbody Hardness($CaCO_3$)*	135 mg/L	
Sector N Results for Outfall 002		
Analyte	**Results**	**Benchmark Monitoring Concentration**
Chemical Oxygen Demand, Total	**500 mg/L**	**120 mg/L**
Total Suspended Solids	**120 mg/L**	**100 mg/L**
Aluminum	0.581 mg/L	0.75 mg/L
Copper	**0.278 mg/L**	**0.0189 mg/L**
Iron	**4.09 mg/L**	**1.0 mg/L**
Lead	0.0399 mg/L	0.122 mg/L
Zinc	**0.834 mg/L**	**0.16 mg/L**
Receiving Waterbody Hardness($CaCO_3$)*	135 mg/L	

* – Provided by EPA
ND – Non Detect

Parameters that are above the Benchmark Monitoring Concentration are bolded within their respective tables. Benchmark Monitoring Concentrations are found in the representative subsector of Part 8 "Sector-Specific Requirements for Industrial Activity," of the National Pollutant Discharge Elimination System (NPDES) Multi-Sector General Permit for Stormwater Discharges Associated with Industrial Activity (MSGP). As per Part 6.2.1 "Benchmark Monitoring," after collection of 4 quarterly samples, if the average of the 4 monitoring values for any parameter exceeds the benchmark, in accordance with Part 3.2, review the selection, design, installation, and implementation of control measures to determine if modifications are necessary to meet the effluent limits in the permit.

2.0 METEOROLOGICAL REPORTING DATA

These data are preliminary and have not undergone final quality control by the National Climatic Data Center (NCDC). Therefore, these data are subject to revision. Final and certified climate data can be accessed at the NCDC - http://www.ncdc.noaa.gov.

Climatological Report (Daily)

```
000
CDUS41 KLWX 310529
CLIDCA

CLIMATE REPORT
NATIONAL WEATHER SERVICE BALTIMORE MD/WASHINGTON DC
129 AM EDT FRI JUL 31 2020

.....................................

...THE WASHINGTON NATIONAL DC CLIMATE SUMMARY FOR JULY 30 2020...

CLIMATE NORMAL PERIOD: 1981 TO 2010
CLIMATE RECORD PERIOD: 1871 TO 2020
```

WEATHER ITEM	OBSERVED VALUE	TIME (LST)	RECORD VALUE	YEAR	NORMAL VALUE	DEPARTURE FROM NORMAL	LAST YEAR
TEMPERATURE (F)							
YESTERDAY							
MAXIMUM	94	3:02 PM	99	1953	88	6	95
MINIMUM	74	11:59 PM	56	1914	71	3	76
AVERAGE	84				80	4	86
PRECIPITATION (IN)							
YESTERDAY	0.15		4.25	1878	0.12	0.03	0.00
MONTH TO DATE	6.44				3.61	2.83	6.48
SINCE JUN 1	9.95				7.39	2.56	10.75
SINCE JAN 1	27.05				23.35	3.70	28.78
SNOWFALL (IN)							
YESTERDAY	0.0		MM	MM	0.0	0.0	0.0
MONTH TO DATE	0.0				0.0	0.0	0.0
SINCE JUN 1	0.0				0.0	0.0	0.0
SINCE JUL 1	0.0				0.0	0.0	0.0

  SNOW DEPTH   0

DEGREE DAYS
 HEATING
  YESTERDAY   0   0   0   0
  MONTH TO DATE   0   0   0   0
  SINCE JUN 1   0   6   -6   0
  SINCE JUL 1   0   0   0   0

 COOLING
  YESTERDAY   19   15   4   21
  MONTH TO DATE 582   445   137   521
  SINCE JUN 1   950   759   191   869
  SINCE JAN 1   1057   893   164   1152
....

WIND (MPH)
  HIGHEST WIND SPEED   29   HIGHEST WIND DIRECTION   SW (240)
  HIGHEST GUST SPEED   41   HIGHEST GUST DIRECTION   W (250)
  AVERAGE WIND SPEED   7.8

SKY COVER
  AVERAGE SKY COVER 0.7

WEATHER CONDITIONS
THE FOLLOWING WEATHER WAS RECORDED YESTERDAY.
  THUNDERSTORM
  HEAVY RAIN
  RAIN
  LIGHT RAIN
  FOG

RELATIVE HUMIDITY (PERCENT)
 HIGHEST   91   7:00 PM
 LOWEST   44   12:00 PM
 AVERAGE   68

....

THE WASHINGTON NATIONAL DC CLIMATE NORMALS FOR TODAY
                          NORMAL   RECORD   YEAR

```
 MAXIMUM TEMPERATURE (F)   88       103      1954
 MINIMUM TEMPERATURE (F)   71        52      1895


SUNRISE AND SUNSET
JULY 31 2020.....SUNRISE   6:09 AM EDT   SUNSET   8:20 PM EDT
AUGUST  1 2020.....SUNRISE   6:10 AM EDT   SUNSET   8:19 PM EDT


-  INDICATES NEGATIVE NUMBERS.
R  INDICATES RECORD WAS SET OR TIED.
MM INDICATES DATA IS MISSING.
T  INDICATES TRACE AMOUNT.
```

The U.S. Naval Observatory (USNO) data is currently unavailable. The links provided are from other US Government sources. When USNO data is returned to service, the links will be updated.

3.0 QUARTERLY VISUAL ASSESSMENT FORMS

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
SMWA Waste/Recycling Facility
NPDES Tracking No.
DC0000221
Outfall Name/Number
001
"Substantially Identical Outfall"?
No
Substitute Sample?
No
Person(s)/Title(s) Collecting Sample
Margaret King
Amount (inches)
.15

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)

Current Rainfall Event
Start Time of Discharge:
08:00 PM
Current Rainfall Amount (inches)
.1
Substitute Sample?
No
Time Sample Collected (must be within one-hour of start of discharge, or explain)
08:30 PM
Time Sample Examined (must be within 30 minutes after sample collected, or explain)
09:00 PM

Comments

Nature of Discharge
Rainfall
If Rainfall, amount (inches)
.15
Previous Storm Ended >72 hours Before Start of Storm?
Yes

Parameter

Color
Other
If Other, describe:
Light yellow
Odor
Sour
Clarity
Slightly Cloudy
Floating Solids
No
Settled Solids
Yes
If Yes, describe
Some sediment

Suspended Solids
No
Foam (gently shake sample)
No
Oil Sheen
None
Other Obvious Indicators of Stormwater Pollution
No
Detail any concerns, additional comments, and any corrective actions taken below

NPDES Quarterly Visual Assessment Form

Photos

Photo Number	Photo Description	Photo
1	Sample	

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:

Name	Signature	Date Signed
Margaret King		07/30/2020

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
Title		

NPDES Quarterly Visual Assessment Form

Assessment

Name of Facility
SWMA Waste/Recycling Facility
NPDES Tracking No.
Site 8
Outfall Name/Number
002
"Substantially Identical Outfall"?
No
Substitute Sample?
No
Person(s)/Title(s) Collecting Sample
Margaret King
Amount (inches)
.15

Duration (time) between Prior Rainfall and Current Rainfall (must be at least 72 hrs or 3 days)

Current Rainfall Event
Start Time of Discharge:
08:00 PM
Current Rainfall Amount (inches)
.1
Substitute Sample?
No
Time Sample Collected (must be within one-hour of start of discharge, or explain)
08:30 PM
Time Sample Examined (must be within 30 minutes after sample collected, or explain)
09:00 PM

Comments

Nature of Discharge
Rainfall
If Rainfall, amount (inches)
0.15
Previous Storm Ended >72 hours Before Start of Storm?
Yes

Parameter

Color
Other
If Other, describe:
Light yellow
Odor
Sour
Clarity
Slightly Cloudy
Floating Solids
No
Settled Solids
Yes
If Yes, describe
Some sediment

Suspended Solids
No
Foam (gently shake sample)
No
Oil Sheen
None
Other Obvious Indicators of Stormwater Pollution
No
Detail any concerns, additional comments, and any corrective actions taken below

NPDES Quarterly Visual Assessment Form

Photos

Photo Number	Photo Description	Photo
1	Sample	

NPDES Quarterly Visual Assessment Form

Person Collecting/Examining Sample:

Name	Signature	Date Signed
Margaret King		07/30/2020

Certification by Facility Responsible Official (Refer to MSGP Subpart 11 Appendix B for Signatory Requirements)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name	Date Signed	Signature
Title		

4.0 ANALYTICAL DATA REPORT

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20G0965

Revised Report: Amended to fix sample name.

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 07/31/2020
Reported: 08/25/2020

Case Narrative

MMM 8/25/2020 Work order amended to switch Sample ID of Sector K with Sector N per client request due to labeling error in the field.

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector N
Sample Matrix: Aqueous
Lab Sample ID: 20G0965-01
Collected By: Customer
Collection Date: 07/30/2020 20:30

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4, Rv. 2 (1993)								
COD, Total	**860**	50	mg/L	1		08/05/20 0958	08/06/20 1533	EIP
SM 2540 D-2011								
Total Suspended Solids	**70**	20	mg/L	20		08/04/20 1612	08/05/20 1014	EIP

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Aluminum	**0.773**	0.0050	mg/L	1	**B12**	08/03/20 0816	08/04/20 1745	GHW
Copper	**0.0745**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1745	GHW
Lead	**0.0182**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1745	GHW
Zinc	**0.456**	0.0050	mg/L	1	**B14**	08/03/20 0816	08/04/20 1745	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**180**	0.999	mg/L	1		08/07/20 0709	08/07/20 2120	KHL

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**61.8**	0.400	mg/L	1		08/07/20 0709	08/07/20 2120	KHL
Iron	**3.43**	0.0800	mg/L	1		08/07/20 0709	08/07/20 2120	KHL
Magnesium	**6.22**	0.400	mg/L	1		08/07/20 0709	08/07/20 2120	KHL

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20G0965

Client Sample ID:	Site # 8 Outfall 001 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20G0965-02	**Collection Date:**	07/30/2020 20:30

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4, Rv. 1 (1993)								
Cyanide, Total	<0.0050	0.0050	mg/L	1		08/03/20 1137	08/03/20 1449	SRZ
EPA 410.4, Rv. 2 (1993)								
COD, Total	**5300**	250	mg/L	1		08/05/20 0958	08/06/20 1533	EIP
SM 4500-NH3 B-2011								
Ammonia as N	**4.8**	1.0	mg/L	1		08/03/20 0920	08/03/20 1145	VAS

Metals Total by CVAA	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1, Rv. 3 (1994)								
Mercury	<0.00020	0.00020	mg/L	1		08/05/20 0908	08/05/20 1333	LNR

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Arsenic	**0.0033**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1749	GHW
Selenium	<0.0050	0.0050	mg/L	1		08/03/20 0816	08/04/20 1749	GHW
Silver	<0.0010	0.0010	mg/L	1		08/03/20 0816	08/04/20 1749	GHW
Cadmium	**0.000618**	0.000250	mg/L	1		08/03/20 0816	08/04/20 1749	GHW
Lead	**0.0253**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1749	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**178**	0.999	mg/L	1		08/07/20 0709	08/07/20 2124	KHL

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**61.0**	0.400	mg/L	1		08/07/20 0709	08/07/20 2124	KHL
Iron	**3.34**	0.0800	mg/L	1		08/07/20 0709	08/07/20 2124	KHL
Magnesium	**6.18**	0.400	mg/L	1		08/07/20 0709	08/07/20 2124	KHL

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20G0965

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20G0965-03	**Collection Date:**	07/30/2020 20:30

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4, Rv. 2 (1993)								
COD, Total	**500**	50	mg/L	1		08/05/20 0958	08/06/20 1533	EIP
SM 2540 D-2011								
Total Suspended Solids	**120**	20	mg/L	20		08/04/20 1612	08/05/20 1014	EIP

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Aluminum	**0.581**	0.0050	mg/L	1	**B12**	08/03/20 0816	08/04/20 1752	GHW
Copper	**0.278**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1752	GHW
Lead	**0.0399**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1752	GHW
Zinc	**0.834**	0.0050	mg/L	1	**B14**	08/03/20 0816	08/04/20 1752	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**420**	0.999	mg/L	1		08/07/20 0709	08/07/20 2127	KHL

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**146**	0.400	mg/L	1		08/07/20 0709	08/07/20 2127	KHL
Iron	**4.09**	0.0800	mg/L	1		08/07/20 0709	08/07/20 2127	KHL
Magnesium	**13.2**	0.400	mg/L	1		08/07/20 0709	08/07/20 2127	KHL

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20G0965

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20G0965-04	**Collection Date:**	07/30/2020 20:30

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4, Rv. 1 (1993)								
Cyanide, Total	<0.0050	0.0050	mg/L	1		08/03/20 1137	08/03/20 1438	SRZ
EPA 410.4, Rv. 2 (1993)								
COD, Total	**2600**	250	mg/L	1		08/05/20 0958	08/06/20 1533	EIP
SM 4500-NH3 B-2011								
Ammonia as N	**19**	1.0	mg/L	1		08/03/20 0920	08/03/20 1145	VAS

Metals Total by CVAA	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1, Rv. 3 (1994)								
Mercury	<0.00057	0.00057	mg/L	1		08/05/20 0908	08/05/20 1335	LNR

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Arsenic	**0.0139**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1756	GHW
Selenium	<0.0050	0.0050	mg/L	1		08/03/20 0816	08/04/20 1756	GHW
Silver	<0.0010	0.0010	mg/L	1		08/03/20 0816	08/04/20 1756	GHW
Cadmium	**0.000956**	0.000250	mg/L	1		08/03/20 0816	08/04/20 1756	GHW
Lead	**0.0384**	0.0010	mg/L	1		08/03/20 0816	08/04/20 1756	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**398**	0.999	mg/L	1		08/08/20 0751	08/10/20 1719	LSJ

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**139**	0.400	mg/L	1		08/08/20 0751	08/10/20 1719	LSJ
Iron	**4.41**	0.0800	mg/L	1		08/08/20 0751	08/10/20 1719	LSJ
Magnesium	**12.5**	0.400	mg/L	1		08/08/20 0751	08/10/20 1719	LSJ

Definitions

B12:	Target analyte detected in initial calibration blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.
B14:	Target analyte detected in method blank >2.2 times the MDL but less than the reporting limit. Concentration found in the samples was 10 times the concentration found in the blank. No impact on data.
mg/L:	Milligrams per Liter
RL:	Reporting Limit

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20G0965

Project Requested Certification(s)

Microbac Laboratories Inc., - Marietta, OH	
E87551	Florida Department of Health
Microbac Laboratories, Inc. - Baltimore	
460285	Commonwealth of Virginia (NELAC) - Baltimore
E871126	Florida - NELAC

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included. ***The services were provided under and subject to Microbac's standard terms and conditions which can be located and reviewed at <https://www.microbac.com/standard-terms-conditions>.***

Reviewed and Approved By:



Marissa Mamone
Client Relations
Reported: 08/25/2020 11:39

MICROBAC

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20G0965

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 7/8/2020
Route:

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH	A
500ml-Bottle HDPE-H2SO4	B
500ml-Bottle HDPE-HNO3	C
½Gal-Jug LDPE-H2SO4	D

Client Sample ID: Site # 8 Outfall 002 Sector K
Lab Sample ID: 20G0965-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 7/30/2020 20:30

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
TSS	SM 2540 D-2011		7.00 days
M_Fe_ICP	EPA 200.7, Rv. 4.4 (1994)		180.00 days
M_Al_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cu_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Zn_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Container(s)	Designator
500ml-Bottle HDPE-H2SO4	A
500ml-Bottle HDPE-HNO3	B
1L-Bottle HDPE	C

Client Sample ID: Site # 8 Outfall 002 Sector N
Lab Sample ID: 20G0965-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 7/30/2020 20:30

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
CN_Total_Seal	EPA 335.4, Rv. 1 (1993)		14.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
NH3_Titration	SM 4500-NH3 B-2011		28.00 days
Hg_Total	EPA 245.1, Rv. 3 (1994)		28.00 days
M_Ag_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_As_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cd_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Mg_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

MICROBAC

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20G0965

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 7/8/2020
Route:

M_Se_ICPMS — EPA 200.8, Rv. 5.4 (1994) — 180.00 days

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH	A
500ml-Bottle HDPE-H2SO4	B
500ml-Bottle HDPE-HNO3	C
½Gal-Jug LDPE-H2SO4	D

Sampled/Relinquished by: Margaret King	Date/Time: 7/30/20 09:30 pm	Received by: Brian Nunez
Printed Name: Customer Margaret King		Printed Name:
Relinquished by: Brian Nunez	Date/Time:	Received by:
Printed Name:		Printed Name: Rick McBride
Relinquished by: Rick McBride	Date/Time: 7/31/2020	Received by: R. Price 7/31/2020
Printed Name: Rick McBride		Printed Name: R. PRICE/MSL 10:32

As Received at Laboratory: On Ice: (Yes) / No Temp: 3.4 °C Thermometer ID:_____ Total Containers: 14

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

RELINQUISHED BY: Roger Price Time:
ROBER PRICE DATE: 7/31/2020 (MSL)

7/31/2020 11:50

7/31/2020 15:00

7/31/2020 1520

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Microbac Laboratories, Inc., Baltimore Division
Control # 606-03
Effective Date: 11/30/2016
Page 1 of 1

Number of Coolers Received: 1
Client: APEX
Form Completed By: JESSICA

Receipt Date / Time: 7-3(-2020
Work Order # 20G0962, G0965, 0963, A0471

☒ Microbac ☐ Client ☐ UPS ☐ FedEx

Shipper:
Custody Tape Intact: YES / NO / NA
Containers Intact: YES / NO
Sample Received on Ice or refrigerated: YES / NO / NA
Infrared (IR) Temperature: 3.4 °C

Chain of Custody Present with shipment: YES / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / NA
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity:

A -	___ Unpreserved	4 H2SO4	4 HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid:	If preserved pH <2___, pH >10___
B -	___ Unpreserved	2 H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
C -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
D -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
E -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
H -	4 Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
K -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
L -	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
M-	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
P -	___ Unpreserved	___ H2SO4 2	HNO3	___ HCl	___ NaOH 2	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
W-	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
V -	___ Unpreserved	___ HCl	___ HCl / Ascorbic Acid	___ HCl / NaTHIO **(Checked at time of Analysis)**			
F -	___ Unpreserved	___ NaTHIO **(Checked at time of Analysis)**					
S -	___ Unpreserved	___ NaTHIO **(Checked at time of Analysis)**					
SN-	___ Unpreserved	___ NaTHIO	___ NaTHIO/EDTA **(Checked at time of Analysis)**				
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
	___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

Describe preservation requirements not met:

All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*

Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added


H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:

Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____

5.0 RELEVANT SITE MAPS



APEX

Apex Companies, LLC
9700 Capital Court
Suite 100
Manassas, VA 20110
Telephone: (703) 396-6730
Fax: (703) 396-6743

Figure 2
Site 8
3200 Benning Road NE, Washington, DC 21002
SWMA Waste/Recycling Facility

0 30 60 120 180 240 Feet

Coordinate System: Lambert Conformal Conic
Central Meridian: 77°0'0"W
1st Std Parallel: 38°18'0"N
2nd Std Parallel: 39°27'0"N
Latitude of Origin: 37°40'0"N

N

Department of Public Works
Washington, DC
SWPPP 2019
Area: 8.45 Acres
2017 USGS Orthoimage
.16 Meter Resolution

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20H0585

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 09/10/2020
Reported: 09/28/2020

Analytical Testing Parameters

Client Sample ID: Site # 8 Outfall 001 Sector N
Sample Matrix: Aqueous
Lab Sample ID: 20H0585-01
Collected By: Customer
Collection Date: 09/09/2020 14:56

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4, Rv. 2 (1993)								
COD, Total	**560**	50	mg/L	1		09/19/20 0954	09/19/20 1340	EIP
SM 2540 D-2011								
Total Suspended Solids	**88**	20	mg/L	20		09/11/20 1323	09/12/20 0950	EIP

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Copper	**0.0588**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1533	GHW
Lead	**0.0177**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1533	GHW
Zinc	**0.367**	0.0250	mg/L	5		09/15/20 0821	09/15/20 1533	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**164**	0.999	mg/L	1		09/21/20 0555	09/21/20 1433	LSJ

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Aluminum	**1.19**	0.160	mg/L	1		09/21/20 0555	09/21/20 1433	LSJ
Calcium	**56.2**	0.400	mg/L	1		09/21/20 0555	09/21/20 1433	LSJ
Iron	**3.54**	0.0800	mg/L	1		09/21/20 0555	09/21/20 1433	LSJ
Magnesium	**5.73**	0.400	mg/L	1		09/21/20 0555	09/21/20 1433	LSJ

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20H0585

Client Sample ID:	Site # 8 Outfall 001 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20H0585-02	**Collection Date:**	09/09/2020 14:56

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4, Rv. 1 (1993)								
Cyanide, Total	<0.0050	0.0050	mg/L	1		09/16/20 0843	09/16/20 1307	SRZ
EPA 410.4, Rv. 2 (1993)								
COD, Total	**850**	50	mg/L	1		09/19/20 0954	09/19/20 1340	EIP
SM 4500-NH3 C-2011								
Ammonia as N	**2.8**	1.0	mg/L	1		09/14/20 1240	09/14/20 1445	EWP

Metals Total by CVAA	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1, Rv. 3 (1994)								
Mercury	<0.00057	0.00057	mg/L	1		09/11/20 1006	09/11/20 1415	LNR

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Arsenic	<0.0050	0.0050	mg/L	5		09/15/20 0821	09/15/20 1534	GHW
Cadmium	<0.00125	0.00125	mg/L	5		09/15/20 0821	09/15/20 1534	GHW
Lead	**0.0174**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1534	GHW
Magnesium	**5.36**	0.0250	mg/L	5	**B2**	09/15/20 0821	09/15/20 1534	GHW
Selenium	<0.0250	0.0250	mg/L	5	**B11**	09/15/20 0821	09/15/20 1534	GHW
Silver	<0.0050	0.0050	mg/L	5		09/15/20 0821	09/15/20 1534	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**166**	0.999	mg/L	1		09/23/20 0557	09/23/20 1522	LSJ

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**56.9**	0.400	mg/L	1		09/23/20 0557	09/23/20 1522	LSJ
Magnesium	**5.73**	0.400	mg/L	1		09/23/20 0557	09/23/20 1522	LSJ

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20H0585

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20H0585-03	**Collection Date:**	09/09/2020 14:42

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 410.4, Rv. 2 (1993)								
COD, Total	**890**	50	mg/L	1		09/19/20 0954	09/19/20 1340	EIP
SM 2540 D-2011								
Total Suspended Solids	**62**	20	mg/L	20		09/11/20 1323	09/12/20 0950	EIP

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Copper	**0.0605**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1535	GHW
Lead	**0.0140**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1535	GHW
Zinc	**0.286**	0.0250	mg/L	5		09/15/20 0821	09/15/20 1535	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**480**	0.999	mg/L	1		09/21/20 0555	09/21/20 1436	LSJ

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Aluminum	**0.637**	0.160	mg/L	1		09/21/20 0555	09/21/20 1436	LSJ
Calcium	**160**	0.400	mg/L	1		09/21/20 0555	09/21/20 1436	LSJ
Iron	**4.78**	0.0800	mg/L	1		09/21/20 0555	09/21/20 1436	LSJ
Magnesium	**19.4**	0.400	mg/L	1		09/21/20 0555	09/21/20 1436	LSJ

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20H0585

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20H0585-04	**Collection Date:**	09/09/2020 14:42

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 335.4, Rv. 1 (1993)								
Cyanide, Total	<0.0050	0.0050	mg/L	1		09/16/20 0843	09/16/20 1309	SRZ
EPA 410.4, Rv. 2 (1993)								
COD, Total	**1000**	50	mg/L	1		09/19/20 0954	09/19/20 1340	EIP
SM 4500-NH3 C-2011								
Ammonia as N	**4.8**	1.0	mg/L	1		09/14/20 1240	09/14/20 1445	EWP

Metals Total by CVAA	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 245.1, Rv. 3 (1994)								
Mercury	<0.00057	0.00057	mg/L	1		09/11/20 1006	09/11/20 1417	LNR

Metals Total by ICPMS	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.2/EPA 200.8, Rv. 5.4 (1994)								
Arsenic	**0.0058**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1537	GHW
Cadmium	<0.00125	0.00125	mg/L	5		09/15/20 0821	09/15/20 1537	GHW
Lead	**0.0177**	0.0050	mg/L	5		09/15/20 0821	09/15/20 1537	GHW
Magnesium	**17.0**	0.0250	mg/L	5	**B2**	09/15/20 0821	09/15/20 1537	GHW
Selenium	<0.0250	0.0250	mg/L	5	**B11**	09/15/20 0821	09/15/20 1537	GHW
Silver	<0.0050	0.0050	mg/L	5		09/15/20 0821	09/15/20 1537	GHW

Analyses Subcontracted to: Microbac Laboratories Inc., - Marietta, OH

Inorganics Total	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
Calculation								
Hardness (as CaCO3)	**452**	0.999	mg/L	1		09/23/20 0557	09/23/20 1526	LSJ

Metals Total by ICP	Result	RL	Units	Dilution	Note	Prepared	Analyzed	Analyst
EPA 200.7, Rv. 4.4 (1994)								
Calcium	**152**	0.400	mg/L	1		09/23/20 0557	09/23/20 1526	LSJ
Magnesium	**17.8**	0.400	mg/L	1		09/23/20 0557	09/23/20 1526	LSJ

Definitions

B11:	Target analyte detected in continuing calibration blank >2.2 times the MDL but less than the reporting limit. Sample result was less than the reporting limit. No impact on data.
B2:	Target analyte detected in method blank at or above reporting limit. Concentration found in the samples was 10 times the concentration found in the method blank.
mg/L:	Milligrams per Liter
RL:	Reporting Limit

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20H0585

Project Requested Certification(s)

Microbac Laboratories Inc., - Marietta, OH	
E87551	Florida Department of Health
Microbac Laboratories, Inc. - Baltimore	
460285	Commonwealth of Virginia (NELAC) - Baltimore
E871126	Florida - NELAC

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included. ***The services were provided under and subject to Microbac's standard terms and conditions which can be located and reviewed at <https://www.microbac.com/standard-terms-conditions>.***

Reviewed and Approved By:

Evelyn Shinas

Customer Relationship Coordinator

Reported: 09/28/2020 17:50

MICROBAC®

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20H0585

TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 8/10/2020
Route:

Client Sample ID: Site # 8 Outfall 001 Sector ~~X~~ N
Lab Sample ID: 20H0585-01
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 14 56

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
TSS	SM 2540 D-2011		7.00 days
M_Fe_ICP	EPA 200.7, Rv. 4.4 (1994)		180.00 days
M_Al_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cu_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Zn_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Container(s)	Designator
500ml-Bottle HDPE-H2SO4	A
500ml-Bottle HDPE-HNO3	B
1L-Bottle HDPE	C

Client Sample ID: Site # 8 Outfall 001 Sector ~~N~~ K
Lab Sample ID: 20H0585-02
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 14 56

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
CN_Total_Seal	EPA 335.4, Rv. 1 (1993)		14.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
NH3_Titration	SM 4500-NH3 B-2011		28.00 days
Hg_Total	EPA 245.1, Rv. 3 (1994)		28.00 days
M_Ag_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_As_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cd_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Mg_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Se_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 8/10/2020
Route:

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH ✓	A
500ml-Bottle HDPE-H2SO4 ✓	B
500ml-Bottle HDPE-HNO3 ✓	C
½Gal-Jug LDPE-H2SO4	D

Client Sample ID: Site # 8 Outfall 002 Sector K N
Lab Sample ID: 20H0585-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1947

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
TSS	SM 2540 D-2011		7.00 days
M_Fe_ICP	EPA 200.7, Rv. 4.4 (1994)		180.00 days
M_Al_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cu_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Zn_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Container(s)	Designator
500ml-Bottle HDPE-H2SO4 ✓	A
500ml-Bottle HDPE-HNO3 ✓	B
1L-Bottle HDPE ✓	C

Client Sample ID: Site # 8 Outfall 002 Sector K L
Lab Sample ID: 20H0585-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 1942

Analysis	Method	Field Results/Comments	Hold Time
Hard_ICP_Calc	NA		180.00 days
CN_Total_Seal	EPA 335.4, Rv. 1 (1993)		14.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
NH3_Titration	SM 4500-NH3 B-2011		28.00 days
Hg_Total	EPA 245.1, Rv. 3 (1994)		28.00 days
M_Ag_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_As_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cd_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Mg_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

MICROBAC®

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20H0585

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 8/10/2020
Route:

M_Se_ICPMS — EPA 200.8, Rv. 5.4 (1994) — 180.00 days

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH	A
500ml-Bottle HDPE-H2SO4	B
500ml-Bottle HDPE-HNO3	C
½Gal-Jug LDPE-H2SO4	D

Sampled/Relinquished by:	Date/Time:	Received by:
Printed Name: Customer		Printed Name:
Relinquished by:	Date/Time: 9/10/20 0930	Received by:
Printed Name: CAROLYN PITERA		Printed Name:
Relinquished by:	Date/Time: 9/10/20 1245	Received by: 9/10/20
Printed Name:		Printed Name: 1515

As Received at Laboratory: On Ice: (Yes) / No Temp: 23 °C Thermometer ID:_____ Total Containers: 14

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

Microbac Laboratories, Inc.
2101 Van Deman Street | Baltimore, MD 21224 | 410.633.1800 p | www.microbac.com

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Number of Coolers Received: 1
Client: Apex Companies
Form Completed By: Kindal Shriver

Receipt Date / Time: 9/10/2020 1519
Work Order # 20H0535

Shipper:	☐ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact:	YES / NO / NA
Containers Intact:	YES / NO
Sample Received on Ice or refrigerated:	YES / NO / NA
	Infrared (IR) Temperature: 2.5 °C
Chain of Custody Present with shipment:	YES / NO
Sample Bottle IDs agree with COC:	YES / NO
Preservation requirements met:	YES / NO / Not Checked
Correct Number of Containers / Sample Volume:	YES / NO (If No, contact client immediately)
Headspace in container:	YES / NO / NA
Type of Sample:	Water Soil Wipes Oil Filter Solid Sludge Food Swab Other

Container Type / Quantity:

A - ___ Unpreserved ___ H_2SO_4 1 HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid: If preserved pH <2___, pH >10___
B - ___ Unpreserved 4 H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
C - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
D - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
E - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
H - 2 Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
K - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
L - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
M- ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
P - ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl 2 NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
W- ___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN- ___ Unpreserved ___ NaTHIO ___ NaTHIO/EDTA **(Checked at time of Analysis)**

___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___
___ Unpreserved ___ H_2SO_4 ___ HNO_3 ___ HCl ___ NaOH ___ NaOH/Ascorbic Acid If preserved pH <2___, pH >10___

Describe preservation requirements not met:

All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*

Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added

H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:

Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____

Microbac Laboratories, Inc. - Baltimore

MICROBAC®

SUBCONTRACT ORDER

20H0585

SENDING LABORATORY:

Microbac Laboratories, Inc. - Baltimore
2101 Van Deman Street
Baltimore, MD 21224
Phone: 410.633.1800
Lab Manager: Evelyn Shinas
Email: evelyn.shinas@microbac.com

RECEIVING LABORATORY:

Microbac - OVD
158 Starlite Dr
Marietta, OH 45750
Phone: (800) 373-4071

Proiect Info:

Project Name: DPW Site #8
Project No: DPW- Site# 8

Client: Apex Companies, LLC
Project Type: ENV-StormWater
Project Location: Washington, DC

Report TAT: **7**
Due: **09/22/2020 17:00**

Sample ID: 20H0585-01 **Sampled: 09/09/2020 14:56**
Matrix: Aqueous **Sampler: Customer**

Analysis	Method	Analysis Due	Expires	Network $
M_Al_ICPMS Aluminum	**EPA 200.8, Rv. 5.4 (1994)** 0.005 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 5.00**
M_Ca_ICP Calcium	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 10.00**
Please include Hardness Calculation!				
M_Fe_ICP Iron	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 5.00**
M_Mg_ICP Magnesium	**EPA 200.7, Rv. 4.4 (1994)** 0.4 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 10.00**

Containers Supplied:
B: 500ml-Bottle HDPE-HNO3

Sample ID: 20H0585-02 **Sampled: 09/09/2020 14:56**
Matrix: Aqueous **Sampler: Customer**

Analysis	Method	Analysis Due	Expires	Network $
M_Ca_ICP Calcium	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 10.00**
Please include Hardness Calculation!				
M_Mg_ICP Magnesium	**EPA 200.7, Rv. 4.4 (1994)** 0.4 mg/L	**09/22/2020 16:00**	**03/08/2021 14:56**	**$ 10.00**

Microbac Laboratories, Inc. - Baltimore

MICROBAC®

SUBCONTRACT ORDER

20H0585

Sample ID: 20H0585-03 **Sampled: 09/09/2020 14:42**

Matrix: Aqueous **Sampler: Customer**

Analysis	Method	Analysis Due	Expires	Network $
M_Ca_ICP Calcium	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:42**	**$ 10.00**
Please include Hardness Calculation!				
M_Fe_ICP Iron	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:42**	**$ 5.00**
M_Mg_ICP Magnesium	**EPA 200.7, Rv. 4.4 (1994)** 0.4 mg/L	**09/22/2020 16:00**	**03/08/2021 14:42**	**$ 10.00**

Containers Supplied:
B: 500ml-Bottle HDPE-HNO3

Sample ID: 20H0585-04 **Sampled: 09/09/2020 14:42**

Matrix: Aqueous **Sampler: Customer**

Analysis	Method	Analysis Due	Expires	Network $
M_Ca_ICP Calcium	**EPA 200.7, Rv. 4.4 (1994)** 0.2 mg/L	**09/22/2020 16:00**	**03/08/2021 14:42**	**$ 10.00**
Please include Hardness Calculation!				
M_Mg_ICP Magnesium	**EPA 200.7, Rv. 4.4 (1994)** 0.4 mg/L	**09/22/2020 16:00**	**03/08/2021 14:42**	**$ 10.00**

Released By	Date	Received By	Date
HMed	09/21/2020		
Released By	Date	Received By	Date

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20L0296

Project Description

DPW- Site# 8

For:

Andrea Owen Heller

Apex Companies, LLC

9700 Capital Court #100

Manassas, VA 20110



Customer Relationship Coordinator

Evelyn Shinas

Wednesday, January 6, 2021

Please find enclosed the analytical results for the samples you submitted to Microbac Laboratories. Review and compilation of your report was completed by Microbac Laboratories, Inc. - Baltimore. If you have any questions, comments, or require further assistance regarding this report, please contact your service representative listed above.

I certify that all test results meet all of the requirements of the accrediting authority listed within this report. Analytical results are reported on a 'as received' basis unless specified otherwise. Analytical results for solids with units ending in (dry) are reported on a dry weight basis. A statement of uncertainty for each analysis is available upon request. This laboratory report shall not be reproduced, except in full, without the written approval of Microbac Laboratories. The reported results are related only to the samples analyzed as received.

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20L0296

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110

Project Name: DPW- Site# 8

Project / PO Number: N/A
Received: 12/08/2020
Reported: 01/06/2021

Sample Summary Report

Sample Name	Laboratory ID	Client Matrix	Sample Type	Sample Begin	Sample Taken	Lab Received
Site # 8 Outfall 001 Sector K	20L0296-01	Aqueous	Grab		12/04/20 20:02	12/08/20 15:57
Site # 8 Outfall 001 Sector N	20L0296-02	Aqueous	Grab		12/04/20 20:02	12/08/20 15:57
Site # 8 Outfall 002 Sector K	20L0296-03	Aqueous	Grab		12/04/20 20:02	12/08/20 15:57
Site # 8 Outfall 002 Sector N	20L0296-04	Aqueous	Grab		12/04/20 20:02	12/08/20 15:57

CERTIFICATE OF ANALYSIS

20L0296

Analytical Testing Parameters

Client Sample ID:	Site # 8 Outfall 001 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20L0296-01	**Collection Date:**	12/04/2020 20:02

Inorganics Total	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4, Rv. 1 (1993)									
Cyanide, Total	<0.0026	0.0026	0.0050	mg/L	1		12/10/20 0820	12/10/20 1025	SRZ
Method: EPA 410.4, Rv. 2 (1993)									
COD, Total	**140**		50	mg/L	1		12/12/20 1145	12/12/20 1436	EIP
Method: SM 4500-NH3 C-2011									
Ammonia as N	<1.0		1.0	mg/L	1		12/09/20 1259	12/09/20 1446	JFL

Metals Total by CVAA	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1, Rv. 3 (1994)									
Mercury	<0.00057		0.00057	mg/L	1	**L2**	12/10/20 0826	12/10/20 1443	AVF

Metals Total by ICPMS	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.8, Rv. 5.4 (1994)									
Arsenic	**0.0044**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1353	GHW
Cadmium	**0.00198**		0.000250	mg/L	1		12/10/20 1549	12/14/20 1353	GHW
Lead	**0.0682**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1353	GHW
Selenium	**0.0014**	0.0014	0.0500	mg/L	10	**B11, J**	12/10/20 1549	12/14/20 1432	GHW
Silver	<0.0010		0.0010	mg/L	1		12/10/20 1549	12/14/20 1353	GHW
Method: EPA 200.2/EPA 6020B									
Magnesium	**6.15**		0.0500	mg/L	10		12/10/20 1549	12/14/20 1432	GHW

CERTIFICATE OF ANALYSIS

20L0296

Client Sample ID:	Site # 8 Outfall 001 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20L0296-02	**Collection Date:**	12/04/2020 20:02

Inorganics Total	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4, Rv. 2 (1993)									
COD, Total	**240**		50	mg/L	1		12/12/20 1145	12/12/20 1436	EIP
Method: SM 2540 D-2011									
Total Suspended Solids	**2600**		40	mg/L	40		12/10/20 1117	12/11/20 1139	DPG

Metals Total by ICP	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7, Rv. 4.4 (1994)									
Iron	**9.0**		0.20	mg/L	1		12/10/20 1552	12/14/20 1424	GHW

Metals Total by ICPMS	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.8, Rv. 5.4 (1994)									
Aluminum	**1.43**		0.0750	mg/L	10		12/10/20 1549	12/14/20 1433	GHW
Copper	**0.0522**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1355	GHW
Lead	**0.0806**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1355	GHW
Zinc	**0.333**		0.0050	mg/L	1		12/10/20 1549	12/14/20 1355	GHW

CERTIFICATE OF ANALYSIS

20L0296

Client Sample ID:	Site # 8 Outfall 002 Sector K		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20L0296-03	**Collection Date:**	12/04/2020 20:02

Inorganics Total	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 335.4, Rv. 1 (1993)									
Cyanide, Total	<0.0026	0.0026	0.0050	mg/L	1		12/10/20 0820	12/10/20 1024	SRZ
Method: EPA 410.4, Rv. 2 (1993)									
COD, Total	**130**		50	mg/L	1		12/12/20 1145	12/12/20 1436	EIP
Method: SM 4500-NH3 C-2011									
Ammonia as N	<1.0		1.0	mg/L	1		12/09/20 1259	12/09/20 1446	JFL

Metals Total by CVAA	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 245.1, Rv. 3 (1994)									
Mercury	<0.00057		0.00057	mg/L	1	**L2**	12/10/20 0826	12/10/20 1445	AVF

Metals Total by ICPMS	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.8, Rv. 5.4 (1994)									
Arsenic	**0.0031**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1356	GHW
Cadmium	<0.000250		0.000250	mg/L	1		12/10/20 1549	12/14/20 1356	GHW
Lead	**0.0042**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1356	GHW
Selenium	<0.0014	0.0014	0.0500	mg/L	10	**B11**	12/10/20 1549	12/14/20 1435	GHW
Silver	<0.0010		0.0010	mg/L	1		12/10/20 1549	12/14/20 1356	GHW
Method: EPA 200.2/EPA 6020B									
Magnesium	**9.36**		0.0500	mg/L	10		12/10/20 1549	12/14/20 1435	GHW

CERTIFICATE OF ANALYSIS

20L0296

Client Sample ID:	Site # 8 Outfall 002 Sector N		
Sample Matrix:	Aqueous	**Collected By:**	Customer
Lab Sample ID:	20L0296-04	**Collection Date:**	12/04/2020 20:02

Inorganics Total	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 410.4, Rv. 2 (1993)									
COD, Total	**96**		50	mg/L	1		12/12/20 1145	12/12/20 1436	EIP
Method: SM 2540 D-2011									
Total Suspended Solids	**35**		10	mg/L	10		12/10/20 1117	12/11/20 1139	DPG

Metals Total by ICP	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.7, Rv. 4.4 (1994)									
Iron	**7.4**		0.20	mg/L	1		12/10/20 1552	12/14/20 1344	GHW

Metals Total by ICPMS	Result	MDL	RL	Units	DF	Note	Prepared	Analyzed	Analyst
Method: EPA 200.2/EPA 200.8, Rv. 5.4 (1994)									
Aluminum	**0.338**		0.0750	mg/L	10		12/10/20 1549	12/14/20 1418	GHW
Copper	**0.0145**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1335	GHW
Lead	**0.0069**		0.0010	mg/L	1		12/10/20 1549	12/14/20 1335	GHW
Zinc	**0.0555**		0.0050	mg/L	1		12/10/20 1549	12/14/20 1335	GHW

Batch Log Summary

Method	Batch	Laboratory ID	Client / Source ID
SM 4500-NH3 C-2011	2050160	20L0296-03	Site # 8 Outfall 002 Sector K
		2050160-MS2	20L0823-02
		2050160-MS1	20L0823-01
		2050160-BS1	
		2050160-DUP2	20L0823-02
		2050160-DUP1	20L0823-01
		2050160-BLK1	
		20L0296-01	Site # 8 Outfall 001 Sector K

Method	Batch	Laboratory ID	Client / Source ID
EPA 335.4, Rv. 1 (1993)	2050212	2050212-BLK1	
		2050212-BS1	
		2050212-DUP1	20L0857-01
		2050212-MS1	20L0857-01
		20L0296-03	Site # 8 Outfall 002 Sector K
		20L0296-01	Site # 8 Outfall 001 Sector K
		2050212-DUP2	20L0008-01
		2050212-MS2	20L0008-01

Method	Batch	Laboratory ID	Client / Source ID
EPA 245.1, Rv. 3 (1994)	2050213	2050213-MRL1	
		2050213-BLK1	
		2050213-BS1	
		2050213-DUP1	20K1393-01
		2050213-MS1	20K1393-01
		2050213-MSD1	20K1393-01
		20L0296-01	Site # 8 Outfall 001 Sector K
		20L0296-03	Site # 8 Outfall 002 Sector K

Method	Batch	Laboratory ID	Client / Source ID
SM 2540 D-2011	2050215	2050215-BS3	
		2050215-BS2	
		20L0296-02	Site # 8 Outfall 001 Sector N
		2050215-BS1	
		2050215-BLK1	
		2050215-BLK2	
		2050215-BLK3	
		2050215-DUP1	20G2094-01
		2050215-DUP2	20G2094-03
		2050215-DUP3	20L0023-03

SM 2540 D-2011	2050215	2050215-DUP4	20L0153-01
		2050215-DUP5	20L0154-01
		20L0296-04	Site # 8 Outfall 002 Sector N

Method	Batch	Laboratory ID	Client / Source ID
EPA 6020B	2050269	2050269-BLK1	
EPA 200.8, Rv. 5.4 (1994)		2050269-BLK1	
EPA 6020B		2050269-BS1	
EPA 200.8, Rv. 5.4 (1994)		2050269-BS1	
		20L0296-04	Site # 8 Outfall 002 Sector N
		2050269-DUP1	20L0296-04
		2050269-MS1	20L0296-04
		20L0296-01	Site # 8 Outfall 001 Sector K
		20L0296-02	Site # 8 Outfall 001 Sector N
		20L0296-03	Site # 8 Outfall 002 Sector K
		20L0296-04RE1	Site # 8 Outfall 002 Sector N
EPA 6020B		2050269-DUP2	20L0296-04RE1
EPA 200.8, Rv. 5.4 (1994)		2050269-DUP2	20L0296-04RE1
		2050269-MS2	20L0296-04RE1
EPA 6020B		2050269-MS2	20L0296-04RE1
		20L0296-01RE1	Site # 8 Outfall 001 Sector K
EPA 200.8, Rv. 5.4 (1994)		20L0296-01RE1	Site # 8 Outfall 001 Sector K
		20L0296-02RE1	Site # 8 Outfall 001 Sector N
		20L0296-03RE1	Site # 8 Outfall 002 Sector K
EPA 6020B		20L0296-03RE1	Site # 8 Outfall 002 Sector K

Method	Batch	Laboratory ID	Client / Source ID
EPA 200.7, Rv. 4.4 (1994)	2050271	2050271-BLK1	
		2050271-BS1	
		20L0296-04	Site # 8 Outfall 002 Sector N
		2050271-DUP1	20L0296-04
		2050271-MS1	20L0296-04
		20L0296-02	Site # 8 Outfall 001 Sector N

Method	Batch	Laboratory ID	Client / Source ID
EPA 410.4, Rv. 2 (1993)	2050417	2050417-MS1	20K0432-01
		20L0296-02	Site # 8 Outfall 001 Sector N
		20L0296-01	Site # 8 Outfall 001 Sector K
		20L0296-04	Site # 8 Outfall 002 Sector N
		20L0296-03	Site # 8 Outfall 002 Sector K
		2050417-MS2	20L0031-01
		2050417-BS1	
		2050417-DUP3	20L0186-01
		2050417-DUP2	20L0031-01

EPA 410.4, Rv. 2 (1993)	2050417	2050417-DUP1	20K0432-01
		2050417-BLK1	
		2050417-MS3	20L0186-01

Batch Quality Control Summary: Microbac Laboratories, Inc. - Baltimore

Inorganics Total	Result		RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050160 - WetChem_Water_Prep - SM 4500-NH3 C-2011											
Blank (2050160-BLK1)				Prepared & Analyzed: 12/09/2020							
Ammonia as N	<1.0		1.0	mg/L							
LCS (2050160-BS1)				Prepared & Analyzed: 12/09/2020							
Ammonia as N	18.8		1.0	mg/L	20		93.8	90-110			
Duplicate (2050160-DUP1)		**Source: 20L0823-01**		Prepared & Analyzed: 12/09/2020							
Ammonia as N	<1.0		1.0	mg/L		ND				20	
Duplicate (2050160-DUP2)		**Source: 20L0823-02**		Prepared & Analyzed: 12/09/2020							
Ammonia as N	<1.0		1.0	mg/L		ND				20	
Matrix Spike (2050160-MS1)		**Source: 20L0823-01**		Prepared & Analyzed: 12/09/2020							
Ammonia as N	18.2		1.0	mg/L	20	ND	91.0	80-120			
Matrix Spike (2050160-MS2)		**Source: 20L0823-02**		Prepared & Analyzed: 12/09/2020							
Ammonia as N	18.8		1.0	mg/L	20	ND	93.8	80-120			
Batch 2050212 - WetChem_Water_Prep - EPA 335.4, Rv. 1 (1993)											
Blank (2050212-BLK1)				Prepared & Analyzed: 12/10/2020							
Cyanide, Total	<0.0026	0.0026	0.0050	mg/L							
LCS (2050212-BS1)				Prepared & Analyzed: 12/10/2020							
Cyanide, Total	0.107	0.0026	0.0050	mg/L	0.10		107	90-110			
Duplicate (2050212-DUP1)		**Source: 20L0857-01**		Prepared & Analyzed: 12/10/2020							
Cyanide, Total	0.0196	0.0026	0.0050	mg/L		0.0201			2.52	20	
Duplicate (2050212-DUP2)		**Source: 20L0008-01**		Prepared & Analyzed: 12/10/2020							
Cyanide, Total	0.0103	0.0026	0.0050	mg/L		0.0105			1.92	20	
Matrix Spike (2050212-MS1)		**Source: 20L0857-01**		Prepared & Analyzed: 12/10/2020							
Cyanide, Total	0.0558	0.0026	0.0050	mg/L	0.050	0.0201	71.4	90-110			
Matrix Spike (2050212-MS2)		**Source: 20L0008-01**		Prepared & Analyzed: 12/10/2020							
Cyanide, Total	0.0435	0.0026	0.0050	mg/L	0.050	0.0105	66.0	90-110			
Batch 2050215 - WetChem_Water_Prep - SM 2540 D-2011											
Blank (2050215-BLK1)				Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	<1.0		1.0	mg/L							
Blank (2050215-BLK2)				Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	<1.0		1.0	mg/L							
Blank (2050215-BLK3)				Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	<1.0		1.0	mg/L							
LCS (2050215-BS1)				Prepared: 12/10/2020 Analyzed: 12/11/2020							

Inorganics Total	Result	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050215 - WetChem_Water_Prep - SM 2540 D-2011										
LCS (2050215-BS1)			Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	94	10	mg/L	100		94.0	90-110			
LCS (2050215-BS2)			Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	97	10	mg/L	100		97.0	90-110			
LCS (2050215-BS3)			Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	90	10	mg/L	100		90.0	90-110			
Duplicate (2050215-DUP1)		**Source: 20G2094-01**	Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	71	10	mg/L		73			2.78	10	
Duplicate (2050215-DUP2)		**Source: 20G2094-03**	Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	88	10	mg/L		91			3.35	10	
Duplicate (2050215-DUP3)		**Source: 20L0023-03**	Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	130	20	mg/L		140			1.48	10	
Duplicate (2050215-DUP4)		**Source: 20L0153-01**	Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	240	200	mg/L		240			0.00	10	
Duplicate (2050215-DUP5)		**Source: 20L0154-01**	Prepared: 12/10/2020 Analyzed: 12/11/2020							
Total Suspended Solids	260	200	mg/L		260			0.00	10	
Batch 2050417 - WetChem_Water_Prep - EPA 410.4, Rv. 2 (1993)										
Blank (2050417-BLK1)			Prepared & Analyzed: 12/12/2020							
COD, Total	<50	50	mg/L							
LCS (2050417-BS1)			Prepared & Analyzed: 12/12/2020							
COD, Total	999	50	mg/L	1000		99.8	90-110			
Duplicate (2050417-DUP1)		**Source: 20K0432-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	81.8	50	mg/L		77.9			4.88	20	
Duplicate (2050417-DUP2)		**Source: 20L0031-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	143	50	mg/L		145			1.32	20	
Duplicate (2050417-DUP3)		**Source: 20L0186-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	<50	50	mg/L		40.4			9.21	20	
Matrix Spike (2050417-MS1)		**Source: 20K0432-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	480	50	mg/L	400	77.9	100	90-110			
Matrix Spike (2050417-MS2)		**Source: 20L0031-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	541	50	mg/L	400	145	99.0	90-110			
Matrix Spike (2050417-MS3)		**Source: 20L0186-01**	Prepared & Analyzed: 12/12/2020							
COD, Total	443	50	mg/L	400	40.4	100	90-110			

Metals Total by CVAA	Result	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050213 - Hg_Prep_Water - EPA 245.1, Rv. 3 (1994)										
Blank (2050213-BLK1)			Prepared & Analyzed: 12/10/2020							
Mercury	<0.00020	0.00020	mg/L							
LCS (2050213-BS1)			Prepared & Analyzed: 12/10/2020							

Metals Total by CVAA	Result		RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050213 - Hg_Prep_Water - EPA 245.1, Rv. 3 (1994)											
LCS (2050213-BS1)				Prepared & Analyzed: 12/10/2020							
Mercury	0.00248		0.00020	mg/L	0.0020		124	85-115			
Duplicate (2050213-DUP1)	**Source: 20K1393-01**			Prepared & Analyzed: 12/10/2020							
Mercury	<0.00020		0.00020	mg/L		ND				20	
Matrix Spike (2050213-MS1)	**Source: 20K1393-01**			Prepared & Analyzed: 12/10/2020							
Mercury	0.00185		0.00020	mg/L	0.0020	ND	92.7	70-130			
Matrix Spike Dup (2050213-MSD1)	**Source: 20K1393-01**			Prepared & Analyzed: 12/10/2020							
Mercury	0.00216		0.00020	mg/L	0.0020	ND	108	70-130	15.3	20	

Metals Total by ICP	Result		RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050271 - EPA 200.2 ICP_W - EPA 200.7, Rv. 4.4 (1994)											
Blank (2050271-BLK1)				Prepared: 12/10/2020 Analyzed: 12/14/2020							
Iron	<0.20		0.20	mg/L							
LCS (2050271-BS1)				Prepared: 12/10/2020 Analyzed: 12/14/2020							
Iron	4.90		0.20	mg/L	5.0		98.1	85-115			
Duplicate (2050271-DUP1)	**Source: 20L0296-04**			Prepared: 12/10/2020 Analyzed: 12/14/2020							
Iron	7.28		0.20	mg/L		7.38			1.28	20	
Matrix Spike (2050271-MS1)	**Source: 20L0296-04**			Prepared: 12/10/2020 Analyzed: 12/14/2020							
Iron	12.4		0.20	mg/L	5.0	7.38	101	75-125			

Metals Total by ICPMS	Result		RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050269 - EPA 200.2 ICPMS_W - EPA 200.8, Rv. 5.4 (1994)											
Blank (2050269-BLK1)				Prepared: 12/10/2020 Analyzed: 12/14/2020							
Silver	<0.0010		0.0010	mg/L							
Aluminum	<0.0075		0.0075	mg/L							
Arsenic	<0.0010		0.0010	mg/L							
Cadmium	<0.000250		0.000250	mg/L							
Copper	<0.0010		0.0010	mg/L							
Magnesium	<0.0050		0.0050	mg/L							
Lead	<0.0010		0.0010	mg/L							
Selenium	<0.0001	0.0001	0.0050	mg/L							
Zinc	<0.0050		0.0050	mg/L							
LCS (2050269-BS1)				Prepared: 12/10/2020 Analyzed: 12/14/2020							
Silver	0.0476		0.0010	mg/L	0.0500		95.2	85-115			
Aluminum	1.88		0.0075	mg/L	2.00		94.2	85-115			
Arsenic	0.204		0.0010	mg/L	0.200		102	85-115			
Cadmium	0.184		0.000250	mg/L	0.200		91.8	85-115			
Copper	0.197		0.0010	mg/L	0.200		98.4	85-115			
Magnesium	1.96		0.0050	mg/L	2.00		97.9	85-115			
Lead	0.202		0.0010	mg/L	0.200		101	85-115			

Metals Total by ICPMS	Result	MDL	RL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 2050269 - EPA 200.2 ICPMS_W - EPA 200.8, Rv. 5.4 (1994)											
LCS (2050269-BS1)					Prepared: 12/10/2020 Analyzed: 12/14/2020						
Selenium	0.201	0.0001	0.0050	mg/L	0.200		100	85-115			
Zinc	0.197		0.0050	mg/L	0.200		98.3	85-115			
Duplicate (2050269-DUP1)		**Source: 20L0296-04**			Prepared: 12/10/2020 Analyzed: 12/14/2020						
Silver	<0.0010		0.0010	mg/L		0.0000474			14.0	20	
Arsenic	0.00356		0.0010	mg/L		0.00373			4.65	20	
Cadmium	<0.000250		0.000250	mg/L		0.000137			7.31	20	
Copper	0.0143		0.0010	mg/L		0.0145			0.940	20	
Lead	0.00688		0.0010	mg/L		0.00690			0.273	20	
Zinc	0.0552		0.0050	mg/L		0.0555			0.458	20	
Duplicate (2050269-DUP2)		**Source: 20L0296-04RE1**			Prepared: 12/10/2020 Analyzed: 12/14/2020						
Aluminum	0.316		0.0750	mg/L		0.338			6.68	20	
Magnesium	9.00		0.0500	mg/L		9.16			1.77	20	
Selenium	0.00158	0.0014	0.0500	mg/L		0.00170			7.41	20	J
Matrix Spike (2050269-MS1)		**Source: 20L0296-04**			Prepared: 12/10/2020 Analyzed: 12/14/2020						
Silver	0.0465		0.0010	mg/L	0.0500	0.0000474	92.9	70-130			
Arsenic	0.206		0.0010	mg/L	0.200	0.00373	101	70-130			
Cadmium	0.187		0.000250	mg/L	0.200	0.000137	93.3	70-130			
Copper	0.189		0.0010	mg/L	0.200	0.0145	87.5	70-130			
Lead	0.187		0.0010	mg/L	0.200	0.00690	90.3	70-130			
Zinc	0.230		0.0050	mg/L	0.200	0.0555	87.2	70-130			
Matrix Spike (2050269-MS2)		**Source: 20L0296-04RE1**			Prepared: 12/10/2020 Analyzed: 12/14/2020						
Aluminum	2.26		0.0750	mg/L	2.00	0.338	96.1	70-130			
Magnesium	10.9		0.0500	mg/L	2.00	9.16	88.6	70-130			
Selenium	0.199	0.0014	0.0500	mg/L	0.200	0.00170	98.5	70-130			

Definitions

B11: Target analyte detected in continuing calibration blank >2.2 times the MDL but less than the reporting limit. Sample result was less than the reporting limit. No impact on data.

DF: Dilution Factor representing the amount the sample was diluted during analysis and may not represent preparation factors.

J: Analyte concentration is greater than the MDL but less than the reporting limit.

L2: The LCS recovery was above the laboratory acceptance limits. The target analyte concentration was below the reporting limit. No negative impact on the data.

MDL: Minimum Detection Limit

mg/L: Milligrams per Liter

RL: Reporting Limit

RPD: Relative Percent Difference

V13: Interferent check recovery was above acceptance limits. The sample(s) did not contain interferences that would affect the sample result.

Cooler Receipt Log

Cooler ID: Default Cooler Temp: 0.6°C

MICROBAC®

Microbac Laboratories, Inc. - Baltimore

CERTIFICATE OF ANALYSIS

20L0296

Cooler Inspection Checklist

Ice Present or not required?	Yes	Shipping containers sealed or not required?	Yes
Custody seals intact or not required?	Yes	Chain of Custody (COC) Present?	Yes
COC includes customer information?	Yes	Relinquished and received signature on COC?	Yes
Sample collector identified on COC?	Yes	Sample type identified on COC?	Yes
Correct type of Containers Received	Yes	Correct number of containers listed on COC?	Yes
Containers Intact?	Yes	COC includes requested analyses?	Yes
Enough sample volume for indicated tests received?	Yes	Sample labels match COC (Name, Date & Time?)	Yes
Samples arrived within hold time?	Yes	Correct preservatives on COC or not required?	Yes
Chemical preservations checked or not required?	Yes	Preservation checks meet method requirements?	Yes
VOA vials have zero headspace, or not recd.?	Yes		

Project Requested Certification(s)

Microbac Laboratories, Inc. - Baltimore

460285	Commonwealth of Virginia (NELAC) - Baltimore
E871126	Florida - NELAC

Report Comments

Samples were received in proper condition and the reported results conform to applicable accreditation standard unless otherwise noted.

The data and information on this, and other accompanying documents, represents only the sample(s) analyzed. This report is incomplete unless all pages indicated in the footnote are present and an authorized signature is included. ***The services were provided under and subject to Microbac's standard terms and conditions which can be located and reviewed at <https://www.microbac.com/standard-terms-conditions>.***

Reviewed and Approved By:



Evelyn Shinas

Customer Relationship Coordinator

Reported: 01/06/2021 16:47

MICROBAC

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20L0296

TAT 7 days

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 12/1/2020
Route:

Client Sample ID: **Site # 8 Outfall 001 Sector K**
Lab Sample ID: **20L0296-01**
Matrix: **Aqueous**
Type: **Grab**

Sampled Date & Time: 12/4/20 20:02

Analysis	Method	Field Results/Comments	Hold Time
CN_Total_Seal	EPA 335.4, Rv. 1 (1993)		14.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
NH3_Titration	SM 4500-NH3 C-2011		28.00 days
Hg_Total	EPA 245.1, Rv. 3 (1994)		28.00 days
M_Ag_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_As_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cd_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Mg_ICPMS	EPA 6020B		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Se_ICPMS	EPA 200.8, Rv. 5.4 (1994)	- lab filter	180.00 days

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH	A
500ml-Bottle HDPE-H2SO4	B
500ml-Bottle HDPE-HNO3	C
½Gal-Jug LDPE-H2SO4	D

Client Sample ID: **Site # 8 Outfall 001 Sector N**
Lab Sample ID: **20L0296-02**
Matrix: **Aqueous**
Type: **Grab**

Sampled Date & Time: 12/4/20 20:02

Analysis	Method	Field Results/Comments	Hold Time
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
TSS	SM 2540 D-2011		7.00 days
M_Fe_ICP	EPA 200.7, Rv. 4.4 (1994)		180.00 days
M_Al_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cu_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Zn_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Container(s)	Designator
500ml-Bottle HDPE-H2SO4	A
500ml-Bottle HDPE-HNO3	B
1L-Bottle HDPE	C

MICROBAC

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20L0296

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 12/1/2020
Route:

Client Sample ID: Site # 8 Outfall 002 Sector K
Lab Sample ID: 20L0296-03
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/1/2020 20:02

Analysis	Method	Field Results/Comments	Hold Time
CN_Total_Seal	EPA 335.4, Rv. 1 (1993)		14.00 days
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
NH3_Titration	SM 4500-NH3 C-2011		28.00 days
Hg_Total	EPA 245.1, Rv. 3 (1994)		28.00 days
M_Ag_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_As_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cd_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Mg_ICPMS	EPA 6020B		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Se_ICPMS	EPA 200.8, Rv. 5.4 (1994)	- lab filter	180.00 days

Container(s)	Designator
250ml-Bottle HDPE-Ascorbic, NaOH	A
500ml-Bottle HDPE-H2SO4	B
500ml-Bottle HDPE-HNO3	C
½Gal-Jug LDPE-H2SO4	D

Client Sample ID: Site # 8 Outfall 002 Sector N
Lab Sample ID: 20L0296-04
Matrix: Aqueous
Type: Grab

Sampled Date & Time: 12/1/2020 20:02

Analysis	Method	Field Results/Comments	Hold Time
COD_Total_HL	EPA 410.4, Rv. 2 (1993)		28.00 days
TSS	SM 2540 D-2011		7.00 days
M_Fe_ICP	EPA 200.7, Rv. 4.4 (1994)		180.00 days
M_Al_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Cu_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Pb_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days
M_Zn_ICPMS	EPA 200.8, Rv. 5.4 (1994)		180.00 days

Container(s)	Designator
500ml-Bottle HDPE-H2SO4	A
500ml-Bottle HDPE-HNO3	B
1L-Bottle HDPE	C

MICROBAC®

Chain of Custody

Microbac Laboratories, Inc. - Baltimore

Lab Manager: Evelyn Shinas

20L0296

Apex Companies, LLC

Andrea Owen Heller
9700 Capital Court #100
Manassas, VA 20110
Phone: (703) 396-6730

Project Name: DPW- Site# 8

Project/PO Number: N/A
Tenatively Scheduled: 12/1/2020
Route:

Sampled/Relinquished by: Kaitlyn Masters	Date/Time: 12/4/20 21:01	Received by:
Printed Name: Customer		Printed Name: Tyler Warren
Relinquished by:	Date/Time:	Received by: Carolyn Pitera
Printed Name: Tyler Warren	12/7/20 0805	Printed Name: CAROLYN PITERA
Relinquished by: Carolyn Pitera	Date/Time: 12/7/20 1241	Received by:
Printed Name: CAROLYN PITERA		Printed Name: 12/8/20 1557

As Received at Laboratory: On Ice: (Yes) / No Temp: 0.6 °C Thermometer ID: 1 Total Containers: 14

Microbac Laboratories may be unable to perform a portion of the requested testing in which case we will subcontract the analysis to an appropriately accredited laboratory. By signing this document you are acknowledging that you have been informed by Microbac that testing could be subcontracted and agree with this arrangement.

Notes:

12/8/20 1545

Cooler Receipt Form / Sample Acceptance & Noncompliance Form

Number of Coolers Received: 1
Client: Apex Companies
Form Completed By: Kimball

Receipt Date / Time: 12/8/20 1557
Work Order # 20L0296

Shipper: ☑ Microbac ☐ Client ☐ UPS ☐ FedEx
Custody Tape Intact: YES / NO / ~~NA~~
Containers Intact: YES / NO
Sample Received on Ice or refrigerated: YES / NO / NA
Infrared (IR) Temperature: 0.6 °C

Chain of Custody Present with shipment: YES / NO
Sample Bottle IDs agree with COC: YES / NO
Preservation requirements met: YES / NO / Not Checked
Correct Number of Containers / Sample Volume: YES / NO (If No, contact client immediately)
Headspace in container: YES / NO / ~~NA~~
Type of Sample: Water Soil Wipes Oil Filter Solid Sludge Food Swab Other _____

***Container Type / Quantity*:**

A - 2	Unpreserved	6 H2SO4	4 HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid:	If preserved pH <2___, pH >10___
B - 2	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
C - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
D - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
E - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
H - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
K - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
L - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
M- ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
P - ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH 2	NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
W- ___	Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

V - ___ Unpreserved ___ HCl ___ HCl / Ascorbic Acid ___ HCl / NaTHIO **(Checked at time of Analysis)**
F - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
S - ___ Unpreserved ___ NaTHIO **(Checked at time of Analysis)**
SN- ___ Unpreserved ___NaTHIO ___NaTHIO/EDTA **(Checked at time of Analysis)**

___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___
___ Unpreserved	___ H2SO4	___ HNO3	___ HCl	___ NaOH	___ NaOH/Ascorbic Acid	If preserved pH <2___, pH >10___

Describe preservation requirements not met:
All Acid preserved <2 pH *NaOH preserved >12 pH* *All others >2 and <10 (usually 4-8)*
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
Sample ID:_____ H_2SO_4 HNO_3 NaOH _____ mls added
H_2SO_4 – Sulfuric Acid, HNO_3 – Nitric Acid, NaOH – Sodium Hydroxide, ASC – Ascorbic Acid, NaTHIO – Sodium Thiosulfate

Describe Anomalies:_____

Contact information / Summary of Actions:
Date / Time:_____ Contact:_____ Contact By:_____
Comments:_____

An Exelon Company

Appendix D

In-situ Remediation Treatability Studies for Cove Sediments

In-situ remediation treatability studies for Cove sediments located in the Benning Road Facility Waterside Investigation Area

Final Report, April 6, 2021

Louis Cheung and Upal Ghosh
Department of Chemical, Biochemical, and Environmental Engineering
University of Maryland Baltimore County

1.0 Introduction

The Potomac Electric Power Company (PEPCO) is performing a Remedial Investigation/ Feasibility Study (RI/FS) at Pepco's Benning Road facility (the Site or the landside investigation area), located at 3400 Benning Road NE, Washington, DC, and a segment of the Anacostia River (the waterside investigation area) adjacent to the Site for impacted sediments at its Benning Road Facility. Historical use of polychlorinated biphenyls (PCBs) has resulted in elevated levels of PCBs found in sediments in a cove of the Anacostia River adjacent to the facility (the Cove), located in the waterside investigation area, that may impact benthic organisms and can potentially serve as a source to the aquatic food web in the water body. As a part of the RI/FS, PEPCO is investigating the use of sorbent amendments to sediments to reduce the bioavailability of PCBs. UMBC is performing a treatability study to assess the effectiveness of treatment amendments in reducing porewater concentrations of PCBs and the bioaccumulation of PCBs in freshwater worms. In addition, the study is performing groundwater seepage measurements to determine seepage velocity in the cove sediments. The work described here is conducted under a contract with AECOM.

2.0. Study objectives

The overall objective of the treatability testing is to evaluate the effectiveness of three carbon/treatment amendments in reducing the bioavailability of PCBs in sediment collected from the Cove, an impacted area near the PEPCO Benning Road facility. PCB bioavailability in sediments is being tested using two metrics: 1) freely dissolved concentration of PCBs in sediment porewater measured using passive sampling, and 2) bioaccumulation of PCBs in the freshwater oligochaete (*Lumbriculus variegatus*) based on laboratory bioaccumulation studies. The specific study objectives are to:

1) Evaluate the effect of dose of sorbent amendments on the reduction of porewater PCB concentration in sediments,
2) Compare across three AC amendment types described in Table 1,
3) Compare reduction in freely dissolved PCB concentration against reduction of bioaccumulation in benthic organisms, and
4) Evaluate effect of treatment dose on any negative impacts on organism growth and survival in the bioaccumulation studies.

An extension of the proposal addresses two additional elements in the Treatability Study Work Plan developed by AECOM/PEPCO:

1) Measurement of groundwater seepage velocity at three locations in the Cove, and
2) Measurement of change in groundwater seepage through sediments after amendment with sorbent materials being tested as part of the treatability study (GAC, AquaGate, and SediMite).

3.0. Study methods and results

3.1. Laboratory treatability study

3.1.1. Sediment selection and collection.

A single composite sediment sample was prepared using sediment samples collected from the top 10 cm at two sampling locations (SED7E and SED7.5E) within the impacted cove area adjacent to the PEPCO Benning Road facility. Sediment sample locations were selected by AECOM based on highest PCB surficial bulk sediment concentration (1,900 micrograms per kilogram [µg/kg] at SED7.5E) and highest dissolved phase PCB pore water concentration (10,000 picograms per liter [pg/L] at SED7E) observed within the Cove; a site map showing these locations is provided in Appendix 1. A total of 30 L of homogenized composited sediment was collected by AECOM for this study. A clean control sediment was prepared using 50% clean sand (Home Depot) and 50% clean sediment collected form Centennial Lake, MD.

3.1.2. Amendment selection and procurement.

The following three amendments listed in the Benning Road Facility Treatability Study Plan were procured by AECOM and provided to UMBC. All three products chosen for testing are readily available in bulk quantities.

1) Granular Activated Carbon from Calgon Corporation (F-300). This coal based activated carbon (20-50 mesh) was recently specified for a large-scale GAC application project for the remediation of Spirit Lake Estuary Site in Duluth Minnesota.
2) SediMite™ made with 50% by weight of activated carbon (80-325 mesh) was procured from the manufacturer for use in the experiments.
3) AquaGate®+PAC made with 10% by weight of a powdered activated carbon (< 325 mesh) was procured from the manufacturer for use in the experiments.

3.1.3. Amendment mixing into sediments.

The sediment sample was first homogenized (Figure 1) prior to collection of triplicate subsamples for the analysis of PCBs and Total Organic Carbon (TOC). Three-liter subsamples of the homogenized sediment were placed in clean containers for mixing with the carbon amendments. The amendments and doses tested are listed in Table 1. Each container with 3L of sediments was treated with an amendment at a dose specified in Table 1. Amendments were mixed well to represent initial mixing, and then allowed to equilibrate for a period of 1 month

prior to porewater and bioaccumulation testing. The mixing conditions tested here will provide an indication of performance of the amendment after natural mixing through bioturbation and other natural processes in the field.



Figure 1. Homogenization of sediment using a mixing paddle attached to an electric drill.

Table 1. Experimental Design for Laboratory Treatability Study

Amendment	**AC in treated sediment**	**AC in amendment product**	**Dose of Amendment**	**# of replicates**
Clean control sediment	0	NA	0	3
Untreated Cove sediment	0	NA	0	3
Treatment 1: GAC (20-50 mesh)	1, 3, and 5%	100%	1, 3, and 5%	3 per dose
Treatment 2: SediMite with AC (80-325 mesh)	1, 3, and 5%	50%	2, 6, and 10%	3 per dose
Treatment 3: AquaGate with powdered AC	1, 3, and 5%	10%	10, 30, and 50%	3 per dose
Total samples				**33**

3.1.4. PCB measurement in sediment porewater and worms.


The bioaccumulation and porewater measurements were performed simultaneously in the same exposure chambers as described below. Laboratory bioaccumulation assays were conducted using the freshwater oligochaete *Lumbriculus variegatus* commonly used to perform bioaccumulation assays for freshwater sediments. The laboratory bioaccumulation studies followed methods described in Beckingham and Ghosh (2010) which is based on standard test guidelines (USEPA 2000). The bioaccumulation is designed to evaluate the effectiveness of the selected carbon amendment in reducing biological uptake of PCBs at the base of the benthic food web. Bioaccumulation assessment was conducted in triplicate for each of the control and treated sediments described in Table 1 resulting in a total of 33 exposure chambers. Clean, laboratory

cultured freshwater oligochaetes (*Lumbriculus variegatus)* were obtained from Aquatic Research Organisms, Hampton, New Hampshire. Organisms were exposed to the sediments in 1L glass beakers (1000 g wet sediment and 1.1 g organisms per beaker; 3 replicates per treatment) for 28 days and maintained at 23 ± 1 ◦C in a water bath with a 16 hour light:8 hour dark photoperiod. The bioaccumulation setup in the laboratory is shown in Figure 2. A 0.5 g polyethylene passive sampler was also inserted into each of the exposure chambers to measure the concentration of freely dissolved PCBs in the porewater. At the termination of the experiment, organisms were successfully removed from the sediments and allowed to depurate ingested sediment for 6 hours in a clean beaker containing water. The porewater passive samplers were also recovered from each beaker and stored for further analysis. Analytical methods are described in Appendix 2.



Figure 2. Photographs of laboratory bioaccumulation study with freshwater oligochaetes. Top: bioaccumulation setup with air tubes supplying sparging air to oxygenate the overlying water; Bottom left & middle: worms being added to the test beakers with sediment; Bottom right: closeup of worms in culture chamber.

Sediment porewater concentrations. The results of the sediment porewater concentrations are shown in Figure 3 for the different PCB homolog groups as well as the total PCBs. The measured freely dissolved PCB concentration in sediment porewater of the untreated sediment was 3.3 ng/L which is a little higher than the reported range of freely dissolved PCB concentration values in surface water measured close to the site of 0.9 – 2.7 ng/L (Site ARP013 in Ghosh et al. 2020). The granular size AC is barely effective in reducing porewater concentration of PCBs even at a dose of 5% by weight of sediment. Both SediMite and AquaGate are effective in reducing porewater PCB concentrations at all dosing levels with the powdered AC used in AquaGate being the most effective for a given dose. This observation is consistent with previous published results that demonstrated that effectiveness of AC is a strong function of particle size. Both 3% and 5% amendment of AC in the 80-325 mesh (SediMite) and all three doses of powdered form (AquaGate) are able to reduce the PCB porewater concentration below the USEPA ambient water quality criteria value of 0.64 ng/L for 10^{-5} incremental cancer risk for human health via fish consumption.



% Reductions	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG 1%	AG3%	AG5%
Mono									
Di	59	88	100	100	100	100	100	100	100
Tri	-11	18	15	92	100	100	95	100	100
Tetra	-21	0	-18	39	77	93	70	99	99
Penta	7	12	1	28	49	75	42	91	97
Hexa	-13	6	-4	3	14	37	22	77	85
Hepta	-1	16	7	10	19	28	19	68	84
Octa	3	8	1	1	20	8	-8	56	54
TOTAL	**-8**	**16**	**8**	**68**	**87**	**94**	**81**	**98**	**99**

Figure 3. PCB concentration in sediment porewater before and after amendment with activated carbon in different forms and particle sizes. Table in the bottom shows % reductions compared to untreated sediment.

The particle size effect is most apparent for the more hydrophobic compounds like the hexa and higher homolog groups. These more hydrophobic compounds have slow mass transfer and are therefore more impacted by particle size in short-term experiments as performed in this laboratory treatability study. Previous work also demonstrated a strong particle size effect. As shown in Figure 4, work by Zimmerman et al. (2005) showed for two AC types that reducing particle size greatly enhanced the effectiveness of porewater PCB reduction in the laboratory study.





Figure 4. Results from Zimmerman et al. (2005) showing the effect of particle size of two different types of AC on the reduction of porewater PCB concentration in sediment. TOG and F400 are two types of AC from Calgon Carbon Corporation.

PCB bioaccumulation in worms. The results of the worm tissue concentrations are shown in Figure 3 for the different PCB homolog groups as well as the total PCBs. PCB concentration in worms exposed to control sediments was very small compared to the uptake in the worms exposed to untreated sediment from the site. Treatment of the sediment with GAC at all three doses showed little change in the biouptake of total PCBs in worms. Among the PCB homolog groups, only di, tri, and tetra chlorobiphenyls showed significant reductions in tissue for the GAC treatments. Little change was observed for the remaining homolog groups. Both SediMite and AquaGate are effective in reducing tissue PCB concentrations at 3% and 5% dosing levels with the powdered AC used in AquaGate being the most effective. The results of PCB bioaccumulation with treatments are consistent with the observation of greater reduction for the lower chlorinated homologs and for the finer sized AC. While, the reduction of PCB uptake for the di, tri, and tetra chlorobiphenyls was 100% for both SediMite and AquaGate amendments of the fine and powdered AC amendments respectively, the powdered AC was more effective for the higher more hydrophobic homologs in the short-term study. As described earlier, this is a reflection of the slow mass transfer of the strongly hydrophobic compounds that require longer

time or finer grained AC for the movement of the molecules from the sediment to the AC particles.

Overall, the bioaccumulation study demonstrates that application of a powdered AC to the study sediments was effective in reducing both porewater PCB concentration and PCB biouptake in worms by more than 90% at a dose of 3% or higher. In the present study the different sized AC were added via different methods of application: as GAC directly or finer sized AC in the form of SediMite or AquaGate+PAC pellets. It is expected that the powdered AC applied via any of these methods of delivery is likely to provide strong reductions in PCB bioavailability in sediments.



% Reductions	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG1%	AG3%	AG5%
Mono									
Di	100	100	100	84	100	100	100	100	100
Tri	76	56	75	95	100	100	100	100	100
Tetra	44	19	40	75	100	100	96	100	100
Penta	30	-3	11	23	75	87	66	98	100
Hexa	22	-1	7	5	56	55	40	87	98
Hepta	20	7	6	16	60	47	26	82	98
Octa	25	17	20	24	52	42	23	85	99
Nona	16	8	18	52	100	100	67	100	100
TOTAL	**31**	**9**	**18**	**30**	**71**	**70**	**55**	**92**	**99**

Figure 5. PCB concentration in worm tissue before and after amendment with activated carbon in different forms and particle sizes. Table in the bottom shows % reductions compared to untreated sediment.

Although these results are based on a short-term laboratory study, longer-term field demonstrations have reported similar reductions after AC amendment. For example, a large field study recently conducted at the Hunters Point Navy Shipyard found 75 to 80% reductions of *in situ* PCB tissue concentration in clams after 8 months and 84–87% after 14 months relative to the reference locations (Yan et al. 2020) for both SediMite and AquaGate applications performed in parallel.

Worm survival and recovery from bioaccumulation study. The main purpose of the bioaccumulation study was to recover worms for chemical analysis of tissue. Thus, it was critical to gently recover the worms without damage so that the worms could stay alive for a 6-hr depuration period post recovery. An exhaustive recovery of all worms from the sediment was not targeted which could have resulted in damage to the worms. Thus, the results presented here are based on worm tissue recovery post bioaccumulation study and should be interpreted with caution to make any growth or survival interpretation. Still, the results presented here can be informative on relative difference in tissue recovery across treatments. As shown in Figure 6, there appears to be a small increase in dry tissue mass in the untreated sediment compared to the dry mass that was added to the beakers (red line). The clean control sediment was sandy with low organic matter and appears to be not very conducive to support the worms and the mass of worms recovered was a factor of 3 lower compared to the untreated control sediment. Worm recovery was good in all three GAC treatments and comparable or higher than the untreated control sediments. Worm recoveries were 86-95% for the three SediMite treatments and 75-114% for the three AquaGate treatments. There appears to be a small impact on worm recovery with decreasing particle size of AC amended. Among the treatments, AquaGate 3% and 5% gave the lowest recoveries, while the 1% GAC treatment gave the highest recovery as shown in Figure 6.




Figure 6. Recovery of worm dry weight from laboratory bioaccumulation experiment.

3.2. Seepage measurements

Groundwater seepage velocity is a critical parameter that determines the ultimate flux of pollutants from deeper sediments into the overlying water. The exchange between groundwater and surface water can vary greatly among sites and can be both positive (from groundwater to surface) or negative (from surface water to groundwater). In addition, the seepage can also be a function of tidal stage for sites influenced by tidal cycling leading to a phenomenon often called tidal pumping where the flux is positive at low tide and switches to a negative value at high tide. The nature of this groundwater-surface water interaction in the Cove is unknown.

3.2.1. Fabrication of seepage meters. The seepage meters used for this study were based on the design described in USGS (2008) which is an adaptation of the original design by Lee and Cherry (1978). The design as illustrated in Figure 7 was constructed out of 55-gallon plastic drums that were cut in half. The drums were fitted with a vent tube and a tube with a stopcock that was connected with a seepage collection bag. A total of 4 seepage meters were fabricated (3 for deployment in the field and a spare one as backup).

3.2.2. Installation of seepage meters in the field and recording of measurements. The seepage meters were installed in the field with assistance from AECOM field crew (See Figure 8). Based on the available bathymetry data presented in the PEPCO Treatability Study Workplan, all three sampling locations were expected to be under less than 2 ft of water at low tide. Therefore, installation was performed at low tide for easy access to the sediment surface. The open side of the half drum was inserted into the sediment bed leaving about 6" above the sediment surface. The seepage meters were installed at the three proposed locations in the Cove (Attachment 1) as indicated in the PEPCO Treatability Study Work Plan. The meters were allowed to equilibrate

for more than a week in the field before performing measurements. To perform the seepage measurement, a 4L plastic bag was first filled with 1L of water and then attached to the collection tube. The stopcock in the collection tube was opened to allow the flow of water between the collection bag and the drum. After 0.5-1 hr of operation, the stopcock was closed and the collection bag removed. The volume of water remaining in the bag was used to calculate the seepage volume. Two sets of measurements were performed:

1) Multiple measurements during a rising tide cycle on October 18, 2020
2) Multiple measurements during a falling tide cycle on October 28, 2020

The discharge velocity was calculated by dividing the discharge flow rate by the cross-sectional area of the seepage meter drum and are provided in Table 2. As shown in Table 2, the average seepage velocity was -0.26 cm/d during a rising tide and 1.78 cm/d during a falling tide with high variability in replicate measurements. Positive value indicates groundwater seepage out of the sediment, while a negative value indicates infiltration of surface water into the sediment. Thus, during a rising tide, as the hydraulic head in the surface water is increasing, there is a small infiltration into the ground (-0.26 cm/d), while during a falling tide, then the hydraulic head in the surface water is decreasing, there is some seepage of groundwater into the surface.




Figure 7. Schematic of seepage meter to be fabricated at UMBC using a 55 gallon drum following method described in USGS (2008).



Figure 8. Images from the field showing seepage meters in the field (top and bottom left), and eight intact cores collected for lab seepage study (bottom right).

Table 2. Data collected from field seepage meters

18-Oct	Rising Tide				
Seepage Meter 1		min	Vol	rate (ml/min)	notes
9:13 AM	10:02 AM	49	0	0.00	
10:02 AM	10:55 AM	53	-100	-1.89	
12:29 PM	1:02 PM	33	160	4.85	
1:04 PM	2:05 PM	61	-160	-2.62	
2:07 PM	2:55 PM	48	0	0.00	
		244	-100	-0.41	
Seepage Meter 2					
10:49 AM	11:58 AM	69	0	0.00	
12:02 PM	12:38 PM	36			vented air
12:42 PM	2:00 PM	78	20	0.26	
2:02 PM	2:50 PM	48	-20	-0.42	
		231	0	0.00	
Seepage Meter 3					
10:55 AM	12:13 PM	78	-275	-3.53	
12:15 PM	1:12 PM	57	0	0.00	
1:14 PM	2:13 PM	59	-40	-0.68	
2:15 PM	3:04 PM	49	60	1.22	
		243	-255	-1.05	
Average of 3 (ml/min)				**-0.49**	
Area of drum =	2721.481	sqcm			
Darcy velocity	**cm/min)**			**-0.00017873**	
	cm/d			**-0.26**	

28-Oct	Falling Tide				
Seepage Meter 1		min	Vol	rate	notes
8:04 AM	8:34 AM	30	300	10.00	
8:42 AM	9:46 AM	64	100	1.56	
9:48 AM	10:35 AM	47	200	4.26	
10:38 AM	11:30 AM	52	128	2.46	
		193	728	3.77	
Seepage Meter 2					
8:07 AM	8:40 AM	33	0	0.00	
8:44 AM	9:50 AM	54	220	4.07	
9:53 AM	10:45 AM	52	80	1.54	
10:48 AM	11:07 AM	19	280	14.74	
		158	580	3.67	
Seepage Meter 3					
8:12 AM	8:47 AM	35	400	11.43	
8:50 AM	9:57 AM	67	140	2.09	
9:58 AM	10:50 AM	52		0.00	not opene
10:51	11:39 AM	48	0	0.00	
		202	540	2.67	
				3.37	
Darcy velocity	**cm/min)**			**0.001239**	
	cm/d			**1.78**	

3.2.3. Hydraulic conductivity of sediment before and after placement of amendments.

For conditions where groundwater discharge can be an important component of pollutant transport, understanding changes in discharge as a consequence of a remedy can be an important factor in the assessment. Thin layer placement of granular material like sand may not have a major impact on hydraulic conductivity and discharge unless additional compaction takes place due to the weight of the placed material. For amendments containing bentonite clays (AquaGate and SediMite), there is potential for the bentonite component to significantly reduce the hydraulic conductivity of the surface sediments where the amendments are mixed into. Bentonite is a swelling clay and is often used in applications where a reduction in hydraulic conductivity is desired. The reduction of the hydraulic conductivity and resulting groundwater discharge can be beneficial from a remedy perspective if the groundwater is redirected from the treated contaminated sediment layer to the adjacent less contaminated areas. This can reduce the overall flux of groundwater through the contaminated zone in sediments. Intact sediment cores (1 ft depth of surficial sediments) were collected from the Cove near Seepage Meter 2 to perform laboratory measurement of the change in seepage with sediment amendments. The eight cores collected from the Cove for the study are shown in Figure 8.

A simulated discharge flow setup was constructed in the laboratory using intact 2” diameter and 1 ft long cores collected from the field. After consolidation in the laboratory, actual depth of sediment in each core was adjusted to ensure a consistent thickness of sediment in all cores by removing excess material from the top of the cores. The final depth of consolidated sediments in each core was 7.5”. A schematic of the laboratory seepage measurement setup and actual picture of the setup in the laboratory are shown in Figure 9. The hydraulic conductivity system was built

using 2” diameter PVC pipe, 90 degrees elbows, PVC tees, and DWV male adapter. The systems configuration is shown below in Figure 9. Each joint was fixed together using PVC cement. The system was placed inside a large water bath that also acted as the reservoir. The reservoir contained a water pump that fed into the top of the constant head tubes. Holes were drilled at different heights above the sediment line to allow adjustment of the constant head. A small amount of filter fiber was added to the bottom of the intact core followed by a rigid circular mesh. These were secured into place with a DWV male adapter. This was done to ensure the intact core would not fall through into the pipe. A total of eight cores were added to the system (4 on each sides). The intact cores were inverted in water to remove trapped air bubbles then threaded into the base of the hydraulic conductivity system. The pump was activated, and the cores were subjected to the hydraulic gradient until the discharge flow rate remained constant. Once all eight cores were equilibrated, 4 cores were capped while beakers were placed underneath the outlets of the other 4 cores to collect the discharge over a fixed time. The content of the beaker was then transferred into a graduated cylinder to determine the volume. Three trials were conducted for the untreated cores. The pump was deactivated before the amendments (GAC, SediMite, and AquaGate) were added to duplicate cores and allowed to stabilize on top of the sediment for 14 hours for the first set of post amendment measurement, and then for 2 days for the second set of post amendment measurements. The pump was reactivated to allow the system to equilibrate once more. The seepage water was collected using the same procedure described above.

The results of the laboratory seepage measurements are shown in Table 3. The first set of replicate columns had a higher flowrate ranging from 80-310 ml/min before amendments were added to the sediment columns. The flowrates in all three columns were reduced to about half 14 hours after amendment placement. Measurements taken 2 days after amendment placement show similar reductions for SediMite and AquaGate treatments, however, for the GAC treatment, the reduction changed to 33%.

The second set of replicate sediment columns exhibited lower flowrates before amendment and ranged from 5.5 to 22.3 ml/min likely reflecting heterogeneity of the collected samples. The flowrates in all three columns reduced 14 hours after amendment placement and ranged from 25% reduction for the AquaGate treatment, and 73% reduction for the GAC treatment. Two days after amendment placement, the flowrate reductions for SediMite treatment increased from 54% to 69%, and for AquaGate treatment from 25% to 42%.

Overall, the laboratory seepage measurements indicate that the amendments can have an influence in reducing seepage through the native sediments. Reductions in the range of 25 – 78% can be anticipated. The initial hypothesis was that the amendments containing bentonite clay (SediMite and AquaGate) may have a greater influence in reducing seepage. However, the experimental results seem to indicate similar reductions for all three amendments. It is possible that after a longer period of hydration and swelling of the bentonite clay, one may observe further reductions in seepage for the bentonite-clay containing amendments.






Figure 9. Laboratory experimental setup to measure change in discharge velocity after placement of amendments.

Table 3. Results of laboratory seepage measurement with and without amendments

REPLICATE 1	**Before Amendment**			**14 hr After Amendment**			
	flow (ml/min)	StdErr			flow (ml/min)	StdErr	% reduction
1A	80.0	0.0		**1A (GAC)**	36.2	0.4	55%
3A	168.3	3.1		**3A (AG)**	97.7	1.0	42%
4A	310.0	8.2		**4A (SM)**	158.3	1.0	49%
				2 days After Amendment			
					flow (ml/min)	StdErr	% reduction
				1A (GAC)	54	0	33%
				3A (AG)	88	0	48%
				4A (SM)	142	0.71	54%
REPLICATE 2	**Before Amendment**			**14 hr After Amendment**			
	flow (ml/min)	StdErr			flow (ml/min)	StdErr	% reduction
2B	5.5	0.015		**2B (GAC)**	1.5	0.015	73%
3B	10.5	0.015		**3B (AG)**	4.8	0.041	54%
4B	22.3	0.041		**4B (SM)**	16.7	0.093	25%
				2 days After Amendment			
					flow (ml/min)	StdErr	% reduction
				2B (GAC)	1.2	0	78%
				3B (AG)	3.2	0.014	69%
				4B (SM)	13.0	0.040	42%

References

Beckingham, B. and Ghosh, U. Comparison of field vs. laboratory exposures of L. variegatus to PCB impacted river sediments. ***Environ. Toxicol. Chem***., 29, 2851-2858, 2010.

Ghosh U., Lombard N., Bokare M., R., Yonkos L., Pinkney F. 2020. Passive samplers and mussel deployment, monitoring, and sampling for organic constituents in Anacostia River tributaries: 2016-2018. DOEE Final Report.

Lee, D.R., and Cherry, J.A., 1978, A field exercise on groundwater flow using seepage meters and mini-piezometers: Journal of Geological Education, v. 27, p. 6–20.

Solder, J.E.; Gilmore, T.E.; Genereux, D.P.; Solomon, D.K. A Tube Seepage Meter for In Situ Measurement of Seepage Rate and Groundwater Sampling. ***Groundwater***. 54, 588–595. 2016.

USGS 2011. Field Techniques for Estimating Water Fluxes Between Surface Water and Ground Water. Techniques and Methods 4–D2. U.S. Department of the Interior, U.S. Geological Survey, Reston, Virginia: 2008.

USEPA 2014. Quantifying Seepage Flux using Sediment Temperatures EPA/600/R-15/454; December 2014.

USEPA *Methods for Measuring the Toxicity and Bioaccumulation of Sediment-Associated Contaminants with Freshwater Invertebrates. 2000.*

Yan, S.; Rakowska, M.; Shen, X.; Himmer, T.; Irvine, C.; Zajac, R.; Eby, J.; Janda, D.; Ohannessian, S.; Reible, D.D. Bioavailability assessment in activated carbon treated coastal sediment with in situ and ex situ porewater measurements. ***Water Research*** 185 (2020) 116259.

Zimmerman, J.R.; D. Werner, U. Ghosh, R.N. Millward, T.S. Bridges, R.G. Luthy. The Effects of Dose and Particle Size on Activated Carbon Treatment to Sequester Polychlorinated Biphenyls and Polycyclic Aromatic Hydrocarbons in Marine Sediments. ***Environ. Toxicol. Chem***. 24, 1594-1601, 2005.

Conflict of interest disclosure: "Dr. Ghosh is a co-inventor of two patents related to the in-situ sorbent amendment technology described in this proposal for which he is entitled to receive royalties upon commercialization. One invention was issued to Stanford University (US Patent # 7,101,115 B2), and the other to the University of Maryland Baltimore County (UMBC) (U.S. Patent No. 7,824,129). In addition, Dr. Ghosh is a partner in a startup company (Sediment Solutions) that has licensed the technologies from Stanford and UMBC and manufacturers the pelletized activated carbon product SediMite™."

List of Appendices:

Appendix 1. Treatability Study Sample Locations.


Appendix 2. Analytical Methods.

Appendix 3. Tables of water quality data from 28-day bioaccumulation study. Full range of water quality measurements were performed every 7 days with daily monitoring of temperature and dissolved oxygen.

Appendix 4. PCB homolog concentration in sediment porewater for Figure 3.

Appendix 5. PCB homolog concentration in worm tissue for Figure 5.

Appendix 1. Treatability Study Sample Locations.



Appendix 2. Analytical Methods.

PCB extraction, cleanup, and analysis.
Sediment and worm tissue PCBs were extracted following EPA method 3550B using three volumes of 40 mL each of acetone-hexane mixture (1:1) and sonicating the slurry for 6 minutes (pulsing for half minute on and half minute off). Pesticide grade hexane and acetone was used for all extractions. PCB cleanup was based on EPA publication SW-846 (Test Methods for Evaluating Solid Waste, Physical/Chemical Methods) methods 3630C (Silica gel cleanup), 3665A (sulfuric acid cleanup) and 3660B (Sulfur removal with copper). In the silica gel cleanup process, the dried and concentrated extracts are passed through a 3% deactivated silica gel column for the removal of organic interferences and to separate the PCBs. Silica gel (chromatographic grade, 100-200 mesh, Fisher Scientific, Fair Lawn, NJ) is activated by heating at 130°C for 16 hours, then deactivated by gradually adding 3% by weight deionized water and rotating on a roller at approximately 2 rpm overnight. The three standard methods were followed without any modifications.

PCB congener specific analysis was performed using a modified EPA Method 8082. An Agilent gas chromatograph (model 6890) with a fused silica capillary column (HP-5, 60 m x 0.25 mm inner diameter) and an electron capture detector was used for analysis. PCB standards for calibration were obtained from the EPA's National Health and Environmental Effects Research Laboratory in Grosse Ile, Michigan and also from Ultra Scientific. A 4-level PCB calibration table is prepared using a known PCB mixture containing 250 μg/L of Aroclor 1232, 180 μg/L of Aroclor 1248 and 180 μg/L of Aroclor 1262 yielding a total PCB concentration of 610 μg/L. Concentrations of individual PCB congeners in the mixture are obtained from Mullin (1994). Two internal standards are used: PCB 30 (2,4,6-trichlorobiphenyl) and PCB 204 (2,2',3,4,4',5,6,6'-octachloro biphenyl), which are not present in commercial Aroclor mixtures. Using this protocol, 92 PCB congeners or congener groups can be identified and quantified. With this analytical method, there are some coeluting PCB peaks in the analysis. Where this occurs, coeluting peaks are calibrated as sum of congeners.

Passive sampling of freely dissolved PCBs. The passive sampling approach followed the recent guidance on passive sampling (USEPA 2017). Passive samplers were prepared using 0.5 g of 25 μm thick polyethylene sheets encased in stainless steel mesh. The samplers were cleaned by solvent extraction followed by the impregnation with four PCB and three PAH performance reference compounds in the laboratory. After retrieval of the passive samplers from the laboratory exposure chambers, they were cleaned using a clean tissue and DI water to remove surface contamination and placed into pre-cleaned 40 mL vials. All samples were stored at 4 °C in closed glass vials until extraction. Extraction of all stored samples were completed within 1 month of generation of the sample. Passive samplers were extracted by dialyzing in hexane as described in Sander et al. (2018). Cleanup and analysis of passive samplers followed methods described in the analytical section above. The presence of different amounts of AC in the treated samples is expected to interfere with the rate of loss of PRC compounds as described in Yan et al. 2020 and confound PRC corrections. Thus, no PRC corrections were performed in this study for the reported porewater concentrations. The final percent reductions of porewater concentrations are not expected to be impacted by PRC corrections as hydrodynamic conditions were maintained the identical in all exposure beakers.

Other water quality measurements in exposure chambers. For each exposure chamber, temperature and dissolved oxygen will be measured daily (Oakton® 100 Series DO/ºC meter, Eutech Instruments, Singapore), and additional water quality parameters, including pH (Accumet® model 15 pH meter, Denver Instrument Company, USA), conductivity (Fisherbrand Traceable® Benchtop Conductivity Meter, Calibration Control Company), alkalinity, hardness and ammonia, will be measured weekly (days 0, 7, 14, and 21). Alkalinity, hardness and ammonia will be measured with water quality test kits (Hach Company, Loveland, CO, USA).

Appendix 3. Tables of water quality data from 28-day bioaccumulation study. Full range of water quality measurements were performed every 7 days with daily monitoring of temperature and dissolved oxygen.

Day 0

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A	0	0	300+	80-120	8.4	1252	0.5	7.95	X	23.7
1% SediMite-B	0	0	300+	80-120	8.4	1250	0.5	8.01	X	23.7
1% SediMite-C	0	0	300+	80-120	8.4	1287	0.5	7.64	X	23.7
3% SediMite-A	0	0	300+	80-120	8.2	1292	0.5	7.96	X	23.7
3% SediMite-B	0	0	300+	80-120	8.2	1268	0.5	7.12	X	23.7
3% SediMite-C	0	0	300+	80-120	8.2	1291	0.5	7.09	X	23.7
5% SediMite-A	0	0	300+	80-120	8.2	1289	0.5	6.8	X	23.7
5% SediMite-B	0	0	300+	80-120	8.2	1261	0.5	6	X	23.7
5% SediMite-C	0	0	300+	80-120	8.2	1281	0.5	6.8	X	23.7
1% GAC-A	0	0	300+	80-120	8.2	1278	0.5	7.32	X	23.7
1% GAC-B	0	0	300+	80-120	8.2	1245	0.5	7.91	X	22.3
1% GAC-C	0	0	300+	80-120	8.2	1260	0.5	7.37	X	22.3
3% GAC-A	0	0	300+	80-120	8	1245	0.5	7.88	X	22.3
3% GAC-B	0	0	300+	80-120	8.2	1209	0.5	7.94	X	22.3
3% GAC-C	0	0	300+	80-120	8	1240	0.5	8.01	X	22.3
5% GAC-A	0	0	300+	80-120	8	1226	0.5	7.64	X	22.3
5% GAC-B	0	0	300+	80-120	8	1218	0.5	7.63	X	22.3
5% GAC-C	0	0	300+	80-120	8	1215	0.5	7.24	X	22.3
1% AquaBlok-A	0	0	300+	80-120	8.2	1232	0.5	7.98	X	22.3
1% AquaBlok-B	0	0	300+	80-120	8	1226	0.5	7.28	X	22.2
1% AquaBlok-C	0	0	300+	80-120	8	1255	0.5	6.09	X	22.2
3% AquaBlok-A	0	0	300+	80-120	8	1318	0.5	7.57	X	22.2
3% AquaBlok-B	0	0	300+	80-120	8.3	1334	0.5	7.72	X	22.2
3% AquaBlok-C	0	0	300+	80-120	8.3	1296	0.5	7.22	X	22.2
5% AquaBlok-A	0	0	300+	80-120	8.2	1336	0.5	7.33	X	22.2
5% AquaBlok-B	0	0	300+	80-120	8.3	1334	0.5	7.05	X	22.2
5% AquaBlok-C	0	0	300+	80-120	8.3	1390	0.5	7.86	X	22.2
Untreated-A	0	0	300+	80-120	8.2	1266	1	7.78	X	22.2
Untreated-B	0	0	300+	80-120	8.2	1262	3	7.95	X	22.2
Untreated-C	0	0	300+	80-120	8.2	1232	2	7.69	X	22.2
Control-A	0	0	300+	80-120	7.4	1022	0.75	7.2	X	23.7
Control-B	0	0	300+	80-120	7.4	1079	0.75	6.97	X	22.3
Control-C	0	0	300+	80-120	7.4	1070	0.75	7.99	X	22.2

Day 1

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.54	X	23.8
1% SediMite-B								7.7	X	23.8
1% SediMite-C								7.62	X	23.8
3% SediMite-A								7.96	X	23.8
3% SediMite-B								7.82	X	23.8
3% SediMite-C								6.96	X	23.8
5% SediMite-A								7.18	X	23.8
5% SediMite-B								7.45	X	23.8
5% SediMite-C								6.4	X	23.8
1% GAC-A								5.8	X	23.8
1% GAC-B								7.65	X	23
1% GAC-C								7.13	X	23
3% GAC-A								7.21	X	23
3% GAC-B								7.52	X	23
3% GAC-C								7.54	X	23
5% GAC-A								6.6	X	23
5% GAC-B								6.16	X	23
5% GAC-C								6.8	X	23
1% AquaBlok-A								7.17	X	23
1% AquaBlok-B								7.13	X	23
1% AquaBlok-C								6.3	X	22.8
3% AquaBlok-A								7.35	X	22.8
3% AquaBlok-B								7.18	X	22.8
3% AquaBlok-C								6.41	X	22.8
5% AquaBlok-A								6.49	X	22.8
5% AquaBlok-B								6.22	X	22.8
5% AquaBlok-C								7.28	X	22.8
Untreated-A								7.57	X	22.8
Untreated-B								7.47	X	22.8
Untreated-C								7.37	X	22.8
Control-A								6.7	X	23.8
Control-B								6.84	X	23
Control-C								7.18	X	22.8

Day 2

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								6.81	X	24
1% SediMite-B								6.97	X	24
1% SediMite-C								7.26	X	24
3% SediMite-A								7.17	X	24
3% SediMite-B								6.45	X	24
3% SediMite-C								6.63	X	24
5% SediMite-A								5.97	X	24
5% SediMite-B								6.53	X	24
5% SediMite-C								6.6	X	24
1% GAC-A								5.87	X	24
1% GAC-B								7.13	X	23
1% GAC-C								6.49	X	23
3% GAC-A								6.53	X	23
3% GAC-B								6.83	X	23
3% GAC-C								6.93	X	23
5% GAC-A								6.55	X	23
5% GAC-B								5.47	X	23
5% GAC-C								6.08	X	23
1% AquaBlok-A								6.31	X	23
1% AquaBlok-B								6.3	X	23
1% AquaBlok-C								6.23	X	22.9
3% AquaBlok-A								6.94	X	22.9
3% AquaBlok-B								7.15	X	22.9
3% AquaBlok-C								5.42	X	22.9
5% AquaBlok-A								6.18	X	22.9
5% AquaBlok-B								6.35	X	22.9
5% AquaBlok-C								7.05	X	22.9
Untreated-A								7.05	X	22.9
Untreated-B								7.07	X	22.9
Untreated-C								6.94	X	22.9
Control-A								6.25	X	24
Control-B								6.3	X	23
Control-C								6.46	X	22.9

Day 3

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8.2			7.13	X	24.3
1% SediMite-B					8.2			6.93	X	24.3
1% SediMite-C					8.2			6.99	X	24.3
3% SediMite-A					8.2			7.07	X	24.3
3% SediMite-B					8.2			6.7	X	24.3
3% SediMite-C					8.2			6.36	X	24.3
5% SediMite-A					8.2			5.6	X	24.3
5% SediMite-B					8.2			5.48	X	24.3
5% SediMite-C					8.2			5.82	X	24.3
1% GAC-A					8.4			6.08	X	24.3
1% GAC-B					8.2			7.02	X	23.3
1% GAC-C					8.2			6.25	X	23.3
3% GAC-A					8.2			6.92	X	23.3
3% GAC-B					8.2			6.91	X	23.3
3% GAC-C					8.8		0.5	6.6	X	23.3
5% GAC-A					8			6.48	X	23.3
5% GAC-B					8			5.93	X	23.3
5% GAC-C					8.4			6.02	X	23.3
1% AquaBlok-A					8			6.4	X	23.3
1% AquaBlok-B					8			5.87	X	23.3
1% AquaBlok-C					8.8		0.5	6.84	X	23
3% AquaBlok-A					8.2			5.91	X	23
3% AquaBlok-B					8.2			6.57	X	23
3% AquaBlok-C					8.2			6.21	X	23
5% AquaBlok-A					8.2			5.6	X	23
5% AquaBlok-B					8.2			6.38	X	23
5% AquaBlok-C					8.2			6.62	X	23
Untreated-A					8.2			6.73	X	23
Untreated-B					8.2			6.6	X	23
Untreated-C					8.2			6.68	X	23
Control-A					8.8		0.25	6.27	X	24.3
Control-B					8.2			6.14	X	23.3
Control-C					8.2			6.41	X	23

Day 4

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8			6.24	X	24.2
1% SediMite-B					8.3			6.42	X	24.2
1% SediMite-C					8.2			6.27	X	24.2
3% SediMite-A					8.3			6.17	X	24.2
3% SediMite-B					8.3			6.15	X	24.2
3% SediMite-C					8.3			6.09	X	24.2
5% SediMite-A					8.2			5.75	X	24.2
5% SediMite-B					8.3			6.19	X	24.2
5% SediMite-C					8.2			5.95	X	24.2
1% GAC-A					8			5.59	X	24.2
1% GAC-B					8			6.37	X	23.2
1% GAC-C					8			6.12	X	23.2
3% GAC-A					8.2			6.19	X	23.2
3% GAC-B					8			6.27	X	23.2
3% GAC-C					8			6.45	X	23.2
5% GAC-A					8			6.12	X	23.2
5% GAC-B					8			5.18	X	23.2
5% GAC-C					8			5.7	X	23.2
1% AquaBlok-A					8			5.96	X	23.2
1% AquaBlok-B					8			6.45	X	23.2
1% AquaBlok-C					8			6.29	X	22.9
3% AquaBlok-A					8.2			6.38	X	22.9
3% AquaBlok-B					8			6.5	X	22.9
3% AquaBlok-C					8.3			6.39	X	22.9
5% AquaBlok-A					8.3			6.15	X	22.9
5% AquaBlok-B					8.3			6.4	X	22.9
5% AquaBlok-C					8.3			6.58	X	22.9
Untreated-A					8.3			6.35	X	22.9
Untreated-B					8.3			6.26	X	22.9
Untreated-C					8.4			6.35	X	22.9
Control-A					8			5.84	X	24.2
Control-B					8			6.28	X	23.2
Control-C					8			6.55	X	22.9

Day 5

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8.2			8.16	X	24
1% SediMite-B					8.2			8.35	X	24
1% SediMite-C					8.2			8.19	X	24
3% SediMite-A					8.2			8.23	X	24
3% SediMite-B					8.2			8.15	X	24
3% SediMite-C					8.2			7.6	X	24
5% SediMite-A					8.2			7.52	X	24
5% SediMite-B					8.2			7.67	X	24
5% SediMite-C					8.2			7.28	X	24
1% GAC-A					7.8			7.72	X	24
1% GAC-B					8			8.23	X	23
1% GAC-C					8			7.71	X	23
3% GAC-A					8			7.55	X	23
3% GAC-B					8			7.81	X	23
3% GAC-C					8			8.15	X	23
5% GAC-A					8			7.5	X	23
5% GAC-B					8			7.73	X	23
5% GAC-C					8			7.41	X	23
1% AquaBlok-A					8			7.21	X	23
1% AquaBlok-B					8			7.73	X	23
1% AquaBlok-C					8			8	X	22.7
3% AquaBlok-A					8			8.45	X	22.7
3% AquaBlok-B					8			8.25	X	22.7
3% AquaBlok-C					8			7.63	X	22.7
5% AquaBlok-A					8.4			8.23	X	22.7
5% AquaBlok-B					8.4			7.83	X	22.7
5% AquaBlok-C					8.4			8.59	X	22.7
Untreated-A					8			8.07	X	22.7
Untreated-B					8			7.87	X	22.7
Untreated-C					8			7.34	X	22.7
Control-A					8			8.16	X	24
Control-B					8			7.84	X	23
Control-C					8			7.25	X	22.7

Day 6

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8.2			8.52	X	23.8
1% SediMite-B					8.2			8.75	X	23.8
1% SediMite-C					8.2			8.59	X	23.8
3% SediMite-A					8.2			8.55	X	23.8
3% SediMite-B					8.2			8.32	X	23.8
3% SediMite-C					8.2			7.85	X	23.8
5% SediMite-A					8.2			7.47	X	23.8
5% SediMite-B					8.2			7.99	X	23.8
5% SediMite-C					8			7.62	X	23.8
1% GAC-A					8.2			7.32	X	23.8
1% GAC-B								8.45	X	22.8
1% GAC-C								8.041	X	22.8
3% GAC-A								8.17	X	22.8
3% GAC-B								7.89	X	22.8
3% GAC-C								8.23	X	22.8
5% GAC-A								7.82	X	22.8
5% GAC-B								6.71	X	22.8
5% GAC-C								7.8	X	22.8
1% AquaBlok-A								8.1	X	22.8
1% AquaBlok-B								7.34	X	22.8
1% AquaBlok-C								7.56	X	23
3% AquaBlok-A								8.51	X	23
3% AquaBlok-B								8.32	X	23
3% AquaBlok-C								7.36	X	23
5% AquaBlok-A								8.27	X	23
5% AquaBlok-B								7.46	X	23
5% AquaBlok-C								7.62	X	23
Untreated-A								7.36	X	23
Untreated-B								7.84	X	23
Untreated-C								7.28	X	23
Control-A								8.1	X	23.8
Control-B								7.52	X	22.8
Control-C								7.04	X	23

Day 7

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A	0	0	300+	80-120		1011	0.25	8.2	X	24.5
1% SediMite-B	0	0	300+	80-120		1008	0	8.29	X	24.5
1% SediMite-C	0	0	300+	80-120		1000	0	8.31	X	24.5
3% SediMite-A	0	0	300+	80-120		1017	0	7.95	X	24.5
3% SediMite-B	0	0	300+	80-120		1024	0	7.61	X	24.5
3% SediMite-C	0	0	300+	80-120		1017	0	7.11	X	24.5
5% SediMite-A	0	0	300+	80-120		9945	0	6.78	X	24.5
5% SediMite-B	0	0	300+	80-120		1005	0	7.44	X	24.5
5% SediMite-C	0	0	300+	80-120		1005	0	7.01	X	24.5
1% GAC-A	0	0	300+	80-120		942	0.5	6.61	X	24.5
1% GAC-B	0	0	300+	80-120		932	0.5	7.78	X	22.8
1% GAC-C	0	0	300+	80-120		934	0.25	7.63	X	22.8
3% GAC-A	0	0	300+	80-120		922	0.5	7.3	X	22.8
3% GAC-B	0	0	300+	80-120		903	0.5	7.29	X	22.8
3% GAC-C	0	0	300+	80-120		925	0.5	7.25	X	22.8
5% GAC-A	0	0	300+	80-120		921	0.5	7.34	X	22.8
5% GAC-B	0	0	300+	80-120		941	0.5	7.3	X	22.8
5% GAC-C	0	0	300+	80-120		915	0.5	7.05	X	22.8
1% AquaBlok-A	0	0	300+	80-120		957	0.25	6.874	X	22.8
1% AquaBlok-B	0	0	300+	80-120		942	0.5	6.88	X	22.8
1% AquaBlok-C	0	0	300+	80-120		942	0.5	7.46	X	22.8
3% AquaBlok-A	0	0	300+	80-120		978	0	8.1	X	22.8
3% AquaBlok-B	0	0	300+	80-120		994	0	8.12	X	22.8
3% AquaBlok-C	0	0	300+	80-120		993	0	7.65	X	22.8
5% AquaBlok-A	0	0	300+	80-120		984	0	8.22	X	22.8
5% AquaBlok-B	0	0	300+	80-120		994	0	7.64	X	22.8
5% AquaBlok-C	0	0	300+	80-120		1006	0	8.11	X	22.8
Untreated-A	0	0	300+	80-120		1014	0.25	8.18	X	22.8
Untreated-B	0	0	300+	80-120		925	0.25	7.99	X	22.8
Untreated-C	0	0	300+	80-120		952	0.25	7.8	X	22.8
Control-A	0	0	300+	80-120		943	0.25	6.84	X	24.5
Control-B	0	0	300+	80-120		9320	0.25	7.08	X	22.8
Control-C	0	0	300+	80-120		944	0.25	6.63	X	22.8

Day 8

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8.4			8.26	X	24.2
1% SediMite-B					8.4			8.62	X	24.2
1% SediMite-C					8.4			8.55	X	24.2
3% SediMite-A					8.4			7.62	X	24.2
3% SediMite-B					8.4			7.85	X	24.2
3% SediMite-C					8.2			6.68	X	24.2
5% SediMite-A					8.2			6.78	X	24.2
5% SediMite-B					8.2			7.02	X	24.2
5% SediMite-C					8.2			6.8	X	24.2
1% GAC-A					8.2			6.52	X	24.2
1% GAC-B					8			7.69	X	22.8
1% GAC-C					8.2			7.82	X	22.8
3% GAC-A					8.2			7.56	X	22.8
3% GAC-B					8.2			7.83	X	22.8
3% GAC-C					8.2			7.2	X	22.8
5% GAC-A					8.2			7.39	X	22.8
5% GAC-B					8.2			7.47	X	22.8
5% GAC-C					8.2			6.92	X	22.8
1% AquaBlok-A					8.2			7.25	X	22.8
1% AquaBlok-B					8.2			7.11	X	22.8
1% AquaBlok-C					8.2			8.02	X	22.7
3% AquaBlok-A					8.4			8.34	X	22.7
3% AquaBlok-B					8.4			7.17	X	22.7
3% AquaBlok-C					8.4			7.21	X	22.7
5% AquaBlok-A					8.4		0	7.74	X	22.7
5% AquaBlok-B					8.4		0	7.95	X	22.7
5% AquaBlok-C					8.4		0	8	X	22.7
Untreated-A					8			7.99	X	22.7
Untreated-B					8			7.32	X	22.7
Untreated-C					8			7.89	X	22.7
Control-A					8.2			7.68	X	24.2
Control-B					8.4			6.91	X	22.8
Control-C					8.4			7.74	X	22.7

Day 9

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.4	X	24.3
1% SediMite-B								7.55	X	24.3
1% SediMite-C								8	X	24.3
3% SediMite-A								7.75	X	24.3
3% SediMite-B								7.77	X	24.3
3% SediMite-C								6.55	X	24.3
5% SediMite-A								7.3	X	24.3
5% SediMite-B								7.52	X	24.3
5% SediMite-C								6.68	X	24.3
1% GAC-A								7.02	X	24.3
1% GAC-B								7.84	X	22.9
1% GAC-C								7.54	X	22.9
3% GAC-A								7.69	X	22.9
3% GAC-B								7.46	X	22.9
3% GAC-C								6.83	X	22.9
5% GAC-A								6.85	X	22.9
5% GAC-B								7.07	X	22.9
5% GAC-C								6.89	X	22.9
1% AquaBlok-A								6.88	X	22.9
1% AquaBlok-B								7.11	X	22.9
1% AquaBlok-C								7.9	X	22.3
3% AquaBlok-A								8.08	X	22.3
3% AquaBlok-B								7.64	X	22.3
3% AquaBlok-C								7.41	X	22.3
5% AquaBlok-A								7.26	X	22.3
5% AquaBlok-B								7.72	X	22.3
5% AquaBlok-C								8.02	X	22.3
Untreated-A								8	X	22.3
Untreated-B								8.03	X	22.3
Untreated-C								7.75	X	22.3
Control-A								7.55	X	24.3
Control-B								6.85	X	22.9
Control-C								7.13	X	22.3

Day 10

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.4	X	24.3
1% SediMite-B								7.55	X	24.3
1% SediMite-C								8	X	24.3
3% SediMite-A								7.75	X	24.3
3% SediMite-B								7.77	X	24.3
3% SediMite-C								6.55	X	24.3
5% SediMite-A								7.3	X	24.3
5% SediMite-B								7.52	X	24.3
5% SediMite-C								6.68	X	24.3
1% GAC-A								7.02	X	24.3
1% GAC-B								7.84	X	22.9
1% GAC-C								7.54	X	22.9
3% GAC-A								7.69	X	22.9
3% GAC-B								7.46	X	22.9
3% GAC-C								6.83	X	22.9
5% GAC-A								6.85	X	22.9
5% GAC-B								7.07	X	22.9
5% GAC-C								6.89	X	22.9
1% AquaBlok-A								6.88	X	22.9
1% AquaBlok-B								7.11	X	22.9
1% AquaBlok-C								7.9	X	22.3
3% AquaBlok-A								8.08	X	22.3
3% AquaBlok-B								7.64	X	22.3
3% AquaBlok-C								7.41	X	22.3
5% AquaBlok-A								7.26	X	22.3
5% AquaBlok-B								7.72	X	22.3
5% AquaBlok-C								8.02	X	22.3
Untreated-A								8	X	22.3
Untreated-B								8.03	X	22.3
Untreated-C								7.75	X	22.3
Control-A								7.55	X	24.3
Control-B								6.85	X	22.9
Control-C								7.13	X	22.3

Day 11

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A					8.4			7.78	X	23.9
1% SediMite-B					8.4			8.23	X	23.9
1% SediMite-C					8.4			7.95	X	23.9
3% SediMite-A					8.4			7.59	X	23.9
3% SediMite-B					8.4			6.99	X	23.9
3% SediMite-C					8.4			6.79	X	23.9
5% SediMite-A					8.4			7.13	X	23.9
5% SediMite-B					8.4			6.88	X	23.9
5% SediMite-C					7.8			7.42	X	23.9
1% GAC-A					8			7.6	X	23.9
1% GAC-B					8			8.12	X	22.9
1% GAC-C					7.8			7.41	X	22.9
3% GAC-A					7.8			7.43	X	22.9
3% GAC-B					8			7.84	X	22.9
3% GAC-C					7.8			7.44	X	22.9
5% GAC-A					7.8			6.54	X	22.9
5% GAC-B					8			7.07	X	22.9
5% GAC-C					8			7.43	X	22.9
1% AquaBlok-A					7.8			7.51	X	22.9
1% AquaBlok-B					8.4			7.33	X	22.9
1% AquaBlok-C					8			7.41	X	22.3
3% AquaBlok-A					8.2			7.23	X	22.3
3% AquaBlok-B					8.4			7.35	X	22.3
3% AquaBlok-C					8.4			7.63	X	22.3
5% AquaBlok-A					8.4			7.11	X	22.3
5% AquaBlok-B					8.4			7.68	X	22.3
5% AquaBlok-C					8.4			8.03	X	22.3
Untreated-A					7.8			8.21	X	22.3
Untreated-B					8			7.94	X	22.3
Untreated-C					7.8			7.86	X	22.3
Control-A					8.4			6.97	X	23.9
Control-B					8.4			7.32	X	22.9
Control-C					8.4			7.64	X	22.3

Day 12

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.56	X	24.5
1% SediMite-B								7.28	X	24.5
1% SediMite-C								7.64	X	24.5
3% SediMite-A								7.6	X	24.5
3% SediMite-B								6.95	X	24.5
3% SediMite-C								6.8	X	24.5
5% SediMite-A								6.3	X	24.5
5% SediMite-B								7.19	X	24.5
5% SediMite-C								7.12	X	24.5
1% GAC-A								6.98	X	24.5
1% GAC-B								7.72	X	22.8
1% GAC-C								7.93	X	22.8
3% GAC-A								6.97	X	22.8
3% GAC-B								6.28	X	22.8
3% GAC-C								7.28	X	22.8
5% GAC-A								7.26	X	22.8
5% GAC-B								7.19	X	22.8
5% GAC-C								7.1	X	22.8
1% AquaBlok-A								6.95	X	22.8
1% AquaBlok-B								7.62	X	22.8
1% AquaBlok-C								6.32	X	22.7
3% AquaBlok-A								7.51	X	22.7
3% AquaBlok-B								7.8	X	22.7
3% AquaBlok-C								7.53	X	22.7
5% AquaBlok-A								7.73	X	22.7
5% AquaBlok-B								7.07	X	22.7
5% AquaBlok-C								7.25	X	22.7
Untreated-A								7.96	X	22.7
Untreated-B								7.64	X	22.7
Untreated-C								7.39	X	22.7
Control-A								7.41	X	24.5
Control-B								7.1	X	22.8
Control-C								7.17	X	22.7

Day 13

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.25	X	24.6
1% SediMite-B								7.08	X	24.6
1% SediMite-C								7.25	X	24.6
3% SediMite-A								7.24	X	24.6
3% SediMite-B								7.1	X	24.6
3% SediMite-C								6.85	X	24.6
5% SediMite-A								6.66	X	24.6
5% SediMite-B								6.12	X	24.6
5% SediMite-C								6.46	X	24.6
1% GAC-A								6.5	X	24.6
1% GAC-B								7.31	X	22.8
1% GAC-C								6.99	X	22.8
3% GAC-A								7.25	X	22.8
3% GAC-B								7.44	X	22.8
3% GAC-C								7.03	X	22.8
5% GAC-A								7.03	X	22.8
5% GAC-B								6.58	X	22.8
5% GAC-C								6.39	X	22.8
1% AquaBlok-A								6.41	X	22.8
1% AquaBlok-B								6.24	X	22.8
1% AquaBlok-C								7.03	X	22.7
3% AquaBlok-A								7.27	X	22.7
3% AquaBlok-B								7.36	X	22.7
3% AquaBlok-C								7.59	X	22.7
5% AquaBlok-A								7.58	X	22.7
5% AquaBlok-B								7.07	X	22.7
5% AquaBlok-C								7.12	X	22.7
Untreated-A								7.36	X	22.7
Untreated-B								7.53	X	22.7
Untreated-C								7.63	X	22.7
Control-A								6.62	X	24.6
Control-B								6.21	X	22.8
Control-C								6.53	X	22.7

Day 14

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A	0	0	300+	80-120	8.4	1160	0.25	7.27	X	24.5
1% SediMite-B	0	0	300+	80-120	8.4	1179	0	7.35	X	24.5
1% SediMite-C	0	0	300+	80-120	8.4	1171	0	7.1	X	24.5
3% SediMite-A	0	0	300+	80-120	8.4	1143	0	7.66	X	24.5
3% SediMite-B	0	0	300+	80-120	8.4	1146	0	7.25	X	24.5
3% SediMite-C	0	0	300+	80-120	8.4	11560	0	6.84	X	24.5
5% SediMite-A	0	0	300+	80-120	8.4	1096	0	6.89	X	24.5
5% SediMite-B	0	0	300+	80-120	8.4	1089	0	6.55	X	24.5
5% SediMite-C	0	0	300+	80-120	8.4	1152	0	6.69	X	24.5
1% GAC-A	0	0	300+	80-120	8	1071	0.25	6.5	X	24.5
1% GAC-B	0	0	300+	80-120	8	1036	0	7.01	X	22.6
1% GAC-C	0	0	300+	80-120	8	1037	0.25	7.5	X	22.6
3% GAC-A	0	0	300+	80-120	8	1029	0.25	7.36	X	22.6
3% GAC-B	0	0	300+	80-120	8	988	0.25	7.21	X	22.6
3% GAC-C	0	0	300+	80-120	8	1020	0.25	7.29	X	22.6
5% GAC-A	0	0	300+	80-120	8	1004	0.25	6.88	X	22.6
5% GAC-B	0	0	300+	80-120	8	1024	0.25	6.66	X	22.6
5% GAC-C	0	0	300+	80-120	8	1000	0.25	6.89	X	22.6
1% AquaBlok-A	0	0	300+	80-120	8.2	1076	0.25	6.99	X	22.6
1% AquaBlok-B	0	0	300+	80-120	8.2	1056	0	7.03	X	22.6
1% AquaBlok-C	0	0	300+	80-120	8.2	1031	0	7.5	X	22.6
3% AquaBlok-A	0	0	300+	80-120	8.4	1131	0	8.03	X	22.6
3% AquaBlok-B	0	0	300+	80-120	8.4	1153	0.25	7.11	X	22.6
3% AquaBlok-C	0	0	300+	80-120	8.4	1108	0	7.6	X	22.6
5% AquaBlok-A	0	0	300+	80-120	8.4	1117	0.25	7.3	X	22.6
5% AquaBlok-B	0	0	300+	80-120	8.4	1125	0	7.39	X	22.6
5% AquaBlok-C	0	0	300+	80-120	8.4	1169	0	7.98	X	22.6
Untreated-A	0	0	300+	80-120	8.2	1010	0	7.64	X	22.6
Untreated-B	0	0	300+	80-120	8.4	1024	0	7.4	X	22.6
Untreated-C	0	0	300+	80-120	8.4	1023	0.25	7.82	X	22.6
Control-A	0	0	300+	80-120	8.2	1080	0	7.09	X	24.5
Control-B	0	0	300+	80-120	8.2	1061	0	6.5	X	22.6
Control-C	0	0	300+	80-120	8.4	1040	0	7	X	22.6

Day 15

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.21	X	24.8
1% SediMite-B								7.45	X	24.8
1% SediMite-C								7.75	X	24.8
3% SediMite-A								7.71	X	24.8
3% SediMite-B								6.8	X	24.8
3% SediMite-C								7.31	X	24.8
5% SediMite-A								6.96	X	24.8
5% SediMite-B								6.59	X	24.8
5% SediMite-C								6.55	X	24.8
1% GAC-A								6.78	X	24.8
1% GAC-B								6.46	X	23
1% GAC-C								7.27	X	23
3% GAC-A								7.14	X	23
3% GAC-B								7.35	X	23
3% GAC-C								7.21	X	23
5% GAC-A								6.88	X	23
5% GAC-B								6.98	X	23
5% GAC-C								7.23	X	23
1% AquaBlok-A								7.33	X	23
1% AquaBlok-B								7.33	X	23
1% AquaBlok-C								6.54	X	23.1
3% AquaBlok-A								7.17	X	23.1
3% AquaBlok-B								6.9	X	23.1
3% AquaBlok-C								7.38	X	23.1
5% AquaBlok-A								6.89	X	23.1
5% AquaBlok-B								6.84	X	23.1
5% AquaBlok-C								7.55	X	23.1
Untreated-A								7.62	X	23.1
Untreated-B								6.58	X	23.1
Untreated-C								6.99	X	23.1
Control-A								7.27	X	24.8
Control-B								7.12	X	23
Control-C								7.19	X	23.1

Day 16

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.21	X	24.6
1% SediMite-B								7.19	X	24.6
1% SediMite-C								7.23	X	24.6
3% SediMite-A								7.49	X	24.6
3% SediMite-B								6.85	X	24.6
3% SediMite-C								6.82	X	24.6
5% SediMite-A								6.78	X	24.6
5% SediMite-B								7.14	X	24.6
5% SediMite-C								7.13	X	24.6
1% GAC-A								7.06	X	24.6
1% GAC-B								7.19	X	23
1% GAC-C								7.26	X	23
3% GAC-A								7.31	X	23
3% GAC-B								7.29	X	23
3% GAC-C								6.87	X	23
5% GAC-A								6.78	X	23
5% GAC-B								6.91	X	23
5% GAC-C								6.52	X	23
1% AquaBlok-A								7.23	X	23
1% AquaBlok-B								7.07	X	23
1% AquaBlok-C								7.15	X	23
3% AquaBlok-A								7.53	X	23
3% AquaBlok-B								6.89	X	23
3% AquaBlok-C								6.94	X	23
5% AquaBlok-A								7.23	X	23
5% AquaBlok-B								7.2	X	23
5% AquaBlok-C								7.29	X	23
Untreated-A								7.51	X	23
Untreated-B								7.22	X	23
Untreated-C								7.31	X	23
Control-A								6.65	X	24.6
Control-B								7.1	X	23
Control-C								7.29	X	23

Day 17

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.28	X	24.9
1% SediMite-B								7.13	X	24.9
1% SediMite-C								7.14	X	24.9
3% SediMite-A								7.42	X	24.9
3% SediMite-B								711	X	24.9
3% SediMite-C								6.81	X	24.9
5% SediMite-A								6.26	X	24.9
5% SediMite-B								6.63	X	24.9
5% SediMite-C								6.68	X	24.9
1% GAC-A								6.88	X	24.9
1% GAC-B								7.35	X	23.5
1% GAC-C								7..23	X	23.5
3% GAC-A								7.39	X	23.5
3% GAC-B								7.35	X	23.5
3% GAC-C								7.37	X	23.5
5% GAC-A								7.55	X	23.5
5% GAC-B								7.43	X	23.5
5% GAC-C								6.88	X	23.5
1% AquaBlok-A								6.98	X	23.5
1% AquaBlok-B								7.3	X	23.5
1% AquaBlok-C								7.65	X	23.1
3% AquaBlok-A								7.63	X	23.1
3% AquaBlok-B								7.64	X	23.1
3% AquaBlok-C								7.66	X	23.1
5% AquaBlok-A								7.96	X	23.1
5% AquaBlok-B								7.2	X	23.1
5% AquaBlok-C								7.53	X	23.1
Untreated-A								7.59	X	23.1
Untreated-B								7.46	X	23.1
Untreated-C								7.56	X	23.1
Control-A								6.23	X	24.9
Control-B								6.89	X	23.5
Control-C								6.79	X	23.1

Day 18

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.95	X	24.9
1% SediMite-B								7.56	X	24.9
1% SediMite-C								7.61	X	24.9
3% SediMite-A								7.86	X	24.9
3% SediMite-B								7.57	X	24.9
3% SediMite-C								7.79	X	24.9
5% SediMite-A								7.19	X	24.9
5% SediMite-B								6.75	X	24.9
5% SediMite-C								7.06	X	24.9
1% GAC-A								6.85	X	24.9
1% GAC-B								7.56	X	23.8
1% GAC-C								7.46	X	23.8
3% GAC-A								7.36	X	23.8
3% GAC-B								7.4	X	23.8
3% GAC-C								7.6	X	23.8
5% GAC-A								7.31	X	23.8
5% GAC-B								6.45	X	23.8
5% GAC-C								6.86	X	23.8
1% AquaBlok-A								7.1	X	23.8
1% AquaBlok-B								7.2	X	23.8
1% AquaBlok-C								7.46	X	23
3% AquaBlok-A								7.54	X	23
3% AquaBlok-B								7.32	X	23
3% AquaBlok-C								7.2	X	23
5% AquaBlok-A								7.14	X	23
5% AquaBlok-B								7.19	X	23
5% AquaBlok-C								7.61	X	23
Untreated-A								7.45	X	23
Untreated-B								7.32	X	23
Untreated-C								7.26	X	23
Control-A								6.64	X	24.9
Control-B								7.12	X	23.8
Control-C								7.06	X	23

Day 19

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								6.91	X	24.9
1% SediMite-B								7.41	X	24.9
1% SediMite-C								7.06	X	24.9
3% SediMite-A								7.05	X	24.9
3% SediMite-B								6.86	X	24.9
3% SediMite-C								6.59	X	24.9
5% SediMite-A								6.45	X	24.9
5% SediMite-B								6.37	X	24.9
5% SediMite-C								7.23	X	24.9
1% GAC-A								6.72	X	24.9
1% GAC-B								7.39	X	23.3
1% GAC-C								7.1	X	23.3
3% GAC-A								7.27	X	23.3
3% GAC-B								7.03	X	23.3
3% GAC-C								7.18	X	23.3
5% GAC-A								6.79	X	23.3
5% GAC-B								6.78	X	23.3
5% GAC-C								6.69	X	23.3
1% AquaBlok-A								6.33	X	23.3
1% AquaBlok-B								6.99	X	23.3
1% AquaBlok-C								6.91	X	22.9
3% AquaBlok-A								6.52	X	22.9
3% AquaBlok-B								6.92	X	22.9
3% AquaBlok-C								7.27	X	22.9
5% AquaBlok-A								7.44	X	22.9
5% AquaBlok-B								7.33	X	22.9
5% AquaBlok-C								7.29	X	22.9
Untreated-A								7.13	X	22.9
Untreated-B								7.42	X	22.9
Untreated-C								7.03	X	22.9
Control-A								7.12	X	24.9
Control-B								6.89	X	23.3
Control-C								7.2	X	22.9

Day 20

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.81	X	24.9
1% SediMite-B								7.84	X	24.9
1% SediMite-C								8.23	X	24.9
3% SediMite-A								8.02	X	24.9
3% SediMite-B								7.76	X	24.9
3% SediMite-C								7.48	X	24.9
5% SediMite-A								7.43	X	24.9
5% SediMite-B								6.83	X	24.9
5% SediMite-C								7.23	X	24.9
1% GAC-A								7.51	X	24.9
1% GAC-B								7.91	X	23.3
1% GAC-C								7.89	X	23.3
3% GAC-A								6.65	X	23.3
3% GAC-B								8.19	X	23.3
3% GAC-C								7.91	X	23.3
5% GAC-A								8.09	X	23.3
5% GAC-B								7.79	X	23.3
5% GAC-C								7.62	X	23.3
1% AquaBlok-A								7.63	X	23.3
1% AquaBlok-B								7.71	X	23.3
1% AquaBlok-C								7.56	X	22.9
3% AquaBlok-A								7.92	X	22.9
3% AquaBlok-B								8.23	X	22.9
3% AquaBlok-C								7.87	X	22.9
5% AquaBlok-A								8.57	X	22.9
5% AquaBlok-B								7.31	X	22.9
5% AquaBlok-C								8.25	X	22.9
Untreated-A								8.3	X	22.9
Untreated-B								7.52	X	22.9
Untreated-C								7.93	X	22.9
Control-A								7.15	X	24.9
Control-B								7.39	X	23.3
Control-C								8.22	X	22.9

Day 21

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A	0	0	300+	80-120	8.2	774	0	7.33	X	24.9
1% SediMite-B	0	0	300+	80-120	8.4	813	0	7.79	X	24.9
1% SediMite-C	0	0	300+	80-120	8.2	812	0	7.95	X	24.9
3% SediMite-A	0	0	300+	80-120	8.4	782	0	7.33	X	24.9
3% SediMite-B	0	0	300+	80-120	8.4	868	0	6.69	X	24.9
3% SediMite-C	0	0	300+	80-120	8.4	790	0	8.02	X	24.9
5% SediMite-A	0	0	300+	80-120	8.4	821	0	7.88	X	24.9
5% SediMite-B	0	0	300+	80-120	8.4	778	0	7.06	X	24.9
5% SediMite-C	0	0	300+	80-120	8.2	762	0	7.36	X	24.9
1% GAC-A	0	0	300+	80-120	8	734	0	7.3	X	24.9
1% GAC-B	0	0	300+	80-120	8.2	640	0	7.07	X	23.3
1% GAC-C	0	0	300+	80-120	8.2	659	0	7.22	X	23.3
3% GAC-A	0	0	300+	80-120	8	700	0	7.52	X	23.3
3% GAC-B	0	0	300+	80-120	8.2	650	0	7.08	X	23.3
3% GAC-C	0	0	300+	80-120	8	667	0	7.62	X	23.3
5% GAC-A	0	0	300+	80-120	8	651	0	7.13	X	23.3
5% GAC-B	0	0	300+	80-120	8.4	675	0	7.08	X	23.3
5% GAC-C	0	0	300+	80-120	8.2	652	0	7.36	X	23.3
1% AquaBlok-A	0	0	300+	80-120	8.2	674	0	7.41	X	23.3
1% AquaBlok-B	0	0	300+	80-120	8.2	685	0	7.67	X	23.3
1% AquaBlok-C	0	0	300+	80-120	8.2	6770	0	7.74	X	22.9
3% AquaBlok-A	0	0	300+	80-120	8.4	752	0	7.24	X	22.9
3% AquaBlok-B	0	0	300+	80-120	8.4	788	0	7.01	X	22.9
3% AquaBlok-C	0	0	300+	80-120	8.4	785	0	7.27	X	22.9
5% AquaBlok-A	0	0	300+	80-120	8.4	820	0	6.71	X	22.9
5% AquaBlok-B	0	0	300+	80-120	8.4	798	0	7.52	X	22.9
5% AquaBlok-C	0	0	300+	80-120	8.4	784	0	7.21	X	22.9
Untreated-A	0	0	300+	80-120	8	738	0	7.38	X	22.9
Untreated-B	0	0	300+	80-120	8.2	721	0	6.98	X	22.9
Untreated-C	0	0	300+	80-120	8	717	0	7.84	X	22.9
Control-A	0	0	300+	80-120	8.2	747	0.25	7.89	X	24.9
Control-B	0	0	300+	80-120	8.2	710	0	7.94	X	23.3
Control-C	0	0	300+	80-120	8.2	688	0	7.7	X	22.9

Day 22

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.8	X	24.8
1% SediMite-B								8.1	X	24.8
1% SediMite-C								8.09	X	24.8
3% SediMite-A								7.45	X	24.8
3% SediMite-B								7.88	X	24.8
3% SediMite-C								7.86	X	24.8
5% SediMite-A								7.03	X	24.8
5% SediMite-B								7.73	X	24.8
5% SediMite-C								7.24	X	24.8
1% GAC-A								7.53	X	24.8
1% GAC-B								7.28	X	23.8
1% GAC-C								7.16	X	23.8
3% GAC-A								7	X	23.8
3% GAC-B								7.23	X	23.8
3% GAC-C								7.06	X	23.8
5% GAC-A								7.91	X	23.8
5% GAC-B								8.05	X	23.8
5% GAC-C								7.83	X	23.8
1% AquaBlok-A								7.85	X	23.8
1% AquaBlok-B								7.88	X	23.8
1% AquaBlok-C								7.59	X	22.9
3% AquaBlok-A								7.93	X	22.9
3% AquaBlok-B								8	X	22.9
3% AquaBlok-C								7.23	X	22.9
5% AquaBlok-A								8.23	X	22.9
5% AquaBlok-B								87.45	X	22.9
5% AquaBlok-C								7.84	X	22.9
Untreated-A								8.37	X	22.9
Untreated-B								7.69	X	22.9
Untreated-C								7.91	X	22.9
Control-A								7.56	X	24.8
Control-B								7.82	X	23.8
Control-C								7.71	X	22.9

Day 23

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.96	X	24.8
1% SediMite-B								8.1	X	24.8
1% SediMite-C								8.05	X	24.8
3% SediMite-A								7.48	X	24.8
3% SediMite-B								7.9	X	24.8
3% SediMite-C								7.58	X	24.8
5% SediMite-A								7.84	X	24.8
5% SediMite-B								7.2	X	24.8
5% SediMite-C								7.79	X	24.8
1% GAC-A								7.89	X	24.8
1% GAC-B								7.99	X	23.6
1% GAC-C								7.24	X	23.6
3% GAC-A								7.18	X	23.6
3% GAC-B								7.39	X	23.6
3% GAC-C								7.37	X	23.6
5% GAC-A								7.66	X	23.6
5% GAC-B								7.14	X	23.6
5% GAC-C								7.48	X	23.6
1% AquaBlok-A								7.53	X	23.6
1% AquaBlok-B								7.25	X	23.6
1% AquaBlok-C								8	X	22.9
3% AquaBlok-A								8.2	X	22.9
3% AquaBlok-B								7.89	X	22.9
3% AquaBlok-C								7.19	X	22.9
5% AquaBlok-A								7.82	X	22.9
5% AquaBlok-B								7.63	X	22.9
5% AquaBlok-C								8.24	X	22.9
Untreated-A								7.4	X	22.9
Untreated-B								7.68	X	22.9
Untreated-C								7.5	X	22.9
Control-A								7.54	X	24.8
Control-B								7.98	X	23.6
Control-C								7.48	X	22.9

Day 24

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.82	X	24.8
1% SediMite-B								7.75	X	24.8
1% SediMite-C								7.69	X	24.8
3% SediMite-A								7.51	X	24.8
3% SediMite-B								7.43	X	24.8
3% SediMite-C								7.58	X	24.8
5% SediMite-A								7.48	X	24.8
5% SediMite-B								7.79	X	24.8
5% SediMite-C								7.26	X	24.8
1% GAC-A								7.42	X	24.8
1% GAC-B								7.62	X	23.6
1% GAC-C								7.58	X	23.6
3% GAC-A								7.99	X	23.6
3% GAC-B								7.77	X	23.6
3% GAC-C								7.92	X	23.6
5% GAC-A								8.28	X	23.6
5% GAC-B								7.92	X	23.6
5% GAC-C								7.56	X	23.6
1% AquaBlok-A								7.65	X	23.6
1% AquaBlok-B								7.7	X	23.6
1% AquaBlok-C								7.36	X	22.9
3% AquaBlok-A								7.7	X	22.9
3% AquaBlok-B								7.34	X	22.9
3% AquaBlok-C								7.58	X	22.9
5% AquaBlok-A								7.93	X	22.9
5% AquaBlok-B								8.11	X	22.9
5% AquaBlok-C								7.29	X	22.9
Untreated-A								7.96	X	22.9
Untreated-B								7.09	X	22.9
Untreated-C								7.59	X	22.9
Control-A								7.62	X	24.8
Control-B								7.68	X	23.6
Control-C								7.61	X	22.9

Day 25

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.98	X	24.8
1% SediMite-B								7.99	X	24.8
1% SediMite-C								7.77	X	24.8
3% SediMite-A								8	X	24.8
3% SediMite-B								7	X	24.8
3% SediMite-C								7.13	X	24.8
5% SediMite-A								6.87	X	24.8
5% SediMite-B								7.27	X	24.8
5% SediMite-C								7.54	X	24.8
1% GAC-A								7.87	X	24.8
1% GAC-B								7.23	X	23.8
1% GAC-C								8.01	X	23.8
3% GAC-A								7.8	X	23.8
3% GAC-B								7.77	X	23.8
3% GAC-C								7.39	X	23.8
5% GAC-A								7.59	X	23.8
5% GAC-B								7.4	X	23.8
5% GAC-C								7.67	X	23.8
1% AquaBlok-A								7.42	X	23.8
1% AquaBlok-B								7.43	X	23.8
1% AquaBlok-C								7.58	X	23
3% AquaBlok-A								7.88	X	23
3% AquaBlok-B								7.68	X	23
3% AquaBlok-C								7.48	X	23
5% AquaBlok-A								7.44	X	23
5% AquaBlok-B								7.26	X	23
5% AquaBlok-C								7.69	X	23
Untreated-A								7.79	X	23
Untreated-B								8.06	X	23
Untreated-C								7.67	X	23
Control-A								7.66	X	24.8
Control-B								7.63	X	23.8
Control-C								7.554	X	23

Day 26

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								8.43	X	24.8
1% SediMite-B								7.99	X	24.8
1% SediMite-C								8.05	X	24.8
3% SediMite-A								7.85	X	24.8
3% SediMite-B								7.96	X	24.8
3% SediMite-C								7.31	X	24.8
5% SediMite-A								7.65	X	24.8
5% SediMite-B								7.99	X	24.8
5% SediMite-C								7.85	X	24.8
1% GAC-A								8.02	X	24.8
1% GAC-B								7.52	X	24.8
1% GAC-C								7.23	X	24.8
3% GAC-A								7.89	X	24.8
3% GAC-B								8.2	X	24.8
3% GAC-C								7.76	X	24.8
5% GAC-A								7.93	X	24.8
5% GAC-B								7.78	X	24.8
5% GAC-C								7.72	X	24.8
1% AquaBlok-A								7.71	X	24.8
1% AquaBlok-B								7.52	X	24.8
1% AquaBlok-C								7.67	X	22.9
3% AquaBlok-A								8.11	X	22.9
3% AquaBlok-B								8.18	X	22.9
3% AquaBlok-C								7.73	X	22.9
5% AquaBlok-A								8.07	X	22.9
5% AquaBlok-B								7.68	X	22.9
5% AquaBlok-C								7.45	X	22.9
Untreated-A								7.64	X	22.9
Untreated-B								7.88	X	22.9
Untreated-C								8.02	X	22.9
Control-A								7.55	X	24.8
Control-B								8.08	X	24.8
Control-C								7.96	X	22.9

Day 27

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A								7.6	X	24.9
1% SediMite-B								7.84	X	24.9
1% SediMite-C								7.25	X	24.9
3% SediMite-A								7.44	X	24.9
3% SediMite-B								6.89	X	24.9
3% SediMite-C								7.27	X	24.9
5% SediMite-A								7.02	X	24.9
5% SediMite-B								7.81	X	24.9
5% SediMite-C								7.25	X	24.9
1% GAC-A								6.89	X	24.9
1% GAC-B								7.85	X	23.8
1% GAC-C								7.82	X	23.8
3% GAC-A								7.34	X	23.8
3% GAC-B								7.98	X	23.8
3% GAC-C								7.67	X	23.8
5% GAC-A								7.78	X	23.8
5% GAC-B								7.62	X	23.8
5% GAC-C								7.58	X	23.8
1% AquaBlok-A								7.63	X	23.8
1% AquaBlok-B								7.32	X	23.8
1% AquaBlok-C								7.69	X	22.9
3% AquaBlok-A								7.83	X	22.9
3% AquaBlok-B								7.36	X	22.9
3% AquaBlok-C								7.36	X	22.9
5% AquaBlok-A								7.95	X	22.9
5% AquaBlok-B								7.77	X	22.9
5% AquaBlok-C								7.98	X	22.9
Untreated-A								7.9	X	22.9
Untreated-B								7.71	X	22.9
Untreated-C								8.03	X	22.9
Control-A								7.5	X	24.9
Control-B								7.52	X	23.8
Control-C								7.42	X	22.9

Day 28

Sediment	Total Chlorine	Free Chlorine	Total Hardness	Total Alkalinity	pH	Conductivity	NH_4^+ PPM	DO	Water Exchange	Temperature (Celsius)
1% SediMite-A	0	0	300+	80-120	8.4	1138	0	7.51		24.8
1% SediMite-B	0	0	300+	80-120	8.2	1156	0	7.654		24.8
1% SediMite-C	0	0	300+	80-120	8.4	1142	0	7.91		24.8
3% SediMite-A	0	0	300+	80-120	8.4	1106	0	7.99		24.8
3% SediMite-B	0	0	300+	80-120	8.4	1132	0	7.68		24.8
3% SediMite-C	0	0	300+	80-120	8.4	1137	0	7.48		24.8
5% SediMite-A	0	0	300+	80-120	8.8	1082	0	7.75		24.8
5% SediMite-B	0	0	300+	80-120	8.4	1105	0	7.7		24.8
5% SediMite-C	0	0	300+	80-120	8.4	1109	0	7.49		24.8
1% GAC-A	0	0	300+	80-120	8.2	1102	0	6.82		24.8
1% GAC-B	0	0	300+	80-120	8.2	1079	0	7.69		23.9
1% GAC-C	0	0	300+	80-120	8.2	1073	0	7.9		23.9
3% GAC-A	0	0	300+	80-120	8.2	1055	0	7.99		23.9
3% GAC-B	0	0	300+	80-120	8.2	1072	0	7.92		23.9
3% GAC-C	0	0	300+	80-120	8.2	1069	0	7.54		23.9
5% GAC-A	0	0	300+	80-120	8.2	1059	0	7.63		23.9
5% GAC-B	0	0	300+	80-120	8.2	1052	0	7.85		23.9
5% GAC-C	0	0	300+	80-120	8	1062	0	7.43		23.9
1% AquaBlok-A	0	0	300+	80-120	8.2	1093	0	7.12		23.9
1% AquaBlok-B	0	0	300+	80-120	8	1080	0	6.99		23.9
1% AquaBlok-C	0	0	300+	80-120	8.2	1050	0	7.23		22.6
3% AquaBlok-A	0	0	300+	80-120	8.4	1092	0	7.59		22.6
3% AquaBlok-B	0	0	300+	80-120	8.4	1081	0	7.62		22.6
3% AquaBlok-C	0	0	300+	80-120	8.4	1083	0	7.87		22.6
5% AquaBlok-A	0	0	300+	80-120	8	1103	0	7.49		22.6
5% AquaBlok-B	0	0	300+	80-120	8.4	1104	0	7.76		22.6
5% AquaBlok-C	0	0	300+	80-120	8.2	1129	0	7.83		22.6
Untreated-A	0	0	300+	80-120	8.8	1051	0	7.95		22.6
Untreated-B	0	0	300+	80-120	8.2	1050	0	8.02		22.6
Untreated-C	0	0	300+	80-120	8.2	1045	0	7.36		22.6
Control-A	0	0	300+	80-120	8.2	1091	0	7.23		24.8
Control-B	0	0	300+	80-120	8	1065	0	7.67		23.9
Control-C	0	0	300+	80-120	8.2	1060	0	7.69		22.6

Appendix 4. PCB homolog concentration in sediment porewater for Figure 3.

PCB homolog concentration in sediment porewater (ng/L)

	Untreated con	Clean control	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG 1%	AG3%	AG5%
Mono	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Di	0.199	0.000	0.081	0.024	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Tri	1.726	0.006	1.917	1.410	1.463	0.142	0.003	0.001	0.088	0.003	0.001
Tetra	1.044	0.048	1.263	1.043	1.232	0.635	0.237	0.072	0.310	0.015	0.006
Penta	0.283	0.030	0.263	0.250	0.281	0.204	0.145	0.071	0.165	0.024	0.010
Hexa	0.063	0.003	0.071	0.059	0.066	0.061	0.054	0.040	0.049	0.014	0.009
Hepta	0.011	0.000	0.011	0.009	0.010	0.010	0.009	0.008	0.009	0.003	0.002
Octa	0.001	0.000	0.000	0.000	0.001	0.001	0.000	0.000	0.001	0.000	0.000
Nona	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Deca	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL	3.33	0.09	3.61	2.80	3.05	1.05	0.45	0.19	0.62	0.06	0.03

PCB concentration in sediment porewater standard deviations

	Untreated	Control	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AB 1%	AB3%	AB5%
Mono	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Di	0.12	0.00	0.03	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Tri	0.22	0.01	0.08	0.36	0.08	0.02	0.00	0.00	0.11	0.00	0.00
Tetra	0.12	0.03	0.07	0.24	0.10	0.02	0.04	0.01	0.07	0.01	0.01
Penta	0.04	0.01	0.04	0.06	0.02	0.04	0.02	0.00	0.03	0.00	0.00
Hexa	0.01	0.00	0.01	0.02	0.00	0.01	0.01	0.00	0.01	0.00	0.00
Hepta	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Octa	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Nona	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Deca	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL	0.20	0.04	0.16	0.70	0.20	0.07	0.07	0.01	0.03	0.01	0.01

Appendix 5. PCB homolog concentration in worm tissue for Figure 5.

PCB concentration in worm tissue (ng/g)

	Untreated c	Clean control	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AG1%	AG3%	AG5%
Mono	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Di	0.78	0.00	0.00	0.00	0.00	0.12	0.00	0.00	0.00	0.00	0.00
Tri	6.24	0.00	1.49	2.76	1.59	0.29	0.00	0.00	0.00	0.00	0.00
Tetra	18.01	0.26	10.11	14.61	10.80	4.56	0.00	0.00	0.71	0.00	0.00
Penta	25.28	1.81	17.68	25.95	22.54	19.48	6.36	3.41	8.51	0.54	0.08
Hexa	27.95	1.83	21.70	28.18	26.13	26.57	12.42	12.47	16.66	3.51	0.46
Hepta	22.88	0.38	18.35	21.36	21.59	19.23	9.21	12.06	16.94	4.03	0.53
Octa	7.45	0.00	5.56	6.21	5.94	5.62	3.57	4.28	5.70	1.12	0.10
Nona	0.45	0.00	0.37	0.41	0.37	0.22	0.00	0.00	0.15	0.00	0.00
Deca	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL	109.05	4.28	75.27	99.48	88.96	76.10	31.56	32.23	48.66	9.19	1.18

PCB concentration in worm tissue standard deviations

	Untreated	Control	GAC 1%	GAC3%	GAC 5%	SM 1%	SM3%	SM5%	AB 1%	AB3%	AB5%
Mono	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Di	1.16	0.00	0.00	0.00	0.00	0.21	0.00	0.00	0.00	0.00	0.00
Tri	3.79	0.00	0.62	1.04	1.19	0.25	0.00	0.00	0.00	0.00	0.00
Tetra	5.63	0.44	3.10	1.99	3.18	3.42	0.00	0.00	1.22	0.00	0.00
Penta	7.54	1.46	4.72	3.03	4.89	7.14	0.78	1.00	2.48	0.50	0.15
Hexa	8.81	1.64	5.49	2.70	7.10	10.16	2.74	3.16	2.60	1.26	0.80
Hepta	7.88	0.54	4.57	1.97	6.10	7.69	2.27	2.23	1.59	1.80	0.82
Octa	0.84	0.00	1.01	0.90	1.71	1.38	0.71	1.07	0.77	0.81	0.17
Nona	0.27	0.00	0.05	0.08	0.32	0.21	0.00	0.00	0.25	0.00	0.00
Deca	0.03	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL	35.08	3.64	18.61	11.44	24.12	28.77	6.23	7.34	8.22	4.24	1.94

An Exelon Company

Appendix E

Macroinvertebrate Community Survey Results

Report on Hester-Dendy Samples for Macroinvertebrates in The Anacostia River Pepco Benning Road Facility, July-August 2020

Introduction

This reports presents the results of a macroinvertebrate community study conducted in June and July 2020 to determine baseline conditions in the approximately 4.2-acre cove of the Anacostia River, which is located just north of the Site beyond the National Park Service (NPS) Kenilworth Maintenance Yard property (the Cove). This macroinvertebrate community study described herein were conducted as part of the Treatability Study of the Cove to evaluate potential remedial alternatives for sediments in the Waterside Investigation Area.

This macroinvertebrate community study used artificial substrates (i.e., Hester Dendy samplers) deployed in a similar manner as described in the ARSP RI Report (Tetra Tech, 2019). Comparisons are made to the ARSP macroinvertebrate data collected using Hester-Dendy samplers in 2016.

A macroinvertebrate community survey was conducted in 2017 for the Baseline Ecological Risk Assessment (BERA), which was conducted on behalf of the Potomac Electric Power Company and Pepco Energy Services, Inc. (collectively "Pepco") as part of a Remedial Investigation/Feasibility Study (RI/FS) for Pepco's Benning Road facility (AECOM 2020). For the 2017 survey, co-located sediment grab samples were collected for synoptic analyses of benthic macroinvertebrate community, sediment bulk chemistry, and toxicity testing for evaluation in the Waterside Investigation Area BERA. The 2020 community survey data reported herein are also compared to the 2017 community survey data.

Methods

Hester-Dendy (HD) samplers (Hester and Dendy 1962) were placed at four sites near the Pepco Benning Road facility on the Anacostia River on 16 June 2020. At each site the HD was attached to a concrete block and set on the river bottom. The sites were marked with either a float and line or garden stake.

During an inspection on 14 July 2020 it was determined that two of the original sites (HD-2 and HD-3) would have to be moved due to exposure during very low tides (Figure 1). Coordinates for the final four sites are in Table 1. HD-01 and HD-04 were placed on 16 June 2020 and retrieved on 29 July 2020. HD-02a and HD-03a were placed on 16 July 2020 and retrieved 27 August 2020.

The Hester-Dendy samplers consisted of 14, 75 mm square masonite plates alternating with 25 mm nylon discs (Wildco, Buffalo, New York) for a total sample area of 0.1575 m^2. Spacing between plates ranged from 3 mm to 12 mm. All samples were placed in labeled plastic bags, and preserved in 70% ethanol for later laboratory analysis. In Normandeau's biological laboratory the HD's were cleaned and the contents sieved through a 500 µm mesh screen, and the macroinvertebrates sorted, counted and identified to the lowest practical taxonomic level.

Cluster analysis was used to evaluate the similarity among the stations. The analysis groups stations based on similarity of taxa composition and abundance (number of individuals), and graphically provides the results as a dendrogram. Average linkage algorithm and Euclidean distance similarity were used. The analysis was conducted with the statistical package R version 3.6.2 (2019-12-12) (The R Foundation for Statistical Computing at: https://www.r-project.org/foundation/).

Results and Discussion

A total of 1,030 individuals representing 36 taxa were collected at the four HD stations in July-August 2020 (Table 2). The number of taxa identified per station ranged from 7 at HD01 and HD02a to 20 at HD04. Abundance ranged from 226 individuals (1,435 individuals/m^2) at HD04 to 287 (1,822 individuals/m^2) at HD01.

The most abundant taxa from the HD samplers were similar to those found in the Anacostia River and other tidal freshwater systems within Chesapeake Bay (Diaz 1989, 1994, Dauer 1993, McGee et al. 2009, Tetra Tech 2019, Normandeau 2020). Tubificid oligochaetes were the dominant faunal group being 59% of all individuals collected. Chironomid insect larvae and gastropod snails were second and third being 16% and 14% of the fauna, respectively. The other 11% of the fauna was spread over six other major taxons (Table 3). Oligochaetes and chironomids each were represented by six species and snails by six genera (only three could be identified to species).

Cluster analysis (average linkage and Euclidian distance) showed that HD02a and HD03a, located in the Anacostia River, were the most similar of the four stations. Stations HD02a and HD03a were moved from their original locations and sampled a month after HD01 and HD04. Station HD04, located in the cove area next to the Pepco Benning Road facility (Figure 1) was the least similar of the four stations. Station HD01 was in-between, but more similar to HD04. What separated HD04 from the other stations was the high number of the naiad *Dero nivea* and low total number of taxa. Stations HD02a and HD03a grouped together primarily on the higher number of total taxa (Table 2).

Hester-Dendy samplers provide qualitative estimates of community composition based on colonization of species to the sampler's substrate geometry. Given the high levels of turbidity and eurytopic nature of tidal freshwater fauna, the major taxa collected for the ARSP in 2016 and for this study in 2020 were similar (Table 4). Total abundance per HD sampler in 2016 was about twice what it was in 2020. This was due primarily to the dominance of chironomid dipteran larvae in 2016 that were over 50% of all individuals (Tetra Tech 2019). In 2020, tubificid oligochaetes were dominant being almost 60% of all individuals.

The taxonomic resolution of the 2017 Ponar samples collected for the Pepco BERA was the same for this study in 2020 based on HD samples and could be qualitatively compared. The total number of taxa collected by HD in 2020 was basically the same as

the number collected by petite Ponar grab in 2017 within the Pepco Benning Road facility study area (Normandeau 2020). The 2017 Ponar samples found a total of 35 taxa with about 43% shared with the 36 taxa in the 2020 HD samples (Table 5). Between the two sampling years (2017 and 2020) there were a total of 55 taxa collected.

The HD samples in both 2016 and 2020 had a high proportion of epifauna taxa. These were primarily amphipods and gastropods (snails) which contributed about 40% of all individuals in 2016 and about 20% in 2020 (Table 4). Epifauna spend most of their time on the sediment surface and are the primary trophic resource for freshwater fishes found in the tidal freshwater Anacostia River (Murdy and Musick 2013). Stomach contents analysis of centrarchids fishes (pumpkinseed, bluegill, and redbreast sunfish) found they foraged primarily on gastropods, chironomid larvae, and other soft-bodied invertebrates (Tetra Tech, 2019). The cyprinids and fundulids (eastern silvery minnow, mummichog, and banded killifish) foraged predominately on chironomid larvae and other soft-bodied invertebrates (Tetra Tech 2019).

The major taxon composition of macroinvertebrates in the Anacostia River matches the major taxon composition from fish stomach content analysis (Table 4). This points to the broad forage base of the fishes and the important role of macroinvertebrates in trophic transfer up the aquatic food web in the tidal freshwater Anacostia River within the Pepco Benning Road facility study area.

Conclusions

Macroinvertebrates that colonized the Hester-Dendy (HD) samplers in 2020 were similar to the taxa found in the 2016 HD samples for the ARSP and also to grab samples from the 2017 Pepco BERA with about 43% of the taxa in common. The principal taxa were oligochaete worms followed by chironomid midge larvae, which are generally tolerant of sediment instability and organic pollutants.

Overall, the macroinvertebrate studies between 2016 and 2020 found the benthos of the tidal freshwater Anacostia River within the Pepco Benning Road facility study area to be typical of tidal freshwater systems with in Chesapeake Bay, which are well adapted to high levels of turbidity and soft unstable substrates, and dominated by oligochaetes and chironomid insect larvae.

Macroinvertebrates in the Anacostia River are an important forage base for fishes and contribute to trophic transfer up the aquatic food web in the tidal freshwater Anacostia River within the Pepco Benning Road facility study area.

References

AECOM. 2020. Remedial investigation report. Final. Benning Road Facility 3400 Benning Road, NE Washington, DC. Final Report to Pepco and Pepco Energy Services 701 9th Street, NW Washington, DC. 267 p. +Appendices.

Dauer, D.M. 1993. Virginia Chesapeake Bay monitoring program: benthic communities report, 1990-1991. Final Report to the Virginia Department of Environmental Quality. 414-S-92-041, 90 pp.

Diaz, R.J. 1989. Pollution and tidal benthic communities of the James River Estuary, Virginia. Hydrobiologia 180:195-211.

Diaz, R.J. 1994. Response of tidal freshwater macrobenthos to sediment disturbance. Hydrobiologia 278:201-212.


Hester, F.E. and J.S. Dendy. 1962. A multiple-plate sampler for aquatic macroinvertebrates. Transactions of the American Fisheries Society 91:420–421.

McGee, B.L., A.E. Pinkney, D.J. Velinsky, J.T.F. Ashley, D.J. Fisher, L.C. Ferrington, and T.J. Norbert-King. 2009. Using the sediment quality triad to characterize baseline condition in the Anacostia River, Washington, DC, USA. Environmental Monitoring and Assessment 156:51-67.

Murdy, E.O. and J.A. Musick. 2013. Field guide to fishes of the Chesapeake Bay. John Hopkins University Press, Baltimore, MD. 345 p.

Normandeau Associates. 2020. Benthic macroinvertebrate community report for the Anacostia River Pepco Benning Road Facility, October 2017. Attachment F, pp. 822-868. In: AECOM, Appendix BB, Baseline Ecological Risk Assessment Report. Benning Road Facility 3400 Benning Road, NE Washington, DC. Report to Pepco and Pepco Energy Services 701 9th Street, NW Washington, DC.

Tetra Tech. 2019. Appendix I Baseline ecological risk assessment, Anacostia River Sediment Project, Washington, D.C. Report to Department of Energy and Environment, Government of the District of Columbia.



AECOM

0 300 Feet

N W E S

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

LOCATION OF HESTER-DENDY SAMPLERS FOR MACROINVERTEBRATE SURVEY

Date: 11/3/2020	Drawn By: JB	Checked By: SED		FIGURE 1




Figure 2. Dendrogram of macroinvertebrate assemblages at the four HD stations on the Anacostia River within the Pepco Benning Road facility study area, July-August 2020. Cluster analysis used average linkage and Euclidian distance.

Table 1. Location of HD samplers. Coordinate system used is US State Plane 1983/ NAD 83/Maryland 1900/ US survey Feet.

LOCATION ID	Northing	Easting
HD 01	449652.467	1323597.122
HD-02a	448752.357	1323121.862
HD-03a	449995.067	1323773.862
HD-04	449689.557	1324177.982

Table 2. Total number of organisms collected at the four HD sample stations in the Anacostia River within the Pepco Benning Road facility study area, July-August 2020.

Taxon	Common Name	HD 01	HD 02a	HD 03a	HD 04	All Stations
Nematoda	round worms		2		1	3
Tricladida						
Planariidae						
Dugesia tigrina	flat worm			40		40
Tubificida						
Naididae						
Dero nivea	naiad worm	7			197	204
Dero sp.	naiad worm			12		12
Haemonais waldvogeli	naiad worm			8		8
Tubificinae						
Aulodrilus limnobius	tube worm			12		12
Branchiura sowerbyi	tube worm		8			8
Limnodrilus sp.	tube worm		242	92		334
Limnodrilus cervix	tube worm		22			22
Limnodrilus hoffmeisteri	tube worm			12		12
Hirudinida						
Erpobdellidae						
Erpobdella punctata	leech			1		1
Glossophoniidae	leech			1		1
Helobdella elongata	leech		1			1
Bivalvia						
Pisidiidae						
Pisidium casertanum	pill clam		1			1
Sphaeridae						
Musculium transversum	fingernail clam			1		1
Gastropoda						
Amnicolidae						
Amnicola sp.	dusky snail	1				1
Planorbidae						
Micromenetus dilatatus	orb snail				5	5
Physidae						
Physella sp.	pouch snail	1			8	9
Planorbidae						
Micromenetus dilatatus	orb snail			3		3
Viviparidae						
Cipangopaludina japonica	mystery snail	119		3		122

Table 2 (Continued.)

Taxon	Common Name	HD 01	HD 02a	HD 03a	HD 04	All Stations
Amphipoda						
Gammaridae						
Gammarus fasciatus	side swimmer	48	1	7		56
Isopoda						
Asellidae						
Caecidotea sp.	water slater		1	1		2
Odonata						
Coenagrionidae						
Argia sp.	damselfly			1		1
Enallagma sp.	damselfly	1	1			2
Coleoptera						
Haliplidae						
Peltodytes sp.	crawling beetle				1	1
Elmidae						
Ancyronyx variegatus	riffle beetle		1			1
Stenelmis crenata gr.	riffle beetle			2		2
Diptera						
Chironomidae						
Chironomini	midge		1			1
Chironomus decorus gr.	midge				8	8
Dicrotendipes sp.	midge		1	7		8
Dicrotendipes simpsoni	midge	110		7	12	129
Orthocladius annectens	midge		2			2
Polypedilum halterale gr.	midge			8		8
Polypedilum scalaenum gr.	midge			7		7
Sublettea coffmani	midge		1			1
Thienemannimyia gr.	midge			1		1
Number of Taxa		7	7	14	20	36
Number of Individuals		287	232	285	226	1,030
Density (no./m2)		1,822	1,473	1,810	1,435	

Table 3. Percent contribution of major taxa summed for the four HD sample stations in the Anacostia River within the Pepco Benning Road facility study area, July-August 2020.

Major Taxon	Common Name	Total Number	% of Total
Tricladida	Flat Worms	40	3.9
Tubificida	True Worms	612	59.4
Hirudinida	Leeches	3	0.3
Bivalvia	Clams	2	0.2
Gastropoda	Snails	140	13.6
Amphipoda & Isopoda	Crustaceans	58	5.6
Insects (Chironomids)	Midges	165	16.0
Insects (not Chironomids)		7	0.7

Table 4. Comparison of macroinvertebrate major taxons collected by Hester-Dendy samplers in 2016 (Tetra Tech 2019) and 2020 (This Study) in the Anacostia River within the Pepco Benning Road facility study area. Major fish forage groups are marked with *

	2020			2016		
Major Taxon	4 Station Total	Per Station Total	Percent Total	9 Station Total	Per Station Total	Percent Total
Tricladida	40	10.0	3.9	0	0.0	0.0
Hirudinida	3	0.8	0.3	40	4.4	0.7
Tubificida*	612	153.0	59.6	99	11.0	1.8
Bivalvia	2	0.5	0.2	5	0.6	0.1
Gastropoda*	140	35.0	13.6	1,222	135.8	22.0
Isopoda*	2	0.5	0.2	49	5.4	0.9
Amphipoda*	56	14.0	5.5	1,040	115.6	18.7
Decapoda	0	0.0	0.0	1	0.1	0.0
Coleoptera	4	1.0	0.4	7	0.8	0.1
Diptera*	165	41.3	16.1	3,033	337.0	54.5
Ephemeroptera	0	0.0	0.0	33	3.7	0.6
Odonata	3	0.8	0.3	2	0.2	0.0
Trichoptera	0	0.0	0.0	32	3.6	0.6
Total Average per Station		257			618	

Table 5. Taxa present at the 20 grab stations in 2017 (Normandeau 2020) and 4 HD stations in 2020 (This Study) in the Anacostia River within the Pepco Benning Road facility study area.

Taxon	Common Name	2017	2020
Nematoda	round worms	x	x
Tricladida			
Planariidae	flat worms		
Dugesia tigrina		x	x
Megadrili	earth worms	x	
Tubificida	aquatic worms		
Enchytraeidae		x	
Naididae			
Dero nivea			x
Dero sp.		x	x
Haemonais waldvogeli			x
Tubificinae			
Aulodrilus pigueti		x	
Aulodrilus limnobius		x	x
Branchiura sowerbyi		x	x
Ilyodrilus templetoni		x	
Limnodrilus sp.		x	x
Limnodrilus claparedeianus		x	
Limnodrilus cervix			x
Limnodrilus hoffmeisteri		x	x
Limnodrilus udekemianus		x	
Quistadrilus multisetosus		x	
Hirudinida	leechs		
Erpobdellidae			
Erpobdella punctata		x	x
Glossophoniidae			x
Helobdella elongata		x	x
Helobdella stagnalis		x	
Batracobdella phalera		x	
Bivalvia	clams		
Corbiculidae			
Corbicula fluminea		x	
Pisidiidae			
Pisidium sp.		x	
Pisidium casertanum			x
Sphaeridae			
Musculium transversum			x
Gastropoda	snails		
Amnicolidae			
Amnicola sp.			x
Planorbidae			
Micromenetus dilatatus			x
Physidae			
Physella sp.			x
Planorbidae			
Micromenetus dilatatus			x
Viviparidae			
Cipangopaludina japonica		x	x
Amphipoda	side swimmers		
Gammaridae			
Gammarus fasciatus		x	x
Isopoda	water slaters		
Asellidae			
Caecidotea sp.		x	x
Odonata	damselflies		
Coenagrionidae			
Argia sp.			x
Enallagma sp.			x
Coleoptera	beetles		
Haliplidae			
Peltodytes sp.			x
Elmidae			
Ancyronyx variegatus			x
Stenelmis crenata gr.			x
Diptera	flies		
Cecidomyiidae		x	
Ceratoponidae			
Ceratopogon sp.		x	
Bezzia/Palpomyia		x	
Chironomidae			
Chironomini			x
Chironomus decorus gr.		x	x
Cladopelma sp.		x	
Cryptochironomus fulvus gr.		x	
Dicrotendipes sp.			x
Dicrotendipes simpsoni			x
Orthocladius annectens		x	x
Phaenopsectra obediens gr.		x	
Polypedilum flavum		x	
Polypedilum halterale gr.		x	x
Polypedilum scalaenum gr.			x
Procladius sp.		x	
Sublettea coffmani			x
Tanypus neopunctipennis		x	
Thienemannimyia gr.			x

An Exelon Company

Appendix F

Anacostia River Native and Amended Sediment Erodibility Study

ANACOSTIA RIVER NATIVE AND AMENDED SEDIMENT ERODIBILITY STUDY

Pepco Benning Road Power Plant
Washington, DC

Prepared for

AECOM

Prepared by

integral consulting inc.

200 Washington Street
Suite 201
Santa Cruz, CA 95060

November 2020

CONTENTS

LIST OF FIGURES ..... **iv**
LIST OF TABLES ..... **vii**
ACRONYMS AND ABBREVIATIONS ..... **ix**
EXECUTIVE SUMMARY ..... **x**
1 INTRODUCTION TO SEDFLUME **1-1**
1.1 SAMPLE COLLECTION 1-1
1.2 EXPERIMENTAL PROCEDURES 1-2
1.2.1 SEDflume Setup 1-2
1.2.2 Measurements of Sediment Erosion Rate 1-5
1.2.3 Measurement of Sediment Bulk Properties 1-7
1.2.4 Intra- and Intercore Comparisons 1-10
1.3 APPLICATION OF AMENDMENT MATERIAL 1-11
2 RESULTS **2-1**
2.1 SED5CSF 2-1
2.1.1 SED5CSF-A 2-1
2.1.2 SED5CSF-B 2-2
2.2 SED6C/RC-04SF 2-5
2.2.1 SED6C/RC-04SF-A 2-5
2.2.2 SED6C/RC-04SF-B 2-6
2.3 SED7BSF 2-10
2.3.1 SED7BSF-A 2-10
2.3.2 SED7BSF-B 2-10
2.4 SED7DSF 2-14
2.4.1 SED7DSF-A 2-14
2.4.2 SED7DSF-B 2-15
2.4.3 SED7DSF-C 2-18
2.4.4 SED7DSF-D 2-22
2.4.5 SED7DSF-E 2-25
2.5 SED7ESF 2-30
2.5.1 SED7ESF-A 2-30
2.5.2 SED7ESF-B 2-31
2.5.3 SED7ESF-C 2-34

2.5.4 SED7ESF-D 2-37
2.5.5 SED7ESF-E 2-41
2.6 SED8CSF 2-44
2.6.1 SED8CSF-A 2-44
2.6.2 SED8CSF-B 2-45
2.7 SED9.5BSF 2-48
2.7.1 SED9.5BSF-A 2-48
2.7.2 SED9.5BSF-B 2-49
3 AMENDMENT COMPARISON 3-1
4 CONCLUSIONS 4-1
5 REFERENCES 5-1

Appendix A. Sampling Locations
Appendix B. Particle Size Distributions
Appendix C. Sand Media Specifications

LIST OF FIGURES

Figure 1. Schematic of SEDflume setup showing top and side views. 1-3

Figure 2. SEDflume in Integral's laboratory, Santa Cruz, California. 1-4

Figure 3. A) Sedimite™ B) Aquagate®+PAC C) Sand+GAC prior to application to sediment surface. 1-12

Figure 4. A) Sample SED7DSF-C prior to amendment application. B) Application of 0.86 cm (0.34 in.) SediMite™ amendment. C) Sample after mixing amendment material into upper 2.5 cm (1 in.) and settling for 28 days. 1-13

Figure 5. A) SED7ESF-D prior to amendment application. B) Application of 4.04 cm (1.55 in.) AquaGate®+PAC amendment. C) Sample after mixing into upper 2.5 cm (1 in.) and settling for 28 days. 1-14

Figure 6. A) Sample SED7ESF-E prior to application of amendment. B) Placement of Sand+GAC amendment. C) Sample after settling for 28 days. 1-15

Figure 7. Photograph of Sample SED5CSF-A. 2-2

Figure 8. Photograph of Sample SED5CSF-B with applied shear and measured erosion rates with depth 2-3

Figure 9. Intracore erosion rate ratios in SED5CSF-B. 2-4

Figure 10. Bulk properties of SED5CSF-B. 2-4

Figure 11. Photograph of Sample SED6C/RC-04SF-A. 2-6

Figure 12. Photograph of Sample SED6C/RC-04SF-B with applied shear and measured erosion rates with depth 2-7

Figure 13. Bivalve removed from surface of SED6C/RC-04SF-B. Scale is in centimeters. 2-8

Figure 14. Intracore erosion rate ratios in SED6C/RC-04SF-B. 2-8

Figure 15. Bulk properties of SED6C/RC-04SF-B. 2-9

Figure 16. Photograph of Sample SED7BSF-A. 2-10

Figure 17. Photograph of Sample SED7BSF-B with applied shear and measured erosion rates with depth 2-11

Figure 18. Two bivalves uncovered in SED7BSF-B. 2-12

Figure 19. Intracore erosion rate ratios in SED7BSF-B. 2-12

Figure 20. Bulk properties of SED7BSF-B 2-13

Figure 21. Photograph of Sample SED7DSF-A. 2-14

Figure 22. Photograph of sample SED7DSF-B with applied shear and measured erosion rates with depth....2-15
Figure 23. Two bivalves removed from the surface of SED7DSF-B. 2-16
Figure 24. Intracore erosion rate ratios in SED7DSF-B.....2-16
Figure 25. Bulk properties of SED7DSF-B. 2-17
Figure 26. Photograph of Sample SED7DSF-C with applied shear and measured erosion rates with depth....2-19
Figure 27. Evidence of continued biotic activity after application of amendment to SED7DSF-C. Left: Sample prior to mixing and 28-day consolidation. Right: SED7DSF-C after 28 days. 2-20
Figure 28. Intracore erosion rate ratios in SED7DSF-C. 2-20
Figure 29. Bulk properties of SED7DSF-C.....2-21
Figure 30. Photograph of Sample SED7DSF-D with applied shear and measured erosion rates with depth....2-23
Figure 31. Invertebrate in burrow observed in SED7DSF-D. 2-23
Figure 32. Intracore erosion rate ratios in SED7DSF-D. 2-24
Figure 33. Bulk properties of SED7DSF-D. 2-24
Figure 34. Photograph of Sample SED7DSF-E with applied shear and measured erosion rates with depth....2-27
Figure 35. Possible invertebrate activity extending from sediment surface into sand cap in SED7DSF-E 6 hours after sand placement. 2-27
Figure 36. Intracore erosion rate ratios in SED7DSF-E.....2-28
Figure 37. Native sediment in SED7DSF-E with embedded sand cap material. 2-28
Figure 38. Bulk properties of SED7DSF-E. 2-29
Figure 39. Photograph of Sample SED7ESF-A. 2-31
Figure 40. Photograph of Sample SED7ESF-B with applied shear and measured erosion rates with depth....2-32
Figure 41. Intracore erosion rate ratios in SED7ESF-B. 2-33
Figure 42. Bulk properties of SED7ESF-B.....2-33
Figure 43. Photograph of Sample SED7ESF-C with applied shear and measured erosion rates with depth....2-35
Figure 44. Intracore erosion rate ratios in SED7ESF-C. 2-36

Figure 45. Bulk properties of SED7ESF-C. 2-36
Figure 46. Photograph of Sample SED7ESF-D with applied shear and measured erosion rates with depth....2-38
Figure 47. Sediment surface in second interval with mix of amendment and native material. 2-39
Figure 48. Intracore erosion rate ratios in SED7ESF-D. 2-39
Figure 49. Bulk properties of SED7ESF-D. 2-40
Figure 50. Photograph of Sample SED7ESF-E with applied shear and measured erosion rates with depth....2-42
Figure 51. Intracore erosion rate ratios in SED7ESF-E. 2-42
Figure 52. Bulk properties of SED7ESF-E. 2-43
Figure 53. Photograph of Sample SED8CSF-A. 2-45
Figure 54. Photograph of Sample SED8CSF-B with applied shear and measured erosion rates with depth....2-46
Figure 55. Intracore erosion rate ratios in SED8CSF-B. 2-47
Figure 56. Bulk properties of SED8CSF-B. 2-47
Figure 57. Photograph of Sample SED9.5BSF-A. 2-49
Figure 58. Photograph of Sample SED9.5BSF-B with applied shear and measured erosion rates with depth....2-50
Figure 59. Intracore erosion rate ratios in SED9.5BSF-B. 2-50
Figure 60. Bulk properties of SED9.5BSF-B. 2-51
Figure 61. Critical shear stresses in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment. 3-3
Figure 62. Median particle size (D50) in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment. 3-4
Figure 63. Dry bulk density in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment. 3-5

LIST OF TABLES

Table 1. Sample collection summary....1-1
Table 2. Parameters measured and computed during the SEDflume analysis....1-9
Table 3. Amendment applications to selected Anacostia River cove samples....1-12
Table 4. Physical parameters and derived critical shear stresses for SED5CSF-B. 2-5
Table 5. Power law fit parameters for SED5CSF-B....2-5
Table 6. Physical parameters and derived critical shear stresses for SED6C/RC-04SF-B. 2-9
Table 7. Power law fit parameters for SED6C/RC-04SF-B. 2-9
Table 8. Physical parameters and derived critical shear stresses for SED7BSF-B....2-13
Table 9. Power law fit parameters for SED7BSF-B....2-13
Table 10. Physical parameters and derived critical shear stresses for SED7DSF-B. 2-17
Table 11. Power law fit parameters for SED7DSF-B. 2-18
Table 12. Physical parameters and derived critical shear stresses for SED7DSF-C....2-21
Table 13. Power law fit parameters for SED7DSF-C....2-22
Table 14. Physical parameters and derived critical shear stresses for SED7DSF-D. 2-25
Table 15. Power law fit parameters for SED7DSF-D....2-25
Table 16. Physical parameters and derived critical shear stresses for SED7DSF-E. 2-29
Table 17. Power law fit parameters for SED7DSF-E. 2-30
Table 18. Physical parameters and derived critical shear stresses for SED7ESF-B....2-34
Table 19. Power law fit parameters for SED7ESF-B....2-34
Table 20. Physical parameters and derived critical shear stresses for SED7ESF-C. 2-37
Table 21. Power law fit parameters for SED7ESF-C....2-37
Table 22. Physical parameters and derived critical shear stresses for SED7ESF-D. 2-40
Table 23. Power law fit parameters for SED7ESF-D. 2-40
Table 24. Physical parameters and derived critical shear stresses for SED7ESF-E....2-43
Table 25. Power law fit parameters for SED7ESF-E....2-44
Table 26. Physical parameters and derived critical shear stresses for SED8CSF-B. 2-48
Table 27. Power law fit parameters for SED8CSF-B....2-48
Table 28. Physical parameters and derived critical shear stresses for SED9.5BSF-B....2-51

Table 29. Power law fit parameters for SED9.5BSF-B. 2-52

ACRONYMS AND ABBREVIATIONS

GAC	granular activated carbon
Integral	Integral Consulting Inc.
LISST	laser *in situ* scattering and transmissometry
SEDflume	sediment-erosion-at-depth flume

EXECUTIVE SUMMARY

Contaminated sediment mobilization and redistribution may be mitigated using an amendment of activated carbon applied to the sediment surface. The effectiveness of the amendment is in part regulated by the changes in critical shear stress for erosion and subsequent erosion rates of the mixture of native and amendment material. The introduction of activated carbon for contaminant sequestration can be achieved using a variety of products, including SediMite™ and AquaGate®+PAC, or emplacing a sand cap containing a percentage of granular activated carbon (GAC). A SEDflume study was conducted to measure erosion rates at a range of applied shear stresses, determine critical shear stresses for erosion, and quantify physical properties of native sediment and sediment treated with three amendment materials. Quantifying the response of the bed to erosive forces in the presence and absence of the potential amendments can support design decisions regarding site response and help identify an appropriate mitigation solution.

This report provides a summary of the SEDflume analysis conducted on the native and amended sediment cores. A field campaign conducted in June 2020 resulted in the collection of 20 sediment samples for treating, testing, and archiving. Samples were safely shipped to Integral's SEDflume laboratory in Santa Cruz, California, where they were treated with a range of amendment alternatives or securely stored for the possibility of supplemental testing. Laboratory measurements of erosion rates at applied shear stresses, ranging from 0.1 to 12.8 Pa, were used to determine the critical shear stress for erosion at multiple depth intervals within each sediment core. The critical shear stress for erosion governs the threshold at which sediment may become mobilized from the sediment bed. Coefficients relating shear stress and erosion rate based on a power law regression are also provided. Additional data of grain size distributions via laser diffraction and bulk density measurements at each test interval were collected to characterize the physical characteristics of the sediment bed. Observations during testing note the presence of biota such as bivalves and invertebrate worms, which can mix sediment by burrowing and transport the amendment material into the sediment bed.

1 INTRODUCTION TO SEDFLUME

Analysis of sediment erosion properties using SEDflume can provide quantitative information on sediment bed characteristics. The sediment bed is governed by a complex and dynamically linked relationship between biologic activity, hydrodynamic forcing, and the physical and chemical makeup of the bed. SEDflume provides measurements of erosion rates to inform how the bedded sediment responds to controlled, measurable hydrodynamic flow. This section outlines collection efforts at the site, an overview of SEDflume setup and processing procedures, and methods used for determining the critical shear stresses for erosion. Supplemental information regarding physical characteristic analyses including particle size distribution and bulk density is also provided.

1.1 SAMPLE COLLECTION

A field campaign to collect 20 sediment cores for SEDflume analysis was conducted from June 1 to 4, 2020. Locations and approximate depths of each sampling location are provided in Appendix A, Sampling Locations. Collection took place with the support of Normandeau Associates staff, and the work was overseen by AECOM personnel. Sample collection consisted of retrieving five cores each from two locations in Anacostia River cove and two cores each from five locations at the river channel outside the cove. Cores were collected from every location except for R6-03SF, which is located in the mid-channel. The sediment was too stiff for core collection so an alternate site, SED9.5BSF, was chosen. The collection of cores in the cove required light hammering due to the clay layer underlying the sandy silt observed near the surface at SED7DSF and the presence of coarse sandy gravel with wood and leaf debris at SED7ESF. The cores located near the bank of the river were generally hand pushed whereas the cores closer to the center of the channel required light hammering from a posthole hammer. Collected samples were securely packaged and shipped from the Pepco Benning Facility to the Santa Cruz laboratory on May 20, 2020 and delivered on June 1, 2020. A summary table of collection times, sampling locations, and number of attempts for a successful recovery is provided in Table 1.

Table 1. Sample collection summary.

Sample ID	Date	Time (EST)	Lat.	Long.	Attempts
R6-03SF-A	6/2/2020	11:00	38.9010	-76.9614	13
R6-03SF-B	6/2/2020	12:45	38.9010	-76.9614	
SED5CSF-A	6/1/2020	15:55	38.9005	-76.9613	2
SED5CSF-B	6/1/2020	16:22	38.9005	-76.9613	3
SED6C/RC-04SF-A	6/2/2020	9:52	38.9011	-76.9607	1
SED6C/RC-04SF-B	6/2/2020	10:26	38.9011	-76.9607	1

Sample ID	Date	Time (EST)	Lat.	Long.	Attempts
SED7BSF-A	6/2/2020	12:55	38.9019	-76.9602	2
SED7BSF-B	6/2/2020	14:01	38.9019	-76.9602	2
SED7DSF-A	6/2/2020	17:15	38.9017	-76.9597	4
SED7DSF-B	6/3/2020	17:30	38.9017	-76.9597	1
SED7DSF-C	6/3/2020	17:54	38.9017	-76.9597	1
SED7DSF-D	6/3/2020	18:12	38.9017	-76.9597	1
SED7DSF-E	6/3/2020	18:40	38.9017	-76.9597	1
SED7ESF-A	6/3/2020	8:46	38.9015	-76.9592	1
SED7ESF-B	6/3/2020	9:30	38.9015	-76.9592	2
SED7ESF-C	6/4/2020	8:25	38.9015	-76.9592	1
SED7ESF-D	6/4/2020	8:53	38.9015	-76.9592	1
SED7ESF-E	6/4/2020	9:27	38.9015	-76.9592	1
SED8CSF-A	6/2/2020	15:05	38.9025	-76.9597	3
SED8CSF-B	6/2/2020	15:40	38.9025	-76.9597	1
SED9.5BSF-A	6/3/2020	15:55	38.9040	-76.9591	1
SED9.5BSF-B	6/3/2020	16:29	38.9040	-76.9591	2

1.2 EXPERIMENTAL PROCEDURES

Detailed descriptions of SEDflume analysis and its application are given in McNeil et al. (1996), Jepsen et al. (1997), and Roberts et al. (1998). The following sections supplement those reports with a general description of the SEDflume analysis procedures used in this study. Supplemental analyses of grain size distribution using laser diffraction (ISO Standard 13-320), water content (ASTM Method D2216-05), and bulk density (ASTM Method D2216-10; Håkanson and Jansson 1983), and loss on ignition (ASTM Method D7348-13) were also implemented at the beginning of each depth interval to quantify physical sediment characteristics.

A subset of samples was identified and treated with three different activated carbon treatments. The use of commercially available products of AquaGate®+PAC, SediMite™, and an appropriate mixture of non-cohesive aggregate and activated carbon. A summary of application procedures for each amendment type is outlined in Section 1.3.

1.2.1 SEDflume Setup

A SEDflume is essentially a straight flume with an open bottom section through which a rectangular, cross-sectional core barrel containing sediment can be inserted (Figure 1). The main components of the flume are the water tank, pump, inlet flow converter (which establishes uniform, fully developed, turbulent flow), the main duct, test section, hydraulic jack, and the core barrel containing sediment (Figure 2). The core barrel, test section, flow inlet section, and

flow exit section are made of transparent acrylic so that the sediment–water interactions can be observed visually. The core barrel has a rectangular cross section, 10 by 15 cm, and a length of 60 cm.




Figure 1. Schematic of SEDflume setup showing top and side views.




Figure 2. SEDflume in Integral's laboratory, Santa Cruz, California.

Water is pumped from a 300-gallon storage tank into a 5-cm-diameter pipe and then through the flow converter into the main duct. The duct is rectangular, 2 cm in height, 10 cm in width, and 120 cm in length; it connects to the test section, which has the same cross-sectional area (2 by 10 cm) and is 15 cm long. The flow converter changes the shape of the cross section from circular to rectangular while maintaining a constant cross-sectional area. A ball valve regulates the amount of water entering the flume so that the flow rates can be carefully controlled. The flume also has a small valve immediately downstream from the test section that opens to the atmosphere, preventing a pressure vacuum from forming and enhancing erosion.

At the start of each test, a core barrel and the sediment it contains are inserted into the bottom of the test section. The sediment surface is aligned with the bottom of the SEDflume channel. When fully enclosed, water is forced through the duct and test section over the surface of the sediment. The shear stress produced by the flow and imparted on the particles causes sediment erosion. As the sediment on the surface of the core erodes, the remaining sediment in the core barrel is slowly moved upward so that the sediment–water interface remains level with the bottom of the flume.

An operator moves the sediment upward using a hydraulically controlled piston that is inside the core barrel. The jack is driven by a release of pressure that is regulated with a switch and valve system. In this manner, the sediment can be raised and made level with the bottom of the test section. The movement of the hydraulic jack can be controlled for measurable increments as small as 0.5 mm.

1.2.2 Measurements of Sediment Erosion Rate

At the start of each core analysis, an initial reference measurement is made of the starting core length. The flume is then operated at a specific flow rate corresponding to a particular shear stress, and sediment is eroded (McNeil et al. 1996; Jepsen et al. 1997). As erosion proceeds, the core is raised if needed to keep the core's surface level with the bottom of the flume. This process is continued until either 10 minutes has elapsed or the core has been raised roughly 2 cm. The erosion rate for the applied shear stress is then calculated as:

$$E = \frac{\Delta z}{T} \qquad [1]$$

Where:

E = erosion rate
Δz = distance that sediment is raised during a particular measurement period
T = measurement time interval

Because material is eroded and the core structure is broken down, repetitive erosion measurements at a given depth are not possible. The following procedures were performed for all Anacostia River cores to best determine the erosion rate at several different shear stresses and depths using only one core:

1. The core was inserted into the bottom of the SEDflume test section.
2. The total length of sediment in the core barrel was measured and recorded.
3. Two 5 g (approximately) subsamples of sediment from the core surface were collected using a clean spoon to be used in particle size distribution and bulk density measurements. Sediment sampling was constrained to the downstream (relative to the SEDflume flow direction) end of the sediment surface, to minimize potential scour effects.
4. Shear stresses (from low to high) were applied to the core's surface, and sediment erosion was measured (if it occurred; 0.5 mm of erosion in 10 minutes was considered quantifiable). Applied shear stresses started at 0.1 Pa and were sequentially doubled until a given shear stress caused approximately 2 cm of erosion in 20 seconds, or a maximum of 5 cm was eroded in a given interval (defined as a continuous succession of increasing shear stress cycles where erosion is measured). Each shear stress cycle was applied for a minimum of 20 seconds and a maximum of 10 minutes. To the extent possible, no more than 2 cm of sediment was allowed to erode at a single shear stress.
5. Once the threshold—2 cm of erosion in 20 seconds, or a maximum of 5 cm of erosion in a single interval—was met, a new depth interval was started and the testing process of

Steps 3 and 4 were repeated.[1] Depth intervals are defined as a set of applied shears with an associated set of aliquots for physical parameter testing. Also, if the sediment composition changed noticeably in appearance or erosion properties, the depth interval was stopped, sediment subsamples were collected, and a new depth interval was started (Step 4).

6. Where practicable, at least three and up to five depth intervals were tested per core.

1.2.2.1 Determination of Critical Shear Stress

The critical shear stress of a sediment bed, τ_{cr}, is the applied shear stress at which sediment motion is initiated. In this study, it is operationally defined as the shear stress required to produce 0.001 mm of erosion in 1 second. This represents an erosion rate of 10^{-4} cm/s, or roughly 1 mm of erosion in 15 minutes.[2]

Because it is difficult to measure τ_{cr} exactly at the 10^{-4} cm/s threshold, erosion was instead measured over a range of shear stresses designed to bracket the initiation of erosion threshold. The highest applied shear stress where erosion *did not occur* is defined by τ_{no}, and τ_{first} is the lowest applied shear stress where erosion *did occur*.

Using the measured erosion rate data in each depth interval, a power law regression analysis (described below) was employed to determine the shear stress (τ_{power}) required to cause 10^{-4} cm/s of erosion. Assimilating the bracketed shear stress values (τ_0 and τ_1) and τ_{power}, the critical shear stress of each interval was then chosen according to the following criteria (where τ_{no} and τ_{first} are determined directly from the SEDflume measurements):

- If $\tau_{no} \leq \tau_{power} \leq \tau_{first}$, then τ_{power} was the selected critical shear stress, τ_{cr}, for the interval.
- If $\tau_{no} \geq \tau_{power}$, then τ_{no} was the selected critical shear stress for the interval.
- If $\tau_{power} \geq \tau_{first}$, then τ_{first} was the selected critical shear stress for the interval.
- If $r^2 < r^2_{thresh}$, then τ_{linear} was selected as the critical shear stress for the interval.

The τ_{cr} criteria allowed for selection of critical shear stresses using the power law results where the regression analysis was in agreement with measured erosion rate data.

[1] If a particular shear stress did not cause any observable erosion over a 10-minute period for consecutive depth intervals (e.g., less than 0.5 mm eroded in 10 minutes), that shear stress was removed from subsequent testing cycles; higher shear stresses were added, as appropriate, to attempt to measure at least three erosion rates.

[2] Though other definitions of critical shear stress erosion rate thresholds can be argued (and considered valid), the value of 10^{-4} cm/s threshold is used here for consistency with previous SEDflume efforts and to keep testing times to a practical duration.

1.2.2.2 Power Law Regression

Following the methods of Roberts et al. (1998), the erosion rates for sediment can be approximated by the power law regression:

$$E = A\tau^n\rho^m \quad [2]$$

Where:

E	=	erosion rate (cm/s)
τ	=	bed shear stress (Pa)
ρ	=	sediment bulk density (g/cm^3)
A, n, and m	=	constants that depend on sediment characteristics

The equation used in the present analysis is an abbreviated variation of Equation 2:

$$E = A\tau^n \quad [3]$$

where the constant A is a function of the sediment bulk density and other difficult properties to measure, such as sediment geochemistry and biological influences. The variation of erosion rate with density typically cannot be determined for field sediment because of natural variation in other sediment properties (e.g., mineralogy, particle size, and electrochemical forces). Therefore, the density term from the equation above, for a particular interval of approximately constant density, is incorporated into the constant A.

For each depth interval, the measured erosion rates (E) and applied shear stresses (τ) were used to determine the A and n constants that provide a best-fit power law curve to the data for that interval. Good regression fits of these parameters, where they existed, were then used to estimate the critical shear stress for the respective intervals. A coefficient of determination (r^2) of 0.70 was used as a threshold criterion for acceptance.[3]

1.2.3 Measurement of Sediment Bulk Properties

In addition to the measurement of erosion rates during the analysis, sediment subsamples were periodically collected at depth to determine the water content, particle size distribution, and loss on ignition of the sediment in each core. Water content and loss on ignition values are incorporated into the determination of wet and dry bulk densities. Subsamples were collected

[3]The coefficient of determination, r^2, is a function of Pearson's r, which is a measure of the linear dependence (correlation) between two variables. Pearson's r can be positive or negative, and is a value between –1 and +1. The more common usage of the correlation coefficient is to square Pearson's r, r^2, and report that value.

from the undisturbed core surface (prior to analysis) as well as the sediment surface at the beginning of each subsequent depth interval. Samples were weighed, dried, and reweighed to determine the mass of water. Samples were then subjected to sufficient heat to ignite the organic material to determine loss on ignition.

Wet bulk density was determined by first measuring the wet and dry weight of the collected sample to determine the water content (*W)* as described in Håkanson and Jansson (1983):

$$W = \frac{M_w - M_d}{M_w} * 100\% \qquad [4]$$

Where:

W	=	water content
M_w	=	wet weight of sample
M_d	=	dry weight of sample

For the determination of wet bulk density, water content in this formulation have value from 0 to 1. Wet bulk densities were then determined using the method described by Håkanson and Jansson (1983):

$$\rho_{wet} = \frac{(100 * \rho_s)}{100 + (W + IG)(\rho_s - 1)} \qquad [5]$$

Where

ρ_w	=	density of water (assumed 1 g/cm^3)
ρ_s	=	density of sediment particle (assumed 2.65 g/cm^3)
IG	=	% loss on ignition based on wet weight (ASTM Method D7348-13)

Dry bulk densities are based on the moisture content (*MC*) defined by ASTM D2216-05 as

$$MC = \frac{M_w - M_d}{M_d} \qquad [6]$$

This formulation represents the ratio of water to solids. Using the moisture content value, dry bulk densities were calculated using the following relationship:

$$\rho_{dry} = \frac{\rho_{wet}}{1 + MC} \quad [7]$$

Particle size distributions were determined using laser diffraction analysis at Integral's laboratory in Santa Cruz, California. Sediment samples were screened with a 2,000-µm sieve to remove large pieces of organic material, dispersed in water, and inserted into a Beckman Coulter LS 13-320 laser diffraction analyzer. Each sample was analyzed in three 1-minute intervals, and the results of the three analyses were averaged automatically by the instrument. The Beckman Coulter LS 13-320 measures volumetric distribution of particles from 0.4 to 2,000 µm. Caution should be taken when comparing directly to more narrowly ranged instruments such as a laser *in situ* scattering and transmissometry (LISST) instrument or traditional mass-based sieve and hydrometer studies. A LISST measures aggregated particles in the natural environment and has detection ranges different from that of the desktop instrument. Use of the Beckman Coulter involves the disaggregation of particles so any direct comparison must consider these factors.

The relationships used to determine sediment bulk properties are summarized in Table 2.

Table 2. Parameters measured and computed during the SEDflume analysis

Measurement	Definition	Units	Detection Limit	Internal Consistency
Water Content	$W = \frac{M_w - M_d}{M_w}$	Dimensionless	0.001 g in sample weight ranging from 1 to 50 g	0 < W < 1
Moisture Content	$MC = \frac{M_w - M_d}{M_d}$	Dimensionless	0.001 g in sample weight ranging from 1 to 50 g	
Wet Bulk Density	$\rho_{wet} = \frac{(100 * \rho_s)}{100 + (W + IG)(\rho_s - 1)}$	g/cm^3	0.001 g in sample weight ranging from 1 to 50 g	$\rho_w < \rho_{wet} < 2.6\ \rho_w$
Dry Bulk Density	$\rho_{dry} = \frac{\rho_{wet}}{1 + MC}$	g/cm^3	0.001 g in sample weight ranging from 1 to 50 g	$\rho_w < \rho_{dry} < \rho_{wet}$
Particle size distribution below 2,000 µm	Distribution of particle sizes by volume percentage using laser diffraction	µm	Method specific	1 µm < grain size < 2,000 µm

Notes:
M_w = wet weight of sample
M_d = dry weight of sample

ρw = density of water (assumed 1 g/cm^3)
ρs = density of sediment particle (assumed 2.65 g/cm^3)

1.2.4 Intra- and Intercore Comparisons

A potentially useful method of comparing sediment characteristics at a specific site is to compute intracore and intercore erosion rates. This method provides a means to quantify the erosion rates within each core (intracore) as well as the general erosion rates of the cores across the site (intercore).

1.2.4.1 Intracore Erosion Rate Ratios

Once the power law regression *A* and *n* coefficients for each depth interval within an individual core were known, the *interval-average* erosion rate for the core was determined using Equation 3 and the logarithmic average of the range of shear stresses tested in the SEDflume analysis.[4] C*ore-average* erosion rates were then computed by:

1. Log-averaging the *A* coefficient values from each depth interval within a core to arrive at an average *A* coefficient for the entire core
2. Arithmetically averaging the *n* coefficient values from each depth interval within a core to arrive at an average *n* coefficient for the entire core
3. Solving for the core-average erosion rate following Equation 3 and using the log-average of the range of shear stresses applied to the depth interval (1.13 Pa).

An intracore erosion-rate-ratio was then defined by dividing the interval-average erosion rate by the core-average erosion rate, providing a quantitative estimation of the relative erosion susceptibility of each depth interval. This method highlights the core intervals that are more or less susceptible to erosion within a particular core, and may indicate layering within a core.

1.2.4.2 Intercore Erosion Rate Ratios

Two additional ratios were computed to evaluate large-scale spatial erosion susceptibility. An intercore erosion rate ratio was computed by comparing the individual core-average erosion rate with a site-wide average erosion rate. The site-wide average erosion rate was computed by:

1. Log-averaging the core-average *A* coefficient values from each core to arrive at an average *A* coefficient for the entire site

[4]The shear stress values averaged were 0.1, 0.2, 0.4, 0.8, 1.6, 3.2, 6.4, and 12.8 Pa. The logarithmic average of these, used to compute erosion rate ratios, was 1.13 Pa.

2. Arithmetically averaging the core-average *n* coefficient values in each core to arrive at an average *n* coefficient for the entire site
3. Solving for the site-wide average erosion rate following Equation 3 and using the log-average of the range of shear stresses (1.13 Pa).

The intercore erosion rate ratio computed in this manner provided a qualitative estimate of the erosion susceptibility of each core (as a whole) relative to other cores in the site, potentially indicating spatial locations that are more or less susceptible to erosion than other locations.

1.3 APPLICATION OF AMENDMENT MATERIAL

Three types of amendment defined by the design team were constructed in the laboratory and applied to the native material. Five sediment cores were collected at SED7DSF and SED7ESF, labeled A through E to reduce any variation within native material during comparison. Each Sample A was set aside for archiving and supplemental testing. Samples SED7DSF-B and SED7ESF-B were analyzed without any amendment as a control sample. Samples C, D, and E were treated with SediMite™, AquaGate®+PAC, and a sand cap media+GAC, respectively (Figure 3). SediMite™ consists of uniformly sized pellets containing carbon. AquaGate®+PAC is applied as a white aggregate coated with powdered active carbon. Both SediMite™ and AquaGate®+PAC were supplied by their respective manufacturer to specifications provided by the design team. When placed in water both products result in a viscous slurry that can be mixed and transported.

The concentration of carbon in the SediMite™ and AquaGate®+PAC amendments was varied between the two sites by altering the thickness of the initial material placement. Thicknesses of each amendment layer were computed to achieve a desired 25 percent overplacement of carbon to the 10 x 15 cm exposed sediment surface. To simulate the long-term effects of biotic activity and mixing, the amendment material was mixed into the top 1 in. (2.5 cm) of native sediment. The thickness of mixed layer was determined from sediment profile imagery survey results indicating a 2.5 cm bioactive zone (R.J. Diaz & Daughters 2017).




Figure 3. A) Sedimite™ B) Aquagate®+PAC C) Sand+GAC prior to application to sediment surface.

Table 3. Amendment applications to selected Anacostia River cove samples.

Sampling Location	Sample Designation	Amendment Types	Concentration of Activated Carbon	Thickness (cm)
SED7DSF	A	Kept in Reserve	N/A	N/A
	B	None	N/A	N/A
	C	SediMite™	3% carbon	0.9
	D	AquaGate®+PAC	5% carbon	8.7
	E	Sand/Cap Media+GAC	5% GAC	15.2
SED7ESF	A	Kept in Reserve	N/A	N/A
	B	None	N/A	N/A
	C	SediMite™	5% carbon	1.1
	D	AquaGate®+PAC	3% carbon	3.9
	E	Sand/Cap Media+GAC	5% GAC	15.2

Application of the amendments followed suggested guidelines agreed upon by team members from AECOM and the University of Maryland, Baltimore County. To develop and apply the correct amendment material thickness of SediMite™ and AquaGate®+PAC to the C and D samples (Figure 4, Figure 5), the following steps were taken:

1. Mock the amendment layer thickness in an empty core barrel to ensure the proper amount of material is applied to the sediment surface.

2. Transfer correct volume to beaker for pouring into sediment core.
3. Pour the amendment material in even sweeping motions across the surface. All cores were stored with at least 15 cm of water and treatments were applied while the water was present.

   Note: the AquaGate®+PAC and SediMite™ material causes the water to go cloudy, highlighting the importance of step 1.
4. Allow the material to settle until the interface between amendment and water is visible.
5. If required, measure and mark 2.5 cm (1 in.) below the amendment to sediment interface. Using a stirring instrument, mix the sediment and amendment material to the desired depth. The water will turn cloudy so the technician must be careful to mix the whole area to the desired depth.
6. Allow to settle for 28 days.




Figure 4. A) Sample SED7DSF-C prior to amendment application. B) Application of 0.86 cm (0.34 in.) SediMite™ amendment. C) Sample after mixing amendment material into upper 2.5 cm (1 in.) and settling for 28 days.




Figure 5. A) SED7ESF-D prior to amendment application. B) Application of 4.04 cm (1.55 in.) AquaGate®+PAC amendment. C) Sample after mixing into upper 2.5 cm (1 in.) and settling for 28 days.

When the 6-in. sand cap was placed on Samples SED7DSF-E and SED7ESF-E, the following steps were used to determine a 5 percent by weight contribution (Figure 6). The aggregate material was sourced from a local construction supply company, GraniteRock, which met requested design specifications outlined in Appendix C. Unlike the SediMite™ and AquaGate®+PAC amendments, the sand+ GAC was not mixed into the bioactive zone of bedded sediment.

1. Determine mass of 6 in. of sand.
2. Calculate 5 percent of that mass.
3. Remove 5 percent of sand.
4. Add GAC to achieve original weight of 6 in. of sand.




Figure 6. A) Sample SED7ESF-E prior to application of amendment. B) Placement of Sand+GAC amendment. C) Sample after settling for 28 days.

2 RESULTS

This section of the report contains both qualitative and quantitative findings from the SEDflume analysis. Results are presented on a core-by-core basis. Appendix B contains additional grain size statistics and distribution plots for each interval in each core. Raw data from the grain size analysis can be provided upon request.

Results are presented both graphically and in tabular form. Erosion rates at applied shear stresses are presented with depths adjacent to an image of the core. The indication of no erosion measured refers to the thin dotted line at 10^{-5} cm/s. As described in the previous sections, values of 10^{-4} cm/s are defined as the erosion rate related to minimum measurable critical shear stress. Tables of the derived constants A and n are provided with the r^2 value. Mean values are also presented over the entire core. The coefficient A is log-averaged because of the order of magnitude variations that can occur within its values, while n is arithmetically averaged because its range is narrow. Values of n typically range from 1 to 4, and values outside of this range may also indicate a spurious data fit.

A table of particle sizes, wet and dry bulk densities, loss on ignition, greatest applied shear with no erosion measured, first applied shear with erosion measured, and power law derived critical shear is also presented. The power law-derived critical shear was determined using the A and n values from tables also provided for each sample. A column labeled "Final Critical Shear" provides the recommended value based on the criteria outlined in Section 1.2.2.1.

Qualitative descriptions of the type of erosion are included when necessary to highlight changing processes. Erosion of the core surface generally occurs via individual particles becoming suspended, aggregated clumps of sediment (clump erosion) breaking off causing an uneven surface, or sheets of material peeling off the sediment bed. Noncohesive materials such as sands, in the absence of any organic matter acting as a "glue," will erode as individual particles. Fine-grained sediment such as silts and clays can bind together and will move together under an applied shear. Cracks and uneven sedimentation may cause this bonded sediment to move together as clumps. Sediment deposited cyclically may deposit in uniform layers and can erode as thin sheets.

2.1 SED5CSF

2.1.1 SED5CSF-A

A 30 cm length of sediment was collected from SED5CSF located south of the river cove. SED5CSF-A is archived in the Santa Cruz SEDflume laboratory if supplemental testing is required.



Figure 7. Photograph of Sample SED5CSF-A.

2.1.2 SED5CSF-B

SED5CSF-B was collected in the Anacostia River south of the river cove. The 27.5 cm of recovered material consisted of brown clayey silt in the upper 11 cm and contained worm burrows and evidence of bioturbation (Figure 8). Unconsolidated sediment at the surface had an orange hue. Sediment 11 cm below the surface included pockets of dark gray and black silt with less evidence of biologic activity. A 2 cm layer of cavities and plant detritus was contained in brown silt 20 cm below the surface.

Analysis included the application of shear stresses ranging from 0.1 to 6.4 Pa in four test intervals (Figure 8). Erosion occurred in multiple forms ranging from individual grains moving

in bedload to clouds of suspended particles. As depth increased, erosion processes transitioned to more clumps and pieces of the surface 1–2 mm in diameter eroding unevenly across the surface. At the surface, an exposed bivalve approximately 1 cm in diameter attempted to bury itself and more worms and their burrow structures were exposed throughout the upper 12 cm. Erosion rates generally decreased with depth resulting in the upper half of the analyzed sample being more erodible than the third and fourth test intervals located 7.8 to 17 cm below the surface (Figure 9).

Wet and dry bulk densities generally increased with depth while grain size distributions were primarily silt with varying proportions of clay and fine sand (Figure 10, Table 4). The fifth data point of physical parameters was taken at the end of the fourth interval. Critical shear stresses determined from the erosion rate data ranged from 0.18 Pa at the surface to 0.68 Pa in the fourth test interval (Table 4). Power law regression parameters presented in Table 5 can be used to relate erosion rate with applied shear stress and values fall within expected ranges for cohesive material.




Figure 8. Photograph of Sample SED5CSF-B with applied shear and measured erosion rates with depth.




Figure 9. Intracore erosion rate ratios in SED5CSF-B.




Figure 10. Bulk properties of SED5CSF-B.

Table 4. Physical parameters and derived critical shear stresses for SED5CSF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	16.42	1.13	0.32	10.7%	0.10	0.20	0.16	0.19	0.19
3.2	19.21	1.16	0.37	10.3%	0.20	0.40	0.23	0.20	0.20
7.8	15.02	1.23	0.49	10.2%	0.20	0.40	0.32	0.31	0.31
12.4	25.31	1.49	0.90	7.3%	0.40	0.80	0.80	0.68	0.68
17.3	40.06	1.39	0.72	7.2%	---	---	---	---	---
Mean	23.20	1.28	0.56	9.1%	0.23	0.45	0.38	0.35	0.35

Table 5. Power law fit parameters for SED5CSF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	2.8	2.17E-05	2.39	0.85
2	3.2	7.8	1.45E-05	2.87	0.94
3	7.8	12.4	6.40E-06	2.40	0.98
4	12.4	17.3	1.15E-06	2.32	0.93

2.2 SED6C/RC-04SF

2.2.1 SED6C/RC-04SF-A

A 30 cm sample of sediment was collected from SED6C/RC-04SF located downstream of the river cove. SED6C/RC-04SF-A is archived in the Santa Cruz SEDflume laboratory in case supplemental testing is required.



Figure 11. Photograph of Sample SED6C/RC-04SF-A.

2.2.2 SED6C/RC-04SF-B

A 30.5 cm sample of sediment was collected at SED6C/RC-04SF-B located downriver from the cove (Figure 12). Unconsolidated, "fluffy" orange material peppered the olive gray sediment. The sample contained evidence of bivalves and invertebrate burrows in the upper 7 cm. The bivalve shown in Figure 13 was removed from the initial sediment surface prior to application of any shear stresses. Other specimens of similar size and shape were observed in samples throughout the site. Intermixed with the olive gray silt were pockets of leaves, twigs, and woody material. A single finger bandage was also discovered 25 cm from the surface during testing.

Five shear stress test intervals were conducted on SED6C/RC-04SF-B with applied stresses ranging from 0.1 to 6.4 Pa. The resulting erosion rates varied with depth (Figure 12). Intracore erosion rates indicate a reduction in erodibility 10 cm from the surface that coincides with analyst observations of less invertebrate and bivalve activity (Figure 14). Erosion occurred in multiple forms ranging from loose particles steadily suspending and eroding away to pieces of the surface 1–2 mm breaking away.

Critical shear stresses ranged from 0.11 Pa at the surface to a maximum of 0.57 Pa in the third interval 10 cm below. The down-core pattern of computed critical shear stresses corresponds to an increase of bulk density and decrease in loss on ignition values (Figure 15, Table 6). Grain size distributions indicate predominantly silt with a consistent presence of fine sand. The fifth interval was stopped prior to a third measurable erosion rate due to leakage through the organic laden material. The lack of a third measured shear stress meant that a power law regression was not appropriate and the analysis defaulted to a linear value for critical shear stress noted in Table 6 and Table 7. Coefficients relating shear stress and erosion rates for each interval are presented in Table 7 and fall within the typical range of values for cohesive material.




Figure 12. Photograph of Sample SED6C/RC-04SF-B with applied shear and measured erosion rates with depth.



Figure 13. Bivalve removed from surface of SED6C/RC-04SF-B. Scale is in centimeters.




Figure 14. Intracore erosion rate ratios in SED6C/RC-04SF-B.




Figure 15. Bulk properties of SED6C/RC-04SF-B.

Table 6. Physical parameters and derived critical shear stresses for SED6C/RC-04SF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
5.0	14.65	1.09	0.27	11.3%	0.10	0.20	0.12	0.11	0.11
9.9	38.90	1.28	0.56	8.9%	0.20	0.40	0.23	0.13	0.20
14.9	14.86	1.34	0.65	7.3%	0.40	0.80	0.64	0.57	0.57
19.7	27.82	1.29	0.57	8.4%	0.20	0.40	0.32	0.33	0.33
23.3	22.70	1.16	0.41	13.6%	0.40	0.80	0.41	---	0.41
Mean	23.79	1.23	0.49	9.9%	0.26	0.52	0.34	0.29	0.32

Table 7. Power law fit parameters for SED6C/RC-04SF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.0	7.62E-05	2.27	0.96
2	5.0	9.9	7.01E-05	1.36	0.81
3	9.9	14.9	2.08E-06	2.23	0.96
4	14.9	19.7	1.43E-05	1.62	0.98
5	19.7	23.3	---	---	0.59

2.3 SED7BSF

2.3.1 SED7BSF-A

A 20 cm sediment core was collected at SED7BSF. SED7BSF-A is archived in the Santa Cruz SEDflume laboratory in case supplemental testing is required.




Figure 16. Photograph of Sample SED7BSF-A.

2.3.2 SED7BSF-B

Sample SED7BSF-B was collected to the west of the river cove in line with the two inner cove sample locations SED7DSF and SED7ESF. Sampling resulted in the recovery of 18 cm of silt (Figure 17). During collection, it was noted that the collected material rested atop a firmer layer of bedded material that resisted penetration. Sediment consisted of brown, unconsolidated silt

at the surface overlying mottled darker and lighter areas of brown and gray silt. The surface contained clusters of bivalves (Figure 18) and invertebrate worm burrows extending 3–5 cm from the initial surface. Below the noted region of invertebrate burrows, the sediment had a homogeneous texture and color.

Shear stresses ranging from 0.1 to 12.8 Pa were applied to the upper 11 cm in two test intervals (Figure 17). Erodibility decreased in the second interval relative to the surface (Figure 19). Erosion nucleated around the biotic structures and leaves interspersed throughout the sample and ranged from individual grains to clumps breaking away from the surface. Often smaller particles eroded first, leading to a larger piece 1–2 mm in diameter fracturing from the surface.

Derived critical shear stress increased with depth and corresponded to an increase in density (Figure 20, Table 8). Coefficients to relate erosion rate and shear stress via a power law regression are presented in Table 9. Values of r^2 indicate a good relationship between the two variables, and the coefficients A and n fall within expected values for cohesive sediment.




Figure 17. Photograph of Sample SED7BSF-B with applied shear and measured erosion rates with depth.



Figure 18. Two bivalves uncovered in SED7BSF-B.




Figure 19. Intracore erosion rate ratios in SED7BSF-B.




Figure 20. Bulk properties of SED7BSF-B

Table 8. Physical parameters and derived critical shear stresses for SED7BSF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	13.49	1.28	0.54	7.9%	0.20	0.40	0.23	0.15	0.20
5.0	17.56	1.43	0.80	7.7%	0.40	0.80	0.52	0.51	0.51
10.9	10.20	1.44	0.82	7.8%	---	---	---	---	---
Mean	13.75	1.38	0.72	7.8%	0.30	0.60	0.38	0.33	0.36

Table 9. Power law fit parameters for SED7BSF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.0	5.72E-05	1.41	0.90
2	5.0	10.9	3.88E-06	2.00	0.96

2.4 SED7DSF

Samples from SED7DSF, located in the fore of the river cove were used to compare the erodibility of native bedded sediment (Sample B) with sediment treated with three amendment types (Samples C, D, E). Sample A is securely stored in the event additional testing is requested.

2.4.1 SED7DSF-A

SED7DSF-A, consisting of 19 cm of sediment, is archived in the Santa Cruz SEDflume laboratory in case supplemental testing is required.




Figure 21. Photograph of Sample SED7DSF-A.

2.4.2 SED7DSF-B

Sample SED7DSF-B was collected in the river cove collocated with four other samples. SED7DSF-B acted as the control for comparison with three samples treated with amendments. The upper 10 cm of brown sediment contained leaves and twigs as well as biota including the two bivalves removed from the surface (Figure 22, Figure 23). Larvae or small worms were observed floating in the waters above the sediment surface prior to analysis. Darker brown sediment with black streaks extended from 10 to 20 cm below the surface along with a smoother visual texture.

Shear stresses ranging from 0.1 to 6.4 Pa were applied in four intervals to the top 20 cm of sediment. Erosion rates varied with depth and generally became less erodible as depth increased (Figure 24). Derived critical shear stresses generally increased with depth and coincided with an increase in density (Table 10, Figure 25). Erosion occurred in multiple forms including streams of individual grains, clumps 1–2 mm in diameter, and thin sheets of sediment intermittently dislodging. Interspersed leaves, twigs, and sticks alternated between protecting underlying sediment and causing sections of the surface to break free as the pieces of macro-organic matter were swept away. Coefficients relating shear stress and erosion rate using a power law regression indicate good agreement between measurements and fall within expected ranges (Table 11).




Figure 22. Photograph of sample SED7DSF-B with applied shear and measured erosion rates with depth.



Figure 23. Two bivalves removed from the surface of SED7DSF-B.




Figure 24. Intracore erosion rate ratios in SED7DSF-B.




Figure 25. Bulk properties of SED7DSF-B.

Table 10. Physical parameters and derived critical shear stresses for SED7DSF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	21.16	1.08	0.27	12.1%	0.20	0.40	0.23	0.18	0.20
5.0	36.07	1.26	0.53	8.5%	0.20	0.40	0.32	0.30	0.30
10.2	39.70	1.30	0.58	8.2%	0.20	0.40	0.26	0.26	0.26
15.2	53.08	1.42	0.78	8.0%	0.80	1.60	0.83	0.55	0.80
20.2	21.91	1.46	0.90	11.6%	---	---	---	---	---
Mean	34.38	1.30	0.61	9.7%	0.35	0.70	0.41	0.32	0.39

Table 11. Power law fit parameters for SED7DSF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.0	3.55E-05	1.75	0.89
2	5.0	10.0	1.87E-05	1.54	0.98
3	10.2	15.2	2.06E-05	1.67	0.94
4	15.2	20.2	2.99E-06	2.05	0.81

2.4.3 SED7DSF-C

SED7DSF-C was collected in the river cove and treated with a 0.9 cm thick layer of SediMite™. The SediMite™ material was mixed in the upper 2.5 cm of native material and allowed to settle and consolidate for 28 days (Figure 26). Prior to mixing, the sediment had characteristics similar to SED7DSC-B. Biotic activity, especially worm burrows and feeding voids, in the upper 10 cm appeared to continue after the addition of cap material (Figure 27). A layer of dark material, possibly activated carbon from the SediMite™, was observed 5 cm from the equilibrated sediment surface and beyond the depth of intentionally mixed material during the amendment application phase. The distinct feature may be a result of biotic activity drawing the SediMite™ material into the burrow network.

Five shear stress intervals were analyzed within the upper 25 cm of SED7DSF-C. The first shear stress analysis was on the mixture of SediMite™ and native material. Subsequent analyses were on sediment undisturbed by the amendment application process. The mixed surface layer had a watery, sleek composition with some sediment and dark glossy material present. No evidence of biotic disturbance was present at the water to sediment interface. Shear stresses from 0.1 to 12.8 Pa were applied to the core (Figure 26). The low-density material on the surface resulted in relatively high erodibility but as density increased, erodibility decreased in SED7DSF-C (Figure 28, Figure 29). The material at the surface exposed to the first shear stresses appeared to be primarily SediMite™ that separated from the mixed sediment. The low-density material eroded evenly across the surface in a steady stream and its removal exposed invertebrate activity throughout the underlying mixed system. Further erosion occurred in multiple modes with individual grains eroding away in streams followed by larger pieces and clumps of sediment eroding across the surface. Invertebrates were observed in the upper 10 cm and leaves, sticks, and twigs were scattered throughout Intervals 3 through 5.

Critical shear stresses increased with depth coincident with an increase in bulk density. Native material was composed primarily of silt with some portions of persistent fine and medium sand and clay throughout the core (Table 12). Coefficients relating shear stress and erosion rate using

a power law regression indicate good agreement between measurements and fall within expected ranges (Table 13).




Figure 26. Photograph of Sample SED7DSF-C with applied shear and measured erosion rates with depth.



Figure 27. Evidence of continued biotic activity after application of amendment to SED7DSF-C. Left: Sample prior to mixing and 28-day consolidation. Right: SED7DSF-C after 28 days.




Figure 28. Intracore erosion rate ratios in SED7DSF-C.




Figure 29. Bulk properties of SED7DSF-C.

Table 12. Physical parameters and derived critical shear stresses for SED7DSF-C.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm³)	Dry Bulk Density (g/cm³)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	16.53	1.05	0.23	15.3%	0.10	0.20	0.13	0.11	0.11
3.0	36.73	1.07	0.34	20.9%	0.40	0.80	0.41	0.28	0.40
8.0	24.59	1.21	0.44	8.8%	0.40	0.80	0.45	0.37	0.40
13.2	37.25	1.41	0.78	8.4%	0.80	1.60	0.92	0.80	0.80
18.8	33.67	1.61	1.07	5.6%	0.80	1.60	0.91	0.77	0.80
Mean	29.75	1.27	0.57	11.8%	0.50	1.00	0.56	0.47	0.50

Table 13. Power law fit parameters for SED7DSF-C.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	3.0	8.23E-05	1.52	0.90
2	3.0	8.0	8.63E-06	2.39	0.81
3	8.0	13.2	6.58E-06	2.06	0.94
4	13.2	18.8	7.38E-07	2.36	0.98
5	18.8	24.5	1.11E-06	2.20	0.97

2.4.4 SED7DSF-D

SED7DSF-D was amended with 8.7 cm of AquaGate®+PAC material. The AquaGate®+PAC consists of a white aggregate coated with particulate activated carbon that decouples from the aggregate when submerged in water (Figure 30). The interface between the amendment and top 2.5 cm of native material was mixed as described in Section 1.3. The volume of AquaGate®+PAC meant that a significant portion was not mixed with sediment and resulted in two noted layers of amendment material. The first consisted of a low density, watery clay (almost gelatin-like in consistency and texture) overlying a second layer of carbon, delivery aggregate, and native material. Evidence of continued biotic activity is noted in the native sediment underlying the mixed layer, as many burrows and structures are notably black (Figure 31).

Six shear stress intervals were analyzed utilizing forces from 0.1 to 12.8 Pa. The first interval of predominantly watery suspended carbon particles eroded at lower shear stresses than the underlying material due to the lack of sediment or aggregate. Intervals 2 and 3 contained varying proportions of sediment, aggregate, and activated carbon. Erosion rates and overall erodibility oscillated as depth increased, a trend mimicked by the bulk density and particle size distributions (Figure 32, Figure 33). Erosion of the combined carbon and sediment occurred as pieces of disturbed sediment and carbon were suspended and eroded followed by the aggregate material dislodging at higher shear stresses. Once the mixed amendment and native material were removed in Intervals 2 and 3, the underlying native material eroded as individual grains and pieces of the sediment surface. Invertebrate disturbance in Interval 4 allowed larger pieces to break free and erode away during processing. The sediment in Intervals 5 and 6 contained leaves, twigs, and gas pockets possibly due to the decay of organic material.

As described above, the surface interval comprised a gelatinous consolidation of carbon particles, jiggling during analysis until all the material was eroded away. This may have led to poor power law correlation between erosion rates and applied shear stress in that interval resulting in the selection of the linearly interpolated critical shear stress value of 0.22 Pa. Despite the change in material type in the predominantly amendment material in Interval 2 and 3 and

native sediment in Intervals 4 through 6, critical shear stresses held relatively steady around 0.8 Pa (Table 14). Coefficients relating shear stress and erosion rate using a power law regression indicate good agreement between measurements and values fall within expected ranges for all but the surface interval (Table 15).




Figure 30. Photograph of Sample SED7DSF-D with applied shear and measured erosion rates with depth.



Figure 31. Invertebrate in burrow observed in SED7DSF-D.




Figure 32. Intracore erosion rate ratios in SED7DSF-D.




Figure 33. Bulk properties of SED7DSF-D.

Table 14. Physical parameters and derived critical shear stresses for SED7DSF-D.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	17.34	0.92	0.11	26.5%	0.20	0.40	0.22	---	0.22
3.1	22.14	1.68	1.16	4.0%	0.80	1.60	0.87	0.76	0.80
6.8	19.66	1.65	1.11	4.1%	0.80	1.60	0.84	0.71	0.80
11.5	25.22	1.67	1.14	4.5%	0.80	1.60	0.89	0.80	0.80
16.2	41.83	1.28	0.56	8.2%	0.80	1.60	0.92	0.87	0.87
20.7	48.30	1.42	0.78	6.9%	0.80	1.60	0.87	0.71	0.80
25.4	32.64	1.58	1.02	5.5%	0.80	1.60	0.96	0.90	0.90
Mean	29.59	1.46	0.84	8.5%	0.71	1.43	0.80	0.79	0.74

Table 15. Power law fit parameters for SED7DSF-D.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	3.1	---	---	0.60
2	3.1	6.8	4.27E-07	2.68	0.98
3	6.8	11.5	2.86E-07	2.98	0.96
4	11.5	16.2	1.03E-07	3.31	0.92
5	16.2	20.7	1.39E-07	3.05	0.98
6	20.7	25.4	6.33E-07	2.59	0.91
7	25.4	29.7	1.52E-07	2.95	0.97

2.4.5 SED7DSF-E

The third amendment material, sand+5% GAC was applied to the surface of SED7DSF-E and the core was allowed to consolidate over 28 days. No manual mixing was administered to the sand and native material interface. The sand and GAC were mixed prior to application and then poured onto the sediment. The horizontal streaking of dark material within the sand cap, seen in Figure 34, is the GAC that differentially settled during placement. At the interface between native sediment and sand, a 1–2 mm layer of darkened sediment formed and evidence of invertebrate activity extended into the sand cap (Figure 35).

Six shear stress intervals were analyzed on SED7DSF-E with applied stresses ranging from 0.1 to 12.8 Pa. The first three intervals were solely within the sand cap media and the second three addressed the native sediment. The non-cohesive sand behaved consistently in Intervals 1–3 and was more erodible than the underlying native material (Figure 36). Of particular note was the behavior of the fourth interval that started at the interface between cap and native sediment. Measured erosion did not start until 1.6 Pa, which was a dramatic difference from the overlying sand and Sample SED7DSF-B. The native material appeared to have solidified or hardened forming a sort of crust and embedded within was aggregate that had been pressed into the surface from the overlying sand cap (Figure 37).

The sand eroded as individual grains in bedload at lower shear stresses and in suspended streams of particles at higher shears. The material in the fourth interval eroded in pieces and sheets of the surface possibly due to the hardening observed. After the "crust" eroded, sediment broke apart in pieces and resulted in an uneven surface. Voids possibly from decaying matter or feeding pockets from invertebrates were also present, which exacerbated the uneven erosion. The native material consisted predominantly of silt and had a lower density than the sand cap (Figure 38). Critical shear stresses were constant within the sand cap but increased in the native cohesive material by an order of magnitude (Table 16). The median particle sizes reported in Table 16 for Intervals 1, 2, and 3 are of the fraction less than 2,000 μm. A full breakdown of grain size distributions of the cap material can be found in Appendix C, which contains the sand aggregate specifications. Coefficients relating shear stress and erosion rate using a power law regression indicate good agreement between measurements and computed values fall within expected ranges (Table 17).




Figure 34. Photograph of Sample SED7DSF-E with applied shear and measured erosion rates with depth.



Figure 35. Possible invertebrate activity extending from sediment surface into sand cap in SED7DSF-E 6 hours after sand placement.




Figure 36. Intracore erosion rate ratios in SED7DSF-E.



Figure 37. Native sediment in SED7DSF-E with embedded sand cap material.




Figure 38. Bulk properties of SED7DSF-E.

Table 16. Physical parameters and derived critical shear stresses for SED7DSF-E.

Sample Depth (cm)	Median Grain Size (μm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	576.50	1.79	1.38	5.9%	0.20	0.40	0.22	0.20	0.20
5.3	660.10	1.55	1.01	8.2%	0.20	0.40	0.22	0.20	0.20
11.2	649.90	1.89	1.49	3.1%	0.20	0.40	0.22	0.19	0.20
16.1	34.69	1.18	0.37	7.4%	1.60	3.20	1.62	1.01	1.60
21.1	25.93	1.36	0.70	8.8%	0.80	1.60	0.86	0.70	0.80
27.0	45.92	1.52	0.93	6.6%	1.60	3.20	1.66	1.31	1.60
Mean	332.17	1.55	0.98	6.7%	0.77	1.53	0.80	0.60	0.77

Note: : Grain size values in first three intervals reflect the fraction of sand less than 2,000 μm.

Table 17. Power law fit parameters for SED7DSF-E.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.3	1.02E-05	3.39	0.97
2	5.3	11.2	7.16E-06	3.71	0.99
3	11.2	16.1	1.28E-05	3.30	0.94
4	16.1	21.1	2.55E-07	2.59	0.75
5	21.1	27.0	1.62E-06	2.12	0.95
6	27.0	32.8	4.13E-08	3.03	0.92

2.5 SED7ESF

Five samples were collected from SED7ESF, located in the intertidal river cove. Sample A was set aside for archiving. Sample B was tested without any amendment treatment. Samples C, D, and E were treated with amendment material and then tested for erodibility properties using SEDflume.

2.5.1 SED7ESF-A

SED7ESF-A is archived in the Santa Cruz SEDflume laboratory if supplemental testing is required.



Figure 39. Photograph of Sample SED7ESF-A.

2.5.2 SED7ESF-B

SED7ESD-B was collected in an intertidal area of the river cove along with four other collocated samples. A heterogeneous mixture of light brown and grey silt contained evidence of biotic activity, leaves, twigs, and sticks (Figure 40). Pink and white worms up to 1 cm in length were observed on the surface and in the upper 2 cm of sediment with tubes and voids extending up to 6 cm into the core.

Shear stresses ranging from 0.1 to 3.2 Pa were applied to SED7ESF-B in four test intervals. Sediment eroded in clumps and pieces around worm structures in the upper 6 cm. As pieces broke away, clouds of particles also eroded in episodic bursts. The presence of worm structures fractured the sediment and erosion occurred unevenly across the surface. Deeper into the

sediment bed, bulk density and particle size distribution increased while the relative erodibility decreased (Figure 41, Figure 42). The silty material gave way to sandier less cohesive material 12 cm from the surface, which also included leaves and twigs that modified the erosion process by alternately sheltering and carrying away sediment as the leaves broke away. Critical shear stresses increased with depth and ranged from 0.12 to 0.4 Pa (Table 18). Coefficients relating shear stress and erosion rate using a power law regression indicate good agreement between measurements, and values for final critical shear stress were chosen based on the criteria outlined in Section 1.2.2.1 (Table 19).




Figure 40. Photograph of Sample SED7ESF-B with applied shear and measured erosion rates with depth.




Figure 41. Intracore erosion rate ratios in SED7ESF-B.




Figure 42. Bulk properties of SED7ESF-B.

Table 18. Physical parameters and derived critical shear stresses for SED7ESF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	12.66	1.12	0.33	11.1%	0.10	0.20	0.13	0.12	0.12
4.6	19.42	1.09	0.35	18.2%	0.20	0.40	0.26	0.25	0.25
8.2	16.66	1.16	0.42	14.4%	0.20	0.40	0.26	0.26	0.26
12.3	133.20	1.37	0.74	10.1%	0.20	0.40	0.40	0.45	0.40
16.6	513.40	1.81	1.39	5.2%	---	---	---	---	---
Mean	139.07	1.31	0.65	11.8%	0.18	0.35	0.26	0.27	0.26

Table 19. Power law fit parameters for SED7ESF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	4.6	6.63E-05	2.01	0.94
2	4.6	8.2	1.08E-05	2.45	0.99
3	8.2	12.3	1.53E-05	1.94	0.96
4	12.3	16.6	1.10E-06	3.00	0.99

2.5.3 SED7ESF-C

A 1.03 cm thick layer of SediMite™ was integrated into the top 2.5 cm of native material from SED7ESF-C. The 15 cm of brown silt contained evidence of invertebrate burrows and voids and pockets of leaves. After mixing, the upper 2 cm were darker than the underlying sediment and appeared to be modified by invertebrate activity during the 28-day consolidation period (Figure 43). Two shear stress intervals were analyzed over the top 7 cm. Sediment below the 7 cm mark was porous due to a significant portion of organic matter causing the core to leak and testing to stop.

The low density, dark material at the surface seemed to be predominantly SediMite™ but resisted erosion at shear stresses less than 0.4 Pa and had a gelatinous texture. The erosion rates and derived critical shear stresses were relatively uniform between the two intervals (Figure 48). The mixture of SediMite™ and native material extended into the top 2.5 cm but varied in proportion as depth increased. The gradual change was noted in a supplemental particle size and bulk density sample at 1.7 cm to highlight the progression down-core

(Figure 49, Table 20). Derived critical shear stresses resulting from a power law regression were uniform at 0.5 for the two intervals despite changes in density and particle size distribution (Table 20). The coefficients relating shear stress and erosion rate fall within typical ranges for cohesive sediment and suggest a good fit between measurements based on r^2 values of 0.99 and 0.98 (Table 21).




Figure 43. Photograph of Sample SED7ESF-C with applied shear and measured erosion rates with depth.




Figure 44. Intracore erosion rate ratios in SED7ESF-C.




Figure 45. Bulk properties of SED7ESF-C.

Table 20. Physical parameters and derived critical shear stresses for SED7ESF-C.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	50.56	0.93	0.16	30.2%	0.40	0.80	0.52	0.50	0.50
1.7	31.38	1.08	0.31	17.7%	---	---	---	---	---
2.7	84.11	1.22	0.52	13.7%	0.40	0.80	0.52	0.51	0.51
6.9	39.09	1.22	0.52	14.0%	---	---	---	---	---
Mean	51.29	1.11	0.38	18.9%	0.40	0.80	0.52	0.51	0.51

Table 21. Power law fit parameters for SED7ESF-C.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	2.7	1.70E-06	2.53	0.99
2	2.7	6.9	5.76E-07	3.15	0.98

2.5.4 SED7ESF-D

AquaGate®+PAC was applied to SED7ESF-D as a 3.9 cm thick layer and then mixed with the upper 2.5 cm of native material. The sample was collected from the intertidal river cove along with four other samples from SED7ESF. The surface consisted of low density, watery carbon material. Subsequent to mixing to integrate the amendment material with the native sediment, the proportions resulted in the upper 2.1 cm to be predominantly AquaGate®+PAC and the second interval to be a more even mixture of amendment and native material (Figure 46, Figure 47). Sediment in the subsequent Intervals 3 and 4 was native material and showed evidence of biotic activity. A band of darkened sediment 8 to 10 cm from the surface could be evidence of biotic transport of activated carbon from the overlying amendment.

The first shear stress interval contained a watery, gelatinous, carbon laden, low-density clay and eroded at the lowest applied shear stress (0.1 Pa). The low-density carbon and water mixture jiggled as it eroded in a steady stream from the surface. The second interval containing carbon, white delivery aggregate, and native sediment started eroding at higher shears than the overlying layer. The native material below the amended surface layers eroded as clumps and pieces of the surface broke free in episodic events around the invertebrate-disturbed sediment. The change in composition with depth appeared to influence the erodibility of the sediment

(Figure 48). Derived critical shear stresses based on power law regressions increased with depth and the coefficients relating erosion rate and shear stress fall within expected ranges (Table 22, Table 23)




Figure 46. Photograph of Sample SED7ESF-D with applied shear and measured erosion rates with depth.



Figure 47. Sediment surface in second interval with mix of amendment and native material.




Figure 48. Intracore erosion rate ratios in SED7ESF-D.




Figure 49. Bulk properties of SED7ESF-D.

Table 22. Physical parameters and derived critical shear stresses for SED7ESF-D.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	17.36	0.89	0.08	29.1%	0.05	0.10	0.06	0.06	0.06
2.1	19.92	1.44	0.79	6.0%	0.40	0.80	0.43	0.29	0.40
6.4	11.99	1.26	0.54	9.8%	0.40	0.80	0.52	0.54	0.54
9.2	19.80	1.18	0.46	14.2%	0.40	0.80	0.48	0.44	0.44
13.5	22.18	1.19	0.47	14.3%	---	---	---	---	---
Mean	18.25	1.19	0.47	14.7%	0.31	0.63	0.37	0.33	0.36

Table 23. Power law fit parameters for SED7ESF-D.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	2.1	2.79E-04	1.77	0.85
2	2.1	6.4	1.48E-05	1.78	0.83
3	6.4	9.2	1.30E-06	2.57	0.95
4	9.2	13.5	1.42E-06	2.87	0.94

2.5.5 SED7ESF-E

A 15.2 cm thick layer of sand+5% GAC was placed over the native sediment collected from the intertidal river cove at Station SED7ESF (Figure 50). The grey native silt contained evidence of biotic activity. The 2 cm of native material underlying the placed sand was a lighter gray than the rest of the bedded sediment. Patches of dark grey extend 10 to 25 cm from the interface and the upper 10 cm of native material contained voids and invertebrate structures.

The non-cohesive sand cap eroded consistently across the first three intervals (Figure 50). At the interface between cap and native material approximately 15 cm from the cap surface, sand aggregate was embedded into the surrounding silt. The sediment was resistive to sampling and appeared hardened relative to the unamended sediment sample tested in SED7ESF-B. The sand cap material in Intervals 1–3 was more erodible than the native sediment in Intervals 4–6 (Figure 51). Derived critical shear stresses were an order of magnitude larger in the native material than the amendment and followed an inverse relationship with density and particle size (Figure 52, Table 24).

The fourth interval, starting at the interface where cap met native material, eroded in sheets and pieces of the surface as though a crust had formed. The material below eroded in episodic events as clumps of sediment broke free around the invertebrate tubes. The sediment 25 to 40 cm below the surface contained leaves and twigs that alternately shielded and promoted erosion events. The presence of sandier sediment 35 to 40 cm from the amendment surface resulted in more consistent, steady erosion throughout the interval as streams of sediment were suspended and eroded away. Coefficients relating shear stress and erosion rate using a power law regression indicate good agreement between measurements, and computed values fall within expected ranges (Table 25).




Figure 50. Photograph of Sample SED7ESF-E with applied shear and measured erosion rates with depth.




Figure 51. Intracore erosion rate ratios in SED7ESF-E.




Figure 52. Bulk properties of SED7ESF-E.

Table 24. Physical parameters and derived critical shear stresses for SED7ESF-E.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm³)	Dry Bulk Density (g/cm³)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	828.50	1.95	1.61	4.6%	0.20	0.40	0.22	0.19	0.20
5.2	771.20	1.89	1.49	2.9%	0.20	0.40	0.22	0.19	0.20
10.2	861.10	1.94	1.58	3.6%	0.20	0.40	0.21	0.18	0.20
16.3	13.75	1.28	0.57	10.0%	1.60	3.20	1.70	1.46	1.60
21.9	20.38	1.24	0.56	14.7%	0.80	1.60	1.00	0.95	0.95
26.1	389.90	1.42	0.80	8.8%	0.80	1.60	0.81	0.53	0.80
Mean	480.81	1.62	1.10	7.4%	0.63	1.27	0.69	0.58	0.66

Table 25. Power law fit parameters for SED7ESF-E.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.2	1.15E-05	3.29	0.96
2	5.2	10.2	1.10E-05	3.38	0.96
3	10.2	16.3	1.50E-05	3.35	0.94
4	16.3	21.3	2.21E-08	3.14	0.96
5	21.9	26.1	1.11E-07	3.02	0.96
6	26.1	32.1	5.80E-07	3.10	0.79

2.6 SED8CSF

2.6.1 SED8CSF-A

A 37 cm sample of sediment from the Anacostia River was collected at SED8CSF. SED8CSF-A is archived in the Santa Cruz SEDflume laboratory in case supplemental testing is required.



Figure 53. Photograph of Sample SED8CSF-A.

2.6.2 SED8CSF-B

SED8CSF-B is located just upstream from the river cove. During sampling, 30 cm of grey silty sediment was collected. Bivalves and evidence of worm tubes on the surface were noted in the upper 2–3 cm along with a dark black layer 2–3 mm thick (Figure 54). During analysis, pockets of sandy sediment intermixed into the gray silty material were noted in the upper 12 cm. Sediment 12 cm below the surface and further into the core was grainy and clumped in texture and eroded unevenly. Interspersed plant material was also present.

Shear stresses ranging from 0.1 to 12.8 Pa, were applied to the core in five test intervals and produced varying erosion rates with depth (Figure 54, Figure 55). The least erodible material was observed in the fourth interval 14 cm below the surface. Critical shear stresses ranged from 0.12 to 1.26 Pa and increased as bulk density increased and median particle size (D50) decreased (Table 26, Figure 56). Relative increases in erodibility and a lower critical shear in Interval 5 than in Interval 4 could be associated with the presence of leaves and sticks and a change in grain size distribution. After the surface material eroded in individual grains and streams of particles, larger clumps with fissures and cracks were exposed and the material eroded unevenly in sporadic events. Coefficients relating shear stress and erosion rate by a power law regression presented in Table 27.




Figure 54. Photograph of Sample SED8CSF-B with applied shear and measured erosion rates with depth.




Figure 55. Intracore erosion rate ratios in SED8CSF-B.




Figure 56. Bulk properties of SED8CSF-B.

Table 26. Physical parameters and derived critical shear stresses for SED8CSF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	23.34	1.21	0.45	8.7%	0.10	0.20	0.12	0.12	0.12
4.9	16.49	1.36	0.69	8.1%	0.40	0.80	0.52	0.44	0.44
9.4	15.76	1.45	0.84	7.8%	0.80	1.60	1.04	1.05	1.05
14	10.15	1.45	0.84	7.9%	0.80	1.60	1.28	1.26	1.26
18.9	14.20	1.44	0.82	7.7%	0.80	1.60	0.83	0.62	0.80
Mean	15.99	1.38	0.73	8.0%	0.58	1.16	0.76	0.70	0.73

Table 27. Power law fit parameters for SED8CSF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	4.9	6.92E-05	2.38	0.95
2	4.9	9.4	7.60E-06	1.74	0.97
3	9.4	14.0	5.47E-07	2.21	0.98
4	14.4	18.9	9.85E-08	2.73	0.97
5	18.9	24.9	1.07E-06	2.48	0.88

2.7 SED9.5BSF

2.7.1 SED9.5BSF-A

A 19 cm sample of sediment was collected upstream from the river cove in the navigation channel region of the Anacostia River. SED9.5BSF-A is archived in the Santa Cruz SEDflume laboratory in case supplemental testing is required.



Figure 57. Photograph of Sample SED9.5BSF-A.

2.7.2 SED9.5BSF-B

Sample SED9.5BSF-B was collected upstream from the river cove in the navigation channel. A 25 cm core of grey sandy silt was collected (Figure 58). A layer of unconsolidated orangey floc material peppered the surface. The surface included evidence of biotic activity and a cluster of bivalve shells was noted 14 cm below the surface.

Erodibility analysis included three shear stress intervals with shear stresses ranging from 0.1 to 3.2 Pa. Erosion rates remained steady with depth possibly due to the presence of sandy material and the observed porous nature of the sediment (Figure 59). Surface sediment had a lower density and median grain size than the underlying sediment (Figure 60). The derived critical shear stress in the first interval was lower (0.17 Pa) than the underlying more homogeneous material (0.2 Pa) (Table 28). Coefficients relating the relating shear stress and erosion rate through a power law regression indicate a good fit between measurements and fall within expected ranges (Table 29).




Figure 58. Photograph of Sample SED9.5BSF-B with applied shear and measured erosion rates with depth.




Figure 59. Intracore erosion rate ratios in SED9.5BSF-B.




Figure 60. Bulk properties of SED9.5BSF-B.

Table 28. Physical parameters and derived critical shear stresses for SED9.5BSF-B.

Sample Depth (cm)	Median Grain Size (µm)	Wet Bulk Density (g/cm^3)	Dry Bulk Density (g/cm^3)	Loss on Ignition (%)	Tau_no (Pa)	Tau_first (Pa)	Tau Crit Linear (Pa)	Tau Crit Power (Pa)	Tau Crit Final (Pa)
0.0	4.16	1.08	0.25	11.2%	0.10	0.20	0.16	0.17	0.17
5.9	63.28	1.37	0.68	6.4%	0.20	0.40	0.22	0.17	0.20
10.6	64.82	1.40	0.75	7.2%	0.20	0.40	0.23	0.20	0.20
15.1	61.95	1.45	0.81	6.6%	---	---	---	---	---
Mean	48.55	1.33	0.62	7.9%	0.17	0.33	0.20	0.18	0.19

Table 29. Power law fit parameters for SED9.5BSF-B.

Interval	Depth Start (cm)	Depth Finish (cm)	A	n	r^2
1	0.0	5.1	2.94E-05	2.24	0.95
2	5.9	10.6	2.81E-05	2.29	0.92
3	10.6	15.1	1.30E-05	2.87	0.96

3 AMENDMENT COMPARISON

Results from this SEDflume study allow for a comparison between amendments and with native sediment response to erosive forces. The following comparative figures are designed to highlight similarities in amended sediment characteristics and show differences from the native unaltered material. Critical shear stresses, median particle sizes, and bulk density trends are presented relative to depth. The horizontal dotted line at zero in each panel represents the approximate depth of the amended sediment.

The observations of unamended and amended sediment reflect changes in the erodibility properties due to the addition of SediMite™, AquaGate®+PAC, or sand+GAC. Unamended Samples SED7DSF-B and SED7ESF-B contained similar bedded sediment (Figure 62 and Figure 63, first panels), and the computed critical shear stress magnitudes aligned with depth (Figure 61, first panel). This consistency in unamended samples suggests that observed differences in Samples C, D, and E are related to the application of amendment material.

The influence of amendment material is shown to be consistent between the two sites with some variations being attributed to differences in amendment thickness. The SediMite™ required the thinnest layer of material, 0.9 and 1.1 cm for SED7DSF-C and SED7ESF-C, respectively. Resulting densities did not vary significantly from that of unamended sediment (Figure 63, panels 2 and 1); however, particle size distribution at the surface increased in both samples (Figure 62). The increase in grain size appears to have had a limited influence on computed critical shear stress.

Because significantly more AquaGate®+PAC was required than SediMite™, more weight was applied to the underlying sediment during the consolidation phase. In both AquaGate®+PAC samples, the surface layer contained the gelatin-like low-density material that eroded relatively easily and had a low critical shear stress (Figure 63, panel 3). The underlying layers where the amendment aggregate, clay and carbon material, and native sediment mixed required more force to erode, and this trend extended into the native material below. The overall lower critical shear stresses in SED7ESF-D relative to SED7DSF-D could be due to the doubled amount of amendment material present pressing down on the native material and increasing the measured density.

The application of sand+GAC appeared to have the same effect on both cove samples with an increase in shear stress at the interface of sand and native material due to the crust-like formation of sediment observed in both samples. Like the AquaGate®+PAC sample SED7DSF-D, the weight of the amendment appeared to consolidate the underlying sediment, increasing the density, and ultimately increasing the critical shear stress. A key difference between the sand cap and other amendments is the lack of carbon penetration into the underlying sediment that was observed in the SediMite™ and AquaGate®+PAC samples (Figure 27, Figure 31). Despite evidence of preliminary biotic activity at the interface

(Figure 35), no darkening of the native material was observed and the overall biotic disturbance seen in the other amended samples was muted.




Figure 61. Critical shear stresses in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment.




Figure 62. Median particle size (D50) in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment.




Figure 63. Dry bulk density in unamended and amended sediment. Left to right: Unamended sediment, SediMite amendment, AquaGate+PAC amendment, sand+GAC amendment.

4 CONCLUSIONS

The SEDflume study conducted on samples from the Anacostia River resulted in the determination of erodibility parameters from seven unamended sediment samples and six amended sediment cores. Application of amendment material was intended to mimic biotic activity that could mix the amendment material into the native sediment to deliver the desired carbon load to the system. The manual mixing into the bioactive zone was exacerbated in some cases by natural biotic activity that extended the presence of carbon into the sediment bed.

Computed critical shear stresses were greater in the amended and underlying native material than in the unamended, collocated samples. The presence and abundance of biota, either active such as worms or passive such as pockets of leaves, seemed to have an impact on the erodibility of surrounding sediment. Observed erosion processes transitioned from streams of individual grains in unconsolidated material to clumps and pieces in deeper sediment.

Samples with likewise amendments behaved similarly to one another but different from the baseline samples that went untreated. Both the AquaGate®+PAC and SediMite™ appear to have delivered the carbon load to the surface sediment. The quantity of AquaGate®+PAC resulted in some differential settling and formation of a low-density layer of pure amendment that was removed easily during testing. The thinner application of SediMite™ meant it was more easily mixed into the native material but appeared to have less influence on erodibility parameters. The sand+GAC had a strong influence on underlying sediment due to the overall weight of material but lacked the penetration of carbon observed in other amended samples.

It is recommended that the data presented here be analyzed in conjunction with other data regarding environmental forces, chemical sequestration needs, and overall site dynamics to determine which amendment will best meet project goals.

5 REFERENCES

ASTM. 2007. *Annual book of ASTM standards.* Vol. 04.08, Soil and Rock (I): D420–D5611. ASTM International, West Conshohocken, PA. pp. 314–315.

Håkanson, L., and M. Jansson. 1983. *Principles of Lake Sedimentology*. 320 pp. Berlin–New York: Springer-Verlag. ISBN 3–540 (Berlin) 0–387 (New York)–12645–7. DM 98, *Int. Revue ges. Hydrobiol.*

Jepsen, R., J. Roberts, and W. Lick. 1997. Effects of bulk density on sediment erosion rates. *Water Air Soil Pollut.* 99:21–31.

McNeil, J., C. Taylor, and W. Lick. 1996. Measurements of erosion of undisturbed bottom sediments with depth. *J. Hydr. Engr.* 122(6):316–324.


R.J. Diaz & Daughters. 2017. Estimation of Biologically Active Zone at Pepco- Benning Road Facility, Washington DC, Using Sediment Profile Imaging. Draft Report. R.J. Diaz & Daughters, Ware Neck, VA.

Roberts, J., R. Jepsen, D. Gotthard, and W. Lick. 1998. Effects of particle size and bulk density on erosion of quartz particles. *J. Hydr. Engr.* 124(12):1261–1267.

Appendix A

Sampling Locations

Sample ID	Easting	Northing	Lat	Lon
SED6C/R6-04SF	1323519.7	449575.6	38.9011	-76.9607
R6-03SF	1323310.8	449529.8	38.9010	-76.9614
SED7BSF	1323647.8	449847.4	38.9019	-76.9602
SED8CSF	1323810.5	450062.6	38.9025	-76.9597
SED5CSF	1323337.1	449338.1	38.9005	-76.9613
SED7DSF	1323814.3	449789.6	38.9017	-76.9597
SED7ESF	1323942.7	449728.2	38.9015	-76.9592
SED9.5BSF	1323970.6	450613.6	38.9040	-76.9591



LEGEND

- SF Sample Locations (5 cores)
- SF Sample Locations (2 cores)
- Sewer
- Utility Crossing
- Navigation Channel
- Benning Road Facility Property Boundary
- Waterside Investigation Area

AECOM

0 400 Feet

BENNING ROAD FACILITY RI/FS PROJECT
3400 BENNING RD., NE
WASHINGTON, DC 20019

SEDFLUME LOCATIONS

Date: 6/3/2020 | Drawn By: DCB | Checked By: RD | FIGURE 1

Appendix B

Particle Size Distributions

(Data Files Available Upon Request)

Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED5CSF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_5_CSF-b_01__001.$av
	SED_5_CSF-b_01__001.$av
File ID:	SED_5_CSF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_5_CSF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	15.81 µm	S.D.:	3.561
Median:	16.42 µm	Variance:	12.68
Mean/Median ratio:	0.963	Skewness:	-0.142 Left skewed
Mode:	18.00 µm	Kurtosis:	-0.199 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.978 µm	6.799 µm	16.42 µm	38.42 µm	80.32 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED5CSF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_5_CSF-b_02__001.$av
	SED_5_CSF-b_02__001.$av
File ID:	SED_5_CSF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_5_CSF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	18.45 µm	S.D.:	4.056
Median:	19.21 µm	Variance:	16.45
Mean/Median ratio:	0.961	Skewness:	-0.132 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.438 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.887 µm	6.910 µm	19.21 µm	51.32 µm	112.7 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED5CSF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_5_CSF-b_03__001.$av
	SED_5_CSF-b_03__001.$av
File ID:	SED_5_CSF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_5_CSF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	14.55 µm	S.D.:	3.833
Median:	15.02 µm	Variance:	14.69
Mean/Median ratio:	0.968	Skewness:	-0.121 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.528 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.441 µm	5.625 µm	15.02 µm	39.18 µm	86.71 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED5CSF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_5_CSF-b_04__001.$av
	SED_5_CSF-b_04__001.$av
File ID:	SED_5_CSF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_5_CSF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	21.50 µm	S.D.:	4.815
Median:	25.31 µm	Variance:	23.18
Mean/Median ratio:	0.849	Skewness:	-0.255 Left skewed
Mode:	45.76 µm	Kurtosis:	-0.682 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.323 µm	6.595 µm	25.31 µm	73.42 µm	148.1 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED5CSF-B-05


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_5_CSF-b_05__001.$av
	SED_5_CSF-b_05__001.$av
File ID:	SED_5_CSF-b_05
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_5_CSF-b_05__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	26.38 µm	S.D.:	4.222
Median:	40.06 µm	Variance:	17.83
Mean/Median ratio:	0.658	Skewness:	-0.829 Left skewed
Mode:	80.07 µm	Kurtosis:	-0.224 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.676 µm	10.59 µm	40.06 µm	80.19 µm	122.6 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED6C/R604SF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_6CR6-04SF-b_01__001.$av
	SED_6CR6-04SF-b_01__001.$av
File ID:	SED_6C/R6-04SF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_6CR6-04SF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	13.24 µm	S.D.:	3.949
Median:	14.65 µm	Variance:	15.59
Mean/Median ratio:	0.904	Skewness:	-0.219 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.693 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.959 µm	4.888 µm	14.65 µm	38.39 µm	77.96 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED6C/R604SF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\#2 SED6CR6-04SF-b_02__001.$av
	#2 SED6CR6-04SF-b_02__001.$av
File ID:	SED6C/R6-04SF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) #2 SED6CR6-04SF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	24.84 µm	S.D.:	4.897
Median:	31.16 µm	Variance:	23.98
Mean/Median ratio:	0.797	Skewness:	-0.405 Left skewed
Mode:	87.90 µm	Kurtosis:	-0.719 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.462 µm	7.545 µm	31.16 µm	90.68 µm	167.2 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED6C/R604SF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_6CR6-04SF-b_03__001.$av
	SED_6CR6-04SF-b_03__001.$av
File ID:	SED6C/R6-04SF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_6CR6-04SF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	12.89 µm	S.D.:	4.133
Median:	14.86 µm	Variance:	17.08
Mean/Median ratio:	0.867	Skewness:	-0.240 Left skewed
Mode:	41.68 µm	Kurtosis:	-0.763 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.701 µm	4.458 µm	14.86 µm	39.80 µm	75.61 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED6C/R604SF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_6CR6-04SF-b_04__001.$av
	SED_6CR6-04SF-b_04__001.$av
File ID:	SED6C/R6-04SF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_6CR6-04SF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	20.29 µm	S.D.:	4.342
Median:	27.82 µm	Variance:	18.85
Mean/Median ratio:	0.729	Skewness:	-0.556 Left skewed
Mode:	55.14 µm	Kurtosis:	-0.574 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.188 µm	7.110 µm	27.82 µm	64.21 µm	109.4 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED6C/R604SF-B-05


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_6CR6-04SF-b_05__001.$av
	SED_6CR6-04SF-b_05__001.$av
File ID:	SED6C/R6-04SF-b_05
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_6CR6-04SF-b_05__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	18.29 µm	S.D.:	4.882
Median:	22.70 µm	Variance:	23.83
Mean/Median ratio:	0.806	Skewness:	-0.302 Left skewed
Mode:	50.23 µm	Kurtosis:	-0.856 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.838 µm	5.282 µm	22.70 µm	66.50 µm	124.9 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7BSF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_BSF-b_01__002.$av
	SED_7_BSF-b_01__002.$av
File ID:	SED_7_BSF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_BSF-b_01__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	12.95 µm	S.D.:	3.839
Median:	13.49 µm	Variance:	14.74
Mean/Median ratio:	0.960	Skewness:	-0.161 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.659 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.081 µm	4.945 µm	13.49 µm	36.21 µm	79.43 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7BSF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_BSF-b_02__001.$av
	SED_7_BSF-b_02__001.$av
File ID:	SED_7_BSF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_BSF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	15.17 µm	S.D.:	4.078
Median:	17.56 µm	Variance:	16.63
Mean/Median ratio:	0.864	Skewness:	-0.285 Left skewed
Mode:	23.82 µm	Kurtosis:	-0.651 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.062 µm	5.479 µm	17.56 µm	44.51 µm	89.87 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7BSF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_BSF-b_03__001.$av
	SED_7_BSF-b_03__001.$av
File ID:	SED_7_BSF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_BSF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	10.38 µm	S.D.:	4.022
Median:	10.20 µm	Variance:	16.17
Mean/Median ratio:	1.017	Skewness:	0.016 Right skewed
Mode:	6.453 µm	Kurtosis:	-0.688 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.606 µm	3.701 µm	10.20 µm	29.41 µm	67.00 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7DSF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_DSF-b_01__001.$av
	SED_7_DSF-b_01__001.$av
File ID:	SED_7_DSF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_DSF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	17.60 µm	S.D.:	4.075
Median:	21.16 µm	Variance:	16.61
Mean/Median ratio:	0.832	Skewness:	-0.390 Left skewed
Mode:	37.97 µm	Kurtosis:	-0.582 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.355 µm	6.434 µm	21.16 µm	52.25 µm	99.62 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7DSF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_DSF-b_02__001.$av
	SED_7_DSF-b_02__001.$av
File ID:	SED_7_DSF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_DSF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	27.04 µm	S.D.:	4.090
Median:	36.07 µm	Variance:	16.73
Mean/Median ratio:	0.750	Skewness:	-0.706 Left skewed
Mode:	87.90 µm	Kurtosis:	-0.224 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.261 µm	11.06 µm	36.07 µm	81.59 µm	132.8 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7DSF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_DSF-b_03__001.$av
	SED_7_DSF-b_03__001.$av
File ID:	SED_7_DSF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_DSF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	29.26 µm	S.D.:	4.242
Median:	39.70 µm	Variance:	17.99
Mean/Median ratio:	0.737	Skewness:	-0.716 Left skewed
Mode:	96.49 µm	Kurtosis:	-0.216 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.274 µm	11.87 µm	39.70 µm	90.18 µm	146.5 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7DSF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_DSF-b_04__001.$av
	SED_7_DSF-b_04__001.$av
File ID:	SED_7_DSF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_DSF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	33.91 µm	S.D.:	4.333
Median:	53.08 µm	Variance:	18.78
Mean/Median ratio:	0.639	Skewness:	-0.912 Left skewed
Mode:	87.90 µm	Kurtosis:	-0.030 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.285 µm	14.41 µm	53.08 µm	102.0 µm	158.0 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7DSF-B-05


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_DSF-b_05__001.$av
	SED_7_DSF-b_05__001.$av
File ID:	SED_7_DSF-b_05
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_DSF-b_05__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	17.84 µm	S.D.:	3.953
Median:	21.91 µm	Variance:	15.63
Mean/Median ratio:	0.814	Skewness:	-0.467 Left skewed
Mode:	31.51 µm	Kurtosis:	-0.374 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.328 µm	7.287 µm	21.91 µm	48.41 µm	93.16 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7ESF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_ESF-b_01__001.$av
	SED_7_ESF-b_01__001.$av
File ID:	SED_7_ESF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_ESF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	10.93 µm	S.D.:	3.530
Median:	12.66 µm	Variance:	12.46
Mean/Median ratio:	0.864	Skewness:	-0.326 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.599 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.794 µm	4.458 µm	12.66 µm	28.72 µm	51.37 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7ESF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_ESF-b_02__002.$av
	SED_7_ESF-b_02__002.$av
File ID:	SED_7_ESF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_ESF-b_02__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	18.56 µm	S.D.:	4.764
Median:	19.42 µm	Variance:	22.69
Mean/Median ratio:	0.956	Skewness:	-0.091 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.669 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.202 µm	5.904 µm	19.42 µm	60.21 µm	144.1 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7ESF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_ESF-b_03__001.$av
	SED_7_ESF-b_03__001.$av
File ID:	SED_7_ESF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_ESF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	16.42 µm	S.D.:	4.677
Median:	16.66 µm	Variance:	21.87
Mean/Median ratio:	0.986	Skewness:	0.0083 Right skewed
Mode:	19.76 µm	Kurtosis:	-0.573 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.062 µm	5.396 µm	16.66 µm	49.32 µm	127.5 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7ESF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_7_ESF-b_04__001.$av
	SED_7_ESF-b_04__001.$av
File ID:	SED_7_ESF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_7_ESF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	81.75 µm	S.D.:	6.111
Median:	133.2 µm	Variance:	37.34
Mean/Median ratio:	0.614	Skewness:	-0.775 Left skewed
Mode:	429.2 µm	Kurtosis:	-0.320 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.934 µm	24.10 µm	133.2 µm	347.9 µm	569.4 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED7ESF-B-05


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\#2-SED_7_ESF-b_05__001.$av
	#2-SED_7_ESF-b_05__001.$av
File ID:	#2-SED_7_ESF-b_05
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) #2-SED_7_ESF-b_05__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	12.74 µm	S.D.:	4.074
Median:	13.15 µm	Variance:	16.59
Mean/Median ratio:	0.968	Skewness:	-0.048 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.622 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.902 µm	4.597 µm	13.15 µm	35.38 µm	84.69 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED8CSF-B-01


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_8_CSF-b_01__001.$av
	SED_8_CSF-b_01__001.$av
File ID:	SED_8_CSF-b_01
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_8_CSF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	20.24 µm	S.D.:	4.695
Median:	23.34 µm	Variance:	22.04
Mean/Median ratio:	0.867	Skewness:	-0.295 Left skewed
Mode:	96.49 µm	Kurtosis:	-0.766 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.251 µm	6.320 µm	23.34 µm	72.74 µm	137.5 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED8CSF-B-02


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_8_CSF-b_02__001.$av
	SED_8_CSF-b_02__001.$av
File ID:	SED_8_CSF-b_02
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_8_CSF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	14.93 µm	S.D.:	4.487
Median:	16.49 µm	Variance:	20.13
Mean/Median ratio:	0.905	Skewness:	-0.183 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.801 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.815 µm	4.849 µm	16.49 µm	48.39 µm	105.4 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED8CSF-B-03


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_8_CSF-b_03__001.$av
	SED_8_CSF-b_03__001.$av
File ID:	SED_8_CSF-b_03
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_8_CSF-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	13.82 µm	S.D.:	4.231
Median:	15.76 µm	Variance:	17.90
Mean/Median ratio:	0.877	Skewness:	-0.234 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.753 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.774 µm	4.750 µm	15.76 µm	42.49 µm	88.73 µm



Beckman Coulter LS Particle Size Analyzer

integral consulting inc.

9 Jul 2020

SED8CSF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_8_CSF-b_04__001.$av
	SED_8_CSF-b_04__001.$av
File ID:	SED_8_CSF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_8_CSF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	9.901 µm	S.D.:	3.961
Median:	10.15 µm	Variance:	15.69
Mean/Median ratio:	0.976	Skewness:	-0.094 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.828 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.484 µm	3.498 µm	10.15 µm	29.25 µm	61.73 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED8CSF-B-05


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_8_CSF-b_05__001.$av
	SED_8_CSF-b_05__001.$av
File ID:	SED_8_CSF-b_05
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_8_CSF-b_05__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	12.51 µm	S.D.:	4.030
Median:	14.20 µm	Variance:	16.24
Mean/Median ratio:	0.881	Skewness:	-0.234 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.685 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.707 µm	4.562 µm	14.20 µm	36.26 µm	74.26 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED9.5BSF-B-01


File name:	**C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_9.5_BSF-b_01__001.$av**
	SED_9.5_BSF-b_01__001.$av
File ID:	**SED_9.5_BSF-b_01**
Optical model:	**Fraunhofer.rf780z**

Volume Statistics (Geometric) SED_9.5_BSF-b_01__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	10.91 µm	S.D.:	3.718
Median:	11.71 µm	Variance:	13.82
Mean/Median ratio:	0.931	Skewness:	-0.160 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.677 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.797 µm	4.157 µm	11.71 µm	29.53 µm	59.27 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED9.5BSF-B-02


File name:	**C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_9.5_BSF-b_02__001.$av**
	SED_9.5_BSF-b_02__001.$av
File ID:	**SED_9.5_BSF-b_02**
Optical model:	**Fraunhofer.rf780z**

Volume Statistics (Geometric) SED_9.5_BSF-b_02__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	37.73 µm	S.D.:	4.637
Median:	63.28 µm	Variance:	21.51
Mean/Median ratio:	0.596	Skewness:	-0.840 Left skewed
Mode:	116.3 µm	Kurtosis:	-0.290 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.384 µm	13.64 µm	63.28 µm	125.9 µm	187.3 µm



Beckman Coulter LS Particle Size Analyzer

25 Aug 2020

SED9.5BSF-B-03


File name:	**C:\Users\smcwilliams74\Desktop\projects\C3070_AECOM_Capping_Study_washington_DC\Processing\PSD\C3070 PSD raw data\Sed_9.5_bsf-b_03__001.$av**
	Sed_9.5_bsf-b_03__001.$av
File ID:	**SED_9.5_BSF-b_03**
Optical model:	**Fraunhofer.rf780z**

Volume Statistics (Geometric) Sed_9.5_bsf-b_03__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	41.62 µm	S.D.:	4.368
Median:	64.82 µm	Variance:	19.08
Mean/Median ratio:	0.642	Skewness:	-0.944 Left skewed
Mode:	127.7 µm	Kurtosis:	0.109 Leptokurtic

<10%	<25%	<50%	<75%	<90%
4.159 µm	17.88 µm	64.82 µm	128.6 µm	188.4 µm



Beckman Coulter LS Particle Size Analyzer

9 Jul 2020

SED9.5BSF-B-04


File name:	C:\Users\smcwilliams74\Desktop\C3070 PSD\SED_9.5_BSF-b_04__001.$av
	SED_9.5_BSF-b_04__001.$av
File ID:	SED_9.5_BSF-b_04
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) SED_9.5_BSF-b_04__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	39.78 µm	S.D.:	4.661
Median:	61.95 µm	Variance:	21.73
Mean/Median ratio:	0.642	Skewness:	-0.811 Left skewed
Mode:	127.7 µm	Kurtosis:	-0.168 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.639 µm	15.17 µm	61.95 µm	130.7 µm	200.0 µm



Beckman Coulter LS Particle Size Analyzer

SEd7DSF-C-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-c1__001.$av Sed-7dsf-c1__001.$av
File ID:	SED-7DSF-c1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-c1__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	14.22 µm	S.D.:	3.805
Median:	16.53 µm	Variance:	14.48
Mean/Median ratio:	0.860	Skewness:	-0.335 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.549 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.144 µm	5.552 µm	16.53 µm	39.74 µm	75.58 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-C-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-c2__001.$av
	Sed-7dsf-c2__001.$av
File ID:	SED-7DSF-c2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-c2__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	29.58 µm	S.D.:	4.810
Median:	36.73 µm	Variance:	23.14
Mean/Median ratio:	0.805	Skewness:	-0.472 Left skewed
Mode:	50.23 µm	Kurtosis:	-0.508 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.989 µm	10.08 µm	36.73 µm	102.9 µm	197.8 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SEd7DSF-C-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-c3__001.$av Sed-7dsf-c3__001.$av
File ID:	SED-7DSF-c3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-c3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	19.78 µm	S.D.:	4.007
Median:	24.59 µm	Variance:	16.06
Mean/Median ratio:	0.805	Skewness:	-0.548 Left skewed
Mode:	45.76 µm	Kurtosis:	-0.404 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.515 µm	7.926 µm	24.59 µm	57.16 µm	106.0 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-C-04


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-c4__001.$av
	Sed-7dsf-c4__001.$av
File ID:	SED-7DSF-c4
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-c4__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	27.61 µm	S.D.:	4.204
Median:	37.25 µm	Variance:	17.67
Mean/Median ratio:	0.741	Skewness:	-0.697 Left skewed
Mode:	66.45 µm	Kurtosis:	-0.242 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.129 µm	11.21 µm	37.25 µm	83.79 µm	140.3 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-C-05


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-c5__001.$av
	Sed-7dsf-c5__001.$av
File ID:	SED-7DSF-c5
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-c5__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	25.62 µm	S.D.:	4.291
Median:	33.67 µm	Variance:	18.41
Mean/Median ratio:	0.761	Skewness:	-0.630 Left skewed
Mode:	80.07 µm	Kurtosis:	-0.368 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.837 µm	9.946 µm	33.67 µm	80.32 µm	139.0 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d1__001.$av Sed-7dsf-d1__001.$av
File ID:	SED-7DSF-d1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d1__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	14.69 µm	S.D.:	2.812
Median:	17.34 µm	Variance:	7.908
Mean/Median ratio:	0.847	Skewness:	-0.687 Left skewed
Mode:	26.15 µm	Kurtosis:	0.188 Leptokurtic

<10%	<25%	<50%	<75%	<90%
3.493 µm	7.816 µm	17.34 µm	31.75 µm	47.89 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d2__001.$av Sed-7dsf-d2__001.$av
File ID:	SED-7DSF-d2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d2__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	20.77 µm	S.D.:	4.360
Median:	22.14 µm	Variance:	19.01
Mean/Median ratio:	0.938	Skewness:	0.097 Right skewed
Mode:	34.59 µm	Kurtosis:	-0.031 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.958 µm	7.753 µm	22.14 µm	48.92 µm	130.0 µm



Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d3__001.$av Sed-7dsf-d3__001.$av
File ID:	SED-7DSF-d3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	16.89 µm	S.D.:	3.667
Median:	19.66 µm	Variance:	13.45
Mean/Median ratio:	0.859	Skewness:	-0.313 Left skewed
Mode:	34.59 µm	Kurtosis:	-0.369 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.716 µm	6.930 µm	19.66 µm	42.54 µm	83.75 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-04


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d4__001.$av Sed-7dsf-d4__001.$av
File ID:	SED-7DSF-d4
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d4__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	22.63 µm	S.D.:	3.736
Median:	25.22 µm	Variance:	13.96
Mean/Median ratio:	0.897	Skewness:	-0.400 Left skewed
Mode:	37.97 µm	Kurtosis:	-0.296 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.728 µm	9.458 µm	25.22 µm	60.65 µm	118.2 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-05


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d5__001.$av
	Sed-7dsf-d5__001.$av
File ID:	SED-7DSF-d5
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d5__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	39.62 µm	S.D.:	4.047
Median:	41.83 µm	Variance:	16.37
Mean/Median ratio:	0.947	Skewness:	-0.164 Left skewed
Mode:	87.90 µm	Kurtosis:	0.199 Leptokurtic

<10%	<25%	<50%	<75%	<90%
6.670 µm	16.34 µm	41.83 µm	99.29 µm	209.6 µm



Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-06


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d6__001.$av Sed-7dsf-d6__001.$av
File ID:	SED-7DSF-d6
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d6__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	36.90 µm	S.D.:	4.222
Median:	48.30 µm	Variance:	17.82
Mean/Median ratio:	0.764	Skewness:	-0.610 Left skewed
Mode:	96.49 µm	Kurtosis:	-0.196 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.544 µm	14.46 µm	48.30 µm	108.5 µm	193.5 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-D-07


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-d7__001.$av Sed-7dsf-d7__001.$av
File ID:	SED-7DSF-d7
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-d7__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	27.58 µm	S.D.:	3.831
Median:	32.64 µm	Variance:	14.68
Mean/Median ratio:	0.845	Skewness:	-0.582 Left skewed
Mode:	37.97 µm	Kurtosis:	0.157 Leptokurtic

<10%	<25%	<50%	<75%	<90%
3.992 µm	13.31 µm	32.64 µm	69.84 µm	131.3 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e1__001.$av Sed-7dsf-e1__001.$av
File ID:	SED-7DSF-e1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e1__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	521.1 µm	S.D.:	2.551
Median:	576.5 µm	Variance:	6.506
Mean/Median ratio:	0.904	Skewness:	-2.852 Left skewed
Mode:	517.2 µm	Kurtosis:	12.73 Leptokurtic

<10%	<25%	<50%	<75%	<90%
263.5 µm	405.4 µm	576.5 µm	849.3 µm	1340 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e2__001.$av Sed-7dsf-e2__001.$av
File ID:	SED-7DSF-e2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e2__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	649.1 µm	S.D.:	1.972
Median:	660.1 µm	Variance:	3.887
Mean/Median ratio:	0.983	Skewness:	-2.889 Left skewed
Mode:	623.3 µm	Kurtosis:	19.93 Leptokurtic

<10%	<25%	<50%	<75%	<90%
352.1 µm	476.5 µm	660.1 µm	972.0 µm	1432 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e3__001.$av Sed-7dsf-e3__001.$av
File ID:	SED-7DSF-e3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	639.0 µm	S.D.:	1.987
Median:	649.9 µm	Variance:	3.950
Mean/Median ratio:	0.983	Skewness:	-2.977 Left skewed
Mode:	623.3 µm	Kurtosis:	20.56 Leptokurtic

<10%	<25%	<50%	<75%	<90%
348.8 µm	470.1 µm	649.9 µm	949.6 µm	1416 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-04


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e4__001.$av Sed-7dsf-e4__001.$av
File ID:	SED-7DSF-e4
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e4__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	34.37 µm	S.D.:	4.626
Median:	34.69 µm	Variance:	21.40
Mean/Median ratio:	0.991	Skewness:	-0.098 Left skewed
Mode:	28.70 µm	Kurtosis:	-0.395 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.733 µm	11.96 µm	34.69 µm	97.68 µm	305.8 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-05


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e5__001.$av Sed-7dsf-e5__001.$av
File ID:	SED-7DSF-e5
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e5__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	22.42 µm	S.D.:	3.787
Median:	25.93 µm	Variance:	14.34
Mean/Median ratio:	0.865	Skewness:	-0.451 Left skewed
Mode:	28.70 µm	Kurtosis:	-0.368 Platykurtic

<10%	<25%	<50%	<75%	<90%
3.508 µm	9.035 µm	25.93 µm	62.95 µm	115.3 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7DSF-E-06


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7dsf-e6__001.$av Sed-7dsf-e6__001.$av
File ID:	SED-7DSF-e6
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7dsf-e6__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	35.26 µm	S.D.:	3.894
Median:	45.92 µm	Variance:	15.17
Mean/Median ratio:	0.768	Skewness:	-0.707 Left skewed
Mode:	96.49 µm	Kurtosis:	-0.048 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.892 µm	15.09 µm	45.92 µm	100.1 µm	165.1 µm



Beckman Coulter LS Particle Size Analyzer

SED7ESF-C-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-c1__001.$av Sed-7esf-c1__001.$av
File ID:	SED-7ESF-c1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-c1__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	49.77 µm	S.D.:	2.857
Median:	50.56 µm	Variance:	8.163
Mean/Median ratio:	0.984	Skewness:	-0.586 Left skewed
Mode:	41.68 µm	Kurtosis:	1.306 Leptokurtic

<10%	<25%	<50%	<75%	<90%
14.57 µm	26.47 µm	50.56 µm	103.6 µm	183.9 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-C-01b


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-c1b__001.$av Sed-7esf-c1b__001.$av
File ID:	SED-7ESF-c1b
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-c1b__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.40 µm	S.D.:	4.765
Median:	31.38 µm	Variance:	22.71
Mean/Median ratio:	1.001	Skewness:	-0.224 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.600 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.059 µm	10.30 µm	31.38 µm	113.6 µm	235.7 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-C-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-c2__001.$av Sed-7esf-c2__001.$av
File ID:	SED-7ESF-c2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-c2__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	64.80 µm	S.D.:	6.446
Median:	84.11 µm	Variance:	41.55
Mean/Median ratio:	0.770	Skewness:	-0.334 Left skewed
Mode:	185.4 µm	Kurtosis:	-0.672 Platykurtic

<10%	<25%	<50%	<75%	<90%
4.831 µm	16.32 µm	84.11 µm	269.6 µm	703.4 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-C-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-c3__001.$av Sed-7esf-c3__001.$av
File ID:	SED-7ESF-c3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-c3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	34.96 µm	S.D.:	5.882
Median:	39.09 µm	Variance:	34.60
Mean/Median ratio:	0.894	Skewness:	-0.261 Left skewed
Mode:	127.7 µm	Kurtosis:	-0.775 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.920 µm	9.299 µm	39.09 µm	147.6 µm	312.4 µm



Beckman Coulter LS Particle Size Analyzer

SED7ESF-D-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-d1__002.$av Sed-7esf-d1__002.$av
File ID:	SED-7ESF-d1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-d1__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	15.29 µm	S.D.:	2.973
Median:	17.36 µm	Variance:	8.841
Mean/Median ratio:	0.881	Skewness:	-0.422 Left skewed
Mode:	21.70 µm	Kurtosis:	0.278 Leptokurtic

<10%	<25%	<50%	<75%	<90%
3.526 µm	7.893 µm	17.36 µm	32.31 µm	52.16 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-D-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-d2__002.$av Sed-7esf-d2__002.$av
File ID:	SED-7ESF-d2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-d2__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	19.30 µm	S.D.:	4.198
Median:	19.92 µm	Variance:	17.62
Mean/Median ratio:	0.969	Skewness:	0.157 Right skewed
Mode:	23.82 µm	Kurtosis:	0.113 Leptokurtic

<10%	<25%	<50%	<75%	<90%
3.013 µm	7.570 µm	19.92 µm	43.53 µm	118.3 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-D-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-d3__001.$av Sed-7esf-d3__001.$av
File ID:	SED-7ESF-d3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-d3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	9.948 µm	S.D.:	3.405
Median:	11.99 µm	Variance:	11.59
Mean/Median ratio:	0.830	Skewness:	-0.439 Left skewed
Mode:	19.76 µm	Kurtosis:	-0.654 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.621 µm	4.162 µm	11.99 µm	26.07 µm	44.89 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-D-04


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-d4__001.$av Sed-7esf-d4__001.$av
File ID:	SED-7ESF-d4
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-d4__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	18.75 µm	S.D.:	4.796
Median:	19.80 µm	Variance:	23.00
Mean/Median ratio:	0.947	Skewness:	-0.145 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.668 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.091 µm	6.158 µm	19.80 µm	61.26 µm	147.1 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-D-05


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-d5__002.$av Sed-7esf-d5__002.$av
File ID:	SED-7ESF-d5
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-d5__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	23.53 µm	S.D.:	5.927
Median:	22.18 µm	Variance:	35.13
Mean/Median ratio:	1.061	Skewness:	0.022 Right skewed
Mode:	19.76 µm	Kurtosis:	-0.794 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.140 µm	6.243 µm	22.18 µm	95.80 µm	277.8 µm



Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-01


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e1__001.$av Sed-7esf-e1__001.$av
File ID:	SED-7ESF-e1
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e1__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	757.2 µm	S.D.:	2.149
Median:	828.5 µm	Variance:	4.617
Mean/Median ratio:	0.914	Skewness:	-3.502 Left skewed
Mode:	1584 µm	Kurtosis:	20.47 Leptokurtic

<10%	<25%	<50%	<75%	<90%
412.1 µm	573.6 µm	828.5 µm	1213 µm	1567 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-02


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e2__001.$av Sed-7esf-e2__001.$av
File ID:	SED-7ESF-e2
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e2__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	738.5 µm	S.D.:	1.892
Median:	771.2 µm	Variance:	3.581
Mean/Median ratio:	0.958	Skewness:	-3.275 Left skewed
Mode:	684.2 µm	Kurtosis:	24.05 Leptokurtic

<10%	<25%	<50%	<75%	<90%
405.4 µm	544.6 µm	771.2 µm	1118 µm	1461 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-03


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e3__001.$av Sed-7esf-e3__001.$av
File ID:	SED-7ESF-e3
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e3__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	796.3 µm	S.D.:	1.916
Median:	861.1 µm	Variance:	3.670
Mean/Median ratio:	0.925	Skewness:	-3.008 Left skewed
Mode:	1584 µm	Kurtosis:	20.66 Leptokurtic

<10%	<25%	<50%	<75%	<90%
409.7 µm	572.3 µm	861.1 µm	1264 µm	1555 µm



Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-04


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e4__001.$av Sed-7esf-e4__001.$av
File ID:	SED-7ESF-e4
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e4__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	11.67 µm	S.D.:	3.614
Median:	13.75 µm	Variance:	13.06
Mean/Median ratio:	0.849	Skewness:	-0.376 Left skewed
Mode:	21.70 µm	Kurtosis:	-0.578 Platykurtic

<10%	<25%	<50%	<75%	<90%
1.796 µm	4.782 µm	13.75 µm	30.59 µm	58.70 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-05


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e5__002.$av Sed-7esf-e5__002.$av
File ID:	SED-7ESF-e5
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e5__002.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	20.34 µm	S.D.:	5.194
Median:	20.38 µm	Variance:	26.98
Mean/Median ratio:	0.998	Skewness:	0.0080 Right skewed
Mode:	19.76 µm	Kurtosis:	-0.550 Platykurtic

<10%	<25%	<50%	<75%	<90%
2.150 µm	6.262 µm	20.38 µm	67.95 µm	169.2 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

SED7ESF-E-06


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Sed-7esf-e6__001.$av Sed-7esf-e6__001.$av
File ID:	SED-7ESF-e6
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Sed-7esf-e6__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	250.2 µm	S.D.:	4.501
Median:	389.9 µm	Variance:	20.25
Mean/Median ratio:	0.642	Skewness:	-1.767 Left skewed
Mode:	429.2 µm	Kurtosis:	3.024 Leptokurtic

<10%	<25%	<50%	<75%	<90%
27.35 µm	180.7 µm	389.9 µm	623.6 µm	942.3 µm



Beckman Coulter LS Particle Size Analyzer

25 Aug 2020

Beckman Coulter Control Samples


File name:	**C:\Users\smcwilliams74\Desktop\projects\C3070_AECOM_Capping_Study_washington_DC\Processing\PSD\C3070 PSD raw data\Control_7-2-20pm__001.$av**
	Control_7-2-20pm__001.$av
File ID:	**control_7/2/20pm**
Optical model:	**Fraunhofer.rf780z**

Volume Statistics (Geometric) Control_7-2-20pm__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.52 µm	S.D.:	1.736
Median:	34.10 µm	Variance:	3.015
Mean/Median ratio:	0.924	Skewness:	-2.545 Left skewed
Mode:	37.97 µm	Kurtosis:	13.23 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.20 µm	25.82 µm	34.10 µm	43.19 µm	52.69 µm



Beckman Coulter LS Particle Size Analyzer

25 Aug 2020

Beckman Coulter Control Samples


File name:	C:\Users\smcwilliams74\Desktop\projects\C3070_AECOM_Capping_Study_washington_DC\Processing\PSD\C3070 PSD raw data\Control_7-7-20am__001.$a
	Control_7-7-20am__001.$av
File ID:	control_7-7-20am
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Control_7-7-20am__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.97 µm	S.D.:	1.717
Median:	34.40 µm	Variance:	2.948
Mean/Median ratio:	0.930	Skewness:	-2.488 Left skewed
Mode:	37.97 µm	Kurtosis:	13.46 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.56 µm	26.11 µm	34.40 µm	43.50 µm	53.28 µm



Beckman Coulter LS Particle Size Analyzer

25 Aug 2020

Beckman Coulter Control Samples


File name:	C:\Users\smcwilliams74\Desktop\projects\C3070_AECOM_Capping_Study_washington_DC\Processing\PSD\C3070 PSD raw data\Control_7-8-20pm__001.$a
	Control_7-8-20pm__001.$av
File ID:	control_7-8-20pm
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Control_7-8-20pm__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.96 µm	S.D.:	1.727
Median:	34.36 µm	Variance:	2.981
Mean/Median ratio:	0.930	Skewness:	-2.512 Left skewed
Mode:	37.97 µm	Kurtosis:	13.70 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.52 µm	26.10 µm	34.36 µm	43.47 µm	53.35 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

Anacostia Particle Size


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Control_08-03-20___001.$av Control_08-03-20___001.$av
File ID:	control_08-03-20_pm
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Control_08-03-20___001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.62 µm	S.D.:	1.727
Median:	34.09 µm	Variance:	2.983
Mean/Median ratio:	0.927	Skewness:	-2.491 Left skewed
Mode:	37.97 µm	Kurtosis:	13.13 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.28 µm	25.83 µm	34.09 µm	43.25 µm	52.87 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

Anacostia Particle Size


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Control_08-03-202__001.$av Control_08-03-202__001.$av
File ID:	control_08-03-2020_am
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Control_08-03-202__001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.58 µm	S.D.:	1.735
Median:	34.10 µm	Variance:	3.009
Mean/Median ratio:	0.926	Skewness:	-2.552 Left skewed
Mode:	37.97 µm	Kurtosis:	13.43 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.28 µm	25.83 µm	34.10 µm	43.26 µm	52.84 µm



integral consulting inc.

Beckman Coulter LS Particle Size Analyzer

Anacostia Particle Size


File name:	\\pfs1w\C2000-C3999\C3070_Anacostia_AECOM\Data\Amendment_samples_data\PSD_C3070_amendment_data\PSD_C3070\Control_08-04-20___001.$av Control_08-04-20___001.$av
File ID:	control_08-04-20_am
Optical model:	Fraunhofer.rf780z

Volume Statistics (Geometric) Control_08-04-20___001.$av

Calculations from 0.375 µm to 2000 µm

Volume:	100%		
Mean:	31.64 µm	S.D.:	1.721
Median:	33.93 µm	Variance:	2.960
Mean/Median ratio:	0.932	Skewness:	-2.345 Left skewed
Mode:	34.59 µm	Kurtosis:	12.24 Leptokurtic

<10%	<25%	<50%	<75%	<90%
18.28 µm	25.73 µm	33.93 µm	43.26 µm	53.32 µm



Appendix C

Sand Media Specifications

Graniterock
350 Technology Drive; Watsonville, CA 95076

Baldrige Award Winner
Research-Technical Services Ph. (831) 768-2100
Sales Ph. (831) 768-2380

Quail Hollow Material Certification
Felton, CA

Product: Oly No.2 Sand (#203) **Date: June 26, 2020**

Contractor: Integral Corporation

Project: SEDflume Study

Graniterock conducts regular sampling and testing of its materials, in accordance with ASTM or other applicable standards. The results listed below are average results derived from these tests. Based on the testing conducted, Graniterock certifies that the material identified on this certificate typically has the following physical properties.

Gradation *ASTM C 136*: Cumulative Percent Passing

Sieve Size	Quail Hollow Oly No.2 Sand
#4 (4.75 mm)	100
#8 (2.36 mm)	97
#16 (1.18 mm)	79
#30 (600 µm)	35
#50 (300 µm)	10
#100(150 µm)	2
#200(75 µm)	1.2

Sand Equivalent *CT 217*:	78
Durability *CT 229*:	76
Organic Impurities *CT 213*:	Satisfactory
Specific Gravity *CT 207*:	2.56
Absorption *CT 207*:	0.6%

Submitted by:

Greg Wilkinson

Research Technical Services

Sand Specification

Ref Maryland DOT, STANDARD SPECIFICATIONS for CONSTRUCTION and MATERIALS, July 2019.

Ref from 901 AGGREGATES - Table 901A, grading requirements for Fine Aggregate — Portland Cement, Concrete, Underdrain, And Pneumatic Mortar

U.S Standard Sieve Size	Percent by Weight Passing
3/8 –inch	100
No. 4	95 - 100
No. 16	45 - 85
No. 50	5 - 30
No. 100	0 - 10

Ref from 920.01.05 (1) for Sand.
Sand shall be washed silica sand that conforms to ASTM C-33 or AASHTO M-6 with less than 1 percent by weight of any combination of diabase, greystone, calcareous, or dolomitic sand.

Additional: Furnish sand that is free of organic material and lumps or balls of clay.

Note - ASTM C-33 or AASHTO M-6 are both for fine aggregates for cement. You can delete these references if ok to be less specific in terms of specifications.

pepco®

An Exelon Company

Appendix G

KEMRON Dewatering Study Report

PEPCO BENNING ROAD
TREATABILITY STUDY
FINAL REPORT

KEMRON PROJECT #: SH0746

February 10, 2021

Prepared for:

AECOM

430 National Business Parkway
Suite 190
Annapolis Junction, MD 20701
410-379-6900 (Phone)

Prepared by:

KEMRON
ENVIRONMENTAL SERVICES

Applied Technologies Group
1359-A Ellsworth Industrial Blvd
Atlanta, GA 30318
404-636-0928 (Phone)
404-636-7162 (Fax)

Written By:

Tomecia Bradley

Tomecia Bradley, CHMM
Program Manager

Reviewed By:

Mark Clark
Senior Technologist

Table of Contents

1.0 INTRODUCTION 1
2.0 MATERIAL RECEIPT AND CHARACTERIZATION 1
3.0 EXPERIMENTAL MIXTURE EVALUATIONS 3
4.0 SOLIDIFICATION / STABILIZATION EVALUATIONS 6
5.0 CONCLUSIONS 8

LIST OF TABLES AND APPENDICES

Table 1 – Untreated Material Characterization
Table 2 – Experimental Mixtures Observations
Table 3 – Solidification-Stabilization Evaluations

Appendix A – Physical Properties Testing Data Sheets
Appendix B – Experimental Mixture Evaluations Photographic Log
Appendix C – Solidification/Stabilization Evaluations Mixture Development Sheets
Appendix D – Paint Filter Testing Data Sheets

1.0 INTRODUCTION

KEMRON Environmental Services, Inc. (KEMRON) is pleased to present AECOM with this report for the solidification study performed on materials from the Pepco Benning Road Site (the site) located in Washington, D.C. The purpose of the study was to physically and chemically characterize the site materials and appropriate additives to reduce free liquids so that the site materials passed paint filter testing, was visually soil-like in consistency, and exhibited approximately six (6) pounds per square inch (psi) compressive strength. This report will describe the protocol used during testing of the site materials as well as the results of testing performed. This study was performed in general accordance with KEMRON's standard operation procedures and subsequent telephone and electronic mail conversations between KEMRON and AECOM.

2.0 MATERIAL RECEIPT AND CHARACTERIZATION

On June 10, 2020 and July 20, 2020 KEMRON received the following samples from the site:

- SED7C-DEW (0-18")
- SED7.5C-DEW (0-18")
- SEC7C-GTX (1)

Immediately following sample receipt, all materials were logged into KEMRON's sample tracking database and placed in secure, refrigerated storage maintained at a temperature of 4 degrees Celsius (^{o}C).

Prior to testing, any free liquid was decanted from the surface of the as-received samples and each material was thoroughly homogenized to ensure uniform materials for testing. KEMRON performed the following physical properties testing on the homogenized samples:

Parameter	**Method**
Moisture Content	ASTM D2216
Grain Size Distribution w/Hydrometer	ASTM D422
USCS Classification	ASTM D2487
Bulk Unit Weight	ASTM D7263
Paint Filter	EPA Method 9095

Results of the as-received characterization testing are presented in **Table 1**. Copies of the physical properties testing data sheets are included in **Appendix A**. Note that all analytical testing was directly subcontracted and managed by AECOM.

Review of the data in **Table 1** shows that all three site materials are classified as silts with sand. The results also indicate that the SED7C-DEW (0-18") material exhibited a bulk unit weight of 93.3 pounds per cubic foot (pcf), a moisture content of 78.79% and passed the paint filter test. The SED7.5C-DEW (0-18") material exhibited a bulk unit weight of 84.5 pounds per cubic foot (pcf), a moisture content of 114.58% and failed the paint filter test. The SED7C-GTX material exhibited a bulk unit weight of 94.8 pounds per cubic foot (pcf), a moisture content of 73.05% and failed the paint filter test.

(1) This sample was run for physical parameters only. The information was needed due to a shipping sample issue which resulted in generating a second sample for dewatering testing performed by others

AECOM
PEPCO BENNING ROAD TS
KEMRON PROJECT No. SH0746

TABLE 1

Untreated Material Characterization

Testing Parameter	Test Method	Unit	Untreated Material		
			SED7C-DEW	SED7.5E-DEW (0-18')	SED7C-GTX
Particle Size Distribution	ASTM D422				
Gravel		%	0.1	0.7	0.5
Sand		%	18.5	16.0	22.7
Silt		%	66.3	68.4	61.9
Clay		%	15.1	14.9	14.9
Sample Description [1]	ASTM D2487		Brown silt with sand	Grayish Brown silt with sand	Dark Olive Gray silt with sand
Sample Classification [2]	ASTM D2487		ML	ML	ML
Moisture Content	ASTM D2216				
Average ASTM Moisture Content		%	78.79	114.58	73.05
Average Percent Solids		%	55.93	46.62	57.79
Unit Weight	ASTM D7263				
Average Bulk Unit Weight		pcf	93.3	84.5	94.8
Paint Filter	EPA Method 9095		PASS	FAIL	FAIL

Notes:
(1)Sample color determined by the Munsell Soil Color Charts.
(2) Sample classification based on the Unified Classification System.
%= Percent
pcf = Pounds per cubic foot

In addition to physical properties testing, aliquots of the SED7C-DEW (0-18") and SED7.5C-DEW (0-18") materials were submitted to Eurofins Test America in Pittsburgh, PA for Total Polychlorinated Biphenyls (PCBs) as Aroclors by EPA Method 8082 and Total PCBs as Congeners by EPA Method 1668C. Note that the results for PCB analyses were sent to and furnished by AECOM.

3.0 EXPERIMENTAL MIXTURE EVALUATIONS

The primary applications of solidification / stabilization include 1) treatment of liquids and sludge for land disposal, 2) remediation of contaminated sites containing organic and inorganic contaminants, and 3) solidification of materials, which are physically unstable. To perform solidification treatment, common binding reagents or proprietary reagents are added to the untreated waste materials. Common binding agents may include materials like Portland cement, blast furnace slag, cement, or lime kiln dusts, fly ash and organophillic clays. For this project, Type I Portland cement, Lime Kiln Dust (LKD), Calciment™ and Zapzorb were selected for evaluation.

KEMRON prepared a total of 19 experimental mixtures utilizing the SED7.5C-DEW (0-18") site material and three experimental mixtures utilizing the SED7C-DEW (0-18") site material. These mixtures were prepared as small cup mixes in order to evaluate the potential effect that the additives may have on the site material, and to potentially identify appropriate addition rates capable of reducing free moisture without consuming large amounts of the site soils. The mixture design formulations are presented in **Table 2**. The mixtures were developed by placing an aliquot of the site material into a stainless-steel bowl. The reagent was added dry to the site material and blended by hand until visually homogeneous. Immediately following mixture development, the mixtures were placed and tamped into cylindrical molds for curing. Note that all reagent addition rates are calculated on a by-weight basis according to the amount of site material being treated. For example, for a mixture developed with the site material at a 2% Portland cement addition rate, 2 grams of Type I Portland cement was added dry to every 100 grams of the site material.

Physical observations of each mixture were recorded while mixing. Pocket Penetrometer testing was performed on each mixture after 24 hours and 4 days of curing. The physical observations and results of the pocket penetrometer testing is presented in **Table 2**. The results in **Table 2** indicates that none of the mixtures exhibited strength gain after 4 days of curing. The results also indicate that only the mixtures that utilized Zapzorb were observed to be soil like after mixing. The other mixtures were observed to be wet and had the consistency of pudding or soft serve ice cream.

Based on the results of the initial experimental mixtures, AECOM requested that KEMRON prepare mixtures EXP-014, EXP-015 and EXP-016 using a two-step process. KEMRON was also instructed to prepare three new mixtures utilizing the SED7.5C-DEW (0-18") site material, also using a two-step process. The mixtures utilized Zapzorb and Type I Portland cement and were prepared following previously mentioned protocols. The two-step process consisted of mixing the Type I Portland cement with the site material first and then adding the Zapzorb after one hour of curing. The mixture design formulations are presented in **Table 2**. Physical observations were recorded for each mixture while mixing and pocket penetrometer testing was performed after 24 hours, 4 days and 14 days of curing.

The results in **Table 2** indicate that the mixture utilizing addition rates of 0.5% Zapzorb and 3% Type I Portland cement exhibited a pocket penetrometer results of 0.25 tons per square foot

(tsf) after 14 days of curing. The results also indicate that the mixtures utilizing Zapzorb at addition rates of 0.5 and 1.0% combined with Type I Portland cement at a 15% addition rate, and the use of Type I Portland cement alone at a 15% addition rate exhibited a pocket penetrometer results of 0.5 tsf after 24 hours of curing.

Photographic Documentation of each phase of testing is included in **Appendix B**.

AECOM
PEPCO BENNING ROAD TS
SH0746

Table 2

Experimental Mixtures Observations

KEMRON Sample No.	Untreated Material	Reagent Type	Reagent Addition % by Wet Soil Wt.	Pocket Penetrometer (TSF) 24 hour	Pocket Penetrometer (TSF) 4 Day	Pocket Penetrometer (TSF) 14 Day	VOC Monitoring (ppm) 24 hour	Observations (after mixing)	Observations (after 24 hours of curing)
EXP-001	SED7.5E-DEW (0-18')	Type I Portland Cement	2	0	0		3.1	Wet; Like pudding	Moist; Like thick pudding
EXP-002	SED7.5E-DEW (0-18')	Type I Portland Cement	4	0	0		7.2	Wet; Like pudding	Slightly moist; Like soft clay
EXP-003	SED7.5E-DEW (0-18')	Type I Portland Cement	8	0	0		5.4	Wet; Like pudding	Slightly moist; Like stiff clay
EXP-004	SED7.5E-DEW (0-18')	Lime Kiln Dust	5	0	0		5.8	Wet; Like pudding	Moist; Like thick pudding
EXP-005	SED7.5E-DEW (0-18')	Lime Kiln Dust	7.5	0	0		3.8	Wet; Like soft serve ice cream	Moist; Like thick pudding
EXP-006	SED7.5E-DEW (0-18')	Lime Kiln Dust	15	0	0		4.4	Wet; Like soft serve ice cream	Slightly moist; Like soft clay
EXP-007	SED7.5E-DEW (0-18')	ZapZorb	0.5	0	0		3.2	Moist; Like soil	Slightly moist; Like soil
EXP-008	SED7.5E-DEW (0-18')	ZapZorb	1.5	0	0		3.0	Moist; Like soil	Slightly moist; Like soil
EXP-009	SED7.5E-DEW (0-18')	ZapZorb	3	0	0		2.8	Moist; Like soil	Dry; Like soil
EXP-010	SED7.5E-DEW (0-18')	Calciment	2	0	0		1.7	Wet; Like pudding	Moist; Like pudding
EXP-011	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	0.25	0	0		1.5	Wet; Like soft serve ice cream	Moist; Like soft serve ice cream
EXP-012	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	5 / 2	0	0			Wet; Like pudding	Moist; like soft clay
EXP-013	SED7.5E-DEW (0-18')	LKD/Type I Portland Cement	10 / 4	0	0			Wet; Like thick oatmeal	Moist; like soft clay
EXP-014	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 3	0	0			Moist; Like soil	Moist; Like soil
EXP-015	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	1 / 3	0	0			Moist; Like soil	Moist; Like soil
EXP-016	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 5	0	0			Moist; Like soil	Moist; Like soft clay
EXP-017	SED7.5E-DEW (0-18')	Calciment	5	0	0			Wet; Like pudding	Wet; Like pudding
EXP-018	SED7.5E-DEW (0-18')	Calciment	7.5	0	0			Wet; Like pudding	Wet; Like pudding
EXP-019	SED7.5E-DEW (0-18')	Calciment	10	0	0			Wet; Like pudding	Wet; Like pudding
EXP-014 (2 step)	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 3	0	0.25	0.25		Moist; Like soil	Moist; Like soil
EXP-015 (2 step)	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	1 / 3	0	0	0		Moist; Like soil	Moist; Like soil
EXP-016 (2 step)	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 5	0	0	0		Moist; Like soil	Moist; Like soft clay
EXP-020 (2 step)	SED7C-DEW	ZapZorb/Type I Portland Cement	0.5 / 3	0				Slightly Moist; Like soil, pass p.f	somewhat dry, like soil, pass p.f
EXP-021 (2 step)	SED7C-DEW	ZapZorb/Type I Portland Cement	1 / 3	0				Slightly Moist; Like soil, pass p.f	somewhat dry, like soil, pass p.f
EXP-022 (2 step)	SED7C-DEW	ZapZorb/Type I Portland Cement	0.5 / 5	0				Slightly Moist; Like soil, pass p.f	somewhat dry, clay like, pass p.f
EXP-023 (2 step)	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	0.5 / 15	0.5				Moist: like soil, fail p.f	
EXP-024 (2 step)	SED7.5E-DEW (0-18')	ZapZorb/Type I Portland Cement	1 / 15	0.5				Moist, like soil, pass p.f	
EXP-025 (2 step)	SED7.5E-DEW (0-18')	Type I Portland Cement	15	0.5				Wet: Clay like, fail p.f	

4.0 SOLIDIFICATION / STABILIZATION EVALUATIONS

Based on the results of the experimental mixture evaluations, KEMRON prepared a total of ten (10) solidification mixtures including five (5) mixtures using the SED7C-DEW (0-18") material and five (5) mixtures using the SED7.5C-DEW (0-18") material. The mixture design formulations are presented in **Table 3** and bench top mixture development sheets are included in **Appendix C**. The mixtures were developed using previously mentioned protocols. Mixtures utilizing a combination of Zapzorb and Type I Portland cement were prepared using the two-step process previously outlined.

Off-gas monitoring was measured for each mixture with a Minirae 3000 photoionization detector (PID) with an 11.8 electron volt (eV) lamp. The off gas was measured while mixing and after one hour of curing. The off-gas monitoring testing results are presented in **Table 3**. Table 3 indicates that the highest VOC off-gas measured was 4.5 ppm.

To evaluate the potential setting characteristics of each mixture, pocket penetrometer testing was performed after 1, 3, 5 and 7 days of curing, and shows that several of the mixtures exhibited some degree of strength gain. Specifically, the mixtures utilizing a 15% Type I Portland cement addition resulted in penetrometer strengths in excess of 4.5 tsf after three (3) days of curing. Additionally, the SED7C-DEW site soil treated with the two-step mixing of Zapzorb and Type I PC at addition rates of 0.5 and 10%, and 10% Type I Portland cement alone exhibited penetrometer strengths of 4.0 and 3.5 tsf respectively. These mixtures when applied to the SED7.5E-DEW site material did not exhibit the same strength gain with pocket penetrometer results of 2.75 tsf for each treated material at the 7-day cure time. The results of pocket penetrometer testing are included in **Table 3**.

At the 7-day cure interval, each solidified material was subjected to Paint Filter testing by EPA Method 9095. The results of the paint filter testing are also presented in **Table 3** and show that all the treated materials passed paint filter. Complete data sheets are included in **Appendix D**.

Based on the results of solidification/stabilization evaluations, KEMRON was instructed to submit mixtures 0746-009 and 0746-010 to Test America in Pittsburgh, PA for Total Polychlorinated Biphenyls (PCBs) as Aroclors by EPA Method 8082 and TCLP PCBs as Aroclors by EPA Method 1311/8082. KEMRON was not provided the analytical results of the treated materials.

AECOM
PEPCO BENNING ROAD TS
KEMRON PROJECT No. SH0746

TABLE 3

Reagent Drying Evaluations
Mixture Designs, VOC Monitoring, Pocket Penotrometer and Paint Filter Testing

KEMRON Sample Number	Untreated Material Type	Reagent Type	Reagent Addition % by Wet Soil wt.	VOC Monitoring (ppm)		Pocket Penetrometer (tsf)				Cure Day	Paint Filter Testing
				At Mixing	1 hour	1 Day	3 Day	5 Day	7 Day		Pass/Fail
0746-001	SED7C-DEW	Zapzorb	0.5	0.0	0.2	0.00	0.00	0.00	0.00	7	Pass
0746-002 (2 step)	SED7C-DEW	Zapzorb/Type I Portland Cement	0.5/10.0	0.7	0.7	1.00	2.50	3.50	4.00	7	Pass
0746-003	SED7C-DEW	Type I Portland Cement	10.0	0.2	2.0	0.50	2.00	3.00	3.50	7	Pass
0746-004	SED7C-DEW	Type I Portland Cement	15.0	1.4	1.6	2.00	>4.5	>4.5	>4.5	7	Pass
0746-005	SED7.5E-DEW	Zapzorb	0.5	0.4	0.2	0.00	0.00	0.00	0.00	7	Pass
0746-006 (2 step)	SED7.5E-DEW	Zapzorb/Type I Portland Cement	0.5/10.0	0.0	0.5	1.50	1.50	1.75	2.75	7	Pass
0746-007	SED7.5E-DEW	Type I Portland Cement	10.0	0.0	0.6	1.00	2.00	2.50	2.75	7	Pass
0746-008	SED7.5E-DEW	Type I Portland Cement	15.0	0.0	0.7	2.50	>4.5	>4.5	>4.5	7	Pass
0746-009	SED7C-DEW	Type I Portland Cement	7.0	0.8	4.5	0.00	0.25	0.25	0.25	7	Pass
0746-010 (2 step)	SED7.5E-DEW	Zapzorb/Type I Portland Cement	0.5/5	0.1	4.4	0.00	0.00	0.00	0.25	7	Pass

Notes:
% = Percent
Wt= Weight

5.0 CONCLUSIONS


KEMRON conducted solidification treatment applications to evaluate potential reagents to improve the physical characteristics of the site materials. Initially, experimental mixtures were prepared with the SED7C-DEW (0-18") and SED7.5C-DEW (0-18") site materials, to evaluate various reagents at various addition rates. The reagents included Type I Portland cement, Zapzorb, Calciment™ and Lime Kiln Dust. The results indicated that mixtures utilizing Zapzorb and Type I Portland cement exhibited more of a soil like material and the most strength gain.

Solidification evaluations were then conducted on the site materials and included Type I Portland cement and Zapzorb, which were individually added dry to the site materials. The results of testing conducted on the site materials treated with Type I Portland cement showed that a 15% addition rate of dry Portland cement exhibited the highest pocket penetrometer results of greater than 4.5 tsf after 7 days of curing. The results also showed that all solidification mixtures passed paint filter testing.

This report should be reviewed in its entirety including all attachments prior to making decisions concerning a remedial approach. This study is intended to suggest what will occur in the field but does not guarantee the same results.

Appendix A:
Physical Properties Testing Data Sheets

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.1	0.1	1.2	17.2	66.3	15.1

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1.5	100.0		
1.0	100.0		
0.75	100.0		
0.5	100.0		
0.375	100.0		
#4	99.9		
#10	99.8		
#20	99.4		
#40	98.6		
#60	97.6		
#140	89.0		
#200	81.4		
0.0313 mm.	60.3		
0.0203 mm.	51.9		
0.0120 mm.	43.7		
0.0087 mm.	37.2		
0.0063 mm.	31.2		
0.0032 mm.	20.2		
0.0014 mm.	12.3		

* (no specification provided)

Soil Description

Brown silt with sand

Atterberg Limits

PL= LL= PI=

Coefficients

D_{90}= 0.1121 D_{85}= 0.0874 D_{60}= 0.0309
D_{50}= 0.0180 D_{30}= 0.0059 D_{15}= 0.0020
D_{10}= C_u= C_c=

Classification

USCS= ML AASHTO= A-4(0)

Remarks

Sample Number: SED7C-DEW

Date: 06/23/20

KEMRON Environmental Services Inc.
Atlanta, Georgia

Client: AECOM
Project: Pepco Benning Road TS
Project No: SH0746 **Figure** E119

Tested By: FA **Checked By:** TNB

MOISTURE CONTENT DETERMINATION

REPORT FORM
ASTM D 2216

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7C-DEW
TESTING DATE:	06/22/20
TESTED BY:	FA
TRACKING CODE:	E119

MOISTURE CONTENT (Dry & Wet Basis)						
1. MOISTURE TIN NO.	A		B		C	
2. WT MOISTURE TIN (tare weight)	1.2791	g	1.2657	g	1.2697	g
3. WT WET SOIL + TARE	18.8431	g	16.9404	g	18.0554	g
4. WT DRY SOIL + TARE	11.1047	g	10.0616	g	10.6256	g
5. WT WATER, Ww	7.7384	g	6.8788	g	7.4298	g
6. WT DRY SOIL, Ws	9.8256	g	8.7959	g	9.3559	g
7. ASTM MOISTURE CONTENT	78.76	%	78.20	%	79.41	%
8. PERCENT SOLIDS	55.94	%	56.12	%	55.74	%
9. AVERAGE ASTM MOISTURE CONTENT	78.79	%				
10. AVERAGE PERCENT SOLIDS	55.93	%				

UNIT WEIGHT DETERMINATION

DATA SHEET
ASTM D7263

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7C-DEW
TESTING DATE:	06/22/20
TESTED BY:	FA
TRACKING CODE:	E119

UNIT WEIGHT (DENSITY)						
1. SAMPLE NO.	A		B		C	
2. WT OF MOLD (tare weight)	18.17	g	18.16	g	18.17	g
3. WT OF MOLD + SOIL	326.09	g	325.91	g	325.46	g
4. WT OF WET SOIL, W	307.92	g	307.75	g	307.29	g
5. DIAMETER OF SPECIMEN, D	2.00	in	2.00	in	2.00	in
6. HEIGHT OF SPECIMEN, H	4.00	in	4.00	in	4.00	in
7. VOLUME OF SPECIMEN	12.57	in^3	12.57	in^3	12.57	in^3
8. BULK UNIT WEIGHT	93.3	pcf	93.3	pcf	93.2	pcf
9. BULK SPECIFIC GRAVITY	1.5		1.5		1.5	
10. AVERAGE BULK UNIT WEIGHT	93.3	pcf				
11. AVERAGE BULK SPECIFIC GRAVITY	1.5					

PAINT FILTER TEST


SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	6/22/2020
PROJECT No.:	SH0746	TESTED BY:	FA
SAMPLE No.:	SED7C-DEW (0-18")	TRACKING CODE:	E119
TESTING METHOD:	EPA Method 9095		

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.7	1.6	3.7	10.7	68.4	14.9

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1.5	100.0		
1.0	100.0		
0.75	100.0		
0.5	100.0		
0.375	99.7		
#4	99.3		
#10	97.7		
#20	96.1		
#40	94.0		
#60	91.6		
#140	86.4		
#200	83.3		
0.0321 mm.	66.4		
0.0206 mm.	61.0		
0.0122 mm.	50.3		
0.0088 mm.	42.2		
0.0064 mm.	34.1		
0.0033 mm.	20.7		
0.0014 mm.	12.0		

* (no specification provided)

Soil Description

Grayish Brown silt with sand

Atterberg Limits

PL= LL= PI=

Coefficients

D_{90}= 0.1885 D_{85}= 0.0875 D_{60}= 0.0193
D_{50}= 0.0121 D_{30}= 0.0053 D_{15}= 0.0020
D_{10}= C_u= C_c=

Classification

USCS= ML AASHTO=

Remarks

Sample Number: SED7.5E-DEW (0-18")

Date: 6/16/20

KEMRON Environmental Services Inc.
Atlanta, Georgia

Client: AECOM
Project: Pepco Benning Road TS
Project No: SH0746 **Figure** E120

Tested By: JBA **Checked By:** TBA

MOISTURE CONTENT DETERMINATION

REPORT FORM
ASTM D 2216

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7.5E-DEW (0-18")
TESTING DATE:	06/12/20
TESTED BY:	FA
TRACKING CODE:	E120

MOISTURE CONTENT (Dry & Wet Basis)					
1. MOISTURE TIN NO.	A		B		C	
2. WT MOISTURE TIN (tare weight)	1.2787	g	1.2789	g	1.2824	g
3. WT WET SOIL + TARE	15.6715	g	15.0745	g	16.1449	g
4. WT DRY SOIL + TARE	7.8233	g	7.7771	g	8.3091	g
5. WT WATER, Ww	7.8482	g	7.2974	g	7.8358	g
6. WT DRY SOIL, Ws	6.5446	g	6.4982	g	7.0267	g
7. ASTM MOISTURE CONTENT	119.92	%	112.30	%	111.51	%
8. PERCENT SOLIDS	45.47	%	47.10	%	47.28	%
9. AVERAGE ASTM MOISTURE CONTENT	114.58	%				
10. AVERAGE PERCENT SOLIDS	46.62	%				

UNIT WEIGHT DETERMINATION

DATA SHEET
ASTM D7263

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7.5E-DEW (0-18")
TESTING DATE:	06/12/20
TESTED BY:	FA
TRACKING CODE:	E120

UNIT WEIGHT (DENSITY)						
1. SAMPLE NO.	A		B		C	
2. WT OF MOLD (tare weight)	18.16	g	18.16	g	18.14	g
3. WT OF MOLD + SOIL	296.61	g	297.02	g	297.13	g
4. WT OF WET SOIL, W	278.45	g	278.86	g	278.99	g
5. DIAMETER OF SPECIMEN, D	2.00	in	2.00	in	2.00	in
6. HEIGHT OF SPECIMEN, H	4.00	in	4.00	in	4.00	in
7. VOLUME OF SPECIMEN	12.57	in^3	12.57	in^3	12.57	in^3
8. BULK UNIT WEIGHT	84.4	pcf	84.5	pcf	84.6	pcf
9. BULK SPECIFIC GRAVITY	1.4		1.4		1.4	
10. AVERAGE BULK UNIT WEIGHT	84.5	pcf				
11. AVERAGE BULK SPECIFIC GRAVITY	1.4					

PAINT FILTER TEST


SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	6/18/2020
PROJECT No.:	SH0746	TESTED BY:	fa
SAMPLE No.:	SED7.5E-DEW (0-18")	TRACKING CODE:	E120
TESTING METHOD:	EPA Method 9095		

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.05	**g**
RESULTS (PASS / FAIL) *	FAIL	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.5	0.7	1.3	20.7	61.9	14.9

SIEVE SIZE	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
1.5	100.0		
1.0	100.0		
0.75	100.0		
0.5	99.8		
0.375	99.7		
#4	99.5		
#10	98.8		
#20	98.0		
#40	97.5		
#60	96.4		
#140	86.0		
#200	76.8		
0.0303 mm.	53.2		
0.0196 mm.	47.8		
0.0116 mm.	40.5		
0.0085 mm.	32.4		
0.0061 mm.	27.9		
0.0031 mm.	20.1		
0.0013 mm.	9.8		

* (no specification provided)

Soil Description

Silt with Sand Dark Olive Gray

Atterberg Limits

PL= LL= PI=

Coefficients

D_{90}= 0.1301 D_{85}= 0.1017 D_{60}= 0.0415
D_{50}= 0.0243 D_{30}= 0.0074 D_{15}= 0.0020
D_{10}= 0.0013 C_u= 31.05 C_c= 0.98

Classification

USCS= ML AASHTO= A-4(0)

Remarks

Sample Number: SED7C-GTX

Date: 7/27/20

KEMRON Environmental Services Inc.
Atlanta, Georgia

Client: AECOM
Project: Pepco Benning Road TS
Project No: SH0746 **Figure** E121

Tested By: JBA **Checked By:** TNB

MOISTURE CONTENT DETERMINATION

REPORT FORM
ASTM D 2216

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7C-GTX
TESTING DATE:	07/21/20
TESTED BY:	JBA
TRACKING CODE:	E121

MOISTURE CONTENT (Dry & Wet Basis)					
1. MOISTURE TIN NO.	A		B		C	
2. WT MOISTURE TIN (tare weight)	1.2705	g	1.2630	g	1.2732	g
3. WT WET SOIL + TARE	26.6225	g	19.0322	g	21.6825	g
4. WT DRY SOIL + TARE	15.8789	g	11.6048	g	13.0166	g
5. WT WATER, Ww	10.7436	g	7.4274	g	8.6659	g
6. WT DRY SOIL, Ws	14.6084	g	10.3418	g	11.7434	g
7. ASTM MOISTURE CONTENT	73.54	%	71.82	%	73.79	%
8. PERCENT SOLIDS	57.62	%	58.20	%	57.54	%
9. AVERAGE ASTM MOISTURE CONTENT	73.05	%				
10. AVERAGE PERCENT SOLIDS	57.79	%				

UNIT WEIGHT DETERMINATION

DATA SHEET
ASTM D7263

PROJECT:	Pepco Benning Road TS
PROJECT No.:	SH0746
SAMPLE No.:	SED7C-GTX
TESTING DATE:	07/21/20
TESTED BY:	FA
TRACKING CODE:	E121

UNIT WEIGHT (DENSITY)						
1. SAMPLE NO.	A		B		C	
2. WT OF MOLD (tare weight)	18.15	g	18.16	g	18.16	g
3. WT OF MOLD + SOIL	331.65	g	328.55	g	332.11	g
4. WT OF WET SOIL, W	313.50	g	310.39	g	313.95	g
5. DIAMETER OF SPECIMEN, D	2.00	in	2.00	in	2.00	in
6. HEIGHT OF SPECIMEN, H	4.00	in	4.00	in	4.00	in
7. VOLUME OF SPECIMEN	12.57	in^3	12.57	in^3	12.57	in^3
8. BULK UNIT WEIGHT	95.0	pcf	94.1	pcf	95.2	pcf
9. BULK SPECIFIC GRAVITY	1.5		1.5		1.5	
10. AVERAGE BULK UNIT WEIGHT	94.8	pcf				
11. AVERAGE BULK SPECIFIC GRAVITY	1.5					

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	7/27/2020
PROJECT No.:	SH0746	TESTED BY:	FA
SAMPLE No.:	SED7C-GTX	TRACKING CODE:	E121
TESTING METHOD:	EPA Method 9095		

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.02	**g**
RESULTS (PASS / FAIL) *	FAIL	


* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

Appendix B:
Experimental Mixture Evaluations
Photographic Log

AECOM
Pepco Benning Road
Treatability Study
Kemron Project No. SH0746

KEMRON
ENVIRONMENTAL SERVICES

Experimental Mixtures Observations



2% Type I Portland Cement
After mixing: Wet; Like pudding



4% Type I Portland Cement
After mixing: Wet; Like pudding




8% Type I Portland Cement
After mixing: Wet; Like pudding



5% Lime Kiln Dust
After mixing: Wet; Like pudding



7.5% Lime Kiln Dust
After mixing: Wet; Like soft serve ice cream



15% Lime Kiln Dust
After mixing: Wet; Like soft serve ice cream



0.5% ZapZorb
After mixing: Moist; Like soil



1.5% ZapZorb
After mixing: Moist; Like soil




3% ZapZorb
After mixing: Moist; Like soil




2% Calciment
After mixing: Wet; Like pudding




0.25% ZapZorb
After mixing: Wet; soft serve ice cream




5% LKD/ 2% Type I Portland Cement
After mixing: Wet; like pudding




10% LKD/ 4% Type I Portland Cement
After mixing: Wet; like thick oatmeal



0.5% ZapZorb/ 3% Type I Portland Cement
After mixing: Moist; like soil



1% ZapZorb/ 3% Type I Portland Cement
After mixing: Moist; like soil



0.5% ZapZorb/ 5% Type I Portland Cement
After mixing: Moist; like soil



5% Calciment
After mixing: Wet; like pudding




7.5% Calciment
After mixing: Wet; like pudding




10% Calciment
After mixing: Wet; like pudding

KEMRON
ENVIRONMENTAL SERVICES


Two Step Mixing Process




3% Type I Portland Cement added and then 0.5% ZapZorb added an hour later
After mixing: Moist; like soil




After 24 hours: Moist; like soil; pocket penetrometer 0.25 tons per square foot after 4 days of curing





3% Type I Portland Cement added and then 1% ZapZorb added an hour later
After mixing: Moist; like soil

After 24 hours: Moist; like soil; pocket penetrometer 0.0 tons per square foot after 4 days of curing



5% Type I Portland Cement added and then 0.5% ZapZorb added an hour later
After mixing: Moist; like soil



After 24 hours: Moist; like soil; pocket penetrometer 0.0 tons per square foot after 4 days of curing

Appendix C:
Solidification/Stabilization Evaluations
Mixture Development Sheets

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-001
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7C-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Zapzorb #1141	0.50 %	5.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

5 grams of Zapzorb was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0	0.2			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	0.00	0.00	0.00	0.00	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-002
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7C-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Zapzorb #1141	0.50 %	5.0 g
Type I Portland Cement #1150	10.00 %	100.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

100 grams of Type I Portland cement was added to the site material. After one hour of curing, 5 grams of Zapzorb was added to the Portland cement/site material mixture.

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.7	0.7			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	1.00	2.50	3.50	4.00	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-003
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7C-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	10.00 %	100.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

100 grams of Type I Portland cement was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.2	2.0			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	0.50	2.00	3.00	3.50	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-004
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7C-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	15.00 %	150.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

150 grams of Type I Portland cement was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	1.4	1.6			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	2.00	>4.5	>4.5	>4.5	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-005
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7.5E-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Zapzorb #1141	0.50 %	5.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

5 grams of Zapzorb was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.4	0.2			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	0.00	0.00	0.00	0.00	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-006
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7.5E-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Zapzorb #1141	0.50 %	5.0 g
Type I Portland Cement #1150	10.00 %	100.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

100 grams of Type I Portland cement was added to the site material. After one hour of curing, 5 grams of Zapzorb was added to the Portland cement/site material mixture.

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0	0.5			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	1.50	1.50	1.75	2.75	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-007
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7.5E-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	10.00 %	100.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

100 grams of Type I Portland cement was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.0	0.6			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	1.00	2.00	2.50	2.75	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-008
MIXING DATE:	15-Sep-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7.5E-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	15.00 %	150.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

150 grams of Type I Portland cement was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.0	0.7			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	2.50	>4.5	>4.5	>4.5	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-009
MIXING DATE:	7-Oct-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7C-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	7.00 %	70.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

70 grams of Type I Portland cement was added to the site material

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.8	4.5			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	0.00	0.25	0.25	0.25	

MIX DEVELOPMENT DATA SHEET

PROJECT:	Pepco Benning Road TS	MIX No.	
PROJECT No.:	SH0746		0746-010
MIXING DATE:	7-Oct-20	MIXED BY:	JA

UNTREATED MATERIAL TYPE		SED7.5E-DEW
WEIGHT OF UNTREATED MATERIAL		1,000 g
REAGENT TYPE AND LOT NUMBER	ADDITION RATE	WEIGHT
Type I Portland Cement	5.00 %	50.0 g
Zapsorb	0.50 %	5.0 g
	%	0.0 g
	%	0.0 g
	%	0.0 g
Water Addition	%	0.0 g

OBSERVATIONS / NOTES

50 grams of Type I Portland cement was added to the site material. After one hour of curing, 5 grams of Zapzorb was added to the Portland cement/site material mixture.

MONITORING ACTIVITIES

MONITORING ACTIVITIES	TIME PERIOD				
	mixing	1 hour			
MAXIMUM PID (ppm)	0.1	4.4			
Notes / Observations:					

PENETROMETER ANALYSES

CURE TIME (Days)	1	3	5	7	
PENETROMETER (tons/ft^2)	0.00	0.00	0.00	0.25	

Appendix D:
Paint Filter Testing Data Sheets

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-001	TRACKING CODE:	E261
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-002	TRACKING CODE:	E262
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-003	TRACKING CODE:	E263
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-004	TRACKING CODE:	E264
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-005	TRACKING CODE:	E265
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-006	TRACKING CODE:	E266
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-007	TRACKING CODE:	E267
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	9/23/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-008	TRACKING CODE:	E268
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	10/10/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-009	TRACKING CODE:	E269
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

PAINT FILTER TEST

SUMMARY OF RESULTS

PROJECT:	Pepco Benning Road TS	TESTING DATE:	10/10/2020
PROJECT No.:	SH0746	TESTED BY:	JBA
SAMPLE No.:	0746-010	TRACKING CODE:	E270
TESTING METHOD:			

TESTING PARAMETER AND RESULTS		
QUANTITY OF MATERIAL	100.00	**g**
LENGTH OF TEST	5.0	**min.**
QUANTITY OF LIQUID	0.00	**g**
RESULTS (PASS / FAIL) *	PASS	

* In accordance with EPA Method 9095, if any liquid from the test material collects after 5 minutes of testing, the material is deemed to contain free liquids, and therefore has failed the paint filter test.

An Exelon Company

Appendix H

IAI Sediment Treatability Testing Report

INFRASTRUCTURE ALTERNATIVES, INC.

July 15, 2020

Ms. Kristine Carbonneau
AECOM
kris.carbonneau@aecom.com

RE: BENNING ROAD FACILITY TREATABILITY REPORT

Dear Ms. Kristine Carbonneau:

Infrastructure Alternatives, Inc. (IAI) was contracted by AECOM to perform treatability testing on sediment collected from Waterside Investigation Area at PEPCO's Benning Road Facility in Washington, DC. Objectives of the testing included identifying a single chemical conditioning program to be used for dewatering sediment in geotextile tubes and developing parameters to help provide information on scalability.

Enclosed, please find the subject report in its entirety. We have closely evaluated the report objectives and corresponding deliverables, and presented our findings in clear and concise format.

Throughout the testing process, IAI is pleased to have developed a quality relationship with AECOM and looks forward to the opportunity of partnering again in the future. Please feel free to contact me with any questions about the report.

Sincerely,

INFRASTRUCTURE ALTERNATIVES, INC.

Connor McNeely,
Chemist

Enclosed: Treatability Report

Benning Road Facility Treatability Report

INTRODUCTION

Infrastructure Alternatives, Inc. (IAI) was contracted by AECOM to perform treatability testing on sediment from the Waterside Investigation Area at PEPCO's Benning Road Facility in Washington, DC.

Objectives of the testing included:

- Evaluating dewatering efficacy of chemically-conditioned sediment with geotextile tubes
- Developing a dataset of physical and chemical dewatering parameters to help provide scale-up information
- Assisting in the generation of analytical data for determination of final disposition options
- Monitoring air emissions during various phases of testing

SAMPLE PREPARATION

On June 11, 2020, three five-gallon buckets of sediment and two five-gallons jugs of surface water were received in good condition at IAI's Rockford, Michigan laboratory. Three additional five-gallon jugs of surface water were delivered to IAI the following day. One five-gallon bucket of sediment and one five-gallon jug of surface water were lost or damaged during the shipping process and were not delivered to IAI. Photos of the material as received, as well as photos taken throughout the testing process, can be found in Attachment A: Photolog. Upon opening the buckets of sediment, it was found that each bucket contained about three to five inches of water above the sediment settling line. In an effort to provide the most accurate representation of in-situ solids content, top-water was removed prior to sediment homogenization, leaving less than one inch of top-water. During the homogenization process in which a drill and paint mixer were used to thoroughly mix the material, observations were made for material characteristics such as odor, consistency, and color. These findings can be seen in Table 1.

Table 1: Observations of Samples

Sample Location	Odor	Consistency	Color
SED 7C-GTX	none	thick sludge	light brown/gray
SED 7.5E-GTX	none	thick sludge, twigs	brown/gray

From each sample location, an aliquot of homogenized in-situ sediment was collected and analyzed for solids content and density. An outside laboratory, Prein & Newhoff, was utilized for sediment analysis during the treatability project. The results of the in-situ solids content and density analyses can be seen in Table 2.

Table 2: In-Situ Solids Content and Density Data

Sample Location	Solids Content (%)	Density (lbs/Gal)
SED 7C-GTX	40.0	11.2
SED 7.5E-GTX	37.9[a]	10.8

Using data from Table 2, slurries to be used for jar testing and bench-scale testing were prepared by mixing sediment with the provided surface water. A mixing ratio was calculated with intent to create slurries with average solids content of approximately 10%, similar to that which is typically produced during hydraulic dredging operations. For both sample locations, an aliquot of slurry was collected and analyzed for solids content. The volumes of surface water and in-situ sediment used to create the slurries, along with the solids content of the slurries, can be found in Table 3.

Table 3: Slurry Mixing Ratio and Solids Content Data

Sample Location	Surface Water Added (L)	Sediment Added (L)	Solids Content (%)
SED 7C-GTX	6	2	9.61
SED 7.5E-GTX	7	2	9.45

[a] Second analysis being reported; first result of 45.5% likely not representative as described in Recommendations and Discussion section.

JAR TESTING

Slurries from each sample location were then used for jar testing to evaluate a range of chemical conditioning programs. Flocculants varying in charge, structure, and molecular weight were added via syringe to pre-determined aliquots of slurry samples (approximately 100 mL) for evaluation. After addition of a dewatering agent, aliquots were sufficiently mixed by pouring from one jar to another. Upon mixing, observations were recorded for qualities such as floc appearance, water release, and water clarity. Observations of the jar tests can be found in Attachment B: Jar Testing Log Sheet. Unless otherwise specified, all dewatering agents throughout the treatability testing were made down to a concentration of 0.5% (product) by volume using a graduated cylinder, distilled water, syringe, and stir bar.

BENCH-SCALE GEOTEXTILE TUBE FEASABILITY TESTING

Bench-scale testing was then performed to evaluate the top-performing conditioning program for facilitating dewatering through geotextile tube fabric. For bench-scale testing, 500 mL aliquots of slurry from both sample locations were conditioned with Aqua Hawk 7840 using a dosage of approximately 2.70 lbs/DT (pounds of neat polymer product used per dry ton of material), and separately poured over individual 100 in^2 pieces of geotextile tube fabric, allowing for solids to be captured on the fabric. Filter cake samples from each bench-scale test were collected 1 minute, 15 minutes, and 24 hours after pouring, and analyzed for solids content. Data from the solids content analyses can be seen in Table 4.

Table 4: Bench-Scale Solids Content Data

Sample Location	Slurry Solids Content (%)	1 Minute Solids Content (%)	15 Minute Solids Content (%)	24 Hour Solids Content (%)
SED 7C-GTX	9.61	34.0	35.9	41.6
SED 7.5E-GTX	9.45	27.4	27.3	34.7

With evidence that the selected conditioning program was able to facilitate successful dewatering through geotextile tube fabric on a bench-scale level, the large-scale geotextile tube feasibility study was able to be started.

LARGE-SCALE GEOTEXTILE TUBE FEASABILITY TESTING

Using mixing ratios found in Table 3, approximately 50 L of slurry was made using surface water and sediment. Aliquots of slurry from both sample locations were collected and analyzed for solids content. The volumes of surface water and in-situ sediment used to create the slurry, along with the solids content of the slurry, can be found in Table 5. Although the slurry solids content values are above10%, they are both still within range of slurry typically produced by hydraulic dredging.

Table 5: GTDT Slurry Mixing Ratio and Solids Content Results

Sample Location	Surface Water Added (L)	Sediment Added (L)	Slurry Solids Content (%)
SED 7C-GTX	36	12	15.7
SED 7.5E-GTX	39	11	12.7

Following solids content analysis, the selected conditioning program was applied to each bucket of slurry and allowed to sufficiently mix by pouring the slurry from one bucket to another. The buckets of conditioned slurry were then poured into a pillow-sized geotextile tube and allowed to dewater. Filtrate from the geotextile tube dewatering test (GTDT) was monitored for 24 hours, and its turbidity was analyzed during the following time intervals: 0-1 minute, 1-10 minutes, 10-60 minutes, and 1-24 hours. GTDT filter cake samples were collected 24 hours, 48 hours, 96 hours, and 7 days from the start of the GTDT and analyzed for solids content. GTDT data can be seen in Attachment C: GTDT Log Sheets. Filter cake samples were collected from different locations of the filter cake, and each cake sample was comprised of the entire vertical column of cake at that spot (i.e. material was not scooped from the surface). At the end of seven days, a paint filter test (EPA SW 846 Method 9095B) was performed on filter cake from each pillow test. Results from the GTDT filter cake solids content analyses, as well as paint filter results, can be found in Table 6.

Table 6: GTDT Filter Cake Solids Content and Paint Filter Results

Sample Location	24 Hour Solids Content (%)	48 Hour Solids Content (%)	96 Hour Solids Content (%)	7 Day Solids Content (%)	7 Day Paint Filter Test (Pass/Fail)
SED 7C-GTX	47.0	47.2	48.8	50.1	Pass
SED 7.5E-GTX	39.5	48.3	38.5	41.7	Pass

AIR MONITORING

Air emissions monitoring for polychlorinated biphenyls (PCBs) was performed during the geotextile feasibility testing. First, ambient air conditions were monitored prior to GTDT performance. Next, air conditions adjacent to individual GTDTs were monitored beginning just after each individual GTDT was started. In each case, a small pump was used to filter air through a cartridge for eight hours at a rate of 0.21 L/min before the cartridge was capped and shipped to ALS Environmental for analysis. Results from the air monitoring can be found in Table 7.

Table 7: Air Monitoring Data

Sample Location	SED 7C-GTX	SED 7.5E-GTX	Background
PCB Concentration	non-detect	non-detect	non-detect

RECOMMENDATIONS AND DISCUSSION

Evaluations indicate this material can be effectively dewatered via geotextile tubes with the use of Aqua Hawk 7840, a medium-high molecular weight polymer with medium cationic charge, at a dosage of approximately 2.70 lbs/DT (pounds of neat polymer product used per dry ton of material).

Data from bench-scale testing originally suggested material from SED 7.5E-GTX did not dewater as well as material from SED 7C-GTX when using in-situ solids content as a reference point. In an attempt to counter this, polymer dosage was slightly increased for the large-scale testing of SED7.5E-GTX. During jar testing and bench-scale testing, a dosage of approximately 2.70 lbs/DT was used to condition material from both sample locations. For the large-scale pillow testing, a dosage of 3.09 lbs/DT was applied to material from SED 7.5E-GTX, while a dosage of 2.71 lbs/DT was applied to material from SED 7C-GTX. In both of the pillow tests, filter cake solids content increased by two to three percent from 24 hours to seven days (viewing the 48 hour solids content value from SED 7.5E-GTX as an outlier). Similarly, solids content increased by about seven percent for both sample locations from the one minute mark to the 24 hour mark during the bench-scale testing. It was then questioned why material from SED 7C-GTX surpassed in-situ solids content values during bench-scale and large-scale testing, but material from SED 7.5E-GTX did not. A second in-situ sample from SED 7.5E-GTX was then analyzed for solids content. This second sample was found to have a solids content value of 37.9%, down from the original value of 45.5%. By acknowledging the second in-situ solids content value for SED 7.5E-GTX, data then suggests material from both sample

locations behave similarly. It is reasonable to believe that the increased polymer dosage for SED 7.5E-GTX was not necessary, and that a dosage of 2.70 lbs/DT works well to effectively dewater material from both sample locations via geotextile tubes.

It is believed that large-scale pillow tests provide valuable information on the performance potential of full-scale operations. However, there are many variables (operational techniques and procedures, climate, geotextile tube surface area to volume ratio, partially representative sediment samples, etc.) that cannot be replicated in a laboratory setting. While it is believed that in-situ solids content can be achieved through full-scale dewatering operations, an accurate timeline for achieving this cannot be provided.

Chemical dosages were calculated using Equation 1.

Equation 1:

$$\frac{\text{Lbs.}}{\text{Dry Ton}} = \frac{(2000\ \text{lbs./ton})(\text{X vol. added})(\text{X \% Dilution})(\text{X SG})}{(\text{Y vol.})(\text{Y \% Solids})(\text{Y SG})}$$

In this equation, Y represents the slurry, X represents the dewatering agent added to the slurry, and SG stands for specific gravity. Specific gravity of dilute coagulants and polymers is typically very close to 1.00, and is thus ignored.

The specific gravity of a slurry was calculated by taking the in-situ specific gravity value and accounting for the slurry dilution ratios found in Table 3. Specific gravity values of slurry samples were calculated using Equation 2.


Equation 2:

$$\text{Slurry SG} = 1 + (\text{InSitu SG} - 1) * \left(\frac{\text{InSitu Sediment Vol. Added}}{\text{Surface Water + InSitu Sediment Vol. Added}} \right)$$

Attached, please find:

- Attachment A: Photolog
- Attachment B: Jar Testing Log Sheets
- Attachment C: GTDT Log Sheets
- Attachment D: Lab Reports
- Attachment E: Geotextile Fabric Specifications
- Attachment F: Safety Data Sheet


ATTACHMENT A: PHOTO LOG




Surface Water Containers as Recieved




Sediment Sample Bucket as Recieved




SED 7.5E-GTX Undistrurbed




SED 7C-GTX Undisturbed




SED 7C-GTX Sediment Prior to Decant




SED 7.5E-GTX Sediment After Decant




SED 7C-GTX Jar Test



SED 7.5E-GTX Jar Test



SED 7C-GTX Jar Test



SED 7.5E-GTX Jar Test




SED 7C-GTX Bench-Scale Test: Initial Pour




SED 7C-GTX Bench-Scale Test: 1 Minute



SED 7C-GTX Bench-Scale Test: 15 Minutes



SED 7C-GTX Bench-Scale Test: 24 Hours



SED 7.5E-GTX Bench-Scale Test: Initial Pour



SED 7.5E-GTX Bench-Scale Test: 1 Minute




SED 7.5E-GTX Bench-Scale Test: 15 Minutes




SED 7.5E-GTX Bench-Scale Test: 24 Hours




Conditioned SED 7C-GTX Slurry



SED 7C-GTX Pillow Test




SED 7C-GTX Pillow Test Filtrate



Air Monitoring Pump and Filter



SED 7.5E-GTX Pillow Test



SED 7.5E-GTX Pillow Test Filtrate



SED 7C-GTX Filter Cake Sample Collection




SED 7.5E-GTX Filter Cake Sample




SED 7C-GTX Filter Cake



SED 7.5E-GTX Filter Cake



SED 7C-GTX Paint Filter Test



SED 7.5E-GTX Paint Filter Test

ATTACHMENT B: JAR TESTING LOG SHEETS

INFRASTRUCTURE ALTERNATIVES, INC.

Project ID: Benning Road Facility
Location: SED-7C-GTX

Date: 6-16-2020
Analyst: Conner

Jar #	Conditioning Product(s)	Dose (mL)	Rated 5-1, Best-Worst: Floc Appearance	Water Clarity	Water Release	Comments
	AH 7840	4	5	4	5	
	AH 7840	3.5	5	4	5	possible clay fines
	AH 7840	3	5	4	5	
	AH 7267 + AH 7840	1, 3	5	5	5	
	AH 7267 + AH 7840	1, 2	5	5	5	good
	AH 7337 + AH 7840	0.5, 2	4	4/5	4	sloppy
	AH 7337 + AH 7840	1, 1.5	3	4	3	
	AH 7387 + AH 7840	1, 1.5	4	5	4	good
	AH 7840	2.5	5	4	4/5	COAG NOT NEEDED
	AH 7840	2	3	3	3	very sloppy
	AH 7850	2	3	2	2	
	AH 7810	2.5	4	3	3	
	AH 7880	2.5	5	4	4	

Slurry % solids: 9.61%

100 mL aliquots of slurry used for each jar test

Conditioning products diluted by factor of 200 unless otherwise specified

INFRASTRUCTURE ALTERNATIVES, INC.

Project ID: Benning Road Facility
Location: SED-75E-GTX

Date: 6-16-2020
Analyst: Connor

			Rated 5-1, Best-Worst			
Jar #	Conditioning Product(s)	Dose (mL)	Floc Appearance	Water Clarity	Water Release	Comments
	AH 9727	4	3	2	3	
	AH 9727	6	4	2	3	
	AH 9650	6	2	1	1	
	AH 1120	4	4	3	4	
	AH 7810	4	5	4	5	
	AH 7840	4	5	5	5	
	AH 7840	3.5	5	5	5	
	AH 7640	3	5	5	5	
	AH 7850	3	5	5	4	
	AH 7880	3	4	5	4	
	AH 7860	3	5	4	5	
	AH 7860	2.5	4	3	3	
	AH 7840	2.5	5	5	5	floc shears
	AH 7840	2	3	4	2	
	AH 7387 + AH 7840	0.5 + 2	4	5	4	
	AH 7387 + AH 7840	1 + 2	5	5	5	dual app

Slurry % solids: 9.45%

100 mL aliquots of slurry used for each jar test

Conditioning products diluted by factor of 200 unless otherwise specified

CO

ATTACHMENT C: GTDT LOG SHEETS

INFRASTRUCTURE ALTERNATIVES, INC.

Project ID: Benning Road Facility
Location: SED-7C-C-TX

Date: 7-2-2020
Analyst: CM

In-Situ % Solids:	40.0	Slurry % Solids:	15.7
In-Situ Sediment Added (L):	12	Cake % Solids after 24 hours:	47.0
Surface Water Added (L):	36	Cake % Solids after 48 hours:	47.2
Coagulant Added (mL):	—	Cake % Solids after 96 hours:	48.8
Flocculant Added (mL):	2,200	Cake % Solids after 7 days:	50.1

Time Interval	Filtrate Collected (mL)	Percentage of Total Filtrate Collected	Filtrate Turbidity (NTU)	Filtrate Total Suspended Solids (mg/L)
0-1 min	14,790	44.6	78	—
1-10 min	8,140	24.5	86	—
10-60 min	6,400	19.3	54	—
1-24 hours	3,860	11.6	27	—

Notes: 2.71 lbs/DT

7888 Childsdale Ave. NE | Rockford, MI 49341 | Phone 616.866.1600 | Fax 616.866.1611
info@iaiwater.com | www.iaiwater.com

INFRASTRUCTURE ALTERNATIVES, INC.

Project ID: Benning Road Facility
Location: SED-7.5E-GTX

Date: 7-2-2020
Analyst: C-M

In-Situ % Solids:	37.9	Slurry % Solids:	12.7
In-Situ Sediment Added (L):	11	Cake % Solids after 24 hours:	39.5
Surface Water Added (L):	39	Cake % Solids after 48 hours:	48.3
Coagulant Added (mL):	—	Cake % Solids after 96 hours:	38.5
Flocculant Added (mL):	2,100	Cake % Solids after 7 days:	41.7

Time Interval	Filtrate Collected (mL)	Percentage of Total Filtrate Collected	Filtrate Turbidity (NTU)	Filtrate Total Suspended Solids (mg/L)
0-1 min	12,260	35.6	40	—
1-10 min	8,950	26.0	33	—
10-60 min	7,880	22.9	22	—
1-24 hours	5,320	15.5	24	—

Notes: 3.09 lbs/DT

7888 Childsdale Ave. NE | Rockford, MI 49341 | Phone 616.866.1600 | Fax 616.866.1611
info@iaiwater.com | www.iaiwater.com

ATTACHMENT D: LAB REPORTS

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

June 16, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2006738

Dear Mr. Sierra Brown:

Prein&Newhof Laboratory received 6 sample(s) on 6/12/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

CC:
Mr. Connor McNeely

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2006738
Project: PBRT

Lab ID: 2006738-01 **Matrix:** SOLID **Collection Date:** 6/12/2020 9:45:00 AM
Client ID: 7C-001-INSITU **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
DENSITY				**SM 2710-F**		Analyst: **SB**
Density	11.2	1.00		lb/Gal	1	6/16/2020 11:53:33 AM
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	40.0	0.0100		%	1	6/12/2020 5:00:00 PM

Lab ID: 2006738-02 **Matrix:** SOLID **Collection Date:** 6/12/2020 9:48:00 AM
Client ID: 7.5E-001-INSITU **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
DENSITY				**SM 2710-F**		Analyst: **SB**
Density	10.8	1.00		lb/Gal	1	6/16/2020 11:53:33 AM
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	46.0	0.0100		%	1	6/12/2020 5:00:00 PM

Lab ID: 2006738-03 **Matrix:** SOLID **Collection Date:** 6/12/2020 9:51:00 AM
Client ID: 7.5E-002-INSITU **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
DENSITY				**SM 2710-F**		Analyst: **SB**
Density	10.8	1.00		lb/Gal	1	6/16/2020 11:53:33 AM
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	45.5	0.0100		%	1	6/12/2020 5:00:00 PM

Qualifiers:
< Not Detected at the Reporting Limit
H Holding times for preparation or analysis exceeded
MCL Maximum Contaminant Level
PL Permit Limit
RL Reporting Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2006738
Project: PBRT

Lab ID: 2006738-04 **Matrix:** SOLID **Collection Date:** 6/12/2020 10:01:00 AM
Client ID: 7C-001-Slurry **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	18.1	0.0100		%	1	6/12/2020 5:00:00 PM

Lab ID: 2006738-05 **Matrix:** SOLID **Collection Date:** 6/12/2020 10:07:00 AM
Client ID: 7.5E-001-Slurry **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	14.6	0.0100		%	1	6/12/2020 5:00:00 PM

Lab ID: 2006738-06 **Matrix:** SOLID **Collection Date:** 6/12/2020 10:15:00 AM
Client ID: 7.5E-002-Slurry **Sampler:** S. Ponstein **Received Date:** 6/12/2020 3:23:36 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **DV**
Total Solids	16.4	0.0100		%	1	6/12/2020 5:00:00 PM

Qualifiers:

<	Not Detected at the Reporting Limit
MCL	Maximum Contaminant Level
RL	Reporting Limit
H	Holding times for preparation or analysis exceeded
PL	Permit Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: Infrastructure Alternatives (IAI)
Project Name: Pepco Beming Rd. (PBRT)
Project #: PBRT
Send Results to: cmcneely@iaiwater.com
Sampling Personnel: Scott Ponstein (SAP)

CHAIN OF CUSTODY

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

Lab Use	Sample Information				Preservative						Analysis Requested																							
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)	MATRIX	None	H2SO4	HNO3	HCl	NaOH	Other	% solids	Density																						
66738-1	6/12/20	0945	PBRT-7C-001-INSITU	L	X						X	X																						
2	"	0948	PBRT-7.5E-001-INSITU	L	X						X	X																						
3		0951	PBRT-7.5E-002-INSITU	L	X						X	X																						
4		1001	PBRT-7C-001-Slurry	L	X						X																							
5		1007	PBRT-7.5E-001-Slurry	L	X						X																							
6		1015	PBRT-7.5E-002-Slurry	L	X						X																							

Comments:
~~Forgy~~ For Slurry samples please mix well. Solids will settle to bottom

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Scott A. Pol	6/12/20	1530									
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 41198		
S. Diem	6/12/20	1530									

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

June 20, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2006A63

Dear Mr. Connor McNeely:

Prein&Newhof Laboratory received 2 sample(s) on 6/19/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

HOLIDAY HOURS: Prein & Newhof will be closed on Friday, July 3 for Independance Day. Bacteria samples will be accepted until 3pm on Thursday, July 2.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

Analytical Report

(consolidated)

WO#: **2006A63**

Date Reported: **6/20/2020**

CLIENT:	Infrastructure Alternatives	**Collection Date:**	6/19/2020 12:00:00 PM
Project:	PBRT	**Received Date:**	6/19/2020 12:10:00 PM
Lab ID:	2006A63-01	**Matrix:**	SEDIMENT
Client Sample ID:	SED-7.5E-GTX	**Sampled By:**	Connor

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **AB**
Total Solids	9.45	0.0100		%	1	6/20/2020 2:21:13 PM

Qualifiers:

<	Not Detected at the Reporting Limit
MCL	Maximum Contaminant Level
RL	Reporting Limit
H	Holding times for preparation or analysis exceeded
PL	Permit Limit

Original

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

Analytical Report

(consolidated)

WO#: **2006A63**

Date Reported: **6/20/2020**

CLIENT:	Infrastructure Alternatives	**Collection Date:**	6/19/2020 12:00:00 PM
Project:	PBRT	**Received Date:**	6/19/2020 12:10:00 PM
Lab ID:	2006A63-02	**Matrix:**	SEDIMENT
Client Sample ID:	SED-7C-GTX	**Sampled By:**	Connor

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **AB**
Total Solids	9.61	0.0100		%	1	6/20/2020 2:21:13 PM

Qualifiers:

<	Not Detected at the Reporting Limit
MCL	Maximum Contaminant Level
RL	Reporting Limit
H	Holding times for preparation or analysis exceeded
PL	Permit Limit

Original

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: IAI
Project Name: PBRT
Project #:
Send Results to: cmcneely@iaiwater.com
Sampling Personnel: Connor McNeely

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

CHAIN OF CUSTODY

Lab Use	Sample Information			MATRIX	Preservative						Analysis Requested																	
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)		None	H2SO4	HNO3	HCl	NaOH	Other	% solids																	
6A631	6-19	12 00	SED-7.5E-GTX		X						X																	
2	6-19	12:00	SED-7C-GTX		X						X																	

Comments:

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Connor McNeely	6-19	12:10									
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 41199		
	6/19	12:10									

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

June 25, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2006C45

Dear Mr. Connor McNeely:

Prein&Newhof Laboratory received 6 sample(s) on 6/24/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

HOLIDAY HOURS: Prein & Newhof will be closed on Friday, July 3 for Independance Day. Bacteria samples will be accepted until 3pm on Thursday, July 2.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2006C45
Project: PBRT

Lab ID: 2006C45-01 **Matrix:** SOIL **Collection Date:** 6/23/2020 11:15:00 AM
Client ID: SED-7C-GTX-1 min **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	34.0	0.0100		%	1	6/25/2020 8:28:26 AM

Lab ID: 2006C45-02 **Matrix:** SOIL **Collection Date:** 6/23/2020 11:30:00 AM
Client ID: SED-7C-GTX-15 min **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	35.9	0.0100		%	1	6/25/2020 8:28:26 AM

Lab ID: 2006C45-03 **Matrix:** SOIL **Collection Date:** 6/24/2020 11:15:00 AM
Client ID: SED-7C-GTX- 24 hr **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	41.6	0.0100		%	1	6/25/2020 8:28:26 AM

Lab ID: 2006C45-04 **Matrix:** SOIL **Collection Date:** 6/23/2020 10:45:00 AM
Client ID: SED-7.5E-GTX-1 min **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	27.4	0.0100		%	1	6/25/2020 8:28:26 AM

Qualifiers:
< Not Detected at the Reporting Limit
MCL Maximum Contaminant Level
RL Reporting Limit
H Holding times for preparation or analysis exceeded
PL Permit Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2006C45
Project: PBRT

Lab ID: 2006C45-05 **Matrix:** SOIL **Collection Date:** 6/23/2020 11:00:00 AM
Client ID: SED-7.5E-GTX-15 min **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	27.3	0.0100		%	1	6/25/2020 8:28:26 AM

Lab ID: 2006C45-06 **Matrix:** SOIL **Collection Date:** 6/24/2020 10:45:00 AM
Client ID: SED-7.5E-GTX-24 hr **Sampler:** Connor **Received Date:** 6/24/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **KF**
Total Solids	34.7	0.0100		%	1	6/25/2020 8:28:26 AM

Qualifiers:

<	Not Detected at the Reporting Limit
MCL	Maximum Contaminant Level
RL	Reporting Limit
H	Holding times for preparation or analysis exceeded
PL	Permit Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: IAI
Project Name: PBRT
Project #:
Send Results to: cmcneely@iaiwater.com
Sampling Personnel: Connor McNeely

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

CHAIN OF CUSTODY

Lab Use	Sample Information			MATRIX	Preservative						Analysis Requested															
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)		None	H2SO4	HNO3	HCl	NaOH	Other	% sol. As															
66451	6-23	11:15	SED-7C-GTX-1min								X															
2	6-23	11:30	SED-7C-GTX-15min								X															
3	6-24	11:15	SED-7C-GTX-24hr								X															
4	6-23	10:45	SED-7.5E-GTX-1min								X															
5	6-23	11:00	SED-7.5E-GTX-15min								X															
6	6-24	10:45	SED-7.5E-GTX-24hr								X															

Comments: 24 hr TOT please, Results by 6-25 10:30 AM.

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Connor McNeely	6-24	12:15									
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 41200		
G. Dean	6/24/20	1215									

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

June 29, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2006D97

Dear Mr. Connor McNeely:

Prein&Newhof Laboratory received 2 sample(s) on 6/26/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

HOLIDAY HOURS: Prein & Newhof will be closed on Friday, July 3 for Independance Day. Bacteria samples will be accepted until 3pm on Thursday, July 2.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2006D97
Project: PBRT

Lab ID: 2006D97-01 **Matrix:** SOIL **Collection Date:** 6/25/2020 12:00:00 PM
Client ID: SED-7C-GTX-slurry **Sampler:** CM **Received Date:** 6/26/2020 11:55:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	15.7	0.0100		%	1	6/26/2020 3:00:00 PM

Lab ID: 2006D97-02 **Matrix:** SOIL **Collection Date:** 6/26/2020 12:00:00 PM
Client ID: SED-7.5E-GTX-slurry **Sampler:** CM **Received Date:** 6/26/2020 11:55:00 AM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	12.7	0.0100		%	1	6/26/2020 3:00:00 PM

Qualifiers:

<	Not Detected at the Reporting Limit	H	Holding times for preparation or analysis exceeded
MCL	Maximum Contaminant Level	PL	Permit Limit
RL	Reporting Limit		

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: IAI
Project Name: PBRT
Project #:
Send Results to: CMCNEELY@IAIWATER.COM
Sampling Personnel: CM

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

CHAIN OF CUSTODY

Lab Use	Sample Information			MATRIX	Preservative						Analysis Requested																	
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)		None	H_2SO_4	HNO_3	HCl	NaOH	Other	% Solids																	
60971	6-26	12:00	SED-7C-GTX-slurry								X																	
2	6-26	12:00	SED-7.5E-GTX-slurry								X																	

Comments: Standard TOT. Please shake contents

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 41184		
K	6/26/21	1210									

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

July 08, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2007262

Dear Mr. Connor McNeely:

Prein&Newhof Laboratory received 8 sample(s) on 7/7/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2007262
Project: PBRT

Lab ID: 2007262-01 **Matrix:** SOIL **Collection Date:** 7/1/2020 2:00:00 PM
Client ID: SED-7C-GTX-24hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	47.0	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-02 **Matrix:** SOIL **Collection Date:** 7/2/2020 2:00:00 PM
Client ID: SED-7C-GTX-48hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	47.2	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-03 **Matrix:** SOIL **Collection Date:** 7/4/2020 2:00:00 PM
Client ID: SED-7C-GTX-96hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	48.8	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-04 **Matrix:** SOIL **Collection Date:** 7/7/2020 12:00:00 PM
Client ID: SED-7C-GTX-7day **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **SJ**
Total Solids	50.1	0.0100		%	1	7/8/2020 8:43:05 AM

Qualifiers:
< Not Detected at the Reporting Limit
H Holding times for preparation or analysis exceeded
MCL Maximum Contaminant Level
PL Permit Limit
RL Reporting Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

CLIENT: Infrastructure Alternatives **Lab Order:** 2007262
Project: PBRT

Lab ID: 2007262-05 **Matrix:** SOIL **Collection Date:** 7/1/2020 12:00:00 PM
Client ID: SED-7.5E-GTX-24hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE					**D2216**	Analyst: **SJ**
Total Solids	39.5	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-06 **Matrix:** SOIL **Collection Date:** 7/2/2020 12:00:00 PM
Client ID: SED-7.5E-GTX-48hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE					**D2216**	Analyst: **SJ**
Total Solids	48.3	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-07 **Matrix:** SOIL **Collection Date:** 7/4/2020 12:00:00 PM
Client ID: SED-7.5E-GTX-96hr **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE					**D2216**	Analyst: **SJ**
Total Solids	38.5	0.0100		%	1	7/8/2020 8:43:05 AM

Lab ID: 2007262-08 **Matrix:** SOIL **Collection Date:** 7/7/2020 12:00:00 PM
Client ID: SED-7.5E-GTX-7day **Sampler:** Connor **Received Date:** 7/7/2020 12:15:00 PM

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE					**D2216**	Analyst: **SJ**
Total Solids	41.7	0.0100		%	1	7/8/2020 8:43:05 AM

Qualifiers:
< Not Detected at the Reporting Limit
H Holding times for preparation or analysis exceeded
MCL Maximum Contaminant Level
PL Permit Limit
RL Reporting Limit

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: IAI
Project Name: PBRT
Project #:
Send Results to: CMCNEELY@IAIWATER.COM
Sampling Personnel: Connor

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

CHAIN OF CUSTODY

Lab Use	Sample Information			MATRIX	Preservative						Analysis Requested																	
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)		None	H2SO4	HNO3	HCl	NaOH	Other	% solids																	
7262-1	7-1	2:00	SED-7C-GTX-24hr	S							X																	
2	7-2	2:00	SED-7C-GTX-48hr	S							X																	
3	7-4	2:00	SED-7C-GTX-96hr	S							X																	
4	7-7	12:00	SED-7C-GTX-7day	S							X																	
5	7-1	12:00	SED-7.5E-GTX-24hr	S							X																	
6	7-2	12:00	SED-7.5E-GTX-48hr	S							X																	
7	7-4	12:00	SED-7.5E-GTX-96hr	S							X																	
8	7-7	12:00	SED-7.5E-GTX-7day	S							X																	

Comments:

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Connor McNeely	7-7	12:15									
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 42228		
K	7/7/20	12:15									

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

July 14, 2020

Infrastructure Alternatives
7888 Childsdale NE
Rockford, MI 49341

RE: PBRT

Order No.: 2007586

Dear Mr. Sierra Brown:

Prein&Newhof Laboratory received 1 sample(s) on 7/13/2020 for the analyses presented in the following report.

There were no problems with the analytical events associated with this report unless noted in the Case Narrative.

Any analyte that exceeds the provided permit level are noted on the report with an "*" in the Qual field. Quality control data is within laboratory defined or method specified acceptance limits except if noted.

Due to the COVID-19 Virus outbreak and the possibility of this affecting our staff and their families, the standard 5 day turnaround time will be lengthened. Prein&Newhof will do our best to get you your results as quickly as we can.

If you have any questions regarding these tests results, please feel free to call.

Thank you for your business.
Sincerely,

Steve Bylsma
Laboratory Manager

CC:
Mr. Connor McNeely

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory

Analytical Report

(consolidated)

WO#: **2007586**

Date Reported: **7/14/2020**

CLIENT:	Infrastructure Alternatives	**Collection Date:**	7/13/2020 2:30:00 PM
Project:	PBRT	**Received Date:**	7/13/2020 4:00:00 PM
Lab ID:	2007586-01	**Matrix:**	SOIL
Client Sample ID:	SED-7.5E-GTX-Redo	**Sampled By:**	Connor

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
PERCENT MOISTURE				**D2216**		Analyst: **JS**
Total Solids	37.9	0.0100		%	1	7/13/2020 4:00:00 PM

Qualifiers:

<	Not Detected at the Reporting Limit
MCL	Maximum Contaminant Level
RL	Reporting Limit
H	Holding times for preparation or analysis exceeded
PL	Permit Limit

Original

3260 Evergreen Drive, NE Grand Rapids, MI 49525 t.616-364-7600 f. 616-364-4222 www.preinnewhof.com

Prein&Newhof
Engineers ▪ Surveyors ▪ Environmental ▪ Laboratory
3260 Evergreen Drive NE
Grand Rapids, MI 49525
t. 616-364-7600
f. 616-364-4222

Client: FAI
Project Name: PBRT
Project #:
Send Results to: CMCNEELY@FAIWATER.COM
Sampling Personnel: Connor

Air	A
Drinking Water	D
Groundwater	W
Soil	S
Sludge	L
Oil	O
Other	X

CHAIN OF CUSTODY

Lab Use	Sample Information				Preservative						Analysis Requested																	
Lab Sample ID #	Date	Time	Sample Description and Location (e.g. MW-1)	MATRIX	None	H2SO4	HNO3	HCl	NaOH	Other	Y. SO Lbs																	
7586-1	7-13	2:30	SED-7.5 E-GTX-Redo		X						X																	

Comments:

Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time
Connor Neely	7-13	4:00									
Relinquished By: (Signature)	Date	Time	Received By: (Signature)	Date	Time	Method of Shipment:			Bill of Lading:		
Received for Laboratory By:	Date	Time	Data Package Relinquished By:	Date	Time	Data Received By:	Date	Time	No. 42382		
S. Dienn	7/13/26	1600									

15-Jul-2020

Connor McNeely
Infrastructure Alternatives
788 Childsdale Avenue NE
Rockford, MI 49341

Tel: (616) 916-1160
Fax:

Re: Not Available Work Order: **2007191**

Dear Connor,

ALS Environmental received 3 samples on 08-Jul-2020 10:25 AM for the analyses presented in the following report.

The analytical data provided relates directly to the samples received by ALS Environmental and for only the analyses requested.

QC sample results for this data met laboratory specifications. Any exceptions are noted in the Case Narrative, or noted with qualifiers in the report or QC batch information. Should this laboratory report need to be reproduced, it should be reproduced in full unless written approval has been obtained from ALS Laboratory Group. Samples will be disposed in 30 days unless storage arrangements are made.

The total number of pages in this report is 8.

If you have any questions regarding this report, please feel free to contact me.

Sincerely,

Shawn Smythe

Electronically approved by: Shawn Smythe

Shawn Smythe
Project Manager

ALS Environmental

Date: 15-Jul-20

Client: Infrastructure Alternatives
Project: Not Available
Work Order: **2007191**

Work Order Sample Summary

Lab Samp ID	Client Sample ID	Matrix	Tag Number	Collection Date	Date Received	Hold
2007191-01	SED-7C-GTX	Air		7/1/2020	7/8/2020 10:25	☐
2007191-02	SED-7.SE-GTX	Air		7/1/2020	7/8/2020 10:25	☐
2007191-03	Background	Air		7/1/2020	7/8/2020 10:25	☐

ALS Environmental

Date: 15-Jul-20

Client:	Infrastructure Alternatives
Project:	Not Available
Work Order:	2007191

Case Narrative

The analytical data provided relates directly to the samples received by ALS Environmental and for only the analyses requested.

Results relate only to the items tested and are not blank corrected unless indicated.

QC sample results for this data met laboratory specifications. Any exceptions are noted in the Case Narrative, or noted with qualifiers in the report or QC batch information. Should this laboratory report need to be reproduced, it should be reproduced in full unless written approval has been obtained from ALS Environmental. Samples will be disposed in 30 days unless storage arrangements are made.

ALS is an EPA recognized NLLAP laboratory for lead paint, soil, and dust wipe analyses under its AIHA-LAP accreditation.

ALS Environmental

Date: *15-Jul-20*

Client: Infrastructure Alternatives
Project: Not Available

Work Order: 2007191

Analytical Results

Lab ID: 2007191-01A
Client Sample ID: SED-7C-GTX

Collection Date: 7/1/2020
Matrix: AIR

Analyses

PCBS		Method: **N5503**	Air Volume (L): **100.8**	Analyst: **ECP**
Date Analyzed: 7/15/2020	µg/sample	Reporting Limit µg/sample	mg/m3	
Aroclor 1016	ND	0.010	<0.000099	
Aroclor 1221	ND	0.020	<0.00020	
Aroclor 1232	ND	0.010	<0.000099	
Aroclor 1242	ND	0.010	<0.000099	
Aroclor 1248	ND	0.010	<0.000099	
Aroclor 1254	ND	0.010	<0.000099	
Aroclor 1260	ND	0.010	<0.000099	

Lab ID: 2007191-02A
Client Sample ID: SED-7.SE-GTX

Collection Date: 7/1/2020
Matrix: AIR

Analyses

PCBS		Method: **N5503**	Air Volume (L): **100.8**	Analyst: **ECP**
Date Analyzed: 7/15/2020	µg/sample	Reporting Limit µg/sample	mg/m3	
Aroclor 1016	ND	0.010	<0.000099	
Aroclor 1221	ND	0.020	<0.00020	
Aroclor 1232	ND	0.010	<0.000099	
Aroclor 1242	ND	0.010	<0.000099	
Aroclor 1248	ND	0.010	<0.000099	
Aroclor 1254	ND	0.010	<0.000099	
Aroclor 1260	ND	0.010	<0.000099	

Note:

ALS Environmental

Date: *15-Jul-20*

Client: Infrastructure Alternatives
Project: Not Available

Work Order: 2007191

Analytical Results

Lab ID: 2007191-03A
Client Sample ID: Background

Collection Date: 7/1/2020
Matrix: AIR

Analyses

PCBS		Method: **N5503**	Air Volume (L): **100.8**	Analyst: **ECP**
Date Analyzed: 7/15/2020	µg/sample	Reporting Limit µg/sample	mg/m3	
Aroclor 1016	ND	0.010	<0.000099	
Aroclor 1221	ND	0.020	<0.00020	
Aroclor 1232	ND	0.010	<0.000099	
Aroclor 1242	ND	0.010	<0.000099	
Aroclor 1248	ND	0.010	<0.000099	
Aroclor 1254	ND	0.010	<0.000099	
Aroclor 1260	ND	0.010	<0.000099	

Note:

ALS Environmental

Date: 15-Jul-20

Client: Infrastructure Alternatives

Work Order: 2007191

Project: Not Available

QC BATCH REPORT

Batch ID: **R179098** Instrument ID **GC3** Method: **N5503**

MBLK Sample ID **MB-R179098-R179098** Units: **µg/sample** Analysis Date: **7/15/2020**

Client ID: Run ID: **GC3_200715A** SeqNo: **2268596** Prep Date: DF: **1**

Analyte	Result	PQL	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
Aroclor 1016	ND	0.010								
Aroclor 1221	ND	0.020								
Aroclor 1232	ND	0.010								
Aroclor 1242	ND	0.010								
Aroclor 1248	ND	0.010								
Aroclor 1254	ND	0.010								
Aroclor 1260	ND	0.010								

LCS Sample ID **LCS-R179098-R179098** Units: **µg/sample** Analysis Date: **7/15/2020**

Client ID: Run ID: **GC3_200715A** SeqNo: **2268597** Prep Date: DF: **1**

Analyte	Result	PQL	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
Aroclor 1016	0.106	0.010	0.1	0	106	70-130	0			
Aroclor 1260	0.107	0.010	0.1	0	107	70-130	0			

LCSD Sample ID **LCSD-R179098** Units: **µg/sample** Analysis Date: **7/15/2020**

Client ID: Run ID: **GC3_200715A** SeqNo: **2268601** Prep Date: DF: **1**

Analyte	Result	PQL	SPK Val	SPK Ref Value	%REC	Control Limit	RPD Ref Value	%RPD	RPD Limit	Qual
Aroclor 1016	0.104	0.010	0.1	0	104	70-130	0.106	1.9	20	
Aroclor 1260	0.106	0.010	0.1	0	106	70-130	0.107	0.939	20	

The following samples were analyzed in this batch: 2007191-01A 2007191-02A 2007191-03A

Note: See Qualifiers Page for a list of Qualifiers and their explanation.

ALS Environmental

Date: 15-Jul-20

Client: Infrastructure Alternatives
Project: Not Available
WorkOrder: **2007191**

QUALIFIERS, ACRONYMS, UNITS

Qualifier	Description
*	Value exceeds Regulatory Limit
a	Not accredited
B	Analyte detected in the associated Method Blank above the Reporting Limit
E	Value above quantitation range
H	Analyzed outside of Holding Time
J	Analyte detected below quantitation limit
n	Not offered for accreditation
ND	Not Detected at the Reporting Limit
O	Sample amount is > 4 times amount spiked
P	Dual Column results percent difference > 40%
R	RPD above laboratory control limit
S	Spike Recovery outside laboratory control limits
U	Analyzed but not detected above the MDL

Acronym	Description
DUP	Method Duplicate
E	EPA Method
LCS	Laboratory Control Sample
LCSD	Laboratory Control Sample Duplicate
MBLK	Method Blank
MDL	Method Detection Limit
MQL	Method Quantitation Limit
MS	Matrix Spike
MSD	Matrix Spike Duplicate
PDS	Post Digestion Spike
PQL	Practical Quantitaion Limit
SDL	Sample Detection Limit
SW	SW-846 Method

Units Reported	Description
µg/sample	

ALS Environmental

Sample Receipt Checklist

Client Name: **INFRASTRUCTURE-ROCKFORD** Date/Time Received: **08-Jul-20 10:25**

Work Order: **2007191** Received by: **DNS**

Checklist completed by Shawn Smythe 08-Jul-20 Reviewed by: Shawn Smythe 08-Jul-20

eSignature Date eSignature Date

Matrices:

Carrier name: UPS

Shipping container/cooler in good condition?	Yes ☑	No ☐	Not Present ☐
Custody seals intact on shipping container/cooler?	Yes ☐	No ☐	Not Present ☑
Custody seals intact on sample bottles?	Yes ☐	No ☐	Not Present ☑
Chain of custody present?	Yes ☑	No ☐	
Chain of custody signed when relinquished and received?	Yes ☑	No ☐	
Chain of custody agrees with sample labels?	Yes ☑	No ☐	
Samples in proper container/bottle?	Yes ☑	No ☐	
Sample containers intact?	Yes ☑	No ☐	
Sufficient sample volume for indicated test?	Yes ☑	No ☐	
All samples received within holding time?	Yes ☑	No ☐	
Container/Temp Blank temperature in compliance?	Yes ☑	No ☐	
Temperature(s)/Thermometer(s):			
Cooler(s)/Kit(s):			
Water - VOA vials have zero headspace?	Yes ☐	No ☐	No VOA vials submitted ☐
Water - pH acceptable upon receipt?	Yes ☐	No ☐	N/A ☐
pH adjusted?	Yes ☐	No ☐	N/A ☐
pH adjusted by:			

Login Notes:

Client Contacted: Date Contacted: Person Contacted:

Contacted By: Regarding:

Comments:

CorrectiveAction:

ATTACHMENT E: GEOTEXTILE FABRIC SPECIFICATIONS

GEOSTRUX™

GEOTEXTILE TUBES

ENVIRONMENTALLY PROVEN SOLUTIONS FOR DEWATERING AND COASTAL APPLICATIONS



GEOSTRUX™ Tubes are produced using high strength woven fabrics which are manufactured to exacting standards by our in-house fabrication group.

Once on site, GEOSTRUX™ Tubes are hydraulically filled with heavily saturated sediment, sand or waste materials. When fully dewatered, the sediment has reduced weight and volume, allowing for more cost-effective material handling. In coastal applications the structure is strategically placed before filling to provide cost effective shoreline protection or habitat creation.





GEO-SYNTHETICS, LLC.

WWW.GEO-SYNTHETICS.COM

PHONE: 800.444.5523

GEOSTRUX@GEO-SYNTHETICS.COM

GEOSTRUX™

GEOTEXTILE TUBES

FIELD PROVEN IN A WIDE VARIETY OF APPLICATIONS

APPLICATIONS

- Habitat Creation
- Coastal Protection
- Breakwaters, Groins & Jetties
- Dewatering Liquid Waste and Sludge
- Dewatering Lake and River Sediments

ADVANTAGES

- Cost Effective
- Passive Dewatering
- Improved Effluent Clarity







GEOSTRUX™ Geotextile Tube

Dimensions and Capacities

Circumference	Capacity*
22.5'**	1.3 CY/LF
30'	2.3 CY/LF
45'	4.1 CY/LF
60'	6.2 CY/LF
75'	8.3 CY/LF
90'	10.1 CY/LF

**Calculated volume – Actual capacity may vary*

***Container Tubes*

Available in either black or tan fabric

Note: Dimensions and capacities are represented as typical values. They should not be used for design purposes. GSI makes no warranties and assumes no liability in connection with the use of this information.

GSI GEO-SYNTHETICS, LLC.

WWW.GEO-SYNTHETICS.COM PHONE: 800.444.5523 GEOSTRUX@GEO-SYNTHETICS.COM

Beltech 4.5 x 6.25

2159

Product Data Sheet

June 2015

A woven geotextile fabric, produced from polypropylene slit-film tapes, which will meet or exceed the following MARV's. This fabric is produced for use in Filtration and Dewatering application. Its sand color makes it more appealing than traditional black fabrics in many applications. The fabric is designed and engineered with 4 inch reinforced selvages to insure maximum fabricated seam strength.

Property	Test Method	English Units			SI Units		
		MARV			MARV		
		MD	CD		MD	CD	
Wide Width Tensile Ultimate	ASTM D-4595	450	622	lbs/in	79	109	kN/m
Wide Width Elongation	ASTM D-4595	20	18	%	20	18	%
Wide Width @ 2% - **Typical**	ASTM D-4595	25	135	lbs/in	4	24	kN/m
Wide Width @ 5% - **Typical**	ASTM D-4595	120	320	lbs/in	21	56	kN/m
Wide Width @ 10% - **Typical**	ASTM D-4595	320	n/a	lbs/in	56	n/a	kN/m
Trapezoid Tear	ASTM D-4533	250	300	lbs	1113	1335	N
CBR Puncture	ASTM D-6241	3000		lbs	13		kN
Puncture	ASTM D-4833	225		lbs	1001		N
Permittivity	ASTM D-4491	0.27		sec^{1}	0.27		sec^{-1}
Water Flow Rate	ASTM D-4491	20		gpm/ft^2	815		$l/min/m^2$
A.O.S.	ASTM D-4751	30		U.S. Sieve	0.6		mm
UV Resistance (1400 hrs) - **Typical**	ASTM D-4355	85		%	85		%
UV Resistance (1400 hrs) - **MARV**	ASTM D-4355	70		%	70		%
Pore Size Distribution (O_{50}) ** - **Typical**	ASTM D-6767	140		U.S. Sieve	100		micron
Pore Size Distribution (O_{95}) ** - **Typical**	ASTM D-6767	40		U.S. Sieve	395		micron

**** Performed by a Third Party Laboratory**



Produced in Belton, South Carolina, U.S.A.

The foregoing is believed to be an accurate representation of information complied from inside and/or outside sources, however, because test values, statistical data, and other information presented may be based solely on results of unverified tests made on random samples, information presented may relate only to tested samples and because the conditions in which such information may be used are beyond the control of Belton Industries, Inc., Belton does not guarantee either the accuracy or reliability of the information or the suggestions and recommendations contained herein. Belton assumes no responsibility for the use of information presented herein and hereby disclaims all liabilities which may arise in connection with the use of information herein presented. All specifications, properties, values, statistical data and applications listed herein are provided as information only, without charge or obligation to the recipient or user, and in no way either makes or creates any warranty with respect to any product or modifies, amends or enlarges any warranty made with respect to any product. Final determination of the suitability, reliability and accuracy of the information and suggested uses is solely the responsibility of the user. The property values expressed are effective on the date shown above, supersede any values previously published, and are subject to change without notice.

PO Box 127 · 1205 Hamby Road · Belton, South Carolina 29627

Phone 864.338.5711 / 800.845.8753 · Fax 864.338.5594 / 800.851.5049 · www.BeltonIndustries.com

ACCREDITED
Testing Lab - Cert 3507.01

LONGITUDINAL SEWING

Height	```	15-ft	15-ft	22.5-ft	22.5-ft	22.5-ft	30-ft	30-ft	30-ft	45-ft	45-ft	45-ft	60-ft	60-ft	60-ft	75-ft	75-ft	75-ft	80.5-ft	80.5-ft	80.5-ft	85-ft	85-ft	85-ft	90-ft	90-ft	90-ft
Feet	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.	SF	CY/l.f.	gal/l.f.
1.0	6.2	0.2	46.4	9.8	0.4	73.3	13.7	0.5	102.5	20.9	0.8	156.4	28.0	1.0	209.5	36.4	1.3	272.3	39.9	1.5	298.5	42.2	1.6	315.7	43.7	1.6	326.9
1.5	8.6	0.3	64.3	14.1	0.5	105.5	19.8	0.7	148.1	30.7	1.1	229.7	41.6	1.5	311.2	52.5	1.9	392.8	57.8	2.1	432.4	61.1	2.3	457.1	63.4	2.3	474.3
2.0	10.7	0.4	80.1	17.8	0.7	133.2	25.5	0.9	190.8	39.5	1.5	295.5	54.5	2.0	407.7	69.1	2.6	517.0	76.2	2.8	570.1	80.7	3.0	603.8	83.7	3.1	626.2
2.5	12.6	0.5	94.3	21.3	0.8	159.4	30.4	1.1	227.4	48.3	1.8	361.4	66.2	2.5	495.3	84.4	3.1	631.4	93.1	3.4	696.5	98.7	3.7	738.4	102.3	3.8	765.4
3.0	14.2	0.5	106.2	24.3	0.9	181.8	35.4	1.3	264.8	56.6	2.1	423.5	78.1	2.9	584.3	99.8	3.7	746.7	110.3	4.1	825.2	117.0	4.3	875.3	121.4	4.5	908.3
3.5	16.8	0.6	125.7	27.2	1.0	203.5	39.9	1.5	298.5	64.2	2.4	480.3	90.4	3.3	676.3	116.1	4.3	868.6	128.5	4.8	961.4	136.4	5.1	1020.5	141.6	5.2	1059.4
4.0	17.5	0.6	130.9	29.7	1.1	222.2	44.1	1.6	329.9	71.6	2.7	535.7	100.3	3.7	750.4	129.4	4.8	968.1	143.4	5.3	1072.8	152.3	5.6	1139.4	158.2	5.9	1183.6
4.2	17.1	0.6	127.9	32.1	1.2	240.2	45.8	1.7	342.7	75.0	2.8	561.1	111.0	4.1	830.4	143.8	5.3	1075.8	151.3	5.6	1131.9	160.8	6.0	1203.0	176.4	6.5	1319.7
5.0				35.5	1.3	265.6	52.5	1.9	392.8	85.8	3.2	641.9	121.0	4.5	905.3	157.5	5.8	1178.3	175.2	6.5	1310.8	186.3	6.9	1393.8	193.8	7.2	1449.9
5.5				40.7	1.5	304.5	54.8	2.0	410.0	92.3	3.4	690.5	131.6	4.9	984.6	170.0	6.3	1271.9	189.3	7.0	1416.2	201.6	7.5	1508.3	209.7	7.8	1568.9
6.0				39.4	1.5	294.8	58.2	2.2	435.4	97.9	3.6	732.4	141.0	5.2	1054.9	183.2	6.8	1370.6	204.3	7.6	1528.5	217.7	8.1	1628.7	226.7	8.4	1696.1
6.5							62.5	2.3	467.6	104.4	3.9	781.1	149.1	5.5	1115.5	197.0	7.3	1473.9	217.5	8.1	1627.2	231.9	8.6	1735.0	241.6	8.9	1807.5
7.0							70.2	2.6	525.2	109.9	4.1	822.2	158.9	5.9	1188.8	209.0	7.7	1563.6	231.2	8.6	1729.7	246.8	9.1	1846.4	257.2	9.5	1924.2
7.5										119.5	4.4	894.0	167.2	6.2	1250.9	218.8	8.1	1636.9	245.3	9.1	1835.2	262.2	9.7	1961.6	273.4	10.1	2045.4
8.0										120.2	4.5	899.3	175.5	6.5	1313.0	231.3	8.6	1730.5	257.0	9.5	1922.7	274.9	10.2	2056.7	286.9	10.6	2146.4
8.5										124.9	4.6	934.4															
9.0																											

Notes:

Shaded areas denote height to width ratio above 0.5 (for structural stability)

Boxes represent results with a T-ult(circumferential) of greater than 4800 lbs/ft. (failure of tube is likely)

Unit weight of slurry estimated to be 78.0 lbs/ft for all calculations

Calculations performed assuming tubes will be filled on land, not in water.

15-ft circumference tube calculated at 14.5 feet

22.5-ft circumference tube calculated at 21.84 feet

30-ft circumference tube calculated at 29.5 feet

45-ft circumference tube calculated at 44.0 feet

60-ft circumference tube calculated at 58.7 feet

75-ft circumference tube calculated at 73.5 feet

80.5-ft circumference tube calculated at 80.5 feet

85-ft circumference tube calculated at 85 feet

90-ft circumference tube calculated at 88.0 feet

Column Headings:

Height: Top elevation of tube

SF: Cross sectional area of tube in square feet

cy/L.F.: Capacity of tube in cubic yards per unit length (ft)

gal/l.f.: Capacity of tube in gallons per unit length (ft)

Fabrication Procedures

Geotextile Tube production protocols to be used on all sew tags

1. **Item Number** is the Integra item number.
   Examples:
   a. TGTUBE4660100 for a 60x100' tube made from black 4x6
   b. TGTUBET60100 for a 60x100' tube made from tan 1853

2. **Product ID # or serial number is assign to a specific tube based on the date of production. Each tube is labeled as** TTYYMMDD# where:
   - TT = Type of material used (i.e.46or 53)
   - YY= two digit designation of the year (e.g. 10)
   - MM = two digit designation of the month
   - DD = date
   - # = the count of tubes manufactured on that date (e.g. the second tube made that day would be "2", even if the first one made was from a different fabric)

   Examples:
   a. 4x6 black tubes
      i. 46YYMMDD#
      ii. e.g. the first tube finished on October 20, 2010 would be 461010201
   b. 1853 Tan
      i. 53YYMMDD#
      ii. e.g. the 2nd tube finished on June 14, 2011 would be 531106142

3. **Size** is the circumference and length of the tube in feet
   e.g. 60' x 100'
4. **Ports** is the number of ports built on the Geotextile tube
5. **Weight** is the estimated weight rounded to the nearest 100 pounds
6. **Inspected by** is where the lead fabricator initials
7. The tag is sewn in a prominent location

SILTTEX


GSI - Waukesha, WI

ITEM NUMBER (1)	*PRODUCT ID #* (2)
Size (3) ____ X ____	*PORTS:* (4) ____ *WEIGHT:* (5) ____

INSPECTED BY: (6) ____

THIS INFORMATION IS PROVIDED FOR REFERENCE PURPOSES ONLY AND IS NOT INTENDED TO IMPLY A WARRANTY OR GUARANTEE. THIS PRODUCT WAS INSPECTED AT TIME OF SHIPMENT AND WAS FOUND TO BE IN GOOD QUALITY AND FREE FROM DEFECTS. GSI ASSUMES NO LIABILITY AS TO DAMAGE FROM SHIPMENT OR ON SITE HANDLING.

GEO-SYNTHETICS, INC.
SEAM STRENGTH TESTING (AST.M D 4884)
Butterfly Seam with 2 Rows of Stitches at Selvage and 3 SPI
Propex 4 x 6 Woven Geotextile
Geotextile Roll # 202255359 and 2022567984
SGI Sample ID No. S17162



Test No.	Maximum Seam Strength (lbs/in.)	Displacement at Maximum (in.)	Time to Rupture (min.)	Failure Mode (-)	Ultimate Strength in XD (lbs/in.)	Seam Efficiency (%)
1	318	4.1	10.2	Rupture of XD Yarns		
2	306	3.6	9.1			
3	334	4.6	11.6			
4	312	4.2	10.6			
5	303	3.8	9.4			
6	308	4.4	11.0			
Mean	313	4.1	10.3	NA	NA	NA
STD	11	0.4	0.9	NA	NA	NA

NOTES:

Clamp:	Roller
Padding:	None
Specimen Width (in.):	8.0
Gage Length (in.):	4.0
Strain Rate (% per minute):	10
MD:	Machine direction
XD:	Cross-machine direction
NA:	Not Applicable

DATE TESTED: 12/11/2012

SGI TESTING SERVICES, LLC

FIGURE NO.	2
PROJECT NO.	SGI10012
DOCUMENT NO.	
FILE NO.	

GEOSTRUX™ GEOTEXTILE TUBE HANDLING AND STORAGE[1]

- Product Delivery, Handling, and Storage
  - Product Delivery
    - The Geotextile tube shall be delivered wrapped in a protective wrap that consists of a nonwoven geotextile and a black plastic wrap. There will be product identification on the outside wrap as well as on the Geotextile tube itself. The identification on the wrap will be the tube size. The information on the tube proper will be the size, weight, and production date. The tube will be rolled on a steel/cardboard core depending on the size of the tube.
  - Product Handling
    - No hooks, tongs, forks, or other sharp devices shall be used to handle the Geotextile Tube. If practical use machinery fitted with poles that can be inserted into the core for moving the Geotextile tube around. Care should be taken so as to not damaging the protective wrap by sliding, dragging, or prodding the roll. Care should be taken to not damage the core with a pole that is not at least two thirds the length of the core. Straps and slings may be used to carry relatively rigid rolls of material provided the slings do not cause damage to the rolls.
  - Product Storage
    - When storing the Geotextile Tube care should be taken to elevate the tube so as to keep the product out of standing/accumulated water. Care should be taken to protect the product from environmental conditions that could reduce the performance of the Geotextile Tube. The protective wrap should remain in place until the product is to be installed on site to assure protection from sunlight and other environmental conditions over extended periods of time. Care should be taken to assure that there are no sharp objects in the storage area that may damage the tube.

Geotextile Tube Repair

It is always best to enlist an experienced geotextile tube installer on the project. They have the ability to assess the damage and provide solutions at the time of the mishap. The first step in repair of a geotextile tube should be to determine the cause for the damage to the tube, if the damage was created by internal or external forces or debris, the process for pumping should be reviewed in order to prevent further damage.

Should a hole develop in the fabric of the tube first clean the area around the hole. Cut a piece of fabric that is 6 inches wider than the hole. Insert the patch material into the hole and spread the patch out to create good contact with the inside of the tube. Then if the inside pressure does not hold the patch in place use the hook needle and thread supplied to attach the patch to the side wall of the tube. If the hole is more of a slit then use the needle and thread supplied to sew the slit together.

Nylon zip ties are also supplied to make a quick repair of a slit area in the wall of the tube. This works for damaged areas less than 18” in length. In areas that are larger then clamp the area with two pieces of wood and “C” clamps and use all weather screws and screw the wood together creating a new “seam”.

[1] ASTM D 4873-02

If the damage is in the seam there may not be a repair solution that will allow for maximum filling of the tube. A replacement may be the only solution. Working around the tube with sharp edges and mechanical equipment should warrant care and where necessary a second person to spot the activity to prevent moving too close to the geotextile tube.

The immediate filling period is when the tube will experience the greatest pressures. As consolidation develops there will be less outward pressure on the damaged area. At that time it is a matter of sealing the hole to prevent migration of the contained materials.

INSTALLATION INSTRUCTIONS

The *information, including technical and engineering* data, *figures, tables, designs, drawings, details, suggested* procedures, *and suggested specifications, presented* in *this publication are for general information only.* The *information contained* herein is subject to change without notice. While every *effort has* been made to ensure *its accuracy, this information should* not be used *or relied upon for any specific application without* independent *professional examination and verification of its accuracy, suitability*, and *applicability.*

Tube installation shall be in accordance with the following specifications:

The foundation for the placement of the geotextile tube shall be smooth and free of protrusions, which could damage the geotextile. Remnant timber piles, piers, footings, underground utilities, etc., at or below grade, shall be removed if located within 6.0 m (20 ft) of the project site. Weak or unsuitable foundation material shall be removed or stabilized. The dewatering area shall be graded to a maximum slope of 1%. The dewatering area shall have a non-erodable surface (gravel, grass, asphalt or concrete) or shall be lined with plastic sheeting.

DEPLOYMENT

Tubes shall be aligned as straight as possible. Means of assuring that the tubes are properly aligned within the specified tolerances shall be incorporated into the placement methodology presented the Plan of Construction. The geotextile tubes shall be deployed along the alignment and secured in place as necessary to assure proper alignment after filling. No portion of the tubes shall be filled until the entire tube segment has been fully anchored to the foundation along the correct alignment and pulled taut. Larger tubes may require concrete barriers to prevent the tubes from rolling during filling. All unused fill ports shall be tied closed.

FILLING

After completing the deployment and anchorage of the geotextile tube, filling with dredged material shall be accomplished in accordance with the approved Plan of Construction. The discharge line of the dredge shall be fitted with a "Y-valve" to allow control of the rate of filling. The Y-valve system shall be fitted with an internal mechanism such as a gate, butterfly valve, ball valve, or pinch valve to allow the contractor to regulate discharge into the geotextile tube. Any excess discharge shall be directed away from the tubes toward the borrow area. The dredge discharge pipe shall be free of protrusions that could that could tear the fill port. It is generally accepted practice to support the dredge discharge pipe above the fill port in a manner, which reduces stress on the fill port seams. The height to width ratio of the full-deployed tube shall not exceed a value, of 0.5. Other height and width specification may be required by the Engineer to assure sliding, overturning, bearing capacity, and global stability of the tube system. If the tube is not to be externally backfilled, the area should be left in a neat and properly graded manner. If the tube is to be externally backfilled, the lines and grade on the Plan of Construction must be followed. The tubes shall not be filled higher than the manufacturer's recommended height.

PROTECTION

No hooks, tongs or other sharp instruments shall be used for handling. The geotextile tube shall not be dragged on the ground.


RECOMMENDED FILL HEIGHT

15'-3', 30'-4', 45'-5.5', 60'- 7.0'


Injection Port Closing Details

1. Geotextile Tubes are shipped with zip ties to close off the port after the filling operation is complete
2. Contractor has the option to use an alternate method to achieve the same result

A closed port should resemble the following:



2401 PEWAUKEE ROAD • WAUKESHA, WI 53188-6904 • 262-524-7979 • Fax: 262-524-7961 • 800-444-5523 • www.geo-synthetics.com




GSI RECOMMENDS AT A MINIMUM PERFORMING A HANGING BAG TEST PRIOR TO STARTING PROJECT.

TUBE TO BE PLACED ON PROPERLY PREPARED SUBGRADE. DETAILS AVAILABLE AT WWW.GEO-SYNTHETICS.COM


FILL PORTS

ALIGNMENT STRAPS


GEOSTRUX™ GEOTEXTILE TUBE PLAN VIEW




LONGITUDINAL SEAM DETAIL



END SEAM DETAIL



ALINGMENT STRAP DETAIL



GEOSTRUX™ GEOTEXTILE TUBE END VIEW

REVISIONS		
NO.	DATE	BY

NOTES:

1) GEOSTRUX™ GEOTEXTILE TUBES ARE CONSTRUCTED WITH 15' PANEL SECTIONS.
2) STANDARD FILL PORTS ARE 18" DIAMETER BY 36" LONG.

DISCLAIMER:
GSI ASSUMES NO LIABILITY FOR THE ULTIMATE USE BY THE PURCHASER. GSI DISCLAIMS ANY AND ALL EXPRESS, IMPLIED, OR STATUTORY STANDARDS, WARRANTIES, OR GUARANTEES, INCLUDING WITHOUT LIMITATION ANY IMPLIED WARRANTY AS TO MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE OR ARISING FROM A COURSE OF DEALING OR USAGE OF TRADE AS TO ANY EQUIPMENT, MATERIALS, OR INFORMATION FURNISHED HEREWITH. THIS DOCUMENT SHOULD NOT BE CONSTRUED AS ENGINEERING ADVICE.

LEGEND

- PANEL OUTLINE
- SEAM
- ALIGNMENT STRAP
- FILL PORT

CUSTOMER'S APPROVAL

THE UNDERSIGNED APPROVES PRODUCTION OF GEOSTRUX™ GEOTEXTILE TUBES BY GEO-SYNTHETICS, LLC AS SHOWN.

_____
SIGNATURE

_____
COMPANY

DRAWN BY: MAR **DATE:** 01/12/10

CHKD BY: **DATE:**

SCALE: NTS **DRAWING #** GT-610

FILENAME: 60100 STANDARD

PROJECT INFORMATION:

60' X 100' GEOSTRUX™ GEOTEXTILE TUBE - STANDARD

GEO-SYNTHETICS, LLC.
2401 PEWAUKEE ROAD
WAUKESHA, WI 53188
262-524-7979

ATTACHMENT F: SAFETY DATA SHEETS

SAFETY DATA SHEET

Version 2

1. Identification of the Substance / Preparation and of the Company / Undertaking

Product Name Aqua Hawk® 7840
Product Code 41777
Recommended Use Industrial, Manufacturing or Laboratory use.
Restrictions on Use None known

Manufacturer
Hawkins, Inc., 2381 Rosegate, Roseville, MN 55113 (612-331-6910)

Emergency Telephone:
CHEMTREC (US): 1-800-424-9300

2. Hazards Identification

GHS - Classification

Skin corrosion/irritation	Category 2
Serious eye damage/eye irritation	Category 2B

Hazards not otherwise classified (HNOC)
Not applicable

Label elements



Signal Word: **Warning**

Hazard Statements:
• Causes skin and eye irritation

Precautionary Statements:
• Wash face, hands and any exposed skin thoroughly after handling
• Wear protective gloves
• IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
• If eye irritation persists: Get medical advice/attention
• IF ON SKIN: Wash with plenty of soap and water
• If skin irritation occurs: Get medical advice/attention
• Take off contaminated clothing and wash before reuse

3. Composition / Information on Ingredients

Chemical name	CAS No.	Weight-%
Trade Secret Aliphatic Hydrocarbon	-	20-30

Any concentration shown as a range is due to batch variation or the exact percentage has been withheld as a trade secret.

4. First Aid Measures

Description of first aid measures

General advice	Show this safety data sheet to the doctor in attendance.
Inhalation	Remove to fresh air. Get medical attention immediately if symptoms occur.
Eye contact	Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Keep eye wide open while rinsing. Remove contact lenses, if present and easy to do. Continue rinsing. Get medical attention if irritation develops and persists.
Skin contact	Wash off immediately with soap and plenty of water for at least 15 minutes. Get medical attention if irritation develops and persists.
Ingestion	Clean mouth with water and drink afterwards plenty of water. Never give anything by mouth to an unconscious person. Do NOT induce vomiting. Call a physician.
Self-protection of the first aider	Avoid contact with skin, eyes or clothing. Wear personal protective clothing (see section 8).

Most important symptoms and effects, both acute and delayed

Symptoms	Redness. May cause redness and tearing of the eyes.

Indication of any immediate medical attention and special treatment needed

Note to physicians	Treat symptomatically.

5. Fire-fighting Measures

Suitable Extinguishing Media	Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.
Large Fire	CAUTION: Use of water spray when fighting fire may be inefficient.
Unsuitable extinguishing media	Do not scatter spilled material with high pressure water streams.
Specific hazards arising from the chemical	Do not allow run-off from fire-fighting to enter drains or water courses.
Hazardous combustion products	Carbon oxides. Nitrogen oxides (NO_x).
Explosion Data	
Sensitivity to mechanical impact	None.
Sensitivity to static discharge	None.
Special protective equipment for fire-fighters	Firefighters should wear self-contained breathing apparatus and full firefighting turnout gear. Use personal protection equipment.

6. Accidental Release Measures

Personal precautions, protective equipment and emergency procedures

Personal precautions	Avoid contact with skin, eyes or clothing. Ensure adequate ventilation. Use personal protective equipment as required.
Other information	Refer to protective measures listed in Sections 7 and 8.

Methods and material for containment and cleaning up

Methods for containment	Prevent further leakage or spillage if safe to do so.
Methods for cleaning up	Dike far ahead of liquid spill for later disposal. Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder, sawdust). Pick up and transfer to properly labeled containers. Clean contaminated surface thoroughly. After cleaning, flush away traces with water.

7. Handling and Storage

Precautions for safe handling

Advice on safe handling	Handle in accordance with good industrial hygiene and safety practice. Avoid contact with skin, eyes or clothing. Do not eat, drink or smoke when using this product. Take off contaminated clothing and wash before reuse.

Conditions for safe storage, including any incompatibilities

Storage Conditions	Keep containers tightly closed in a dry, cool and well-ventilated place.
Incompatible materials	Strong oxidizing agents.

8. Exposure Controls / Personal Protection

Control parameters

Exposure Limits The following ingredients are the only ingredients of the product above the cut-off level (or level that contributes to the hazard classification of the mixture) which have an exposure limit applicable in the region for which this safety data sheet is intended or other recommended limit. At this time, the other relevant constituents have no known exposure limits from the sources listed here.

Chemical name	ACGIH TLV	OSHA PEL	NIOSH IDLH
Trade Secret Aliphatic Hydrocarbon	TWA: 200 mg/m³ (total hydrocarbon vapor)	TWA (Mist): 5 mg/m³	-

Appropriate engineering controls

Engineering controls Showers
Eyewash stations
Ventilation systems.

Individual protection measures, such as personal protective equipment

Eye/face protection Tight sealing safety goggles.
Hand protection Wear suitable gloves. Impervious gloves.

Skin and body protection Wear suitable protective clothing. Long sleeved clothing.
Respiratory protection No protective equipment is needed under normal use conditions. If exposure limits are exceeded or irritation is experienced, ventilation and evacuation may be required.
Environmental exposure controls Do not allow into any sewer, on the ground or into any body of water. Prevent product from entering drains.
General hygiene considerations Wear suitable gloves and eye/face protection. Do not eat, drink or smoke when using this product. Avoid contact with skin, eyes or clothing.

9. Physical and Chemical Properties

9.1. Information on basic physical and chemical properties

Physical State: Liquid
Appearance: Emulsion
Color: White to off-white
Odor: Mineral oil-like
Odor Threshold: No information available

Property	Values	Remarks • Method
pH:	4	
Salt Out Point:		No information available
Melting Point/Freezing Point:		No information available
Boiling Point/Boiling Range:	100 °C / 212 °F	
Flash Point:	> 100 °C / 212 °F	ASTM D92: Standard Test Method for Flash and Fire Points by Cleveland Open Cup
Evaporation Rate (BuAc=1):		No information available
Flammability (solid, gas)		Not highly flammable
Flammability Limits in Air:		No information available
Upper Flammability Limit:		**Lower Flammability Limit:**
Vapor Pressure (mm Hg):		No information available
Vapor density (Air =1)		No information available
Specific Gravity (H_2O=1):		No information available
Specific Gravity (2nd value):		No information available
Water Solubility:	Dispersible	
Solubility(ies):		No information available
Partition Coefficient (n-octanol/water)		No information available
Autoignition Temperature:		Not self-igniting
Decomposition Temperature:		No information available
Kinematic Viscosity:	>20.5 mm²/s	
Dynamic Viscosity:	1000 mPa.s	
Oxidizing Properties:	Not fire-propagating	
Explosive Properties:	Not considered to be an explosion hazard	

9.2. Other information

Softening Point:	No information available
Molecular Weight:	N/A
VOC Content(%):	No information available
Liquid Density	ca. 1.0 g/cm3
Bulk density	No information available

10. Stability and Reactivity

Reactivity	No information available.
Chemical stability	Stable under normal conditions.
Possibility of hazardous reactions	None under normal processing.
Conditions to avoid	Heat, flames and sparks.
Incompatible materials	Strong oxidizing agents.
Hazardous decomposition products	Carbon oxides. Nitrogen oxides (NO_x).

11. Toxicological Information

Information on likely routes of exposure

Product Information

Inhalation	Specific test data for the substance or mixture is not available. May cause irritation of respiratory tract.
Eye contact	Specific test data for the substance or mixture is not available. Irritating to eyes. (based on components). Causes eye irritation.
Skin contact	Specific test data for the substance or mixture is not available. Causes skin irritation. (based on components).
Ingestion	Specific test data for the substance or mixture is not available. Ingestion may cause gastrointestinal irritation, nausea, vomiting and diarrhea.

Symptoms related to the physical, chemical and toxicological characteristics

Symptoms Redness. May cause redness and tearing of the eyes.

Numerical measures of toxicity

Not applicable

Acute Toxicity:

Unknown Acute toxicity No information available

Component Information

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Skin corrosion/irritation	Classification based on data available for ingredients. Irritating to skin.
Serious eye damage/eye irritation	Classification based on data available for ingredients. Irritating to eyes.
Respiratory or skin sensitization	No information available.
Germ cell mutagenicity	No information available.
Carcinogenicity	This product does not contain any carcinogens or potential carcinogens as listed by OSHA, IARC or NTP.
Reproductive toxicity	No information available.
STOT - single exposure	No information available.
STOT - repeated exposure	No information available.
Other Adverse Effects:	No information available.
Aspiration hazard	No information available.

12. Ecological Information

Ecotoxicity Toxic to aquatic life.

Persistence and Degradability: No information available.
Bioaccumulation: There is no data for this product.

Mobility: Assessment transport between environmental compartments: Adsorption to solid soil phase is expected.
Other Adverse Effects: No information available.

13. Disposal Considerations

Waste treatment methods

Waste from residues/unused products Dispose of in accordance with local regulations. Dispose of waste in accordance with environmental legislation.
Contaminated packaging Do not reuse empty containers.

14. Transport Information

DOT

Description Not DOT Regulated

15. Regulatory Information

International Inventories

AICS	-
TSCA	-
DSL/NDSL	-
EINECS/ELINCS	-
ENCS	-
IECSC	-
KECL	-
PICCS	-

Inventory Legend

AICS - Australian Inventory of Chemical Substances
TSCA - United States Toxic Substances Control Act Section 8(b) Inventory
DSL/NDSL - Canadian Domestic Substances List/Non-Domestic Substances List
EINECS/ELINCS - European Inventory of Existing Chemical Substances/European List of Notified Chemical Substances
ENCS - Japan Existing and New Chemical Substances
IECSC - China Inventory of Existing Chemical Substances
KECL - Korean Existing and Evaluated Chemical Substances
PICCS - Philippines Inventory of Chemicals and Chemical Substances

RESTRICTIONS - REACH TITLE VII No information available

US Federal Regulations

CERCLA

This material, as supplied, does not contain any substances regulated as hazardous substances under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302) or the Superfund Amendments and

Reauthorization Act (SARA) (40 CFR 355). There may be specific reporting requirements at the local, regional, or state level pertaining to releases of this material

SARA 313
Section 313 of Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA). This product does not contain any chemicals which are subject to the reporting requirements of the Act and Title 40 of the Code of Federal Regulations, Part 372

SARA 311/312 Hazard Categories

Acute health hazard	Yes
Chronic health hazard	No
Fire hazard	No
Sudden release of pressure hazard	No
Reactive hazard	No

U.S. State Right-to-Know Regulations

California Proposition 65:
WARNING! This product contains a chemical known in the State of California to cause cancer This product contains chemicals known to the state of California to cause birth defects or other reproductive harm

16. Other Information

Prepared By:	HSE Department
Issue Date:	30-Jul-2014
Revision Date:	10-Mar-2020
Revision Note:	Reviewed and Re-issued

Disclaimer:
The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

End of Safety Data Sheet